

Himachal Pradesh  
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2025-2026-

10141-42

Dated:-

15/9/25

To


The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender notice are urgent in nature and in public interest.


DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.



Executive Engineer,  
Shimla Division No-1.,  
HPPWD., Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4<sup>th</sup> Circle HPPWD Shimla .



Executive Engineer,  
Shimla Division No-1.,  
HPPWD., Shimla-3.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- |  |                                   |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 23-09-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:-            | 23-09-2025 12:00 PM upto 4:00 PM  |
| 3. Date of receipt of tender:-                       | 24-09-2025 .up to 10:30 AM        |
| 4. Date of opening of tender:-                       | 24-09-2025 up to 11:00 AM         |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O kasumpti to Basant vihar road in km. 0/00 to 0/550 (SH;- Construction of Breast wall between at RD. 0/310.50 to 0/313 under parimahla section).	96574/-	2000/-	350/-	30 days	Class-D
2	A/R & M/O to various Residential qtrs. Under kasumpti sub Division Shimla-9 (SH;- Supplying of material to sub division No.VIII Mehli section Shimla-9).	99052/-	2000/-	350/-	30 days	Class-D
3	A/R & M/O to various Residential qtrs. Under kasumpti sub Division Shimla-9 (SH;- Supplying material to sub division No.. VIII Mehli Section Shimla-9).	99175/-	2000/*-	350/-	30 Days	Class-D
4	Construction of link road from Cheog Bazar to Viaage Mehana road Distt. Shimla (HP) km. 0/00 to 0/790 (SH;- Preparation of Geo Referenced Digital Map and Collection data for FRA).	70000/-	1400/-	350/-	30 Days	Class-D
5	A/R & M/O various Type-I to Type-VI GAD Residential qtrs. At kasumpti Shimla (SH;- Covering of stair case oover polycarbonate sheet set No.19 type-VI at Mehli Shimla).	99590/-	1900/-	350/-	30 days	Class-D
6	A/R & M/O various Type-III to Type-IV.Qtrs of GAD at Parimahal kasumpti Shimla-9 (SH;- Repair work in toilet, bathroom, kitchen, providing and fixing cupboard white washing/distempering etc in type-III set No.45 Under Parimahal section).	97282/-	1900/-	350/-	30 days	30 Days
7	A/R & M/O various Type-I to Type-VI GAD Residential qtrs. At kasumpti Shimla-9 (SH;- Painting work in type-V set No.23 under kasumpti section).	80750/-	1700/-	350/-	30 days	30 Days
8	Restoration of Rain Damages various roads under Shimla Division No.1 (SH;- Removal of slips at various Rds).	94500/-	1900/-	350/-	30 Days	Class-D
9	A/R & M/O to type-VI qtr set No.17 type-VI at mehli Shimla (SH;- Providing and stair case in set no.17 type-VI Mehli Shimla).	99976/-	2000/-	350/-	30 Days	Class-D
10	Restoration of rain damages on Fagu to Cheog road km. 0/00 to 5/600 (SH;- C/O unlined surface drain at various RDs in km. 0/00 to 5/600).	96280/-	2000/-	350/-	30 Days	Class-D
11	Restoration of Rain Damages in Baldeyan section under Mashobra sub Division (SH;- Hiring of Excavator cum roller for removal of slips on various roads of Baldeyan section, Shimla Mandi road km. 7/00 to 20/00, Baldeyan Dharpur road km. 1/ to 9/500, Kanda to mulkoti road km. 8/00 to 13/00).	99855/-	2000/-	350/-	30 Days	Class-D
12	Improvement of Bhatta kufer to AIMSS road km. 0/00 to 2/400 (SH;- Improvement of passing place on encroached portion at RD. 0/350 to i/c Rec slab and safety railings).	98403/-	2000/-	350/-	30 Days	Class-D
13	Restoration of Rain Damages in Baldeyan section under Mashobra sub Division (SH;- Hiring of Excavator cum roller for removal of slips on Baldeyan to Shenal road km. 0/00 to 4/720, Sadhora to Mohanpur road in km. 0/00 to 6/525 and Mohanpur Nallah to kiar koti in km. 0/00 to 2/00).	99750/-	2000/-	350/-	30 Days	Class-D
14	Restoration of rain damges on koti to Satlai road inn km. 0/00 to 15/00 (SH;- Removal of slips at Rd. 3/910 to 12/675).	99460/-	2000/-	350/-	30 Days	Class-D
15	Annual Repair and Maintenance road on Mashohbra to Bhaikhility road in km. 0/00 to 18/300 (SH;- Supplying and stacking pot seal bags cold mix Various Rds between km. 6/00 to 12/00).	97350/-	2000/-	350/-	30 Days	Class-D
16	Annual Repair and Maintenance road on Shimla Mandi road in km. 6/00 to 22/00 (SH;- Supplying and stacking pot seal bags cold mix various Rds between km. 6/00 to 22/00).	96525/-	2000/-	350/-	30 Days	Class-D
17	Annual Repair and Maintenance road on Fagu to Cheog road in km. 0/00 to 7/00 (SH;- Supplying and Stacking pot seal bags could mix various Rds between km. 0/00 to 5/00).	94875/-	2000/-	350/-	30 Days	Class-D
18	Annual Repair and Maintenance road on Challanda to Piran road in km.0/00 to 28/00 (SH;- Supplying and stacking pot seal bags cold mix various rds between km. 22/00 to 28/00).	98175/-	2000/-	350/-	30 Days	Class-D
19	A/R & M/O Shimla Mandi road km. 6/00 to 22/00 (SH;- Providing and Fixing of road studs (Valley side) at Rd. 6/00 to 6/175).	97890/-	2000/-	350/-	30 Days	Class-D
20	A/R & M/O Shimla Mandi road km. 6/00 to 22/00 (SH;- Providing and Fixing of road studs (Valley side) at RD. 6/675 to 6/870).	99450/-	2000/-	350/-	30 Days	Class-D
21	Annual Repair and Maintenance road on Baldiyan road on Daldiyan Dharpur road	99000	2000/-	350/-	30	Class-D

					Days	
	in km. 0/00 to 7/00 & Nauti to Thaila road km. 0/00 to 7/300 (SH:- Supplying and stacking pot seal bags cold mix Various Rds between km. 7/00 & 0/00 to 7/300).					
22	Annual Repair and Maintenance road on Internal road of Kasumpti road colony road in km. (SH:- Supplying and stacking pot seal bags cold mix various Rds between km. )	95700/-	2000/-	350/-	30 Days	Class-D
23	Restoration of Rain damages on koti to Satlai road in km. 0/00 to 15/00 (SH:- Removal of slips at RDs 3/910 to 12/675).	99460/-	2000/-	350/-	30 Days	Class-D
24	Restoration of Rain Damage on various roads kanda Mool koti road in km. 4/00 to 13/240, Baldeyan to Dharpur road in km. 0/00 to 10/00, Baldeyan to Shannel road in 0/00 to 4/720, Shimla to Mandi road in km. 0/00 to 10/00, Baldeyan to Shannel road in km. 0/00 to 4/720, Shimla to Mandi road in km. 0/00 to 22/00 (SH:- Removal of slips at various roads under Baldeyan section).	99200/-	2000/-	350/-	30 Days	Class-D
25	Restoration of Rain damages to various road under Bharari section (SH:- Hiring of Excavator cum loader for Removal of slips in various Rds Bhont kakar Bhaogra road km. 0/900 to 0/920, 1/450 to 1/600).	98700/-	2000/-	350/-	30 Days	Class-D
26	Restoration of Rain Damages on Nariga pul to Jagher road km. 0/00 to 1/660 (SH:- Removal of slips at Rd 0/00 to 1/660).	99000/-	2000/-	350/-	30 Days	Class-D
27	A/R & M/O to various Type-I to Type-VI Qtrs of GAD at kasumpti Shimla (SH:- Providing and fixing cupboard in Type-IV set nO.19 under kasumpti Section).	99967/-	2000/-	350/-	30 Days	Class-D
28	A/R & M/O to various Type-I to Type-VI qtrs. Qtrs of Gad at kasumpti Shimla (SH:- Providing and fixing cupboard in type-IV set nO.45 under kasumpti section).	99939/-	2000/-	350/-	30 Days	Class-D
29	Construction of Bharari to Padhai Mata road km. 0/00 to 1/800 in Distt. Shimla HP (SH:- Preparation of Technical sanction working, Estimate and DNIT).	36900/-	800/-	350/-	30 Days	Class-D
30	Restoration of Rain Damages on various road under Fagu section (SH:- Hiring of Excavator cum loader for removal of slips in Fagu to Cheog road km. 0/00 to 5/00, Cheog to Dharech road km. 0/00 to 7/00, Talai to Dehna road km. 0/00 to 2/500, Talai to Dehna road km. 0/00 to 2/00, Bangapani to Chatog road km. 0/00 to 2/00 at various Rds).	99750/-	2000/-	350/-	30 Days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.
- 14.

No.PW-SD-I/CB-Tender/2025-2026-  
Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Dsitt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,  
Shimla Division No-I.,  
HPPWD. Shimla-3.

Dated : 15-9-2025

Executive Engineer,  
Shimla Division No-I.,  
HPPWD Shimla.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 96,574.00		
Name of Work :- A/R & M/O Kasumpti to Basant Vihar road in Km. 0/000 to 0/550. (SH:- Construction of					Earnest Money :- 2,000.00		
Breast Wall between at RD 0/310.50 to 0/313 under Parimahal Section).					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	<p>Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.</p>	13.60	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4420.00


2	<p>Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping-site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.</p>	2.63	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1052.00
3	<p>Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)</p>	8.01	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	43254.00
4	<p>Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: Five sand: Ten graded stone agg.40mm nominal size).</p>	1.04	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	3952.00

5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	15.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	2700.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	1.76	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	1848.00
7	Disposal of excavated earth work by debris material upto site on approved dumping site approved by M.C. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.11	Cum	600.00	Rupees Six Hundred Only	Per Cubic Metre	6066.00
8	Square rubble masonry with hard stone in superstructure above plinth level and upto floor five level including leveling up with cement concrete 1:6:12 (One cement: Six Coarse sand : Twelve graded stone aggregate 20mm nominal size) at window sills, ceiling level and the like including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	4.38	Cum	6400.00	#NAME?	Per Cubic Metre	28032.00
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Thermo Mechanically Treated bars of grade Fe-500D or more.	50.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	5250.00
						<b>Total</b>	<b>96574.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

TIS No - 9414-15 Dt - 3-9-25 Amount = 99477

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

### SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							Estimated Cost:-99052 .00	
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Mehli Section Shimla-9).							Earnest Money :- 2000.00	
							Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Kgs.	280.00	Rupees Two Hundred Eighty Only	Per Kilo-gram	560.00	
2	S.S. connection 15x450 Viking	12.00	Nos	290.00	Rupees Two Hundred Ninety Only	Each	3480.00	
3	P.V.C. pipe finolex 100mm	12.00	Nos	1005.00	Rupees One Thousand Five Only	Each	12060.00	
4	P.V.C. pipe Finolex 90mm	12.00	Nos	900.00	Rupees Nine Hundred Only	Each	10800.00	
5	P.V.C door Tee 100mm	10.00	Nos	375.00	Rupees Three Hundred Seventy Five Only	Each	3750.00	
6	P.V.C door Tee 90mm	10.00	Nos	290.00	Rupees Two Hundred Ninety Only	Each	2900.00	
7	P.V.C. Plain Bend 100 mm	5.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1250.00	
8	P.V.C. Plain Bend 90mm	10.00	Nos	184.00	Rupees One Hundred Eighty Four Only	Each	1840.00	
9	P.V.C Door Bend 100mm	5.00	Nos	275.00	Rupees Two Hundred Seventy Five Only	Each	1375.00	
10	P.V.C. Door Bend 90mm	5.00	Nos	205.00	Rupees Two Hundred Five Only	Each	1025.00	
11	P.V.C. Collar 100mm	8.00	Nos	225.00	Rupees Two Hundred Twenty Five Only	Each	1800.00	
12	P.V.C. Collar 90mm	5.00	Nos	210.00	Rupees Two Hundred Ten Only	Each	1050.00	
13	P.V.C. Floor Trap 90mm	6.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	1980.00	
14	C.P. Waste 32mm	4.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1000.00	
15	P.V.C. Ball valave for cistern	5.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	1750.00	


16	P.V.C. handle for cistern	5.00	Nos	98.00	Rupees Ninety Eight Only	Each	490.00
17	Acrylic shelf 450mm	5.00	Nos	630.00	Rupees Six Hundred Thirty Only	Each	3150.00
18	Glass putty Asian	6.00	Kgs.	88.00	Rupees Eighty Eight Only	Per Kilo-gram	528.00
19	Gate Hook 150mm (Heavy)	5.00	Nos	171.00	Rupees One Hundred Seventy One Only	Each	855.00
20	Spindle for bib cock/Mixer with washer.	4.00	Nos	245.00	Rupees Two Hundred Forty Five Only	Each	980.00
21	G.I. Nipple 15x50mm Jindal Make	4.00	Nos	18.00	Rupees Eighteen Only	Each	72.00
22	C.P. Sink Waste 100mm Diamond make	4.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	1000.00
23	Acrylic Bathroom Corner Diamond make.	8.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	5200.00
24	Iron Door Hinges 100mm (Heavy)	12.00	Nos	40.00	Rupees Forty Only	Each	480.00
25	Iron Door Hinges 75mm (Heavy)	12.00	Nos	23.00	Rupees Twenty Three Only	Each	276.00
26	Brass sliding door bolt complete	4.00	Nos	1890.00	Rupees One Thousand Eight Hundred Ninety Only	Each	7560.00
27	Brass Non Return Valve 15mm	4.00	Nos	590.00	Rupees Five Hundred Ninety Only	Each	2360.00
28	PTMT Ball Cock 15mm with Ball complete (Heavy)	5.00	Nos	515.00	Rupees Five Hundred Fifteen Only	Each	2575.00
29	M. Seal	6.00	Packet	30.00	Rupees Thirty Only	Per Packet	180.00
30	C.P. Waste 32mm (Heavy)	4.00	Nos	298.00	Rupees Two Hundred Ninety Eight Only	Each	1192.00
31	Fastner 100mm Long with Pin & Nut Bolt	2.00	Nos	70.00	Rupees Seventy Only	Each	140.00
32	Soap Dish Heavy Diamond.	4.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	1520.00
33	PVC Waste pipe plain 32mm Viking Heavy.	4.00	Nos	210.00	Rupees Two Hundred Ten Only	Each	840.00
34	PVC Ball Cock Long with Ball for Cistern	4.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
35	Aluminium Sheet Heavy Duty.	4.00	Sft	60.00	Rupees Sixty Only	Per Square fit	240.00
36	C.P. Bib Cock Seeko Delux long body.	5.00	Nos	1050.00	Rupees One Thousand Fifty Only	Each	5250.00

37	C.P. Bib Cock Benson Gold.	4.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	3760.00
38	C.P. Angel Cock Seeko Delux.	4.00	Nos	900.00	Rupees Nine Hundred Only	Each	3600.00
39	C.P. Angel Cock Benson Gold.	4.00	Nos	940.00	Rupees Nine. Hundred Forty Only	Each	3760.00
40	Pillor Cock Benson Gold.	4.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	3760.00
41	PVC Connection 24" Hot Wired Viking.	4.00	Nos	310.00	Rupees Three Hundred Ten Only	Each	1240.00
42	PVC Fiber Washer 15mm.	12.00	Nos	2.00	Rupees Two Only	Each	24.00
						<b>Total</b>	<b>99052.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 9410-11 dated 3-9-28 Amounting to Rs. 102023/-

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla 3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99175 .00		
Name of Work :- A/R and M/O to various Residential Qtrs. Under Kasumpti Sub Division Shimla-9. (SH:- Supplying of material to Sub division no. VIII Mehli Section Shimla-9).					Earnest Money :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying of Black Nails size 20mm complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Kgs.	280.00	Rupees Two Hundred Eighty Only	Per Kilo-gram	1120.00
2	Nails 20mm	3.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	660.00
3	Nails 25mm	2.00	Kgs.	220.00	Rupees Two Hundred Twenty Only	Per Kilo-gram	440.00
4	Nails 40mm to 100mm	2.00	Kgs.	115.00	Rupees One Hundred Fifteen Only	Per Kilo-gram	230.00
5	Screw 20,25,30,35mm	3.00	Packet	70.00	Rupees Seventy Only	Per Packet	210.00
6	Hexa Blade	12.00	Nos	20.00	Rupees Twenty Only	Each	240.00
7	White cement in packing	5.00	Kgs.	35.00	Rupees Thirty Five Only	Per Kilo-gram	175.00
8	Powder coated pegs	5.00	Per Peg	55.00	Rupees Fifty Five Only	Per Pegs	275.00
9	Glass Pan 4mm plain frosted	20.00	Sft	120.00	Rupees One Hundred Twenty Only	Per Square fit	2400.00
10	C.P. Door Bolt	5.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	950.00
11	C.P. Curtain rod 20mm thick S.S 304 Grade	10.00	Nos	320.00	Rupees Three Hundred Twenty Only	Each	3200.00
12	Curatrain rod M.S. powder coated (Heavy)	10.00	Nos	458.00	Rupees Four Hundred Fifty Eight Only	Each	4580.00
13	Curatin Bracket Powder coated	10.00	Nos	95.00	Rupees Ninety Five Only	Each	950.00
14	Wire mesh fly proof	35.00	Sft	55.00	Rupees Fifty Five Only	Per Square fit	1925.00


15	C.P. curtain bracket any shape	20.00	Nos	48.00	Rupees Forty Eight Only	Each	960.00
16	C.P. iron sliding door bolt 200x16mm	10.00	Nos	330.00	Rupees Three Hundred Thirty Only	Each	3300.00
17	C.P iron sliding door bolt 250x 16mm	10.00	Nos	380.00	Rupees Three Hundred Eighty Only	Each	3800.00
18	C.P. iron sliding door bolt 300x 16mm	8.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	3600.00
19	Aluminium Handle 150mm HEAVY	5.00	Nos	48.00	Rupees Forty Eight Only	Each	240.00
20	Aluminium tower bolt 100x10mm	5.00	Nos	45.00	Rupees Forty Five Only	Each	225.00
21	Aluminium tower bolt 150x10mm	6.00	Nos	65.00	Rupees Sixty Five Only	Each	390.00
22	Aluminium tower bolt 200x 10mm	5.00	Nos	85.00	Rupees Eighty Five Only	Each	425.00
23	Iron door spring	8.00	Nos	395.00	Rupees Three Hundred Ninety Five Only	Each	3160.00
24	Door stoper S.S Steal	5.00	Nos	175.00	Rupees One Hundred Seventy Five Only	Each	875.00
25	C.P. S.S Gate Hook	10.00	Nos	148.00	Rupees One Hundred Forty Eight Only	Each	1480.00
26	P.V.C. royal Plough	10.00	Packet	69.00	Rupees Sixty Nine Only	Per Packet	690.00
27	M-Seal	10.00	Packet	30.00	Rupees Thirty Only	Per Packet	300.00
28	Leak Stop	12.00	Kgs.	325.00	Rupees Three Hundred Twenty Five Only	Per Kilo-gram	3900.00
29	G.I. Pipe 1/2" medium	10.00	Rmt	270.00	Rupees Two Hundred Seventy Only	Per Running Meter	2700.00
30	G.I. Socket 1/2"	5.00	Nos	40.00	Rupees Forty Only	Each	200.00
31	G.I. Elbow 1/2"	5.00	Nos	45.00	Rupees Forty Five Only	Each	225.00
32	G.I. Tee 1/2"	5.00	Nos	65.00	Rupees Sixty Five Only	Each	325.00
33	G.I. Union 1/2"	5.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	600.00

34	Brass stop cock 1/2"	5.00	Nos	368.00	Rupees Three Hundred Sixty Eight Only	Each	1840.00
35	Brass Bib cock 1/2"	5.00	Nos	368.00	Rupees Three Hundred Sixty Eight Only	Each	1840.00
36	C.P. Pillar cock Nova Heavy	8.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	7520.00
37	C.P. Pillar cock Seekko	8.00	Nos	900.00	Rupees Nine Hundred Only	Each	7200.00
38	C.P. Angle cock Nova Heavy	7.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	6580.00
39	C.P. Angle cock Seekko	8.00	Nos	900.00	Rupees Nine Hundred Only	Each	7200.00
40	C.P. Bib cock Nova Heavy	5.00	Nos	940.00	Rupees Nine Hundred Forty Only	Each	4700.00
41	C.P. Bib cock Seekko long body	5.00	Nos	1050.00	Rupees One Thousand Fifty Only	Each	5250.00
42	Gun Metal full way valve 15mm	5.00	Nos	563.00	Rupees Five Hundred Sixty Three Only	Each	2815.00
43	Brass ball cock heavy	12.00	Nos	525.00	Rupees Five Hundred Twenty Five Only	Each	6300.00
44	G.I. Tank nipple	12.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	1800.00
45	P.V.C. waste pipe 32mm	12.00	Nos	115.00	Rupees One Hundred Fifteen Only	Each	1380.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	<b>99175.00</b>

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 9412-13 dated 3-9-25 Amounting to Rs. 1025102150/2

  
Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY


<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>	<b>Estimated Cost:- 70,000.00</b>
<b>Name of Work :- Construction of Link road from Cheog Bazar to Viaage Mehana road Distt. Shimla (HP) Km. 0/00 to 0/790. (SH:- Preparation of Geo Referenced Digital Map and Collection data for FRA).</b>	<b>Earnest Money :- 1,400.00</b>
	<b>Time:- One Month.</b>

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Geo reference digital map and collecting of the data for proposed site including field visit. Preparation of KMI files with Geo Coordinates along with marking of Habitations to be benefited by construction of project and dumping area of proposed site. Marking the alignment in soft copy and submission in hard copy. Processing the case for preparation of forest diversion under forest conservation Act 2006 (FRA for Short) including preparation of Revenue papers for land acquire in the project & collection of other field data and all relevant document formats Mandatory required to be attached with the case as per latest requirement of ministry of Environment & forest b conservation Govt. of India Letter No. 11-9/98-FC(PT) dated 3rd August 2009. Deharadun after gating the joint inspection of site including computer typing of six copy to the case binding complete and gating in through from DFO including all the observations if raised at any time by any office & to pursue and resubmitt the same by neatly and accurately filling in all the formats documents online submissions rectifying observations (if any) and receiving approvals in all respect as per direction and complete citification of user Agency and forest Department. The rates are inclusive of octroi, royalty malkana, tool GST or other taxes imposed by the Government including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Job	70000.00	Rupees Seventy Thousand Only	Per Job	70000.00
						<b>Total</b>	<b>70000.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

(T/S No. 9420-2) Dated 3-9-25 Amount to  
Rs. 72.10.0.....)

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-Rs. 99590.00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla (						Earnest Money :-Rs .1900.00	
SH:- Covering of stair case over polycarbonate sheet set no.19 Type VI at Melhi Shimla )						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections,MS hollow pipe framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	866.00	Kgs	115.00	Rupees One Hundred Fifteen Only	Per kilo gram	99590.00
						Total	99590.00
prem	Quoted rates Percentage in words						

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 9422-23 dated 3-9-25 Amounting to Rs. 102577=

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.							
Name of Work :- A/R & M/O various Type-III to Type-IV Qtrs. of GAD at Parimahal, Kasumpti, Shimla-9.						Estimated Cost:- 97,282.00	
(SH:- Repair work in Toilet, Bathroom, Kitchen, Providing and fixing Cupboard, White washing/distemping etc in Type-III Set No. 45 Under Parimahal Section).						Earnest Money :- 1,900.00	
(SH:- Repair work in Toilet, Bathroom, Kitchen, Providing and fixing Cupboard, White washing/distemping etc in Type-III Set No. 45 Under Parimahal Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.73	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	913.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)For thickness of tiles 10 mm to 25 mm	26.54	Sqm	50.00	Rupees Fifty Only	Per Square Meter	1327.00
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Of area 3 sq. metres and below	2.00	Nos	300.00	Rupees Three Hundred Only	Each	600.00
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	0.73	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	3942.00
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Nominal mix 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm nominal size)	0.03	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	195.00
6	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	7.40	Sqm	1200.00	Rupees One Thousand Two Hundred Only	Per Square Meter	8880.00
7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	40.44	Sqm	1200.00	Rupees One Thousand Two Hundred Only	Per Square Meter	48528.00


8	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) ordinary closet <b>MAKE ESS ESS or Equivalent.</b>	1.00	Nos.	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
9	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1) SOLID TYPE (a) White plastic seat and cover. <b>Make ESS ESS</b>	1.00	Nos.	1049.36	Rupees One Thousand Forty Nine and Paise Thirty Six Only	Each	1049.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White <b>MAKE ESS ESS</b>	1.00	Nos.	2473.40	Rupees Two Thousand Four Hundred Seventy Three and Paise Forty Only	Each	2473.00
11	Providing and fixing hand faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	875.44	Rupees Eight Hundred Seventy Five and Paise Forty Four Only	Each	875.00
12	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.00	Nos.	200.00	Rupees Two Hundred Only	Each	800.00
13	Providing and fixing C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	1.00	Nos.	600.00	Rupees Six Hundred Only	Each	600.00
14	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	550.00	Rupees Five Hundred Fifty Only	Each	550.00
15	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
16	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden plug with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (E.S) <b>Make ESS ESS or Equivalent.</b>	3.00	Nos.	650.00	Rupees Six Hundred Fifty Only	Each	1950.00
17	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore <b>Make ESS ESS</b>	3.00	Nos.	900.00	Rupees Nine Hundred Only	Each	2700.00

18	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore with 45 cm length	7.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	1050.00
19	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Flexible pipe (a) 32 mm dia	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00
20	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	700.00	Rupees Seven Hundred Only	Each	700.00
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm nominal bore <b>MAKE ESS ESS</b>	9.00	Nos.	900.00	Rupees Nine Hundred Only	Each	8100.00
22	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting chases and making good the all including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	21.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	7350.00
23	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws complete (New work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	3.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	450.00
						<b>Total</b>	<b>97282.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

(T/S No. 9426-27 Dated 3-9-25 Amount to Rs. 1,00,200.00).


  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-80750=00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 ( SH:- Painting work in TypeV set No -23 under Kasumpti section						Earnest Money :-1700=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	350.00	Sqm	10.00	Rupees Ten Only	Per Square Metre	3500.00
2	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	350.00	Sqm	60.00	Rupees Sixty Only	Per Square Metre	21000.00
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	500.00	Sqm	60.00	Rupees Sixty Only	Per Square Meter	30000.00
4	Wall painting (One coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	350.00	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	26250.00
shah	Quoted rates Percentage in words						
						G.Total	80750.00

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 9424-25 dated 3-9-25 Amounting to Rs. 831727

  
Executive Engineer  
Shimla Division No.I,  
HP PWD Shimla-3.


## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost: 94,500.00		
Name of Work :- Restoration of Rain damages on various roads under Shimla Division No.1. (SH:-Removal of Slips at various Rds.)					Earnest Money :-1900.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	90.00	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Meter	94500.00
						Total	94500.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

T/SN<sup>o</sup> 9277-78 dt 1-9-25 Amount 97335=

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:99976=00	
Name of Work :- A/R & M/O to Type VI Qtr set no 17 type - VI at Melhi Shimla ( SH:- Providing stair case in set No 17						Earnest Money :2000=00	
Type - VI Melhi shimla						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections,framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	350.00	Kgs	105.00	Rupees One Hundred Five Only	Per kilo gram	36750.00
2	Providing and fixing stainless steel grills in window ventilaters A- ISI 304 includingn carriage of materials in all leads as per directions on Engineer - in - charge Make jindal .	82.98	Kgs	445.00	Rupees Four Hundred Forty Five Only	Per kilo gram	36926.10
3	Providing and Fixing CPVC pipe for hot and cold water supply fixing wall clamps etc including carriage of materials in all lifts as per directions of Enginner - in - charge .						
(i)	20 mm nominal	9.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Running metre	3150.00
(ii)	25mm nominal	12.00	Rmt	445.00	Rupees Four Hundred Forty Five Only	Running metre	5340.00
(iii)	32mm nominal	12.00	Rmt	550.00	Rupees Five Hundred Fifty Only	Running metre	6600.00
4	Provioding and fixing CPVC plain & brass thread fittings including fixing the pipe including cariage of materials in all leads and lifts as per direction of Enginner - in - charge .20 mm dia						
(i)	Plain union	4.00	Nos	170.00	Rupees One Hundred Seventy Only	each	680.00
(ii)	CPVC plain Tee 20 mmm dia	4.00	Nos	55.00	Rupees Fifty Five Only	each	220.00
(iii)	CPVC brass MTA 20 mm dia	4.00	Nos	160.00	Rupees One Hundred Sixty Only	each	640.00
(iv)	Brass elbow 20 mm dia	10.00	Nos	160.00	Rupees One Hundred Sixty Only	each	1600.00
(v)	Gate valve	3.00	Nos	350.00	Rupees Three Hundred Fifty Only	each	1050.00

(vi)	CPVC brass FTA	5.00	Nos	220.00	Rupees Two Hundred Twenty Only	each	1100.00
5	Providing and fixing CPVC plain & brass thread fittings including fixing the pipe including carriage of materials in all leads and lifts as per direction of Engineer-in-charge 32mm dia						
(i)	Plain union	3.00	Nos	75.00	Rupees Seventy Five Only	each	225.00
(ii)	CPVC plain Tee 32mm dia	3.00	Nos	75.00	Rupees Seventy Five Only	each	225.00
(iii)	Brass elbow 32mm dia	8.00	Nos	220.00	Rupees Two Hundred Twenty Only	each	1760.00
(iv)	CPVC brass FTA	5.00	Nos	300.00	Rupees Three Hundred Only	each	1500.00
(v)	Reducer	4.00	Nos	170.00	Rupees One Hundred Seventy Only	each	680.00
(v)	Gate valve	1.00	Nos	450.00	Rupees Four Hundred Fifty Only	each	450.00
6	Providing and fixing CPVC plain & brass thread fittings including fixing the pipe including carriage of materials in all leads and lifts as per direction of Engineer-in-charge 25mm dia						
(i)	Plain albow	6.00	No	180.00	Rupees One Hundred Eighty Only	each	1080.00
BD	Quoted rates Percentage in words						
						<b>G.Total</b>	99976.10

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance


T/s No 9416-17 dated 3-9-25 amounting to Rs. 102975/=

Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 96,280.00		
Name of Work :- Restoration of rain damages on Fagu to Cheog road KM 0/000 to 5/600 (SH:- C/O Unlined surface drain at Various Rd's in Km 0/000 to 5/600).					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Construction of unlined surface drain of average cross-Section area 0.40 Sqm (zero point four zero square metre) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical specification Clause 307 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Mechanical Means)	3320	Rmt	29.00	Rupees Twenty Nine Only	Per Running Meter	96280.00
						<b>Total</b>	<b>96280.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

TIS No 9.746-97 D + 8/9/25 Am. 27/68.

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,855.00		
Name of Work :- Restoration of Rain Damages in Baldeyan Section under Mashobra Sub Division. (SH:- Hiring of Excavator cum roller for removal of slips on various roads of Baldeyan section). <i>Shimla Mandi Road R.O. 7/00 to 20/00, Baldeyan Dhara-pur Road R.O. 1/00 to 9/00, Kanda Muktabhi Road R.O. 8/00 to 13/00.</i>					Earnest Money :- 2,000.00		
					Time:- One Month		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minium Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximun usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.10	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99855.00
						<b>Total</b>	<b>99855.00</b>

**CONDITION:**

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

(T/S No. 9744-25 Dated ... 8-9-25 ... Amount to Rs. 1,028.51.....).


  
Executive Engineer,  
Shimla Division No. I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:98,403 .00	
Name of Work :- Improvement of Bhatta Kufer to AIMSS road km.0/00 2/400.(SH:-Improvement of passing place on encroached portion at Rd. 0/350 i/c Rec slab and safety railings.)						Earnest Money :-2000 .00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 & 1202 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	156.49	Kgs.	95.00	Rupees Ninety Five Only	Per Kilogram	14867.00
2	Providing and laying in position cement concrete specified grade including the cost of centering and shuttering.All work up to plinth level. 1:1.5:3 (1 cement :1.5: Sand : 3 graded stone aggregate 20 mm nominal size and curing complete carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3.28	Cum	7600.00	Rupees Seven Thousand Six Hundred Only	Per Cubic Metre	24928.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	535.36	Kgs.	100.00	Rupees One Hundred Only	Per Kilogram	53536.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	4.83	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	5072.00
						<b>Total</b>	<b>98403.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

T/S No 9770-41 Dated 8-9-25 amounting to Rs. ~~1,01,355/-~~

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.


## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.				Estimated Cost:- 99,750.00			
Name of Work :- Restoration of Rain Damages in Baldeyan Section under Mashobra Sub Division. (SH:- Hiring of Excavator cum roller for removal of slips on Baldeyan to Shenal road Km. 0/00 to 4/720, Sadhora to Mohanpur road in Km. 0/00 to 6/525 and Mohanpur Nallah to Kiar Koti in Km. 0/00 to 2/00).				Earnest Money :- 2,000.00			
				Time:- One Month			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minium Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximun usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
						<b>Total</b>	<b>99750.00</b>

**CONDITION:**

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

(T/S No. 9742-43. Dated 8-9-25. Amount to Rs. 102743..)

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.


## DRAFT SCHEDULE OF QUANTITY

Tender inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,460.00		
Name of Work :-- Restoration of Rain damages on Koti to Satlai Road in Km. 0/00 to 15/00. (SH :-Removal of slips at RDs 3/910 to 12/675).					Earnest Money :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	497.30	cum	200.00	99460	Per Cubic Metre	99460.00
						<b>Total</b>	<b>99460.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DNIT approved for Rs.99,460/- Only (Rupees Ninety nine Thousand four hundred sixty only ) vide DNIT Register Sr.No..... the financial year 2025-26.T/S No.        Dated                    amounting to Rs.

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 97,350.00	
Name of Work :- Annual Repair and Maintenance road on Mashobra to Bhaikhlity road in Km. 0/00 to 18/300. (SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km 6/00 to 12/000 )						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	118.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	97350.00
						<b>Total</b>	<b>97350.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-** 1. All the material will procured by the contractor him self.

2. Rates should be quoted for all heights including all leads and lifts.

3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.



<b>SCHEDULE OF QUANTITY</b>							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 96,525.00	
Name of Work :- Annual Repair and Maintenance road on Shimla Mandi road in Km 6/000 to 22/00 (SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km 6/00 to 22/000 )						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	117.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	96525.00
						<b>Total</b>	<b>96525.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-** 1.All the material will procured by the contractor him self.

2. Rates should be quoted for all heights including all leads and lifts.

3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per

Indian standard in the market should confirm to bureau of indian standars

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.  



## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 94,875.00		
Name of Work :- Annual Repair and Maintenance road on Fagu to Cheog road in Km. 0/00 to 7/00 (SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km 0/00 to 5/000)					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	115.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	94875.00
						<b>Total</b>	<b>94875.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-** 1. All the material will procured by the contractor him self.

2. Rates should be quoted for all heights including all leads and lifts.

3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per


  
 Executive Engineer  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 98,175.00	
Name of Work :- Annual Repair and Maintenance road on Challanda to Piran road in Km. 0/000 to 28/000(SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km 22/00 to 28/000) )						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	119.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	98175.00
						<b>Total</b>	<b>98175.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-** 1.All the material will procured by the contractor him self.


2. Rates should be quoted for all heights including all leads and lifts.

3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer  
 Shimla Division No.1,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 97,890.00	
Name of Work :- A/R & M/O Shimla Mandi road Km. 6/00 to 22/000. (SH:- Providing and Fixing of Road Studs ( Valley side ) at RD 6/000 to 6/175).						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and Fixing cat eye make (3m) of size 100x20mm made of heavy duty body shall be molded dual ASA/Acyclic Styrene Acrylonitrile or HP/High impact polystyreaon on ABS having electronically welded micro prisnatics lens with abrasion resistant coating as approved by Engineer-in-Charge. The road stud shall support a load of 13635 bt tesdted in accordance with ASTMD4280. The slope of retro reflective surface shall be 35+/-5degree to hences. The reflective panel on both side with at least 12cm of each area side. Te luminance intesity should be as pae the specification ASTM as recommended in BS-S873 part 41973 as per approved sample and manufacture by the Engineer-in-Charge including carriage of material within all leads and lifts the rate are inclusive of octroi, ryalty, malkana GST, toll tax, sale tax or other taxes imposed by the Government.	251.00	Nos	390.00	Rupees Three Hundred Ninety Only	Per Each	97890.00
						<b>Total</b>	<b>97890.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY


<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>					<b>Estimated Cost:- 99,450.00</b>		
<b>Name of Work :- A/R &amp; M/O Shimla Mandi road Km. 6/00 to 22/000. (SH:- Providing and Fixing of Road Studs</b>					<b>Earnest Money :-2000.00</b>		
<b>( Valley side ) at RD 6/675 to 6/870).</b>					<b>Time:- One Month.</b>		
Sr. No.	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and Fixing cat eye make (3m) of size 100x20mm made of heavy duty body shall be molded dual ASA/Acyclic Styrene Acrylonitrile or HP/High impact polystyreaon on ABS having electronically welded micro prisnatics lens with abrasion resistant coating as approved by Engineer-in-Charge. The road stud shall support a load of 13635 bt tesdted in accordance with ASTMD4280. The slope of retro reflective surface shall be 35+/-5degree to hences. The reflective panel on both side with at least 12cm of each area side. Te luminance intesity should be as pae the specification ASTM as recommended in BS-S873 part 41973 as per approved sample and manufacture by the Engineer-in-Charge including carriage of material within all leads and lifts the rate are inclusive of octroi, rayality, malkana GST, toll tax, sale tax or other taxes imposed by the Government.	255.00	Nos	390.00	Rupees Three. Hundred Ninety Only	Per Each	99450.00
						<b>Total</b>	<b>99450.00</b>
Quated rates Percentage in figures							
Quoted rates Percentage in words						<b>G.Total</b>	

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

<b>SCHEDULE OF QUANTITY</b>							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,000.00	
Name of Work :- Annual Repair and Maintenance road on Baldiyan Dharampur road in Km. 0/000 to 7/00 & Nauti to Thaila road Km 0/000 to 7/300 (SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km 0/00 to 7/000 & 0/000 to 7/300 )						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	120.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	99000.00
						<b>Total</b>	<b>99000.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

- CONDITION:-** 1. All the material will procured by the contractor him self.
2. Rates should be quoted for all heights including all leads and lifts.
3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.


## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 95,700.00		
Name of Work :- Annual Repair and Maintenance road on Internal road of kasumpti road colony road in Km. (SH:- Supplying and Stacking Pot seal bags cold mix Various Rds between Km ).					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	116.00	No	825.00	Rupees Eight Hundred Twenty Five Only	Per Each	95700.00
						<b>Total</b>	<b>95700.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-** 1.All the material will procured by the contractor him self.

2. Rates should be quoted for all heights including all leads and lifts.

3. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,460.00		
Name of Work :-- Restoration of Rain damages on Koti to Satlai Road in Km. 0/00 to 15/00. (SH :-Removal of slips at RDs 3/910 to 12/675).					Earnest Money :- 2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	497.30	cum	200.00	99460	Per Cubic Metre	99460.00
						<b>Total</b>	<b>99460.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

### CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>						<b>Estimated Cost:- 99,200.00</b>	
<b>Name of Work :- Restoration of Rain Damages on various roads Kanda Mool Koti road in Km. 4/00 to 13/240, Baldeyan to Dharampur road in Km. 0/00 to 10/00, Baldeyan to Shannel road in Km. 0/00 to 4/720, Shimla to Mandi road in Km. 0/00 to 22/00. (SH:- Removal of slips at various roads under Baldeyan Section).</b>						<b>Earnest Money :- 2,000.00</b>	
						<b>Time:- One Month</b>	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	496.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99200.00
						<b>Total</b>	<b>99200.00</b>

(T/S No..... Dated ..... Amount to  
Rs.....).

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.


352

6

### DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,200.00	
Name of Work :- Restoration of Rain Damages on various roads Kanda Mool Koti road in Km. 4/00 to 13/240, Baldeyan to Dharampur road in Km. 0/00 to 10/00, Baldeyan to Shannel road in Km. 0/00 to 4/720, Shimla to Mandi road in Km. 0/00 to 22/00. (SH:- Removal of slips at various roads under Baldeyan Section).						Earnest Money :- 2,000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	496.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99200.00
						<b>Total</b>	<b>99200.00</b>


DNIT approved for Rs. 99,200/- Only (Rupees Ninety nine Thousand Two Hundred only) vide DNIT Register Sr.No..... the financial year 2025-26. (T/S No..... Dated ..... Amount to Rs.....).

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>						<b>Estimated Cost:- 99,200.00</b>	
<b>Name of Work :- Restoration of Rain Damages on various roads Kanda Mool Koti road in Km. 4/00 to 13/240, Baldeyan to Dharampur road in Km. 0/00 to 10/00, Baldeyan to Shannel road in Km. 0/00 to 4/720, Shimla to Mandi road in Km. 0/00 to 22/00. (SH:- Removal of slips at various roads under Baldeyan Section).</b>						<b>Earnest Money :- 2,000.00</b>	
						<b>Time:- One Month</b>	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	496.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99200.00
						<b>Total</b>	<b>99200.00</b>


(T/S No..... Dated ..... Amount to  
Rs.....).

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>						<b>Estimated Cost:- 99,200.00</b>	
<b>Name of Work :- Restoration of Rain Damages on various roads Kanda Mool Koti road in Km. 4/00 to 13/240, Baldeyan to Dharampur road in Km. 0/00 to 10/00, Baldeyan to Shannel road in Km. 0/00 to 4/720, Shimla to Mandi road in Km. 0/00 to 22/00. (SH:- Removal of slips at various roads under Baldeyan Section).</b>						<b>Earnest Money :- 2,000.00</b>	
						<b>Time:- One Month</b>	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	496.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99200.00
						<b>Total</b>	<b>99200.00</b>

(T/S No..... Dated ..... Amount to  
Rs.....).


  
 Executive Engineer  
 Shimla Division No. I,  
 HP PWD Shimla-3.

### SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost: 98,700.00		
Name of Work :--Restoration of Rain damages to various road under Bharari Section. (SH:-Hiring of Excavator cum loader for Removal of Slips in various RDs Bhot Kakar Bhogora road km.0/900 to 0/920. 1/450 to 1/600.					Earnest Money :-2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	94.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per hour	98700.00
						Total	98700.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	


**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWID Shimla-3.

### SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-</b>					<b>Estimated Cost:- 99,000.00</b>		
<b>Name of Work :- Restoration of Rain Damages on Nariga pul to Jagher road Km 0/000 to 1/660</b>					<b>Earnest Money :- 2,000.00</b>		
<b>).(SH:- Removal of slips at Rd 0/000 to 1/660).</b>					<b>Time:- One Month</b>		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	495.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99000.00
						<b>Total</b>	<b>99000.00</b>

  
 Executive Engineer,  
 Shimla Division No. 1,  
 HP PWD Shimla-3.

## DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.				Estimated Cost:- 99,967.00			
Name of Work :- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla. (SH:-				Earnest Money :- 2,000.00			
Providing and fixing cupboard in Type-IV Set No. 19 under Kasumpti Section).				Time:- One Month.			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick <b>HDMR Board</b> water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	30.19	Sqm.	2200.00	Rupees Two Thousand Two Hundred Only	Per Square Meter	66418.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.30	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square meter	8755.00
3	Providing and fixing <b>HDMR Ply wood</b> lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	12.96	Sqm	900.00	Rupees Nine Hundred Only	Per Square Meter	11664.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	54.00	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	3510.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	32.00	Nos	50.00	Rupees Fifty Only	Each	1600.00
6	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	32.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	4800.00


363

7	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i) 2nd Pine wood	0.035	Cum	92000.00	Rupees Ninety Two Thousand Only	Per Cubic Metre	3220.00
						<b>Total</b>	<b>99967.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved for Rs. 99,967/- Only (Rupees Ninety nine Thousand Nine Hundred Sixty seven only ) vide DNIT Register Sr.No..... the financial year 2025-26. (T/S No..... Dated ..... Amount to Rs.....).

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,939.00		
Name of Work :- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla. (SH: Providing and fixing cupboard in Type-IV Set No. 45 under Kasumpti Section).					Earnest Money :- 2,000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick <b>HDMR Board</b> water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	30.90	Sqm	2200.00	Rupees Two Thousand Two Hundred Only	Per Square Meter	67980.00
2	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	5.40	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	7290.00
3	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.32	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square meter	3672.00
4	Providing and fixing <b>HDMR Ply wood</b> lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	10.64	Sqm	900.00	Rupees Nine Hundred Only	Per Square Meter	9576.00
5	Providing and fixing <b>Ply wood</b> lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	4.32	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	2592.00
6	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	18.60	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	1209.00

7	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	22.00	Nos	50.00	Rupees Fifty Only	Each	1100.00
8	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	22.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	3300.00
9	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 2nd Pine wood	0.035	Cum	92000.00	Rupees Ninety Two Thousand Only	Per Cubic Metre	3220.00
						<b>Total</b>	<b>99939.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


(T/S No..... Dated ..... Amount to Rs.....).

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 36,900.00	
NAME OF WORK:- Construction of Bharari to Padhai Mata road Km 0/000 to 1/800 in Distt Shimla (HP) ( SH:- Preparation of Technical Sanction , Working Estimate and DNIT).						Earnest Money :- 800.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Technical Sanction. The work will we carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to division office and there after approval from competent authority.	1.800	Kms.	7000.00	Rupees Seven Thousand Only	Per Kilometer	12600.00
2	Preparation of Working Estimate. The work will we carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to division office and there after approval from competent authority.	1.800	Kms.	7000.00	Rupees Seven Thousand Only	Per Kilometer	12600.00
3	Preparation of DNIT. The work will we carried in accordance with latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to division office and there after approval from competent authority.	1.800	Kms.	6500.00	Rupees Six Thousand Five Hundred Only	Per Kilometer	11700.00
						<b>Total</b>	<b>36900.00</b>
Quoted rates Percentage in figures							
Quoted rates Percentage in words							
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>				<b>Estimated Cost:- 99,750.00</b>			
<b>Name of Work :- Restoration of Rain Damages on various road under Fagu section. (SH:- Hiring of Excavator cum loader for removal of slips in Fagu to Cheog road km 0/00 to 5/00, Cheog to Dharech road km 0/00 to 7/00, Talai to Dehna road km 0/00 to 2/500, Talai to Dehna road km 0/00 to 2/00, Bangapani to Chatog road km.0/00 to 2/00 at various RDs).</b>				<b>Earnest Money :- 2,000.00</b>			
				<b>Time:- One Month.</b>			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximun usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burns, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hour	99750.00
						<b>Total</b>	<b>99750.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3.