Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

No PW/TDD/GA/Tender/2025-26 7650-7710 Dated: - 15-05-2025
To

The Executive Engineer(IT Cell),
Nigam Vihar HP Shimla-171002.

Subject - Publication of Tender Notice

Enclosed please find herewith the tender notice of various works as given in the Notice Inviting Tender . As per Notification Pr.Secy.(PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th Jyly 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website

ECL: -Notice Inviting Tender/ Scheduled of Quantity and Certificate.

Yours faithfully,

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Copy forwarded to the following for information: -

1. The Engineer-in-Chief HPPWD., Shimla
2. The Chief Engineer (HZ), HP.PWD, Hamirpur
3. The Deputy Commissioner Hamirpur
4. The Superintending Engineer, 8th Circle HP.PWD, Hamirpur
5. The B.D.O Tauni Devi
6. All the Assistant Engineer working in this Division.
7. Notice Board.
8. AB & DB.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/ emergency in calling these tender without press vide this office letter No. No. PW/TDD/GA/Tender/2025-26 7650-7700 dated 15-09-2025

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION

H.P. Public Works Department, TAUNI DEVI 177023

Telephone. 01972-278422, e.mail: ee-tou-hp@gov.in

Tender Notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Tauni Devi Division, H.P. PWD, Tauni Devi on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/firms enlisted in HP PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the HP General Sales Tax Act 1968 so as to reach in his office on or before **23.09.2025 up to 10.30 AM**. And the same shall be opened on the same day at **11.00 AM** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) up to**22.09.2025** up **to 5.00 PM** and the application for issue of tender form shall be received up **22.09.2025 up to 12.00 PM**. The earnest money in the shape of NSC/Time deposit account/saving account of the post office in HP duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S No	Name of work	Estimated cost	Earnest money	Time
1	Restoration of rain damages on Garne-Da Galu to Kuther via Panyala Km. 0/0 to 3/915(SH:- Hiring of excavtor cum loader for removal of slips Km. 0/0 to 1/500, clearance of drains and dressing of berms in Km. 0/250 to 2/500)	85883.00	1700.00	Two Months.
2	Restoration of rain damages on link road to village Sarohal Km. 0/00 to 1/00 (SH:- C/o PCC drain at Various RD,s) Deposit work	96440.00	2000.00	Two Months.
3	Restoration of rain damages on link road Chabhutra Amb Gahra Salasi road Km. 0/0 to 4/00 (SH:-Providing and laying cement concrete pavement at RD 3/210 to 3/237)	99451.00	2000.00	Two Months
4	Restoration of rain damages on Chabutra Amb Gahra to Nihari Darghod Balhi road Km. 0/00 to 4/00 (SH:- ROFD from RD 0/740 to 0/802)	98662.00	2000.00	Two Months.
5	Stock storage HPPWD., Sub-Division Sujanpur (SH:- Providing supplying and stacking of Machine mde bricks(1st Class).	87500.00	1800.00	Two Months
6	Restoration of rain damages on link road Jandroo to village Ropa Km. 0/00 to 1/00 (SH:- C/o wing wall at RD 0/128.50 to 0/131)	90601.00	1900.00	Two Months.
7	Restoration of rain damages on link road Chabhutra Amb Gahra Salasi road Km. 0/0 to 4/00 (SH:-Providing and laying cement concrete pavement at RD 3/237 to 3/264)	99451.00	2000.00	Two Months.
8	Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road Km. 0/0 to 7/300 (SH:- Providing patch work from 3/050 to 4/00	97667.00	2000.00	Two Months.
9	C/o link road Bharmar to Bhaleth via Miyana Km. 0/0 to 4/00 (SH:- C/o D/S side toe wall at RD 2/645 along with laying of 900mm dia RCC pipe (Deposit work)	98628.00	2000.00	Two Months
10	Stock storage HPPWD., Sub-Division Kakkar(SH:- Providing supplying and stacking of Machine mde bricks(1st Class).	87500.00	1800.00	Two Months.
11	Restoration of rain damages on link road Jandroo to village Ropa Km. 0/00 to 1/00 (SH:- C/o wing wall at RD 0/136.50 to 0/141.50)	95576.00	2000.00	Two Months
12	Restoration of rain damages on link road Chabhutra Amb Gahra Salasi road Km. 0/0 to 4/00 (SH:-ROFD from RD 3/220 to 3/360)	99134.00	2000.00	Two Months.
13	Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra (SH:- Dismenting floor slab for providing and fixing tiles and applying 2mm thick plaster of parts putty at various locations) Deposit work)	98267.00	2000.00	Two Months
14	Restoration of rain damages on Various roads undedr Sujanpur Sub-Division HPPWD., Sujanpur (SH:- Hiring of JCB /Front end loader for removal of slips/clearing of drain, maintenance of road side shoulder(Chabutra Section)	99750.00	2000.00	Two Months

Scanned with CamScanner

15	C/o link road Bharmar to Bhaleth via Miyana Km. 0/0 to 4/00 (SH:- C/o D/S toe wall upto road level and construction of cath pit on upstream side of the road at RD 2/645) (Deposit work)	99844.00	2000.00	Two Months.
16	Upgradation of link road from Utpur to Bakkar Khad via Harizan Basti Kuthar from Km. 0/00 to 4/00 (SH:- Preparation of Detail Report from Km 0/00 to 2/850) Under Nabard	97750.00	2000.00	Two Months
17	Construction of link road from Utpur (Kaloh) to Bakkar Khad via Tap from Km. 0/00 to 4/500 (SH:- Prepartion of Detailed Report from Km. 2/850 to 4/00, CBR,BBD test and pavement design for 4/00 Km. road length (Under NABARD)	99450.00	2000.00	Two Months
18	Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra (SH:- Dismenting floor slab for providing and fixing tiles and applying 2mm thick plaster of parts putty at various locations) Deposit work)	99028.00	2000.00	Two Months
19	Restoration of rain damages on link road to village Sarohal Km. 0/00 to 1/00 (SH:- Repair of pot holes at various RD's) Deposit work	99975.00	2000.00	Two Months.
20	Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road Km. 0/0 to 7/300 (SH:- Providing patch work from 4/050 t o 5/00	99824.00	2000.00	Two Months.

Certifed that above works are of urgent nature and tenders are being called in exigency of works and in public interest.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Garne-Da-Galu to kuther via Panyala km. 0/0 to 3/915.(SH:-Hiring of excavator cum loader for removal of slips km. 0/0 to 1/500, clearance of drains and dressing of berms in km. 0/250 to 2/500).

Estimated Cost:-	Rs. 85583.00
Earnest Money:-	Rs. 1700.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.5mtr. (one paint five metre) and lead up 1000m(one thousand metre) as per technical specification 302.3.5 and 1611 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.he rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	610.00	140.30	Rupees one hundred forty and paise thirty only	Per cubic metre	85583.00
					Total	85583.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 34 for the year 2025-26 duly approved for ~~Rs.85,583/-~~ Eighty five thousand five hundred eighty three) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Scanned with CamScanner

2

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Sarohal km. 0/00 to 1/00.(SH:- C/O PCC drain at various RD's). Work C Deposit

Estimated Cost:-	Rs. 96440.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	12.50	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre	3627.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	18.75	4950.00	Rupees four thousand nine hundred fifty only	Per Cubic metre	92813.00
					Total	96440.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 71 for the year 2025-26 duly approved for Rs.96,440/- (Ninety six thousand four hundred forty) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

(3)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Chabutra Amb Gahra Salasi road km. 0/0 to 7/500.(SH:- P/L cement concrete pavement at RD. 3/210 to 3/237).

Estimated Cost:-	Rs. 99451.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Loosening of the ground upto a level of 300mm(three hundred millimeters) below the sub-grade level, watered, graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub-grade construction as per technical specification clause 303.5.2 and as per direction of Engineer-in-Charge.as per direction of Engineer- in -Charge, Including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	12.76	47.80	Rupees forty seven and paise eighty only	Per square metre	610.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads and lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	8.51	1900.00	Rupees one thousand nine hundred only	Per cubic metre	16169.00
3	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1.5:3 (one cement : one point five coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	12.76	6479.00	Rupees Six thousand four hundred seventy nine ohly	Per cubic metre	82672.00
					Total	99451.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 80 for the year 2025-26 duly approved for Rs. 99,451/- (Ninety nine thousand four hundred fifty one) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Chabutra Amb Gahra to Nkiari Darghod Balhi road km. 0/00 to 4/00.(SH:- ROFD from RD. 0/740 to 0/802).

Estimated Cost:-	Rs. 98662.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e.38.99/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only per cubic metre) amounting to Rs. 11,588/- only.	254.12	388.25	Rupees three hundred eighty eight and paise twenty five only	Per cubic metre	98662.00
					Total	98662.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 83 for the year 2025-26 duly approved for Rs. 98,662/-
(Ninety eight thousand six hundred sixty two) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Stock Storage HP:PWD., Sub-Division Sujanpur. (SH:- Providing Supplying and stacking of Machine made bricks (1st class).

Estimated Cost:-	Rs. 87500.00
Earnest Money:-	Rs.1800.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing Supply and stacking in uniform stacks Machine Made modular 1st class bricks of good quality and durability including entire carriage of material within all leads and lifts and as per drawings and technical specifications as per the direction of the Engineer-in-charge within all leads and lifts and other incidentals. he rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2500.00	35.00	Rupees thirty five only	Each	87500.00
					Total	**87500.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 85 for the year 2022-23 duly approved for Rs 87,500/-(Eighty seven thousand five hundred only) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

(5)

Scanned with CamScanner

(6)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Jandroo to village Ropa km. 0/00 to 1/00.(SH:- C/O wing wall at RD. 0/128.50 to 0/131).

Estimated Cost:-	Rs. 90601.00
Earnest Money:-	Rs. 1900.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	9.54	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	2768.00
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	19.90	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	84575.00
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	2.00	278.00	Rupees two hundred seventy eight only	Each.	556.00
4	Back filling with granular material behind abutements, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, Including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	3.86	700.00	Rupees seven hundred only	Per cubic metre	2702.00
					Total	**90601.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 179 ..... for the year 2025-26 duly approved for Rs. 90,601/-(Ninety thousand six hundred one) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(7)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Chabutra Amb Gahra Salasi road km. 0/0 to 4/000.(SH:- P/L cement concrete pavement at RD. 3/237 to 3/264).

Estimated Cost:-	Rs. 99451.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Loosening of the ground upto a level of 300mm(three hundred millimeters) below the sub-grade level, watered, graded and compacted in layers to meet requirement of table 300.1 and 300.2 for sub-grade construction as per technical specification clause 303.5.2 and as per direction of Engineer-in-Charge as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	12.76	47.80	Rupees forty seven and paise eighty only	Per square metre	610.00
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads and lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	8.51	1900.00	Rupees one thousand nine hundred only	Per cubic metre	16169.00
3	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1.5:3 (one cement : one point five coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the-Government.	12.76	6479.00	Rupees Six thousand four hundred seventy nine ohly	Per cubic metre	82672.00
					Total	99451.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....81..... for the year 2025-26 duly approved for Rs. 99,451/-(Ninety nine thousand four hundred fifty one) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Scanned with CamScanner

(8)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 7/300.(SH:- Providing patch work from RD. 3/050 to 4/000).

Estimated Cost:-	Rs. 97667.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achievethe desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	4.52	2110.00	Rupees two thousand one hundred ten only	Per cubic metre	9537.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	255.45	345.00	Rupees three hundred forty five only	Per square metre	88130.00
					Total	**97667.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 38 for the year 2025-26 duly approved for Rs.97,667/- (Ninety seven thousand six hundred sixty seven) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Draft Schedule of Quantity

NAME OF WORK:- C/O link road Bharmar to Bhaleth via Miyana km. 0/0 to 4/00.(SH:- C/O D/S side toe wall at RD. 2/645 along with laying of 900mm dia RCC hume pipe).(Deposit work).

Estimated Cost:-	Rs. 98628.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals	14.14	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre	4103.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	9.30	4950.00	Rupees four thousand nine hundred fifty only	Per Cubic metre	46035.00
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar joints with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 900mm(nine hundred millimeters) dia as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	10.00	3850.00	Rupees three thousand eight hundred fifty only	Per running metre	38500.00
4	Removal of land slide in hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material within all leads and lifts as per direction of the Engineer-in-Charge as per HP:PWD., specification including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	60.00	90.00	Rupees ninety only	Per cubic metre	5400.00
5	Back filling with granular material behind abutements, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	6.12	750.00	Rupees seven hundred fifty only	Each	4590.00
					Total	**98628.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 63 for the year 2025-26 duly approved for Rs 98,628/-(Ninety eight thousand six hundred twenty eight) Only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

(9)

Scanned with CamScanner

(10)

Draft Schedule of Quantity

NAME OF WORK:- Stock Storage HP:PWD., Sub-Division Kakkar. (SH:- Providing Supplying and stacking of Machine made bricks (1st class).

Estimated Cost:-	Rs. 87500.00
Earnest Money:-	Rs.1800.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing Supply and stacking in uniform stacks Machine Made modular 1st class bricks of good quality and durability including entire carriage of material within all leads and lifts and as per drawings and technical specifications as per the direction of the Engineer-in-charge within all leads and lifts and other incidentals. he rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2500.00	35.00	Rupees thirty five only	Each	87500.00
					Total	**87500.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 84 for the year 2025-26 duly approved for Rs.87,500/-(Eighty seven thousand five hundred only) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Jandroo to village Ropa km. 0/00 to 1/00.(SH:- C/O wing wall at RD. 0/136.50 to 0/141.50).

Estimated Cost:-	Rs. 95576.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax. GST or other taxes imposed by the Government	9.39	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	2725.00
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government	20.76	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	88230.00
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government	3.00	278.00	Rupees two hundred seventy eight only	Each.	834.00
4	Back filling with granular material behind abutements, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.41	700.00	Rupees seven hundred only	Per cubic metre	3787.00
					Total	95576.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 177 for the year 2025-26 duly approved for Rs. 95,576/- (Ninety five thousand five hundred seventy six) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(12)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Chabutra Amb Gahra Salasi road km. 0/00 to 4/00.(SH:- ROFD from RD. 3/220 to 3/360).

Estimated Cost:-	Rs. 99134.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603 1,1603 2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. (Recovery of useful stone i.e 37.94/-cubic metre shall be made from the contractor @ Rs. 300/-(three hundred only)per cubic metre) amounting to Rs. 11,382/- only.	291.51	340.07	Rupees three hundred forty and paise seven only	Per cubic metre	99134.00
					Total	**99134.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 82 for the year 2025-26 duly approved for Rs. 99,134/- (Ninety nine thousand one hundred thirty four) only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(13)

Draft Schedule of Quantity

NAME OF WORK:- Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra. (SH:- Dismentling floor slab for providing and fixing tiles and applying 2mm thick plaster of paris putty at various locations). (Deposit work).

Estimated Cost:-	Rs. 98267.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50mtr. (fifty metre) lead, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	334.38	249.02	Rupees two hundred forty nine and paise two only	Per Square metre	83267.00
2	Providing and laying plaster of paris putty of 2mm (two millimeters) thickness over plastered surface to prepare the surface even and smooth complete(Birla white putty), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	150.00	100.00	Rupees one hundred only	Per Square metre	15000.00
					Total	98267.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 45 for the year 2025-26 duly approved for Rs.98.267/- (Ninety eight thousand two hundred sixty seven) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(14)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various roads under Sujanpur Sub-Division, HP:PWD., Sujanpur.(SH:- Hiring of JCB/front end Loader for removal of slips/clearing of drain, maintenance of road side shoulder).(Chabutra Section).

Estimated Cost:-	Rs. 99750.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearence of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully componsated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95.00	1050.00	Rupees one thousand fifty only	Per hour	99750.00
					Total	99750.00

Terms and Condition

1. The contractor shall be responsible for any kind of breakage in the meachinery and accident happens during working hours.
2. Nothing shall be paid for idle hours
3. All bear and tear and POL charges are to be born by the contractor.

DNIT No.....18..... for the year 2025-26 duly approved for Rs. 99,750/-(Ninety nine thousand seven hundred fifty) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(15)

Draft Schedule of Quantity

NAME OF WORK:- C/O link road Bharmar to Bhaleth via Miyana km. 0/0 to 4/00.(SH:- C/O D/S toe wall upto road level and construction of cath pit on upstream side of the road at RD. 2/645).(Deposit work).

Estimated Cost:-	Rs. 99844.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	11.78	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre	3418.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement three sand six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	19.48	4950.00	Rupees four thousand nine hundred fifty only	Per Cubic metre	96426.00
					Total	99844.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 64 for the year 2025-26 duly approved for Rs. 99,844/-(Ninety nine thousand eight hundred forty four) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Upgradation of link road from Utpur to Bakkar Khad via Harizan Basti Kuthar from Km 0/00 to 4/00 (SH:- Preparation of Detailed Report from KM 0/00 to 2/850) (Under NABARD)

Estimated Cost:- Rs.97750.00
Earnest Money:- Rs.2000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Preparation of detailed project report complete in all respect in manuscript form and submission of the same to higher office, the same may be corrected as desired and directed by the Engineer-in-Charge complete in all respect. After approval same should be submitted in five copies duly computerised along with soft copy complete in all respect as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2.85	35000.00	Rupees thirty five thousand and paise zero only.	Per kilometre	99750.00
					Total	99750.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 48 for the year 2025-26 duly approved for Rs. 97,750/- (Rupees ninety seven thousand seven hundred fifty) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Scanned with CamScanner

17

Draft Schedule of Quantity

NAME OF WORK:- Construction of link road from Utpur(Kaloh) to Bakkar Khad via Tap from Km 0/00 to 4/500. (SH:- Preparation of Detailed Report from KM 2/850 to 4/00, CBR, BBD test and Pavement design for 4/00 km road length) (Under NABARD)

				Estimated Cost:-	Rs.99450.00	
				Earnest Money:-	Rs.2000.00	
				Time:-	Two Months	
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Preparation of detailed project report complete in all respect in manuscript form and submission of the same to higher office, the same may be corrected as desired and directed by the Engineer-in-Charge complete in all respect. After approval same should be submitted in five copies duly computerised along with soft copy complete in all respect as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	1.15	35000.00	Rupees thirty five thousand and paise zero only.	Per kilometre	40250.00
2.00	CBR value and pavement design of crust as per IRC: 137-2012/sp-72-2015(4 samples at each kilometer) for both flexible and rigid pavement, submission of the same to higher office, the same may be corrected as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	16.00	3000.00	Rupees three thosuand paise zero only.	Per kilometre	48000.00
3.00	B.B.D test for pavement design of crust as per IRC: 81-1997 (@ 1 samples at each kilometre) submission of the same to higher office, the same may be corrected as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	4.00	2800.00	Rupees two thousand eight hundred and paise zero only.	Per kilometre	11200.00
					Total	99450.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 49 for the year 2025-26 duly approved for Rs. 99,450/- (Rupees ninety nine thousand four hundred fifty) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

(18)

Draft Schedule of Quantity

NAME OF WORK:- Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra. (SH:- Dismentling floor slab for providing and fixing tiles and applying 2mm thick plaster of paris putty at various locations). (Deposit work).

Estimated Cost:-	Rs. 99028.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50mtr. (fifty metre) lead, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	220.98	249.02	Rupees two hundred forty nine and paise two only	Per Square metre	55028.00
2	Providing and laying plaster of paris putty of 2mm (two millimeters) thickness over plastered surface to prepare the surface even and smooth complete(Birla white putty), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	440.00	100.00	Rupees one hundred only	Per Square metre	44000.00
					Total	99028.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 74 for the year 2025-26 duly approved for Rs.99,028/- (Ninety nine thousand twenty eight) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

(19)

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Sarohal km. 0/00 to 1/00.(SH:- Repair of pot hole at various RD's). (Deposit work).

			Estimated Cost:-		**Rs. 99975.00**	
			Earnest Money:-		**Rs. 2000.00**	
			Time:-		**Two Months**	
Sr.No.	**Description of Items**	**Qty.**	**Rate**		**Unit**	**Amount**
			In Fig.	**In Words**		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-In-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	225.16	340.00	Rupees three hundred forty only	Per square metre	76554.00
2	Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	11.26	2080.00	Rupees two thousand eighty only	Per Cubic metre	23421.00
					Total	**99975.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 77 for the year 2025-26 duly approved for Rs 99,975/- Ninety nine thousand nine hundred seventy five) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 7/300.(SH:- Providing patch work from RD. 4/050 to 5/00).

Estimated Cost:-	Rs. 99824.00
Earnest Money:-	Rs. 2000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm)(fifty three millimeter to zero point zero seven five millimeter) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achievethe desired density, complete as per specifications and directions of Engineer-in-Charge. including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	4.52	2110.00	Rupees two thousand one hundred ten only	Per cubic metre	9537.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	261.70	345.00	Rupees three hundred forty five only	Per square metre	90287.00
					Total	99824.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 39 for the year 2025-26 duly approved for Rs.99,824/- (Ninety nine thousand eight hundred twenty four) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner