

Himachal Pradesh  
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2025-2026-

10698-92

Dated:-

22/9/25

To

The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.


Subject :-

Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.

  
Executive Engineer,  
Shimla Division No-1.,  
HPPWD, Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4<sup>th</sup> Circle HPPWD Shimla .


  
Executive Engineer,  
Shimla Division No-1.,  
HPPWD, Shimla-3.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- |  |                                   |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 30-09-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:-            | 30-09-2025 12:00 PM upto 4:00 PM  |
| 3. Date of receipt of tender:-                       | 01-10-2025 .up to 10:30 AM        |
| 4. Date of opening of tender:-                       | 01-10-2025 up to 11:00 AM         |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O various Type-I to type-VI GAD Residential qtrs. At kasumpti Shimla (SH:- Providing and fixing accessories and white washing in type-II set No.649 under kasumpti section)	99821/-	2000/-	350/-	30 days	Class-D
2	Restoration of Rain Damages on various roads under Bharari section (SH:- Hiring of Excavator cum loader for removal of slips in various Rds).	98700/-	2000/-	350/-	30 days	Class-D
3	Restoration of Rain Damages on koti Junga road km. 0/00 to 12/405 (SH:- C/O B/wall between Rd. 1/090 to 1/094.40).	99889/-	2000/-	350/-	30 Days	Class-D
4	Restoration of Rain Damages on various roads to Fagu to Cheog in km. 0/00 to 5/600, Talai to Dena in km. 0/00 to 2/555, Talai to Kadrab in km. 0/00 to 2/085 (SH:- Removal of slips at various roads)	99600/-	2000/-	350/-	30 Days	Class-D
5	A/R & M/O various Type-I to Type-VI GAD Residential qtrs. At kasumpti Shimla-9 (SH:- Providing and laying PVC Flooring set No.12 Type -II Transit accommodation set No.34 type-III set no.5 at Mehli Shimla (HP).	99940/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O to various Type-III and type-IV GAD qtrs. At pari Mehal kasumpti Shimla-9 (SH:- Covering of Balcony in type-III set No.73 under Parimahahal ).	97681/-	2000/-	350/-	30 days	30 Days
7	A/R & M/O to various Type-I to Type-VI Qtrs of GAD at kasumpti Shimla-9 (SH:- Providing and Fixing sunmica Teak ply and 9mm ply etc in IV set nO.58 in kasumpti Shimla-9).	85415/-	1700/-	350/-	30 days	30 Days
8	Construction of road Shyar to kufer km. 0/00 to 0/750 (SH;- C/O Grating for link road at RD. 0/105 to 0/120).	97695/-	2000/-	350/-	30 Days	Class-D
9	Construction of road Shyar to Kufer km. 0/00 to 0/750 (SH:- C/O Grating for link road at RD. 0/085 to 0/100).	97694/-	2000/-	350/-	30 Days	Class-D
10	A/R & M/O various Type-I to VI GAD Residential qtrs. At kasumpti Shimla-9 (SH:- Providing and fixing pota cabin plate from etc in set NO.17 type-VI Mehli Shimla)	99627/-	2000/-	350/-	30 Days	Class-D
11	A/R & M/O various Type-III to Type-VI GAD Residential qtrs. At kasumpti Shimla (SH:- White washing/Distempering type-III 61 other due sets on vacation under Parimahahal section).	99796/-	2000/-	350/-	30 Days	Class-D
12	A/R & M/O various Type-I to Type-VI GAD Residential qtrs. At kasumpti Shimla-9 (SH;- Providing and fixing door and window shutters type-III-132,131,57 and 68,42 under kasumpti sub Division ).	96827/-	1800/-	350/-	30 Days	Class-D
13	A/R & M/O Sanjulli to Dhalli Bye pass road km. 0/00 to 3/700 (SH;- Construction of U-Shape drain RD. 4/115 to 4/435).	96682/-	2000/-	350/-	30 Days	Class-D
14	Restoration of Rain Damages on koti Junga road km. 0/00 to 12/405 (SH:- Removal of slips at RD. 0/00 to 6/00)	98400/-	2000/-	350/-	30 Days	Class-D
15	Restoration of Rain Damages on Challanda link rod km. 0/00 to 4/800 (SH:- Removal of slips at RD. 0/00 to 4/800).	97800/-	2000/-	350/-	30 Days	Class-D
16	A/R & M/O type-I to type-IV Qtrs at kasumpti Shimla (SH;- Providing and fixing polycarbonate Sheet over proch and Stair set No.19 type-VI at mehli Shimla).	99095/-	2000/-	350/-	30 Days	Class-D
17	A/R & M/O various roads under sub Division No-VIII kasumpti Shimla-9 (Falling of dry standing tree/green tree & conversion of logs sleeper/fuel wood etc & stacking in PWD store).	79600/-	1600/-	350/-	30 Days	Class-D
18	Reconstruction & Restoration on Shoghi mehli Junga Sadhupul road in km. 12/375 to 48/925 (SH;- Providing and laying CC Shoulders at RD. 21/400 to 21/460 Valley side)(Balance work).	90975/-	1800/-	350/-	30 Days	Class-D
19	A/R & M/O to various type-I to Type-VI Qtrs GAD at kasumpti Shimla-9 (SH:- Providing and fixing PVC Flooring in type-IV set NO.49 under kasumpti Section).	96121/-	1900/-	350/-	30 Days	Class-D
20	A/R & M/O to various type-III and type-IV Gad Qtrs at pari mehal kasumpti Shimla-9 (SH;- Covering of Balcony covering etc in type-II set nO.648 and 650 under kasumpti section).	93700/-	1900/-	350/-	30 Days	Class-D
21	A/R & M/O to Type-VI Qtrs at mehli Shimla (SH:- Change of water pipe line set NO.9 11,12A,15,17 and 19 type-VI at mehli Shimla).	99095/-	2000/-	350/-	30 Days	Class-D
22	A/R & M/O Zila Parishad bhawan at Sanjuli Dhalli bye pass (SH:- Providing and fixing MS steel fencing with preprinted sheet there in Front side portion).	90175/-	1800/-	350/-	30 Days	Class-D



23	Restoration of Rain Damages on Nariga to piran road km. 0/00 to 3/00 (SH;- Removal of slips at Rd. 0/00 to 1/150).	98400/-	2000/-	350/-	30 Days	Class-D
----	--	---------	--------	-------	---------	---------

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.
- 14.

Executive Engineer,  
Shimla Division No-1.,  
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2025-2026-  
Copy forwarded to:-

10898-711

Dated :- 22/9/25

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Dsitt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,  
Shimla Division No-1.,  
HPPWD. Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99821=00		
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9					Earnest Money :-2000=00		
(SH:- Providing and fixing accessories and white washing in type - II set no 649 under kasumpti section )					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 40mm thick (i)2nd class deodar wood.	2.52	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Metre	11340.00
2	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)40mm thick 2nd class deodar wood	1.37	Sqm	4200.00	Rupees Four Thousand Two Hundred Only	Per Square Metre	5754.00
3	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 150x10mm	5.00	Nos.	80.00	Rupees Eighty Only	Each	400.00
(i)	200x10 mm	2.00	Nos.	100.00	Rupees One Hundred Only	Each	200.00
4	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	10.00	Nos	80.00	Rupees Eighty Only	Each	800.00
5	Providing and fixing bright finished brass hard drawn hooks and eyes including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 200 mm	5.00	Nos.	60.00	Rupees Sixty Only	Each	300.00
6	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 2nd class deodar wood	0.054	Cum	110000.00	Rupees One Lakh Ten Thousand Only	Per Cubic Metre	5940.00
7	Providing and fixing 15 mm mixer for kitchen sink top / bottom swinging spout make ESSCO/ Bathsense or equivalent make .	1.00	Nos.	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
8	Providing and fixing one hole basin mixing Faucet including carriage of materials in all leads as per directions of the Engineer-in-Charge. MAKE ESS ESS	1.00	Nos.	4000.00	Rupees Four Thousand Only	Each	4000.00

9	Providing and fixing wall mixing faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. MAKE ESS ESS	3.00	Nos.	4000.00	Rupees Four Thousand Only	Each	12000.00
10	Providing and fixing vitreous china wash basin with single hole for pillar tap C.I or M.S brackets painted white including cuttings holes and making good the same but excluding fittings (i) 550 mmx 400mm MAKE ESS ESS or equivalent.	1.00	Nos.	4902.50	Rupees Four Thousand Nine Hundred Two and Paise Fifty Only	Each	4902.50
11	Providing and fixing 32 mm dia CP brass waste for wash basin or sink complete with in lead lifts of materials and other incidentals make ESSCO / Bathsense or equivalent make.	1.00	Nos.	600.00	Rupees Six Hundred Only	Each	600.00
12	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of designation 85 G with wire of dia 0.56 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary secrows.	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square Meter	600.00
13	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty (i) Float glass panes of nominal thickness 4 mm including carriage of materials in all leads as per directions of the Engineer-in-Charge. (weight not less than 10kg/sqm)	2.00	Sqm	900.00	Rupees Nine Hundred Only	Per Square Meter	1800.00
(i)	(ii) Frosted glass 4 mm thick	1.00	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square Meter	1050.00
14	Marble work (table rubbed and polished for walls lining) Veneer work 2.50cm. thick in cement mortar 1:3 (1 cement:3 sand) including pointing with white cement mortar 1:2 (1 white cement: 2 marble dust) with an admixture of pigment to match the marble shade including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) Baroda Green Marble	0.99	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Meter	4455.00
15	Providing and fixing PVC corner shelves complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	2.00	Nos	600.00	Rupees Six Hundred Only	Each	1200.00
16	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	3000.00	Rupees Three Thousand Only	Each	3000.00
17	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	54.40	Kgs	105.00	Rupees One Hundred Five Only	Per KilogramMetre	5712.00
18	Providing and fixing 100mm sand cast iron grating for gully floor or Nahni trap including carriage of materials all leads and lifts as per directions of the Engineer-in-Charge.	3.00	No	200.00	Rupees Two Hundred Only	Each	600.00
19	Providing and fixing toilet paper holder including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Make Stainless steel	1.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	650.00


20	Distempering with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade. Old work (one or more coats) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	100.00	Sqm	55.00	Rupees Fifty Five Only	Per Square Metre	5500.00
21	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	75.00	Sqm	12.00	Rupees Twelve Only	Per Square Meter	900.00
22	Providing and applying white cement based putty of average thickness 1mm of approved brand and manufacture over the plastered wall surface to prepare the surface even and smooth including carriage of materials upto all leads and lifts as per the direction of the Engineer-in-Charge.	45.00	Sqm	55.00	Rupees Fifty Five Only	Per Square Meter	2475.00
23	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	100.00	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	6500.00
24	Wall painting (One coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.00	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	750.00
25	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	4.10	Sqm	38.00	Rupees Thirty Eight Only	Per Square Meter	156.00
26	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enamel paint.	4.10	Sqm	70.00	Rupees Seventy Only	Per Square Meter	287.00
27	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 510x1040 mm bowl depth 250 mm	1.00	Nos.	4200.00	Rupees Four Thousand Two Hundred Only	Each	4200.00
28	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six millimetre)thick	2.25	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	1350.00
29	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but with out fittings and the base support for tank including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i) 500 Ltrs Capavity.	500.00	ltr	9.50	Rupees Nine and Paise Fifty Only	per litre	4750.00

30	Providing and fixing whel valve with CI wheel of approved quality ( screwed 15 mm nominal bore )	2.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	1100.00
31	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a)15mm dia nominal bore	5.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	1750.00
32	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc nominal bore including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (New work) (i) 15 mm dia.	2.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	300.00
						<b>Total</b>	<b>99821.50</b>

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 10499500 dated 18.9.25 Amounting to Rs. 1,02,816/-

  
Executive Engineer  
Shimla Division No.1,  
HP PWD Shimla-3.


## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 98,700.00	
Name of Work :- Restoration of Rain Damages on various roads under Bharari Section. (SH:- Hiring of Excavator cum loader for removal of slips in various RDs).						Earnest Money :- 2,000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minimum Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	94.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
						<b>Total</b>	<b>98700.00</b>

**CONDITION:**

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

(T/S No. 10497-98 Dated 18-9-25 Amount to Rs. 1,0,1,66,1...)

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>						<b>Estimated Cost:- 99,889.00</b>	
<b>Name of Work :- Restoration of Rain Damages on Koti Junga road Km 0/000 to 12/405 ( SH:- C/O B/Wall between Rd 1/090 to 1/094.40).</b>						<b>Earnest Money :-2,000.00</b>	
						<b>Time:- One Month.</b>	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	5.94	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	1931.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	5.54	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre.	2216.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: five sand: Ten graded stone agg.40mm nominal size).	5.90	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	22420.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 M 7.5 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty milimetre) nominal size).	15.57	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Metre	71622.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification	10.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	1800.00
						<b>Total</b>	<b>99989.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DN/TA:No 384 T/S No 10495-96 Dt-09-25 Amt 102886/-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,600.00	
Name of Work :- Restoration of Rain Damages on various roads to Fagu to Cheog in Km. 0/00 to 5/600, Talai to Dena in Km. 0/00 to 2/555, Talai to Kadrab in Km. 0/00 to 2/085.(SH:- Removal of slips at various roads).						Earnest Money :- 2,000.00	
						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	498.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	99600.00
<b>Total</b>							<b>99600.00</b>

(T/S No..1008999 Dated 12-9-25 Amount to Rs.1,02,588..)


  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99940=00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 (SH:- Providing and laying PVC Flooring set no - 12 Type - II Transit accommodation set No - 34 type - III set No 5 at melhi Shimla ( H.P.)						Earnest Money :-2000=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
I	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	105.20	Sqm	950.00	Rs One thousand fifty only	Per Square Metre	99940.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
vis						G.Total	99940.00

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 10493-94 dated 18-9-25 Amounting to Rs. 102938/=

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.		Estimated Cost:- 97,681.00					
Name of Work :-A/R & M/O to Various type-III and type-IV GAD Qtrs at Pari mehal Kasumpti Shimla-9 (sh:- Covering of Balcony in Type-III Set No.73 under Parim Mehal ).		Earnest Money :- 2,000.00					
		Time:- One Month.					
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	303.40	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram	31857.00
2	supplying and fixing welded mesh 25x25x3mm to wood or steel members in partitions etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.72	Sqm	650.00	Rupees Six Hundred Fifty Only	Per square metre	4368.00
3	Painting two coats (excluding priming coat)on new steel and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign maters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a)With enamel paint other than white.	15.12	Sqm.	65.00	Rupees Sixty Five Only	Per Square Metre	983.00
4	Providing and fixing Copper oxidised fittings (iron) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)Butt hinges:75x47x 1.70mm	8.00	Nos	100.00	Rupees One Hundred Only	Each	800.00
5	Providing and fixing oxidised M.S. sliding door bolts with bolts and nuts screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 250x16mm (two hundred fifty into sixteen milimetre)	2.00	Nos	105.00	Rupees One Hundred Five Only	Each	210.00
6	Providing and fixing oxidised M.S tower bolts complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)150x10mm	8.00	Nos	75.00	Rupees Seventy Five Only	Each	600.00

7	Providing and fixing polycarbonated sheet 2.00mm thick in lining with galvanised self driven screws complete with all accessories as required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	26.82	Sqm.	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Square Metre	57663.00
8	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	8.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	1200.00
						<b>Total</b>	<b>97681.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DNIT R. No. 382 T/S No 1049192 Dt 18.9.25 Amt 1,00,611/=

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 85,415.00	
NAME OF WORK:- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9.						Earnest Money :- 1,700.00	
(SH:- Providing and Fixing sunmica Teak Ply and 9mm Ply etc in IV Set No. 58 in Kasumpti Shimla-9).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	22.88	Sqm	900.00	Rupees Nine Hundred Only	Per Square meter	20592.00
2	Providing and fixing Ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 9mm (Nine milimetre)thick	17.94	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Meter	17043.00
3	Providing and fixing with <b>4mm thick Teak ply</b> in the door shutter panel including fixing of beading with nail/screws as required in all respect as per Architectural Drawing/design and instruction of the Engineer-in-Charge.	39.84	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Meter	37848.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class teak wood.	83.57	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	5432.00

5	Providing and fixing cupboard handles, ISI marked, with necessary screws etc including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge. (i) 100mm dia.	25.00	Nos	180.00	Rupees One Hundred Eighty Only	Each	4500.00
						<b>Total</b>	<b>85415.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

(T/S No. 1048490 Dated 18-9-25 Amount to Rs. 87,977...).

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 97,695.00	
Name of Work :- Construction of road Shyar to Kufer Km 0/000 to 0/750 ( SH:- C/O Grating for link road at Rd 0/105 to 0/120).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials in all labour equipment and materials to various leads and lifts as per directions of the Engineer-in-Charge. (a)Thermo-Mechanically Treated bars of grade Fe-500 D more.	5.58	Kgs.	100.00	Rupees One Hundred Only	Per Kilogram	558.00
2	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	925.11	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram	97137.00
						<b>Total</b>	<b>97695.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DNIT A.No 2807/5 No 10487-88 Dated 18-9-25 Amt Rs 100626/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 97,694.00	
Name of Work :- Construction of road Shyar to Kufer Km 0/000 to 0/750 ( SH:- C/O Grating for link road at Rd 0/085 to 0/100).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials in all labour equipment and materials to various leads and lifts as per directions of the Engineer-in-Charge. (a)Thermo-Mechanically Treated bars of grade Fe-500 D more..	5.58	Kgs.	100.00	Rupees One Hundred Only	Per Kilogram	558.00
2	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	925.10	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram	97136.00
						<b>Total</b>	<b>97694.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DNIT A.No. 379 T/S No 10485-86 Dt 18-9-25 Amt 1,00,625/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99627=00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 ( SH:- providing and fixing Pota Cabin Plate Form etc in Set No 17 Type - VI Mehli Shimla						Earnest Money :-2000=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, hollow framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. finished welded Holloow type - tube	787.80	Kgs	115.00	Rupees One Hundred Fifteen Only	Per kilo gram	90597.00
2	Provding and fixing polycarbonated sheet 2.00mm thick in lining with galvanised self driven screws complete with all accessories as required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.20	Sqm.	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Square Metre	9030.00
BD	Quoted rates Percentage in words						
						G.Total	99627.00

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 10483-84 dated 18-9-25 Amounting to Rs. 102616/-

Executive Engineer  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY								
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99796=00			
Name of Work :- A/R & M/O various Type - III TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 ( SH:- White washing / Distemping Type - III - 61 other due sets on vacation under Parimahal section ).					Earnest Money : 2,000=00			
					Time:- One Month.			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit		Amount
				In figures	In words			
1	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	7.58	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	10233.00	
3	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.39	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	3732.00	
4	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 6mm thick	13.58	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	8148.00	
5	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood	20.20	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	1313.00	
6	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	22.00	Nos	50.00	Rupees Fifty Only	Each	1100.00	
7	Providing and fixing bright finished brass handles with screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 100mm (One hundred milimetre)	22.00	Nos	180.00	Rupees One Hundred Eighty Only	Each	3960.00	
8	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	7.28	Sqm	35.00	Rupees Thirty Five Only	Per Square Meter	255.00	
9	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enenal paint.	7.28	Sqm	70.00	Rupees Seventy Only	Per Square Meter	510.00	
10	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i) 2nd class deodar wood	0.12	Cum	97000.00	Rupees Ninety Seven Thousand Only	Per cubic Meter	11640.00	

11	Distemping with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade. Old work (one or more coats) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	419.45	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	18875.00
12	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	200.73	Sqm	10.00	Rupees Ten Only	Per Square Meter	2007.00
13	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	190.82	Sqm	55.00	Rupees Fifty Five Only	Per Square Meter	10495.00
14	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	250.04	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	16253.00
15	Finishing wall with weather proof exterior grade emulsion of approved design Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	10.00	Sqm	70.00	Rupees Seventy Only	Per Square Meter	700.00
16	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	10.00	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Meter	2500.00
17	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	8.50	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Meter	8075.00
						<b>Total</b>	<b>99796.00</b>
NK							

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 10481-82 dated 18-9-25 Amounting to Rs. 1,92,790/-

Executive Engineer  
Shimla Division No. I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							Estimated Cost:-96827=00	
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							Earnest Money :-1800=00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla -9 (SH:- Providing and fixing door and window shutters Type - III-132,131,57 and 68,42 under kasumpti sub division )							Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount	
				In figures	In words			
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Of area 3 sq. metres and below	10.00	Nos	300.00	Rupees Three Hundred Only	Each	3000.00	
2	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 40mm thick (i)2nd class deodar wood.	10.96	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Metre	49320.00	
3	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)40mm thick 2nd class deodar wood	4.88	Sqm	4200.00	Rupees Four Thousand Two Hundred Only	Per Square Metre	20496.00	
4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. 150x10mm	14.00	Nos.	80.00	Rupees Eighty Only	Each	1120.00	
(ii)	200x10 mm	10.00	Nos.	120.00	Rupees One Hundred Twenty Only	Each	1200.00	
5	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125 mm	20.00	Nos.	80.00	Rupees Eighty Only	Each	1600.00	
6	Providing and fixing bright finished brass hard drawn hooks and eyes including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 200 mm	16.00	Nos.	60.00	Rupees Sixty Only	Each	960.00	
7	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 2nd class deodar wood	0.061	Cum	100000	Rupees One Lakh Only	Per Cubic Metre	6100.00	

8	Providing and fixing wire gauge in shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square Meter	600.00
9	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty (i) Float glass panes of nominal thickness 4 mm including carriage of materials in all leads as per directions of the Engineer-in-Charge. (weight not less than 10kg/sqm)	2.00	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	1700.00
10	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	6.75	Sqm	270.00	Rupees Two Hundred Seventy Only	Per Square Meter	1823.00
11	Providing and fixing chicken mesh in wall with wood screws and nails including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.75	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	1688.00
12	Providing Dubbing out an old irregular walls average 10mm thick with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) cement mortar 1:5 (One cement: Five sand).	6.75	Sqm.	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	1890.00
13	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	38.91	Sqm	40.00	Rupees Forty Only	Per Square Meter	1556.00
14	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enenal paint.	38.91	Sqm	70.00	Rupees Seventy Only	Per Square Meter	2724.00
	Quated rates Percentage in figures						
yp	Quoted rates Percentage in words						
						G.Total	96827.00

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No. 10479-80 dated 18-9-25 Amounting to Rs. 99732/-  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:96,682.00	
Name of Work :- A/R & M/O Sanjauli to Dhalli Bye Pass road Km. 0/00 to 3/700. (SH: Construction of U-Shape drain Rd.4/115 to 4/435).						Earnest Money :- 2000.00	
Shape drain Rd.4/115 to 4/435).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil.	11.50	Cum	650.00	Rupees Six Hundred Fifty Only	Per Cubic Metre	7475.00
2	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	510.38	Kgs.	105.00	Rupees One Hundred Five Only .	Per Kilogram	53590.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(one cement:Three sand:Six graded stone aggregate 20mm(Twenty milimetre) nominal size).	6.66	Cum	5300.00	Rupees Five Thousand Three Hundred Only	Per Cubic Meter	35298.00

4	Painting Steel work with Deluxe MultiSurface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	4.90	sqm	65.00	Rupees Sixty Five Only	Per Square Meter	319.00
						Total	96682.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

(T.S. 1047778 Dated 18.9.25 Amount to Rs. 99,582/-)

**CONDITION:-**


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer  
Shimla Division No.1,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-</b>					<b>Estimated Cost:- 98,400.00</b>		
<b>Name of Work :- Restoration of Rain damages on Koti Junga road 0/000 to 12/405, (SH:-</b>					<b>Earnest Money :- 2,000.00</b>		
<b>Removal of slips at Rd 0/000 to 6/000).</b>					<b>Time:- One Month</b>		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	492.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	98400.00
						<b>Total</b>	<b>98400.00</b>

DNIT No. 371 T/S No 10469-70 D 18-9-25 Amt 101352/=


  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 97,800.00		
Name of Work :- Restoration of Rain damages on Challanda link road 0/000 to 4/800, ..(SH:-					Earnest Money :- 2,000.00		
Removal of slips at Rd 0/000 to 4/800).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	489.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	97800.00
						<b>Total</b>	<b>97800.00</b>

DNIT R.22.372 T/S No. 104772 Dated 18-9-25

Amt to Rs 10,17,34/=


  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,095.00	
Name of Work :- A/R & M/O type-1 to type-VI Qtrs at Kasumpti Shimla ( SH:- Providing Fixing Polycarbonated Sheet over porch and Stair Set No.19 type- VI at Mehli Shimla).						Earnest Money :- 2,000.00	
						Time:- 30 Days.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing polycarbonated sheet 2.00mm thick in lining with galvanised self driven screws complete with all accessories as required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	37.25	Sqm.	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per Square Metre	80088.00
2	Finishing wall with weather proof exterior grade emulsion of approved design Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and final finish after throughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	253.42	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	19007.00
						<b>Total</b>	<b>99095.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

DNIT R. No 373, T/S No 10473-74 Dt 18-9-25 Amt 102067/=

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge
3. Agency has to provide all T&P as required for day to day maintenance of GAD Qtrs building & its compus along with safety tools and do take care of all safety measures to the inforstructure, workers, execution of work. Agency has to provide all safety equipments, tools, dress, etc as required for each job work fo maintenance.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

374

### SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 79,600.00	
Name of Work :- A/R & M/O various roads under Sub-Division No-VIII, Kasumpti, Shimla-9. (Falling of dry standing tree/green tree & conversion of logs sleeper/fuel wood etc & stacking in PWD Store).						Earnest Money :- 1,600.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Felling trees of the girth (measured at a height of 1m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. (i) Beyond 30 cm girth upto and including 60cm girth.	2.00	Nos.	4000.00	Rupees Four Thousand Only	Each	8000.00
1.1	Beyond 60 cm girth upto and including 120cm girth.	1.00	Nos.	10000.00	Rupees Ten Thousand Only	Each	10000.00
1.2	Beyond 120 cm girth upto and including 240cm girth.	2.00	Nos.	15000.00	Rupees Fifteen Thousand Only	Each	30000.00
1.3	Above 240 cm girth	1.00	Nos.	20000.00	Rupees Twenty Thousand Only	Each	20000.00
2	Conversion of tumber any type of tree into longs and further into sleeper and scantling standered side including the same as per the directions of the Engineer-in-Charge	1.50	Cum	4200.00	Rupees Four Thousand Two Hundred Only	Per Cubic Metre	6300.00
3	Conversion of log into fuel wood into appropriate pieces as directed by the Engineer-in-Charge.	1000.00	Kgs.	1.60	One Rupee and Paise Sixty Only	Per Kilo-gram	1600.00
4	Carriage of materials from site of work to PWD store as per the directions of the Engineer-in-Charge.	1.50	Cum	600.00	Rupees Six Hundred Only	Per Cubic Metre	900.00

5	Lopping of tree branches of any species of tree including carriage of materials in all leads as per directions of the Engineer-in-Charge.	7.00	Nos.	400.00	Rupees Four Hundred Only	Each	2800.00
						<b>Total</b>	<b>79600.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

(T/S No. 10475-76 Dated 18-9-25 Amount to Rs. 81,988.)

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 90,975.00

Name of Work :- Reconstruction & Restoration on Shoghi Mehli Junga Sadhupul road in Km. 12/375 to 48/925.

Earnest Money :- 1,800.00

(SH:- Providing and Laying CC Shoulders at RD 21/400 to 21/460 Valley side). ( Balance Work)

Time:- One Month.


Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All usefull material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	15.00	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate20 mm(Twenty milimetre) nominal size).	9.00	Cum	4500.00	Rupees Four Thousand Five Hundred Only	Per Cubic Metre	40500.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:1:5:3(One cement:One point Five sand:Three graded stone aggregate 20mm(Twenty milimetre) nominal size).	6.00	Cum	7600.00	Rupees Seven Thousand Six Hundred Only	Per Cubic Metre	45600.00
						<b>Total</b>	<b>90975.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

DNITR No. 369 T/S No 10.417-18 Dt 18/9/25 Amt 93,704/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 96,121,00	
Name of Work :- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:-						Earnest Money :- 1,900.00	
Providing and Fixing PVC Flooring in Type-IV Set No. 49 Under Kasumpti Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing Ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	29.23	Sqm	650.00	Rupees Six Hundred Fifty Only	Per Square Meter	19000.00
2	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	81.18	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	77121.00
						<b>Total</b>	<b>96121.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

T/S No. 10413-14 Dated 18-9-25 Amount to Rs. 99,005.00.

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

368

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 93,700.00	
Name of Work :-A/R & M/O to Various type-III and type-IV GAD Qtrs at Pari mehal Kasumpti Shimla-9 (sh:- Covering of Balcony Covering etc in type-II,Set No.648 and 650 under Kasumpti Section).						Earnest Money :- 1,900.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	674.94	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram Metre	70869.00
2	supplying and fixing welded mesh 25x25x3mm to wood or steel members in partitions etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	22.14	Sqm	650.00	Rupees Six Hundred Fifty Only	Per square metre	14391.00
3	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign matters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With enamel paint other than white.	47.68	Sqm.	65.00	Rupees Sixty Five Only	Per Square Metre	3099.00
4	Providing and fixing Copper oxidised fittings (iron) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Butt hinges: 75x47x 1.70mm	24.00	Nos	100.00	Rupees One Hundred Only	Each	2400.00
5	Providing and fixing oxidised M.S tower bolts complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (j) 150x10mm	20.00	Nos	75.00	Rupees Seventy Five Only	Each	1500.00
6	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Ready mixed red oxide zinc chromate primer of approved brand.	22.14	Sqm	38.00	Rupees Thirty Eight Only	Per Square meter	841.00
7	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square Metre.	600.00
						<b>Total</b>	<b>93700.00</b>
Quoted rates Percentage in figures							
Quoted rates Percentage in words							
						<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNR No 368 T/S No 1041516 Dated 18-9-25

Amt to Rs 96511/=

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.


## SCHEDULE OF QUANTITY

<b>Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.</b>				<b>Estimated Cost:- 99,095.00</b>			
<b>Name of Work :- A/R &amp; M/O to Type-VI Qtrs. At Mehli Shimla. (SH:- Change of Water pipe line Set No. 9, 11, 12A, 15, 17 and 19 Type-VI at Mehli Shimla).</b>				<b>Earnest Money :- 2,000.00</b>			
				<b>Time:- One Month.</b>			
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting chases and making good the all including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	239.08	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	83678.00
2	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws complete (New work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	24.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	3600.00
3	Providing and fixing (brass) ball valve of approved quality, High or low pressure with plastic floats including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore.	6.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	3900.00
4	Providing and fixing CPVC pipe including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 20mm dia.	12.18	Rmt	650.00	Rupees Six Hundred Fifty Only	Per Running Meter	7917.00
<b>Total</b>							<b>99095.00</b>
Quoted rates Percentage in figures							
Quoted rates Percentage in words							
<b>G.Total</b>							

(T/S No. 10.411-12 Dated 18-9-25 Amount to Rs. 1,02,068.00)

### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer,  
 Shimla Division No.1,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 90175=00		
Name of Work :- A/R & M/O Zila Parishad bhawan at Sanjuali Dhalli bye Pass ( SH:-					Earnest Money : 1800=00		
( SH:- Providing and fixing MS steel fencing with prepainted sheet there in Front side portion )					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work. ornamental work.	579.60	Kg	110.00	Rs one hundred and five only	Per kilo gramme	63756.00
2	Providing and fixing 0.47 to 50mm (Zero point forty seven to fifty milimeter) thick prepainted steel liner in partition with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic ting of 20 micrones over 5 microne primer coating to back coat of polyster of 5 microns over a micrones primer i/c fixing with self drilling screws 55mm size with prepainted it and rubber washer complete with all accessories as required as per the directions of Engineer-in-Charge. Tata Make	19.57	Sqm	1350.00	Rs one Thousand thre hundred fifty only	Per square Metre	26419.50
						<b>Total</b>	<b>90175.50</b>

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-

T/s No. 10295-96 dated 16-9-25 Amounting to Rs. 92880/=


Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 98,400.00	
Name of Work :- Restoration of Rain Damages on Nariga to Piran road Km 0/000 to 3/000						Earnest Money :- 2,000.00	
).(SH:- Removal of slips at Rd 0/000 to 1/150).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift upto 1.5 meter and land upto 1000 meter as per technical specification 302.3.5 and 1611. The work shall be executed as per the direction of the Engineer-in-Charge.	492.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	98400.00
						<b>Total</b>	<b>98400.00</b>

DNIT R. & No - 360 T/S No 299-300 D+16-9-25

Amt to Rs 10.1392

  
 Executive Engineer,  
 Shimla Division No. I,  
 HP PWD Shimla-3.