



Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION

H.P. Public Works Department, TAUNI DEVI 177023

Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

No. PW/TDD/GA/Tender/2025-26
To

8017-8068

Dated: - 18-09-2025

The Executive Engineer(IT Cell),
Nigam Vihar HP Shimla-171002.

Subject: - Publication of Tender Notice

Enclosed please find herewith the tender notice of various works as given in the Notice Inviting Tender . As per Notification Pr.Secy.(PW) to the Govt of Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website

ECL: -Notice Inviting Tender/ Scheduled of Quantity and Certificate.

Yours faithfully,

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Copy forwarded to the following for information: -

1. The Engineer-in-Chief HPPWD., Shimla
2. The Chief Engineer (HZ), HP.PWD, Hamirpur
3. The Deputy Commissioner Hamirpur
4. The Superintending Engineer, 8th Circle HP.PWD, Hamirpur
5. The B.D.O Tauni Devi
6. All the Assistant Engineer working in this Division.
7. Notice Board.
8. AB & DB.

Executive/Engineer
Tauni Devi Division
HPPWD, Tauni Devi



**Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023**

Telephone. 01972-278422, e.mail: ee-tou-hp@gov.in

Tender Notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Tauni Devi Division, H.P. PWD, Tauni Devi on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/firms enlisted in HP PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the HP General Sales Tax Act 1968 so as to reach in his office on or before **27.09.2025 up to 10.30 AM** And the same shall be opened on the same day at **11.00 AM** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) up to **26.09.2025 up to 1.00 PM** and the application for issue of tender form shall be received up to **25.09.2025 up to 5.00 PM**. The earnest money in the shape of NSC/Time deposit account/saving account of the post office in HP duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

No	Name of work	Estimated cost	Earnest money	Time
	Restoration of rain damages on link road to village Sarohal Km. 0/00 to 1/00 (SH:- Repair of pot holes at various RD's) Deposit work	99993.00	2000.00	Two Months
	Restoration of rain damages on link road to village Sanwan Di Thathi Km. 0/00 to 2/030 (SH:- C/o wire crate / Gabion structure for R/wall at Rd 0/545 to 0/551.30)	98499.00	2000.00	Two Months
	Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra (SH:- Dismantling floor slab for providing and fixing tiles and applying 2mm thick plaster of parts putty at various locations) Deposit work)	99589.00	2000.00	Two Months
	Restoration of rain damages on various roads under Kakkar Sub-Division HPPWD., Kakkar (SH:- Hiring of JCB/front end loader for removal of slips, clearance of catch pits and drains, berms dressing) Section Bir Baghera	94500.00	2000.00	Two Months
	C/o link road Bharmar to Bhaletth via Miyana Km. 0/0 to 4/00 (SH:- C/o wing wall Bhaletth side at RD 2/645 and and C/o R/wall at RD 2/619 to 2/623) Deposit work	99933.00	2000.00	Two Months.
	Preparation of DPR for the construction of Rajiv Gandhi Day Boarding School at Karot Tehsil Sujanpur Distt. Hamirpur (Deposit work)	99000.00	2000.00	Two Months.
	Restoration of rain damages on link road to village Sanwan Di Thathi Km. 0/00 to 2/030 (SH:- C/o wire crate / Gabion structure for R/wall at Rd 0/790 to 0/793.80 and R/wall at RD 1/335 to 1/340)	99824.00	2000.00	Two Months
	Restoration of rain damages on link road to village Sarohal Km. 0/00 to 1/00 (SH:- Repair of pot holes at various RD's) Deposit work	99315.00	2000.00	Two Months.
	Restoration of rain damages on link road Jandroo to village Ropa Km. 0/00 to 1/00 (SH:- C/o wing wall at RD 0/131 to 0/133.50)	90601.00	1900.00	Two Months
	Restoration of rain damages on various roads under Kakkar Sub-Division HPPWD., Kakkar (SH:- Hiring of JCB/front end loader for removal of slips, clearance of catch pits and drains, berms dressing) Section Jangle Beri	94500.00	2000.00	Two Months
	A/R&M/O on various roads under Sujanpur Sub-Division HPPWSD., Sujanpur (SH:- Tree cutting on Hamairpur Sujanpur road Km. 16/00 to 24/785 at Various RDs and tree cutting on premises of rest house at Sujanpur HPPWD., Sub-Division Sujanpur)	98632.00	2000.00	Two Month

12	Restoration of rain damages on various roads under Kakkar Sub-Division HPPWD., Kakkar (SH:- Hiring of JCB/front end loader for removal of slips, clearance of catch pits and drains, berms dressing) Kakkar Section-I&II)	94500.00	2000.00	Two Months
13	Restoration of rain damages on link road Jandroo to village Ropa Km. 0/00 to 1/00 (SH:- C/o RCC Hume pipe culvert 900mm dia at RD 0/135) Catchpit)	55259.00	1100.00	Two Months
14	Restoration of rain damages on various roads under Kakkar Sub-Division HPPWD., Kakkar (SH:- Hiring of JCB/front end loader for removal of slips, clearance of catch pits and drains, berms dressing) Kakkar Section-I&II)	94500.00	2000.00	Two Months
15	Restoration of raon damages on various road under Sujanpur Sub-Division HPPWD., Sujanpur (SH:- Hiring of JCB/ front loader for removal of slips/ clearing of drain due to heavy rains) (Chouri Section)	84000.00	1700.00	Two Months
16	Restoration of rain damages on link road to village Sanwan Di Thathi Km. 0/00 to 2/030 (SH:- C/o wire crate / Gabion structure for R/wall at RD 0/755 to 0/759.35 and above step at RD 0/545 to 0/552.30)	97817.00	2000.00	Two Months
17	Restoration of rain damages on link road Jandroo to village Ropa Km. 0/00 to 1/00 (SH:- C/o RCC hume pipe culvert 900mm dia at RD 0/135) Down stream))	89076.00	1800.00	Two Months
18	Construction of Rest House at Uhal Tauni Devi Distt. Hamirpur (SH:- Construction of edge wall and plantation of trees, shrub& hedge)	91685.00	1900.00	Two Months
19	C/o link road Bharmar to Bhalesh via Miyana Km. 0/0 to 4/00 (SH:- C/o wing wall Bhalesh side at RD 2/645 and laying of flooring in cath pit at RD 2/645) Deposit work	99071.00	2000.00	Two Months
20	Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra (SH:- Dismenting floor slab for providing and fixing tiles and applying 2mm thick plaster of parts putty at various locations) Deposit work)	99853.00	2000.00	Two Months
21	Restoration of rain damages on various roads under Kakkar Sub-Division HPPWD., Kakkar (SH:- Hiring of JCB/front end loader for removal of slips, clearance of catch pits and drains, berms dressing) Kakkar Section- II)	94500.00	2000.00	Two Months
22	C/o link road Bharmar to Bhalesh via Miyana Km. 0/0 to 4/00 (SH:- C/o wing wall Bhalesh side at RD 2/645) Deposit work	99469.00	2000.00	Two Months
23	Restoration of rain damages of (i) Tauni Devi Uhal Kakkar Jangle Beri road Km. 0/00 to 7/300 (ii) Bakkar Khad to Gwardoo via Harizan Basti Km. 0/000 to 3/00(iii) Jhanikar to Palahal Kuan via Kohlwin road Km 0/00 to 2/450 under Tauni Devi Sub-Division HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips)	97650.00	2000.00	Two Months
24	Restoration of rain damages of (i) Koloh to Bakniyar road Km.0/00 to 7/00 (ii) Nanot to Bakkar Khad via Jamli Km. 0/00 to 4/00(iii) Uhal to Bakkar Khad via Parnali road Km. 0/00 to 5/700 under Tauni Devi Sub-Division HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drains)	99750.00	2000.00	Two Months
25	Restoration of rain damages of (i) Langwan Tauni Devi road Km. 3/345 to 7/305 (ii) Hawani Baffrin Panahar Narsin road 0/00 to 5/00(iii) Baru Tapre road Km. 2/265 to 8/705 under Tauni Devi Sub-Division HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drains)	98700.00	2000.00	Two Months
26	Restoration of rain damages of (i) Hindu-Di-Dhar via Jandroo road Km. 0/00 to 9/00 (ii) Lagdevi Chouri road Km. 0/00 to 0/500 under Tauni Devi Sub-Division HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, Clearance of drains)	99750.00	2000.00	Two Months

27	Restoration of rain damages of (i) Garne-Da-Galu to Kuthera road Km. 0/00 to 3/865 (ii) Darkoti Mohin road Km. 0/00 to 3/00 (iii) NIT to Muthan road Km. 0/00 to 3/865 under Tauni Devi Sub-Division HPPWD Tauni Devi ((SH - Hiring of Excavator cum loader for removal of slips, Clearance of drains)	97650.00	2000.00	Two Months
28	Construction of Rest House at Uhal Tauni Devi Distt. Hamirpur (SH: _ Construction of edge wall and P/I turf in lawn area)	99567.00	2000.00	Two Months
29	Restoration of rain damages on Uhal to Indu-Di-Dhar via Jandroo road Km. 0/0 to 22/0 (SH:- C/o E/wall at RD 1/120 to 1/140)	84227.00	1700.00	Two Months
30	Repair and maintenance of Ravi Hostel Sainik School Sujanpur Tihra (SH:- Dismantling floor slab for providing and fixing tiles and applying 2mm thick plaster of parts putty at various locations) Deposit work)	99853.00	2000.00	Two Months
31	Restoration of rain damages on Gahra to Chamardha via Lamber Km. 0/00 to 3/500 (SH:- Hiring of JCB/front end loader for removal of slips.	99750	2000.00	Two Months
32	A/R&M/O on various roads under Sujanpur Sub-Division HPPWSD. Sujanpur (SH:- Tree cutting on Hamairpur Sujanpur road Km. 8/00 to 16/00 at Various RDs	62235.00	1250.00	Two Month

Certified that above works are of urgent nature and tenders are being called in exigency of works and in public interest.



Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi



Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/ emergency in calling these tender without press vide this office letter No. No. PW/TDD/GA/Tender/2025-26 *80/7-808'* dated *18-9-2025*


Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

NAME OF WORK:- Restoration of rain damages on link road to village Sarohal km. 0/00 to 1/00. (S.II:- Repair of pot hole at various RD's).
 (Devi + work)

Draft Schedule of Quantity

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earrest Money:-	Rs. 2000.00		
				Time:-		Two Months	
				Rate		In Words	
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing lack coal, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2.503 and 500.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	224.20	341.00	Rupees Three hundred forty one only	Per square metre	76452.00	
2	Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-basebase course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	11.21	2100.00	Rupees two thousand one hundred only	Per Cubic metre	23541.00	
Total						99993.00	

DNT No **78** for the year 2025-26 duly approved for Rs. 99,993/- (ninetly nine thousand nine hundred/ninety three) only


 Executive Engineer,
 Tauni Devl Division,
 HPPWD, Tauni Devl

Terms and Condition
 1. Work shall be executed as per PWD specification.

2. The Billment/returnson will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

Draft Schedule of Quantity
NAME OF WORK:- Restoration of rain damages on link road to village Sanwan Di Thathi km. 0/00 to 2/030.(SI:- C/O wire crate/Gabion structure for R/Wall at RD. 0/545 to 0/551.30).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	Time:-		
				Rs. 98499.00	Rs. 2000.00		
				In Words	Two Months		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm (ten square metre on plan) including dressing of sides and ramming of bottoms. lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.55	2900.00	Rupees two hundred ninety only		Per Cubic metre	4220.00
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS:280 and IS: 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogram) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	32.51	2900.00	Rupees two thousand nine hundred only		Per cubic metre	94279.00
				Total			98499.00

Terms and Condition
 1. Work shall be executed as per PWD specification.

DNIT No. 33 for the year 2024-25 duly approved for Rs. 98,499/- (Ninety eight thousand four hundred ninety nine only). Only.

Executive Engineer,
 Tauni Devt Divn
 HPPWD, Tauni

20

Draft Schedule of Quantity

NAME OF WORK:- Repair and maintenance of Kavi Hostel Sahnik School Sulajpur Thira, (SH:- Dismantling floor slab for providing and fixing tiles and applying 2mm thick plaster of paris putty at various locations). (Deposit work).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount	
				Rate	In Words			
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50mtr. (fifty metre) lead, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, loll tax, GST or other taxes imposed by the Government.	375.83	249.02	Rs. 2000.00	Two Months	Per Square metre	93589.00	
2	Providing and laying plaster of paris putty of 2mm (two millimeters) thickness over plastered surface to prepare the surface even and smooth complete (Bira while putty), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, loll tax, GST or other taxes imposed by the Government.	60.00	100.00	Rs. 1000.00	Per Square metre	Per Square metre	60000.00	
Total								99589.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bid/contract will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNT No. **73** for the year 2025-26 duly approved for Rs. 99,589. (Ninety nine thousand five hundred eighty nine) only


 Executive Engineer,
 Taunl Devi Division,
 HPPWD: Taunl Devi

3

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various roads under Kakkar Sub-Division, HPP:PWD, Kakkar (SH: Hiring of JCB/Front end loader for removal of slips, clearance of drain/culverts.) (BIR Baghera Section).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			Earnest Money:-	Rs. 94500.00		
			Time:-	Two Months		
			Rate			
			In Fig.	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1050.00	Rs. 94500.00 Ninety four thousand five hundred only	Per hour	94500.00
					Total	94500.00

Terms and Condition

- 1 The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- 2 Nothing shall be paid for idle hours
- 3 All bear and tear and POL charges are to be born by the contractor.

DNT No. 29 for the year 2025-26 duly approved for Rs. 94,500/- (Ninety four thousand five hundred) Only.

Executive Engineer,
Tauli Devi Division,
HPPWD:-Tauli Devi

(4)

05

NAME OF WORK:- C/O link road Bhammar to Bhaleth via Mlyana km. 0/0 to 4/00.(SIH:- C/O wing wall Bhaleth side at RD-2/645 and C/O R/Wall at RD-2/619 to 2/623).(Deposit work).

Draft Schedule of Quantity

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-	Unit	Amount
				Rs. 99933.00		
				Earrest Money:-	Rs. 2000.00	
				Time:-	Two Months	
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan) including dressing of sides and ramming of bottoms. (lit upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals	10.98	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre	3186.00
2	Providing and laying concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets coping, bed blocks, anchor blocks, plain window sills, files, sunken floor etc. up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government	11.95	4200.00	Rupees four thousand two hundred only	Per Cubic metre	50232.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	1.80	750.00	Rupees seven hundred fifty only	Per cubic metre	1350.00
4	Providing and laying in position cement concrete of 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimeter) nominal size graded stone aggregate for all works upto plinth level excluding the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge, including all incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	9.40	4600.00	Rupees four thousand six hundred only	Per cubic metre	43240.00
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe. De-plastifinolex/ vecus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (V) 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	7.00	275.00	Rupees two hundred seventy five only	Each	1925.00
Total						99933.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNIT No..... **66** for the year 2025-26 (Duly approved for Rs 99,933/ (Ninety nine thousand nine hundred thirty three) only.

Executive Engineer,
Tamil Dev Division,
HPPWD:- Tamil Dev

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Sanwan Di Thathi km. 0/00 to 2/030 (SIH:- C/O wire crate/gabion structure for R/Wall at RD. 0/790 to ~~0/790-40~~ and R/Wall at RD. 1/335 to 1/340).
~~C/793-80~~

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m one point five metre) in width or 10 sqm (ten square metre on plan), including dressing of sides and ramming of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.82	290.00	Rupees two hundred ninety only	Rs. 2000.00	Per Cubic metre	2848.00
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS 280 and IS 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilograms) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	33.44	2900.00	Rupees two thousand nine hundred only	Rs. 2000.00	Per cubic metre	96976.00
	Total						99824.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNTT No. 24..... for the year 2024-25 duly approved for Rs. 99,824/- (Ninety nine thousand eight hundred twenty four) Only.

Executive Engineer,
 Taunil Devi Division,
 HPPWD: Taunil Devi.

NAME OF WORK:- Restoration of rain damages on link road to village Sarohal km. 0/00 to 1/00.(SH:- Repair of pot hole and C/O unlined drain at various RD's). (Deposit work).

Bill Schedule of Quantity


Sl.No.	Description of Items	Qty.	In Fig.	In Words	Estimated Cost:-	Unit	Amount
					Earnest Money:-		
				Rate:-	Rs. 99315.00	Rs. 2000.00	Two Months
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat, type-B with VG-10 (ten) as per MORD specification clause 1504, 2, 503 and 508, 1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	156.70	345.00	Rupees three hundred forty five only	Per square metre	67862.00	
2	Providing laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by lopper to site, laying in uniform layers in sub-base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, electrica as per Tables 400, 11 & 400, 12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	3.93	2100.00	Rupees two thousand one hundred only	Per Cubic metre	8253.00	
3	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification Clause 307, as per direction of Engineer-in-Charge, including carriage of materials within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	400.00	58.00	Rupees fifty eight only	Per running metre	23200.00	
Total						99315.00	

1. Work shall be executed as per PWD specification.

2. The Bill/extension will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No **79** for the year 2025-26 duly approved for Rs. 99,315/- (Ninety nine thousand three hundred/fifteen) only

Executive Engineer,
Taanai Devi Division,
HPPWD: Taanai Devi



0.79

NAME OF WORK:- Restoration of rain damages on link road Jandroo to village Ropa km. 0/00 to 1/00. (SI:- C/O wing wall at RD. @/131 to 0/133.50).

Draft Schedule of Quantity

S.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	In Words		
					Rs. 90601.00		
					Rs. 1900.00		
					Two Months		
1	Excavation work by mechanical means (Hydraulic excavator/ manual means in foundation trenches or drains not exceeding 1.5m (one point five metre) in width or 10 sqm (ten square metre on plan) including dressing of sides and ramming of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.54	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	2768.00	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	19.90	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	84575.00	
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe De-plastifiolev/ vedus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (1V) : 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 as per direction of Engineer- in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	2.00	278.00	Rupees two hundred seventy eight only	Each.	556.00	
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204, 3.8 as per direction of Engineer- In-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.86	700.00	Rupees seven hundred only	Per cubic metre	2702.00	
Total						90601.00	

Terms and Condition
1. Work shall be executed as per PWD specification.

DNT No. 178 for the year 2025-26 duly approved for Rs. 90,601/- (Ninety thousand six hundred one) Only.

Executive Engineer,
Taunl Devi Division,
HPPWD: Taunl Devi

(Signature)

Drain Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various roads under Kakkar Sub-Division, HPPWD, Kakkar (SH- Hiring of JCB/front end Loader for removal of slips, clearance of drain/culverts etc.) (Section Savage Beri)

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:- Time:-	Rs. 94500.00 Rs. 2000.00		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soil and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1050.00	Rate In Words Rupees one thousand fifty only	Per hour	94500.00	
					Total	94500.00	

Terms and Condition

- The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- Nothing shall be paid for idle hours
- All bear and tear and POL charges are to be born by the contractor.

DNIT No. 98..... for the year 2025-26 duly approved for Rs. 94,500/- (Ninety four thousand five hundred) Only.

[Signature]
Executive Engineer,
Taanli Devi Division,
HPPWD, Taanli

11

Draft Schedule of Quantity

NAME OF WORK:-A/R & M/O on various roads under Sujampur Sub-Division, HP-PWD, Sujampur.(SH:- Tree cutting on Hamirpur Sujampur road km. 16/00 to 24/785 at various RD's and tree cutting on premises of Rest House at Sujampur HP-PWD, Sub-Division Sujampur).

Sr.No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount
			In Fig.	In Words		
1	Felling trees of the girth (measured at a height of 1m (one meter) above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Melkatali tax, GST or other taxes imposed by the Government.					
1.01	Hamirpur Sujampur road km. 16/00 to 24/785 trees					
i	Beyond 60 cm (sixty centimetre) girth upto and including 120cm (one hundred twenty centimetre) girth.	6.00	1390.85	Rupees one thousand three hundred ninety and paise eighty five only	Each	8345.00
ii	Beyond 120cm (one hundred twenty centimetre) girth upto and including 240 cm (two hundred forty centimetre) girth.	10.00	6444.98	Rupees six thousand four hundred forty four and paise ninety eight only	Each	64450.00
iii	Above 240 cm (two hundred forty centimetre) girth	2.00	12918.25	Rupees twelve thousand nine hundred eighteen and paise twenty five only	Each	25837.00
					Total	98632.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNT No. 99 for the year 2025-26 duly approved for Rs. 98632/- (NINE EIGHT THOUSAND SIX HUNDRED THIRTY TWO) ONLY.

Executive Engineer,
Tannal Devi Division,
HPPWD-Tannal Devi

NAME OF WORK: Restoration of rain damages on link road landroo to Village Kopa Km 0/00 to 1/00. (SH: Construction R.C.C. Estimated Cost:- Rs.55259.00)

Draft Schedule of Quantity
Hume pipe culvert 900mm dia at RD 0/135(Catchpit).

Estimated Cost:- Rs.55259.00
Earliest Money:- Rs.1100.00

13

Sr No	Description of Items	Qty.	In Fig.	Time:-		Unit	Amount	
				In Words	Rate			
1.00	Excavation for road work in soil with hydraulic excavator of 0.9cum (zero joint nine cubic metre) bucket capacity including cutting and loading in tippers, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-section, and transporting to the embankment location with a lift upto 1.5m(one point five metre) and lead upto 1000m(one thousand metre) as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	6.39	102.55	Rupees one hundred two and paise fifty five only.		Per cubic metre	655.00	
2.00	Rampwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	17.38	290.15	Rupees two hundred ninety and paise fifteen only.		Per cubic metre	5043.00	
3.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm(forty millimetre) nominal size(as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	1.42	4420.00	Rupees four thousand four hundred twenty and paise zero only.		Per cubic metre	6276.00	
4.00	Providing and laying cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	8.79	4950.00	Rupees four thousand nine hundred fifty and paise fifty only.		Per cubic metre	43511.00	
5.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm(twenty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkanatali tax, GST or other taxes imposed by the Government.	0.07	6127.10	Rupees six thousand one hundred twenty seven and paise ten only.		Per cubic metre	429.00	
Total								55259.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNT No. 181 for the year 2024-25 duly approved for Rs. 55,259/- (Rupees fifty five thousand two hundred fifty nine only)

Executive Engineer,
Tauri Devi Division,
HPPWD, Tauri Devi

15

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Sulampur sub-division H.P.W.D., Sulampur (SI:- Hiring of JCB/front end loader for removal of slips/clearing of drain due to heavy rains). (CRWD Section),

Sl.No.	Description of items	Qty.	In Fig.	Rate	In Words	Unit	Amount	Estimated Cost:-	
								Rs. 84000.00	
							Earnest Money:-	Rs. 1700.00	
							Time:-	Two Months	
1	Hiring of J.C.B (front end loader- 1 cum capacity with breaker) for widening of road, repair of beams, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	80.00	1050.00	Rs. 84000.00 fifty only	Per hour	84000.00			
Total							84000.00		

Terms and Condition

1 The contractor shall be responsible for any kind of breakage in the meachinery and accident happens during working hours.

2 Nothing shall be paid for idle hours

3 All bear and tear and POL charges are to be born by the contractor.

DNR No. 101/..... for the year 2025-26 duly approved for Rs. 84,000/- (Eighty four thousand) Only.

[Signature]

Executive Engineer,
Tamil Devl Division,
HPPWD: Tamil Devl

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Sanwan Di Thathi km. 0/00 to 2/030. (SH:- C/O wire crate/gablon structure for R/Wall at RD. 0/755 to 0/759.35 and above step at RD. 0/545 to 0/552.30).

Sr.No.	Description of Items	Qty.	* In Fig. 2900.00	Estimated Cost:-		Unit	Amount
				Rs. 97817.00	Rs. 2000.00		
				Earrest Money:-	Time:-		
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m one point five metre) in width or 10 sqmt (ten square metre on plan) including dressing of sides and ramming of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	2.70	2900.00	Rupees two thousand ninety only	Per Cubic metre	783.00	
2	Providing and laying laid in wire crates with 4mm (four millimeters) dia G.I. wire conforming to IS 280 and IS 4826 in 100x100mm (one hundred into one hundred millimeters) mesh including ten percent extra for laps and joints laid with stone boulders weighing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specification clause 1301, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	33.46	2900.00	Rupees two thousand nine hundred only	Per cubic metre	97034.00	
Total							97817.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNIT No. 85 for the year 2024-25 duly approved on Rs. 97817/- (Ninety seven thousand eight hundred seventeen), Only.

Executive Engineer,
Taanl Devi Divison,
HPPWD: Taanl, Jy.

17

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road landroo to village Ropa km. 0/00 to 1/00.(SH:- C/O RCC hume pipe culvert 900mm dia at RD. 0/135)(Down stream).

Sr.No.	Description of Items	Qty.	In Fig.	Rate	In Words	Unit	Amount	Estimated Cost:-
								Earnest Money:-
								Rs. 89076.00
								Rs. 1800.00
								Time:- Two Months
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan) including dressing of sides and ramming of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.47	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	6810.00		
2	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.67	4420.00	Rupees four thousand four hundred twenty only	Per Cubic metre	11801.00		
3	Providing and laying cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.13	4950.00	Rupees four thousand nine hundred fifty only	Per cubic metre	45194.00		
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar joints with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900mm(nine hundred millimeters) dia. as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.00	3610.15	Rupees three thousand six hundred ten and paise fifteen only	Per cubic metre	25271.00		
	Total						89076.00	

Terms and Condition
1. Work shall be executed as per PWD specification.

DNR No. 180..... for the year 2025-26 duly approved for Rs. 89,076/ Eighty nine thousand seventy six] Only.

Executive Engineer,
 Taunl Devi Division,
 HPPWD: Taunl Devp

Draft Schedule of Quantity

NAME OF WORK:- Construction of Rest House at Uhal Tanni Devi Dist. Hamirpur (SH:- Construction of edge wall and plantation of trees, shrub & hedge)

18

Sl. No.	Description of Items	Qty.	Estimated Cost:-		Unit	Amount	
			Rs.1900.00	Rs.91685.00			
		Time:-					
		Rate					
		In Fig.	In Words				
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octroi royalty, Malkana,toll tax, GST or other taxes imposed on the work.	8.91	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	2585.00		
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	17.82	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	75735.00		
3.06	Plantation of tree, shrub and hedge at site including watering and removal of unserviceable materials as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octroi, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.						
3.01	Ashwagandha	3.00	Rupees one hundred twenty and paise zero only.	Each	360.00		
3.02	Neem	1.00	Rupees one hundred twenty and paise zero only.	Each	120.00		
3.03	Leemon Grass	2.00	Rupees one hundred twenty and paise zero only.	Each	240.00		
3.04	Carapher	2.00	Rupees one hundred sixty seven and paise zero only.	Each	334.00		
3.05	Harid	2.00	Rupees one hundred eighteen and paise zero only.	Each	236.00		
3.06	Bhera	2.00	Rupees one hundred eighteen and paise zero only.	Each	236.00		
3.07	Moringa	2.00	Rupees one hundred eighteen and paise zero only.	Each	236.00		

3.08	Peace lilly	2.00	1080.00	Rupees one thousand eighty and paise zero only.	Each	2160.00
3.09	Money Plant	3.00	826.00	Rupees eight hundred twenty six and paise zero only	Each	2478.00
3.10	Snake Plant	3.00	355.00	Rupees three hundred fifty five and paise zero only.	Each	1065.00
3.11	Chouri Pot	5.00	1180.00	Rupees one thousand one hundred eighty and paise zero only.	Each	5900.00
Total						91685.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 47 for the year 2025-26 duly approved for Rs. 91,685 (Rupees ninety thousand three hundred ninety nine only)

Executive Engineer,
Tauri Devi Division,
HPPWD, Tauri Devi.

Drain Schedule of Quantity

NAME OF WORK:- C/O link road Bharmar to Bhalach via Miyana km. 0/0 to 4/00.(SH:- C/O wing wall Bhalach side at RD. 2/645 and laying of flooring in catch pit at RD. 2/645).(Deposit work).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 2000.00		
				Time:-	Two Months		
				Rate	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm/ ten square metre on plan) including dressing of sides and ramming of bottoms. (ill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals	9.11	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre	2643.00	
2	Providing and laying cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government	2.35	6100.00	Rupees six thousand one hundred only	Per Cubic metre	14335.00	
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government	16.89	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	71783.00	
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer- in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government	11.18	750.00	Rupees seven hundred fifty only	Per cubic metre	8385.00	
5	Providing weep holes in brickstone masonry/ plant/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-pas/finde/ ventis pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square) extending through the full width of the structures with slopes of (N) 20(H) towards drawing face complete as per drawing and technical specification clauses 6/4, 7/09, 1204.3.7 as per direction of Engineer- in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government	7.00	275.00	Rupees two hundred seventy five only	Each	1925.00	
				Total			99071.00

DNTT No. 65 for the year 2025-26 duly approved for Rs. 99,071/- (Ninety nine thousand seventy one) Only.

Executive Engineer,
Taunl Dey Division,
HPPWD- Taunl Dey

[Signature]

Draft Schedule of Quantity

NAME OF WORK:- Repair and maintenance of Raw Hostel Sainik School Sulampur Tlira. (SI). Dismantling floor slab for providing and fixing tiles and applying 2mm thick plaster of paris putty at various locations). (Deposit work) **Job No. 1**

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	Amount		
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50mtr. (fifty meter) lead, as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	376.89	249.02	Rupees two hundred forty nine and paise two only	Rs. 2000.00	Per Square metre	93853.00
2	Providing and laying plaster of paris putty of 2mm (two millimeters) thickness over plastered surface to prepare the surface even and smooth complete (Birda while putty), as per the direction of the Engineer-in-charge including entire cartage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	60.00	100.00	Rupees one hundred only	Rs. 99853.00	Per Square metre	6000.00
Total							99853.00

Terms and Condition

1. Work shall be executed as per PWD specification.
2. The bid/contract will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIIT No. **71** for the year 2025-26 duly approved for Rs. 99,853/- (Ninety nine thousand eight hundred fifty three) only

Executive Engineer,
Taani Devi Division,
HPPWD-Taani Devi

90

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various roads under Kakkar Sub-Division, HP:PWD, Kakkar.(Sfr:- Hiring of JCB/front end Loader for removal of slips, clearance of drain/culverts.) (Bir Baghera Section/ Kakkar-II).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:- Time:-	Rs. 2000.00 Two Months		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1050.00	Rate In Words Rupees one thousand fifty only	Per hour	94500.00	
	Total					94500.00	

- Terms and Condition**
- 1 The contractor shall be responsible for any kind of breakage in the meachinery and accident happens during working hours.
 - 2 Nothing shall be paid for idle hours
 - 3 All bear and rear and POL charges are to be born by the contractor.

DNT No. 22..... for the year 2025-26 duly approved for Rs. 94,500/- (Ninety four thousand five hundred) Only.

Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni

21

Draft Schedule of Quantity

NAME OF WORK:- C/O link road Bharnar to Bhalath via Miyana km. 0/0 to 4/00.(SH:-C/O wing wall Bhalath side at HD. 2/645).(Deposit work).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-	Rs. 99469.00
				Earrest Money:-	Rs. 2000.00
				Time:-	Two Months
				Rate	Unit
				In Words	Amount
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm. ten square metre on plan) including dressing of sides and ramming of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	5.40	290.15	Rupees two hundred ninety and paise fifteen only	Per Cubic metre 1567.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, (fills, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing. 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	16.55	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre 70330.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and MORD technical specifications clause 1204.3.8 as per direction of Engineer. in -Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	12.34	750.00	Rupees seven hundred fifty only	Per cubic metre 9255.00
4	Providing and laying in position cement concrete of 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimeter) nominal size graded stone aggregate for all works upto plinth level excluding the cost of centering and shuttering including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	3.76	4650.00	Rupees four thousand six hundred fifty only	Per cubic metre 17484.00
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plastimolex vedus pipe having pressure 4kg per centimeter square. (four kilogram per centimeter square.) extending through the full width of the structures with slopes of (1V) 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	3.00	275.00	Rupees two hundred seventy five only	Each 825.00
Total					99469.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNT No. 617..... for the year 2025-26 duly approved for Rs. 99,469/- (Ninety nine thousand four hundred sixty nine) Only.

Executive Engineer,
Tanni Devi Division,
HPPWD: Tanni Dev

99

Draft Schedule of Quantity


NAME OF WORK:- Restoration of rain damages of (i) Tauni Devi Uhal kaikar Jangle Beri road Km 0/00 to 7/300 (ii) Balkar Khad to Gwardoo via Harizan Basti km 0/000 to 3/00 (iii) Jhanakar to Palahal Kuan via Kohlwain road Km 0/00 to 2/450 under Tauni Devi Sub Division, HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, clearance of drains)

Estimated Cost:- Rs 97650.00
 Earnest Money:- Rs 2000.00
 Time:- Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Hiring of J.C.B. (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8:00 hours from 9:00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	93.00	1050.00	Rupees one thousand fifty and paise zero only.	Per Hour	97650.00
Total						97650.00

Terms and Condition

- The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours. 40
 (Rupees ninety seven thousand six hundred fifty) Only.
- Nothing shall be paid for idle hours.
- All bear and tear and POL charges are to be born by the contractor.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi.

633


Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages of (i) Kallath to Bakniyar road Km 0/00 to 7/00 (ii) Nantot to Bakkar Khad via Jamli km 0/000 to 4/00 (iii) Ithal to Bakkar Khad via Parnath road KM 0/00 to 5/700 under Tauni Devi Sub Division, HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, clearance of drains)

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	Estimated Cost:- Earntest Money:- Time:-		
1.00	Hiring of J.C.B. (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8:00 hours from 9:00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, MalkanatoK tax, GST or other taxes imposed by the Government.	94.00	1050.00	Rupees one thousand fifty only.	Rs.99750.00 Rs.2000.00	Per Hour	98700.00
Total							98700.00

Terms and Condition

- The contractor shall be responsible for any kind of breakage in the machinery and accident happens DNTT No..... for the year 2025-26 duly approved for Rs. 98,700/-
- Nothing shall be paid for idle hours.
- All bear and tear and POL charges are to be bornn by the contractor.


Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Dept

24

95

Draft Schedule of Quantity


NAME OF WORK:- Restoration of rain damages of (i) Langwan Tauni Devi road Km 3/345 to 7/305(ii) Hawani Bafrin Panahar Narshn road 0/00 to 5/00 (iii) Baru Tapre road Km 5/265 to 8/705 under Tauni Devi Sub Division, HPPWD

Tauni Devi (SH:- Hiring of Excavator cum loader for removal of silps, clearance of drains)

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-	Unit	Amount
				Time:-		
				In Words		
1.00	Hiring of J.C.B. (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8:00 hours from 9:00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	94.00	1050.00	Rupees one thousand fifty and paise zero only.	Per Hour	98700.00
Total						98700.00

Terms and Condition

- The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours. DNTT No. 42 for the year 2025-26 duly approved for Rs. 98,700/- (Rupees ninety eight thousand seven hundred) Only.
- Nothing shall be paid for idle hours.
- All bear and tear and POL charges are to be born by the contractor.


 Executive Engineer,
 Tauni Devi Division
 HPPWD: Tauni Devi

Draft Schedule of Quantity


NAME OF WORK:- Restoration of rain damages of (i) Hindu-Di-Dhar via landroo road Km 0/00 to 9/00 (ii) Lagdevi Chouri road Km 0/00 to 0/500 under Tauni Devi Sub Division, HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, clearance of drains)

Estimated Cost:- Rs.99750.00
Earnest Money:- Rs.2000.00
Time:- Two Months

Sr.No.	Description of Items	Qty.	In Fig.	Rate		Unit	Amount
				In Words	In Words		
1.00	Hiring of J.C.B. (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8:00 hours from 9:00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	95.00	1050.00	Rupees one thousand fifty only.	Per Hour	99750.00	
Total							99750.00

43

Terms and Condition
 1. The contractor shall be responsible for any kind of breakage in the machinery and accident happens DNT No. for the year 2025-26 duly approved for Rs. 99750/- during working hours.
 2. Nothing shall be paid for idle hours.
 3. All bear and tear and POL charges are to be born by the contractor.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

96


Draft Schedule of Quantity

NAME OF WORK:-		Estimated Cost:-	Earnest Money:-			
Restoration of rain damages of (i) Garne-Da-Galu to Kuthera road Km 0/00 to 3/865 (ii) Darkoti Mohin road Km 0/00 to 3/00. (iii) NIT to Muthan road km 0/00 to 3/865 under Tauni Devi Sub Division, HPPWD Tauni Devi (SH:- Hiring of Excavator cum loader for removal of slips, clearance of drains)		Rs.97650.00	Rs.2000.00	Two Months		
Sr.No.	Description of Items	Qty.	In Fig.	Rate In Words	Unit	Amount
1.00	Hiring of J.C.B. (front end loader 1 cum(one cubic metre) capacity with breaker) for widening of road, repair of berms, removal of slips and clearance of drains in all kind of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8:00 hours from 9:00 AM to 5:00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified as per the direction of Engineer in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	93.00	1050.00	Rupees one thousand fifty only.	Per Hour	97650.00
Total						97650.00

Terms and Condition

- The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
- Nothing shall be paid for idle hours.
- All bear and tear and POL charges are to be born by the contractor.

for the year 2025-26 duly approved for Rs. 99,650/-
(Rupees ninety nine thousand six hundred fifty) Only.


 Executive Engineer,
 Tauni Devi Division,
 HPPWD: Tauni Devi

27

26

Draft Schedule of Quantity

NAME OF WORK:- Construction of Rest House at Uhal Tauni Devi Dist. Hamirpur (HP) (SH:- Construction of edge wall and P/1 turf in lawn area)

Sr. No.	Description of Items	Qty.	In Fig.	In Words	Unit	Amount	Estimated Cost:-		
							Earrest Money:-	Time:-	
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government	2.16	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	627.00	Rs.99567.00	Rs2000.00	
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	4.32	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	18360.00			
3.00	Supplying and stacking of good earth at site for the bed to turf as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	16.00	390.00	Rupees three hundred ninety and paise zero only.	Per cubic metre	6240.00			
4.00	Providing and laying of selection 1 turf with eath 50mm (fifty millimetre) to 60mm(sixty millimetre) thickness of existing ground prepared with proper level and ramming with required tools wooden and than rolling the surface with light roller make the surface smoothen and light watering the same maintenance for 30(thirty) days or more till the grass establish properly as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	84.00	885.00	Rupees eight hundred eighty five and paise zero only	Per square metre	74340.00			
Total							99567.00		

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 46 for the year 2025-26 duly approved for Rs. 99,567 (Rupees ninety nine thousand five thousand sixty seven only)

[Signature]
Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devl.


Drill Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Uhal to Indu-Di-Dhar via Jandiroo road km. 0/0 to 22/0.(SIH:- C/O E/Wall at RD. 1/120 to 1/140).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount	
				Rate	In Words			
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m/one point five metre) in width or 10 sqm (ten square metre or plan) including dressing of sides and rammimg of bottoms. fill upto 1.5 m. (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	14.40	290.15	Rs. 1700.00	Two Months	Per cubic metre	4178.00	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing. 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	18.00	4250.00	Rupees four thousand two hundred fifty only		Per Cubic metre	76500.00	
3	Providing weep holes in brickstone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm (one hundred ten millimeter) dia PVC pipe. De-plas/Inclux veeclus pipe having pressure 4kg per centimeter square. (four kilogramme per centimeter square) extending through the full width of the structures with slopes of (V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	13.00	273.00	Rupees two hundred seventy three only		Each.	3549.00	
Total								84227.00

Terms and Condition
1. Work shall be executed as per PWD specification.

30
DNIT No..... for the year 2025-26 duly approved for Rs. 84,227/- (Eighty four thousand two hundred twenty seven) Onk.


 Executive Engineer,
 Taml Devl Division,
 HPWR, Taml Devl

29

30

Draft Schedule of Quantity


NAME OF WORK:- Repair and maintenance of Ravi Hostel Salnik School Sujapur Tihra. (SI:- Dismantling floor slab for providing and fixing tiles and applying 2mm thick plaster of paris putty at various locations). (Deposit work) **SB No 2.**

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Rate	In Words		
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50mtr. (fifty metre) lead, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	376.89	249.02	Rupees two hundred forty nine and paise two only	Per Square metre	93853.00	
2	Providing and laying plaster of paris putty of 2mm (two millimeters) thickness over plastered surface to prepare the surface even and smooth complete (Brida white putty), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	60.00	100.00	Rupees one hundred only	Per Square metre	6000.00	
Total							99853.00

Terms and Condition

1. Work shall be executed as per PWD's specification.
2. The bid/contract will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill

DNIT No **72** for the year 2025-26 duly approved for Rs. 99,853/- (Ninety nine thousand eight hundred fifty three) only


 Executive Engineer,
 Taini Devi Division,
 IPRWD, Taini Dev

34

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Gahra to Channaratha via lamher km. 0/00 to 3/500.(Site:- Hiring of JCB/front end loader for removal of slips.)

Sl.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Rs. 2000.00		
				Time:-	Two Months		
				Rate	In Words		
1	Hiring of J.C.B. (front end loader 1 cum capacity with breaker) for widening of road, repair of beams, removal of slips and clearance of drains in all kinds of soil including breaking and chiselling with breaker of soft and hard rock as per direction of Engineer in charge. The JCB or breaker should be made available by the contractor as and when required even on Sunday and other holiday. JCB should be worked minimum 8.00 hours from 9.00AM to 5.00 PM daily and any loss to the public/private property or any accident etc. happened during the course of hiring period shall be the absolute responsibility of the JCB owner which shall have fully compensated by the contractor in all cases. The log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95.00	1050.00	Rupees one thousand fifty only	Per hour	99750.00	
Total							99750.00

- Terms and Condition**
- The contractor shall be responsible for any kind of breakage in the machinery and accident happens during working hours.
 - Nothing shall be paid for idle hours
 - All bear and tear and P.O.L charges are to be born by the contractor.

DNTT No. 21/..... for the year 2025-26 duly approved for Rs. 99,750/- (Ninety nine thousand seven hundred fifty) Only.


 Executive Engineer,
 Tannal Devi Division,
 HPPWD: Tannal Devi.

32

Draft Schedule of Quantity

NAME OF WORK:- A/R & M/O on various roads under Sujampur Sub-Division, H.P.P.W.D., Sujampur. (Sfr:- Tree cutting on Hamirpur Sujampur road km. 8/00 to 16/00 at various RD's).

Sr.No.	Description of Items	Qty.	In Fig.	Estimated Cost:-		Unit	Amount
				Earnest Money:-	Time:-		
1	Felling trees of the girth (measured at a height of 1m (one metre) above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana/leil tax, GST or other taxes imposed by the Government.						
1.01	Hamirpur Sujampur road km. 8/00 to 16/00 trees						
i	Beyond 60 cm (sixty centimetre) girth upto and including 120cm (one hundred twenty centimetre) girth.	300	1390.85	Rupees one thousand three hundred ninety and paise eighty five only	Two Months	Each	4173.00
ii	Beyond 120cm (one hundred twenty centimetre) girth upto and including 240 cm (two hundred forty centimetre) girth.	500	6444.98	Rupees six thousand four hundred forty four and paise ninety eight only		Each	32225.00
iii	Above 240 cm (two hundred forty centimetre) girth	200	12918.25	Rupees twelve thousand nine hundred eighteen and paise twenty five only		Each	25837.00
						Total	62235.00

Terms and Condition
1. Work shall be executed as per PWD specification.

DNR No. 188 for the year 2025-26 and approved by Rs. 62,235/- (Sixty two thousand two hundred thirty five). Only

Executive Engineer,
Tauri Deol Division,
HPPWD-Tauri Deol