

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NO. PWP/CB/Tender Notice/2025-26- 5173-74  
To

Through e-mail  
eeict-pwd-shi@hp.gov.in  
Dated:- 11-09-2025


✓  
The Executive Engineer (IT Cell),  
HPPWD, Nigam Vihar, Shimla-2.  
[eeict-pwd-shi@hp.gov.in](mailto:eeict-pwd-shi@hp.gov.in)  
[cc-pwd-hp@nic.in](mailto:cc-pwd-hp@nic.in)

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 20.09.2025.


Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature due to rainy season and in the public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.(29 Nos.)

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD. Paonta Sahib

Copy forwarded along with tender notice via e mail for information to:-  
1. The Superintending Engineer Nahan 12<sup>th</sup> Circle HP.PWD Nahan for information please.

  
Executive Engineer,  
Paonta B&R Division,  
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed Percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 20.09.2025 up to 02.30 PM and shall be opened on 20.09.2025 the same day at 3.00P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 19.09.2025 for which the applications should reach in this office up to 4.00 PM on 18.09.2025. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Repair of Baila Gang Hut Building . (SH:- Repair of Plaster, Dismantling Door, Window, Wooden work) Non Residential building.	Rs. 99,940/-	Rs. 2000/-	Two Months.	350/-	C & D
2	Repair of Baila Gang Hut Building. (SH:- Distempering with oil paint, Putty water proofing cement paint, Grill and Roof treatment etc) Non residential building.	Rs. 99,989/-	Rs. 2000/-	Two Months.	350/-	C & D
3	Restoration of rain damages to kolar Bilaspur road km. 0/0 to 12/0. (SH:- Repair of pot holes and repair of berms by filling with granular material in km 0/00 to 12/00).	Rs. 98,911/-	Rs. 2000/-	Two Months.	350/-	C & D
4	Restoration of rain damages to kolar Bilaspur road km. 0/0 to 12/0. (SH:- Removal of slips in km 0/00 to 12/00).	Rs. 99,826/-	Rs. 2000/-	Two Months.	350/-	C & D
5	Restoration of rain damages to Jamnighat Jheebankabara Dhaunwala road km 0/0 to 5/200 and Haripur to Jamnighat km. 0/00	Rs. 99,805/-	Rs. 2000/-	Two Months.	350/-	C & D

4

	to 2/00. (SH:- Removal of slips at various RDs).					
6	Restoration of rain damages to various roads under Dhaulakuan Section. (SH:- Repair of pot holes and repair of berms by filling with granular material on various roads).	Rs. 98,911/-	Rs. 2000/-	Two Months.	350/-	C&D
7	Restoration of rain damages to Jamta Rajban road km. 23/00 to 43/00. (SH:- Removal of slips in km 23/00 to 43/00).	Rs. 99,805/-	Rs. 2000/-	Two Months.	350/-	C & D
8	Restoration of rain damages to Jamta Rajban road km. 23/00 to 43/00. (SH:- Repair of pot holes and repair of berms by filling with granular material in km 23/00 to 43/00).	Rs. 98,911/-	Rs. 2000/-	Two Months.	350/-	C & D
9	Restoration of rain damages Mehat Gawana Khali Achon road km.0/00 to 12/00. (SH:- Removal of slips in km 0/00 to 12/00).	Rs. 99,826/-	Rs. 2000/-	Two Months.	350/-	C & D
10	Restoration of rain damages Girinagar Jaton road km. 0/00 to 28/500. (SH:- Removal of slips in km 15/600 to 28/500).	Rs. 99,805/-	Rs. 2000/-	Two Months.	350/-	C & D
11	Restoration of rain damages to link road to Guttanpur km. 0/0 to 2/500. (SH:- Repair of pot holes and repair of berms by filling with granular material in km 0/00 to 2/500).	Rs. 97,975/-	Rs. 2000/-	Two Months.	350/-	C & D
12	Restoration of rain damages on link road from NH-07 to Gadriya Basti Surajpur km.0/00 to 0/650 and Johron Pipliwala Bhagwanpur road 0/00 to 2/00 kms. (SH:- Providing and laying Granular Sub Base, Pot holes, repair of berms at various RDs).	Rs. 98,947/-	Rs. 2000/-	Two Months.	350/-	C & D
13	Restoration of rain damages to Thakkar Kujewala road km. 0/00 to 4/750. (SH:- Removal of slips in km 0/00 to 4/750).	Rs. 99,613/-	Rs. 2000/-	Two Months.	350/-	C & D
14	Restoration of rain damages to Patlion to Surajpur road km. 0/00 to 3/150. (SH:- Providing and laying Granular Sub Base Pot holes, repair of berms at various RDs).	Rs. 98,794/-	Rs. 2000/-	Two Months.	350/-	C & D

J

15	Restoration of rain damages to Badripur Jamniwala Parduni road km. 0/00 to 15/0.and Main road to Jhaba Basti in GP Kundion km. 0/0 to 1/390. (SH:- Repair of Pot holes filling with Granular material and construction of drain at various RDs).	Rs. 98,794/-	Rs. 2000/-	Two Months.	350/-	C & D
16	Restoration of rain damages Paonta Puruwala Singhpura Bhagani Dakpathar road km. 0/0 to 26/500. (MDR-94) (SH:- Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material in km. 3/0 to 8/0).	Rs. 99,135/-	Rs. 2000/-	Two Months.	350/-	C & D
17	Restoration of rain damages Paonta Puruwala Singhpura Bhagani Dakpathar road km. 0/0 to 26/500. (MDR-94) (SH:- Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material and removal of slips in km.23/0 to 25/0).	Rs. 98,965/-	Rs. 2000/-	Two Months.	350/-	C & D
18	Restoration of rain damages to Various road under Puruwala Section under Paonta Sub-Division No. I. (SH:- Dressing of berms and C/O unlined drain at various RDs).	Rs. 97,975/-	Rs. 2000/-	Two Months.	350/-	C & D
19	Repair of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall at RD. 0/874 to 0/878.50). Under VKVNY (MLALAD).	Rs. 99,000/-	Rs. 2000/-	Two Months.	350/-	C & D
20	Repair of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall at RD. 0/868 to 0/872.50). Under VKVNY (MLALAD).	Rs. 98,692/-	Rs. 2000/-	Two Months.	350/-	C & D
21	Repair of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall at RD. 0/862 to 0/866.50). Under VKVNY (MLALAD).	Rs. 98,538/-	Rs. 2000/-	Two Months.	350/-	C & D
22	Restoration of rain damages to Khairni Basti Palhori road km. 0/0 to 7/00. (SH:- Providing and laying Granular Sub Base 2/700 to 2/880 and Repair of pot holes and repair of berms by filling with granular material in km. 0/00 to 3/500).	Rs. 98,911/-	Rs. 2000/-	Two Months.	350/-	C & D

23	Restoration of rain damages to Gulabgarh to Fatehpur road km. 0/0 to 0/500 and GSSS Toka to Laa Devi Mandir in GP Kundion km. 0/0 to 1/525. (SH:- Repair of pot holes filling with granular material and Construction of drain at various RDs).	Rs. 98,947/-	Rs. 2000/-	Two Months.	350/-	C & D
24	Restoration of rain damages to Khairni Basti Palhori road km. 0/0 to 7/00. (SH:- Repair of pot holes and repair of berms by filling with granular material in km. 4/00 to 7/00).	Rs. 98,984/-	Rs. 2000/-	Two Months.	350/-	C & D
25	Restoration of rain damages to Majra Bias Mandir km. 0/00 to 2/340. (SH:- Construction of Retaining wall in Plain Concrete at RD. 1/763 to 1/767.50).	Rs. 99,894/-	Rs. 2000/-	Two Months.	350/-	C & D
26	Restoration of rain damages to link road Majra Bridge to Bias Mandir km. 0/00 to 2/340. (SH:- Construction of Retaining wall in Plain Concrete at RD. 1/768 to 1/772.50).	Rs. 99,527/-	Rs. 2000/-	Two Months.	350/-	C & D
27	Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/0 to 0/045). Under Deposit work.	Rs. 98,294/-	Rs. 2000/-	Two Months.	350/-	C & D
28	Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/045 to 0/095). Under Deposit work.	Rs. 94,497/-	Rs. 2000/-	Two Months.	350/-	C & D
29	Hiring of excavator cum loader for dressing of berms & shoulder along with tractor with trolley under HPPWD (B&R) Paonta Sahib, Sub Division Paonta No. I, for link road Harijan Basti Khairni Palhori upto Simbalwara Km. 0/00 to 5/00 of Behral Section.	Rs. 99,050/-	Rs. 2000/-	Two months	350/-	C & D

**CERTIFICATE:-** Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature due to rainy season and in public interest.

**Conditions:-**

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number, Permanent Account Number and EPF Number.

3. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
4. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
5. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
6. The contractor / Firms are requested to insert the percentage rate in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
7. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills along with proof of ownership of JCB/Affidavit from owner of JCB and Tractor with Trolley on hire basis.
8. GST Clearance Certificate from GST Department and up to date filling return as per instruction issued by the GST Department.

Executive Engineer,  
Paonta B&R Division,  
HP. PWD., Paonta Sahib  
Dated:- 11-09-2024

No.PWP/CB-Tender Notice/2025-26-

5175-5223

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.

Executive Engineer,  
Paonta B&R Division,  
HP. PWD., Paonta Sahib

Job No - 1

24

Name of work :- Repair of Baila Gangghat Building (SH- Repair of plaster, Dismantling door, window, wooden work) (Non Residential building)		SCHEDULE OF QUANTITY			Estimated cost :- Rs. 99940 /- only Earnest Money :- Rs. 2000/- only. Time allowed :- Two months.		
S. No.	Sub-head & item of works	Quantity	Figure	Rate		Unit	Amount
				Words	Amount		
1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all	111.60	264.65	Rs. Two hundred sixty four & paise sixty only.		Per square meter	29535
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : Of area 3 sq. metres and below including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in Charge	8.00	156.25	Rs. One hundred fifty six & paise twenty five only.		Each	1250
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length ( hold fast lugs or dash fastener shall be paid for	0.394	95763.05	Rs. Ninety five thousand seven hundred sixty three & paise zero five		Per cubic meter	37731
4	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws,	7.56	3122.60	Rs. Three thousand one hundred twenty & paise sixty only.		Per square meter	23607
5	Providing and fixing wire gauge laminated veneer lumber shutters conforming to IS : 14616, and as per TADS 15 :2001 (Part B) using galvanised wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm as per IS :1568, for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, as per directions of Engineer-in-charge:	7.86	994.55	Rs. Nine hundred ninety four & paise Fifty five only.		Per square meter	7817
							99940



Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

SCHEDULE OF QUANTITY					9999/-only		
Name of work :- Repair of Baila Gangghat Building (SHI- Distemping with oil paint, putty water proofing cement paint, grill & roof treatemet etc) ( Non Residential building)					Estimated cost :- Rs. 99990/- only Earnest Money :- Rs. 2000/- only. Time allowed :- Two months.		
S. No.	Sub-head & item of works	Quantity	Figure	Rate		Unit	Amount
				Words	Amount		
1	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete :	24.00	70.05	Rs. Seventy & paise zero five only.		Each	1681
2	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete	16.00	32.40	Rs. Thirty two & paise Forty only.		Each	518
3	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	1.00	962.75	Rs. Nine hundred Sixty two & paise seventy five only.		Each	963
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade :	189.13	130.48	Rs. One hundred thirty & paise forty eight only.		Per sqm	24678
5	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	18.91	103.22	Rs. One hundred three & paise twenty two only.		Per sqm	1952
6	Finishing walls with water proofing cement paint of required shade Old work (one or more coats applied @ 2.20 kg/10 sqm) complete	101.52	142.75	Rs. One hundred forty two & paise Seventy five only.		Per sqm	14492
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	23.43	94.3	Rs. Ninety four & paise thirty paise only.		Per sqm	2209
8	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding	81.00	129.20	Rs. One hundred twenty nine & paise twenty only.		Per kg	10465
9	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4	0.54	723.85	Rs. Seven hundred twenty three & paise eighty five only.		Per sqm	391
10	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including of hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer in charge.	7.22	5905.85	Rs. Five thousand nine hundred five & paise eighty five only.		per cum	42640
							99990

Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Kolar Bilaspur road km 0/00 to 12/00 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 0/00 to 12/00)		Job:-		Estimated Cost:- <del>98904</del> /- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.27 cubic metre	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98911.00
<b>Total:-</b>						<b>98911.00</b>

Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 4

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages Kolar Bilaspur road KM 0/00 to 12/00 (SH:- Removal of slips in km 0/00 to 12/00 )		Job:-		Estimated Cost:- 99755/- Only.	
Sub-Head and item of work		Quantity	Unit	Figures	Words
Sr. No.					
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	703.00 cubic metre	Per cubic metre	142.00	Rupees one hundred forty two and paise zero only
					Amount
					99826.00
					Total:-
					99826.00

Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

Job No. S

**SCHEDULE OF QUANTITY**


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	702.85	Per cubic metre	142.00	Rupees one hundred forty two and paise zero only	99805.00
<b>Total:-</b>						<b>99805.00</b>

Name of work:- Restoration of rain damages to Jamnighat jheelbankabara dhauwala road km 0/00 to 5/200 and Haripur to Jamnighat KM 0/00 to 2/00 (SH:- Removal of slips at various RDs )

Job.-

Estimated Cost:- 99755/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - Two Months.


99805/-

  
Executive Engineer,  
Paonta B&R Division  
HP. PWD. Paonta Sahib

Job No. 6.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to various roads under Dhaulakuan Section(SH):- Repair of pot holes and repair of berms by filling with granular material on various roads)		Estimated Cost:- 98911/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.				
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		
				Figures	Words	Amount
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.27 cubic metre	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98911.00
				<b>Total:-</b>		<b>98911.00</b>

  
Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 7.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Jamta Rajban road km 23/00 to 43/00 (SH:- Removal of slips in km 23/00 to 43/00 )		Job:-		Estimated Cost:- 99805 /-		
Sr. No.		Sub-Head and item of work		Earnest Money:- 2000/- Only		
		Quantity		Time Limit:- Two Months.		
		Unit		Rate in		
				Words		
				Figures		
				Amount		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	702.85	Per cubic metre	142.00	Rupees one hundred forty two and paise zero only	99805.00
				Total:-		99805.00

Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

Job No. 8.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Jamta Rajban road km 23/00 to 43/00 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 23/00 to 43/00)		Job.-	Estimated Cost:- <del>98911</del> Only.	
Sub-Head and item of work		Figures	Rate in Words	Amount
Sr. No.	Quantity	Unit	Rate in Words <td>Amount</td>	Amount
1	109.27 cubic metre	Per cubic metre	Rupees nine hundred five and paise twenty only	98911.00
			<b>Total:-</b>	<b>98911.00</b>

98911/-  
 Earned Money:- 2000/- Only  
 Time Limit: - Two Months.

Executive Engineer,  
 Paonta B&R Division  
 HP. PWD, Paonta Sahib

Job No. 9.

99826/-

Estimated Cost:- 99755/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - Two Months.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Mehat Gawana Khali Achon road km 0/00 to 12/00 (SH:- Removal of slips in km 0/00 to 12/00 )		Job:-		Estimated Cost:- 99755/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in
				142.00	Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	703.00 cubic metre	Per cubic metre	142.00	Rupees one hundred forty two and paise zero only
<b>Total:-</b>					<b>99826.00</b>


Executive Engineer,  
Paonta B&R Division  
HP. PWD. Paonta Sahib

Job No. 10.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Girinagar Jaton road km 0/00 to 28/500 (SH:- Removal of slips in km 15/600 to 28/500 )		Job :-		Estimated Cost:- <del>99755/-</del> Only.	
Sub-Head and item of work		Quantity	Unit	Figures	Rate in Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	702.85 cubic metre	Per cubic metre	142.00	Rupees one hundred forty two and paisa zero only
					Amount
					99805.00
<b>Total:-</b>					<b>99805.00</b>

99805/-  
 Earnest Money:- 2000/- Only  
 Time Limit: - Two Months.

  
 Executive Engineer,  
 Paonta B&R Division  
 HP. PWD, Paonta Sahib

**SCHEDULE OF QUANTITY**

Job No. 11.

Sr. No.	Name of work:- Restoration of rain damages to Link road to Guttanpur km 0/0 to 2/500 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 0/0 to 2/500 ) Sub-Head and item of work	Quantity	Unit	Figures	Rate in		Amount
					Words	Amount	
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1200.00 sqm	Per square metre	17.50	Rupees seventeen and paise fifty only	21000.00	
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	850.00 sqm	Per square metre	63.50	Rupees sixty three and paise fifty only	53975.00	
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1000.00 Rmt	Per running metre	23.00	Rupees twenty three and paise zero only	23000.00	
<b>Total:-</b>						<b>97975.00</b>	

Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

Job No. 12.

**SCHEDULE OF QUANTITY**

98947/-

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.31 cubic metre	Cubic metre	905.20	Rupees nine hundred five and paise twenty only	98947.00
<b>Total:-</b>						<b>98947.00</b>

Estimated Cost:- 98947/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - Two Months.

Name of work:- Restoration of rain damaged on link road from NH-07 to Gadiya Basti Surajpur KM 0/00 to 0/650 and Johron Pipiliwla Bhagwanpur road 0/00 to 2/00 kms (SH:- Providing and Laying Granular Sub base, Pot holes, repair of berms at various RDs)

Job.-

Executive Engineer,  
Paonta B&R Division  
HP. PWD. Paonta Sahib

Job No. 13.

99613/-

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Thakkar Kujewala road km 0/00 to 4/750 (SH:- Removal of slips in km 0/00 to 4/750 )		Job:-		Estimated Cost:- 99755/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in
				142.00	Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	701.50 cubic metre	Per cubic metre		Rupees one hundred forty two and paise zero only
<b>Total:-</b>					<b>99613.00</b>

Executive Engineer,  
Paonta B&R Division  
HP. PWD. Paonta Sahib

Job No. 14.


**SCHEDULE OF QUANTITY**

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.14 cubic metre	Cubic metre	905.20	Rupees nine hundred five and paise twenty only	98794
<b>Total:-</b>						<b>98794</b>

Name of work:- Restoration of rain damages to Pattion to Surajpur road km 0/0 to 3/150 (SH:- Providing and Laying Granular Sub base Pot holes, repair of berms ~~and~~ various RDs)

Estimated Cost:- ~~98994/-~~ Only.  
Earnest Money:- 2000/- Only  
Time Limit: - Two Months.

98794/-

  
Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 15.

**SCHEDULE OF QUANTITY**


Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 98794/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.
				Figures	Rate in Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.14 cubic metre	Cubic metre	905.20	Rupees nine hundred five and paise twenty only	98794
<b>Total:-</b>						<b>98794</b>

Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 16.

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages Paonta Puruwala Singhpura Bhagani Dakpathar road km 0/0 to 26/500. (MDR-94) (SH:- Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material in km 3/0 to 8/0.)		Estimated Cost:- 99135/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.				
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per	57.00	hours	1055.00	Rupees one thousand fifty five and paise zero only	60135.00
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	12.00	Days	3250.00	Rupees three thousand two hundred fifty and paise zero only	39000.00
				G.Total		99135.00

  
Executive Engineer,  
Paonta B&R Division  
HP. PWD. Paonta Sahib

Job No. 17.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Paonta Puruwala Singhpura Bhagani Dakpathar road km 0/0 to 26/500 (MDR-94). (SH:- Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material and removal of slips in km 23/0 to 25/0.)		Estimated Cost:- 98965/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.				
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	63.00 hours	Per hour	1055.00	Rupees one thousand fifty five and paise zero only	66465.00
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	10.00 Days	Per day	3250.00	Rupees three thousand two hundred fifty and paise zero only	32500.00
				G.Total		98965.00

Executive Engineer,  
Paonta B&R Division  
HP. PWD, Paonta Sahib

Job No. 18,


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Various road under Puruwalla Section under Paonta Sub Division No I.(SH):- Dressing of berms & c/o unlined drain at Various RDs		Job.- Paonta Sub Division		Estimated Cost:- 97975/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in	Amount
				Figures	
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1200.00 sqm	Per square metre	17.50	Rupees seventeen and paise fifty only 21000.00
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	850.00 sqm	Per square metre	63.50	Rupees sixty three and paise fifty-only 53975.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1000.00 Rmt	Per running metre	23.00	Rupees twenty three and paise zero only 23000.00
				<b>Total:-</b>	<b>97975.00</b>

Executive Engineer,  
Paonta B&R Division  
H.P. PWD, Paonta Sahib

Job No. 19.

Name of Work:- Repair of link road Rampur Bharapur Gunglow road km 0/0 to 5/0 (SHI-C/O R/wall at RD 0/874 to 0/878.50)		Estimated cost:-99000/-only				
Under VKVNY (MILALAD)		Estimated Money:-2000/-only				
Ser No.	Sub heads and items of work.	Qty	Unit	Time:- Two Months		Amount
				Figures	Rate in Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas ( 30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	9.72	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	1847
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	19.31	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	95685
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	4.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	1468
<b>Total</b>						99000

  
**Executive Engineer,**  
**Paonta B&R Division**  
**HP. PWD. Paonta Sahib**

Job No. 20.

Name of Work:- Repair of link road Rampur Bharapur Gunglow road km 0/0 to 5/0 (SH:-C/O R/wall at RD 0/868 to 0/872.50) Under VKVNY (MLALAD)		Schedule of Quantity				Estimated cost:-98692/-only
		Sub heads and items of work.	Qty	Unit	Figures	Rate in Words
Ser No.						Time:-Two Months
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas ( 30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	8.10	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	1539
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	19.31	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	95685
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	4.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	1468
<b>Total</b>						<b>98692</b>

Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 21.


**Schedule of Quantity**

Name of Work:- Repair of link road Rampur Bharapur Gunglow road km 0/0 to 5/0 (SH:-C/O R/wall at RD 0/862 to 0/866.50)  
Under VKVNY (MLALAD)

Estimated cost:-98538/-only  
Estimated Money:-2000/-only  
Time:-Two Months

Sub heads and items of work.

Ser No.	Qty	Unit	Figures	Rate in		Amount
				Words	Amount	
1	7.29	Per cubic metre	190.00	Rupees One hundred ninety and paise nil only	1385	
2	19.31	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	95685	
3	4.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	1468	
<b>Total</b>					<b>98538</b>	

  
Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 22.

**SCHEDULE OF QUANTITY**

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.27	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98911.00
<b>Total:-</b>						<b>98911.00</b>

Name of work:- Restoration of rain damages to Kharini Basti Palhori road km 0/0 to 7/00 (SH):- Providing and Laying Granular Sub base 2/700 to 2/880 and Repair of pot holes and repair of berms by filling with granular material in km 0/00 to 3/500 )

Job.-  
Providing and Laying Granular Sub base 2/700 to 2/880 and Repair of pot holes and repair of berms by filling with granular material in km 0/00 to 3/500 )


Estimated Cost:- 98911/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - Two Months.

Executive Engineer,  
Paonta B&R Division  
HP, PWD, Paonta Sahib

Job No. 23.

**SCHEDULE OF QUANTITY**


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
<p>Name of Work:- Restoration of rain damage to Gulabgarh to Fatehpur road Km 0/0 to 0/500 and GSSS Tokka to Laa Devi Mandir in GP Kundion Km 0/0 to 1/525.(SH):- Repair of Pot holes filling with granular Material and construction of drain at various RDs.)</p>						
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.31 cubic metre	Cubic metre	905.20	Rupees nine hundred five and paise twenty only	98947
<b>Total:-</b>						<b>98947</b>

  
**Executive Engineer,**  
**Paonta S&R Division**  
**HP. PWD, Paonta Sahib**

Job No - 24.

**SCHEDULE OF QUANTITY**

Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 98984/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.
				Figures	Rate in Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.35 cubic metre	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98984.00
				<b>Total:-</b>		<b>98984.00</b>


  
 Executive Engineer,  
 Paonta B&R Division  
 HP, PWD, Paonta Sahib

## SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earth Work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm in plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.	5.06	cum	190.00	Rupees One Hundred Ninety Only.	961.40
2	Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.	16.20	cum	5424.85	Rupees Five Thousand Four Hundred Twenty Four Point Eighty Five Only.	87882.57
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7	20.00	Each	367.00	Rupees Three Hundred Sixty Seven Only.	7340.00
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	18.56	cum	199.90	Rupees One Hundred Ninety Nine Point Ninety Only.	3710.14
Total =						99894.00

Name of Work:-Restoration of rain damages to Majra Blass Mandir km 0/00 to 2/340 (SH: Construction of R/Wall in Plain Cement Concrete at RD 1/763 to 1/767.50)

Estimated Cost:- 99894/-  
 Earnest Money:- 2000/-  
 Time Limit: ~~one~~ **Two** Month.

  
 Executive Engineer,  
 Paonta B&R Division  
 HP. PWD. Paonta Sahib

Job No- 26.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
Name of Work:- Restoration of rain damages to link road Majra Bridge to Bias Mandir km 0/00 to 2/340 (SH: Construction of R/Wall in Plain Cement Concrete at RD 1/768 to 1/772.50)						
				Estimated Cost:- 99527/- Earnest Money:- 2000/- Time Limit: <del>one</del> <b>Two</b> Month.		
1	Earth Work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm in plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m.	5.06	cum	190.00	Rupees One Hundred Ninety Only.	961.40
2	Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.	16.20	cum	5424.85	Rupees Five Thousand Four Hundred Twenty Four Point Eighty Five Only.	87882.57
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7	19.00	Each	367.00	Rupees Three Hundred Sixty Seven Only.	6973.00
4	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	18.56	cum	199.90	Rupees One Hundred Ninety Nine Point Ninety Only.	3710.14
				Total =		99527.00

Executive Engineer,  
Paonta S&R Division  
HP, PWD, Paonta Sahib

Job No- 27

SCHEDULE OF QUANTITY						Estimated cost :- Rs :- 98,294/-	
Name of work:- Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/0 to 0/045). Under Deposit work.						Earnist Money:- Rs:- 2000/- Time:- Two Months.	
Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount	
				Figure	Words		
1	Excavation in earth work in hilly area in all kinds of soils such as pick work, Jumper work, soft and hard rock and hard rock including chiseling, wedging out of rock (where blasting is prohibited), if required and saturated soil and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer -in-charge. The recovery of the stones whether useful or not for 21.74 (Twenty one decimal seventy four) cubic metre in all cases at the rate of Rupees 300/-only (Three hundred only) per cubic metre shall be effected on pro rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be dully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge.	434.93	Per Cubic metre	226.00	Rupees-Two hundred twenty six and paise nil only	98294.00	
<b>Total :-</b>							<b>98294.00</b>

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Executive Engineer,  
Executive Engineer,  
Punjab Road Division  
H.P. PWD, Raigarh Subdiv

Jobno- 28.

SCHEDULE OF QUANTITY					Estimated cost :- Rs :- 94,497/-	
Name of work:- Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/045 to 0/095). Under Deposit work.					Earnist Money:- Rs:- 2000/- Time:- Two Months.	
Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Excavation in earth work in hilly area in all kinds of soils such as pick work, jumper work, soft and hard rock and hard rock including chiseling, wedging out of rock (where blasting is prohibited), if required and saturated soil and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer -in-charge. The recovery of the stones whether useful or not for 21.74(Twenty one decimal seventy four) cubic metre in all cases at the rate of Rupees 300/-only (Three hundred only) per cubic metre shall be effected on pro rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge.	418.13	Per Cubic metre	226.00	Rupees-Two hundred twenty six and paise nil only	94497.00
<b>Total :-</b>						<b>94497.00</b>

Quoted rate in Figure (+/-) (.....%)


Quoted rate in words (+/-) (.....%)

Executive Engineer,  
Roads (B&R) Division  
H.P.P.W.D. Paonta Sahib

Job No - 29

**SCHEDULE OF QUANTITY**

Name of work :- Hiring of excavator cum loader for dressing of berms & sholder along with tractor with trolley under HPPWD(B&R) Paonta Sahib, Sub. Division Paonta-I for Link road harijan basti kherni palhori upto simbalwara km 0/00 to 5/00 of Behral section.		Qty.	Unit	Figures	Rate In		Amount
					Item of Work	Words	
1	Hiring of excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	60.00	Hrs	1055.00	Rupees One Thousand Fifty Five only	63300.00	
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	11.00	Days	3250.00	Rupees Three Thousand Two Hundred Fifty only	35750.00	
						<b>Total:-</b>	<b>99050.00</b>

  
 Executive Engineer,  
 Paonta B&R Division  
 HP. PWD. Paonta Sahib