

**Himachal Pradesh
Public works Department
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **01-11-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **31-10-2025**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 30-10-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- Construction of B/wall at RD 117/920 to 117/945) Under PDNA	310414	6300	Two Months
2	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- Construction of B/wall at RD 115/250 to 115/260) Under PDNA	235851	4800	Two Months
3	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00(SH:- Construction of R/wall at RD 125/690 to 125/708) Under PDNA	407210	8200	Two Months
4	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- construction of R/wall at RD 118/610 to 118/625) Under PDNA	416485	8400	Two Months
5	RRD on Shimla Mandi via Tattapani road km. 115/00 to 135/00 (SH:- construction of R/wall at RD 134/780 to 134/794) Under PDNA	436540	8800	Two Months
6	RRD on Chail Gohar Pandoh road km 0/00 to 24/00 (SH:- construction of PCC R/wall with Toe wall at RD 1/865 to 1/884.50) Under PDNA	487427	9800	Two Months
7	RRD on Kot Devidarh road km. 0/00 to 22/500 (SH:- C/o PCC R/wall at RD 5/690 to 5/705 with parapets) Under PDNA	445881	9000	Two Months
8	RRD on Kot Devidarh road km. 0/00 to 22/500 (SH:- Construction of PCC R/wall at RD 14/820 to 14/830) Under PDNA	291887	5900	Two Months
9	RRD on Kot Devidarh road km. 0/00 to 22/500(SH:- construction of PCC & wire crate B/wall at RD 1/315 to 1/340) Under PDNA	481531	9700	Two Months

10	RRD on Jachh to Lot road km.0/00 to 6/300 (SH:- Construction of PCC R/wall at RD 4/795 to 4/805) Under PDNA	193190	3900	Two Months
11	RRD on Kot Devidarh road km. 0/00 to 22/500(SH:- Construction of PCC R/wall at RD 8/660 to /675) Under PDNA	385281	7800	Two Months
12	RRD on Kot Devidarh road km. 0/00 to 22/500(SH:- Construction of PCC R/wall at RD 21/860 to 21/875) Under PDNA	329640	6600	Two Months
13	RRD on Kot Devidarh road km. 0/00 to 22/500 (SH:- Construction of PCC R/wall at RD 8/060 to 8/075) Under PDNA	385479	7800	Two Months
14	RRD on kukadigalu saroa road km 0/00 to 8/00 (SH:- construction of stone Masonry R/wall at RD 4/300 to 4/320)	427029	8600	Two Months
15	RRD on Chail Moviseri road km. 0/00 to 11/200(SH:- construction of PCC R/wall at RD 2/775 to2/782)	205691	4200	Two Months
16	RRD on Old Shimla Mandi road km. 0/00 to 5/250 (SH:- construction of PCC R/wall at RD 2/415 to 2/425.60) Under PDNA	292818	5900	Two Months
17	RRD on Kainad to Chattar road km. 0/00 to 1/00 (SH:- Providing and laying CC Pavement from km. 0/860 to 1/00) Under PDNA	479030	9600	Two Months
18	RRD on Maloh Kateru road km. 0/00 to 14/250 (SH:- Providing and laying Interlocking Paver block 80 mm thick in km. 9/905 to 10/00) Under PDNA	474731	9500	Two Months
19	RRD on Maloh Kateru road km. 0/00 to 14/250 (SH:- Repair f pot holes at various RDs Between km. 6/00 to 14/250) Under PDNA	498540	10000	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.

8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated 23-10-2025

No. PW-GHR-Tender/NIT/2025

5766-75

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.
4. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.


Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

BILL OF QUANTITY

Name of work :- RRD on Shimla Mandi via Tattapani road km 115/000 to 135/000 (SH:- Construction of B/Wall at RD 117/920 to 117/945) जेडर पदना


Estimated cost Rs. - 3,10,414/-
Earnest Money cost Rs.6300/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	50.00	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	66.70	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	23.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Jhansi


BILL OF QUANTITY

Description of work :- RRD on Shimla Mandi via Tattapani road km 115/000 to 135/000 (SH:- Construction of R/Wall at D 115/250 to 115/260) Under PDMA						Estimated cost Rs. - 2,35,851/-
						Earnest Money cost Rs.4800/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	26.75	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	49.53	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	7.75	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	16.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Shimla Mandi via Tattapani road km 115/000 to 135/000 (SH:- Construction of R/Wall at RD 125/690 to 125/708) Under PDNA						Estimated cost Rs. - 4,07,210/-
						Earnest Money cost Rs.8200/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	52.38	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	84.06	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	16.47	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	32.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 K.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Shimla Mandi via Tattapani road km 115/000 to 135/000 (SH:- Construction of R/Wall at RD 118/610 to 118/625) Under PDNA					Estimated cost Rs. - 4,16,485/-	Earnest Money cost Rs.8400/-	Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	52.62	Per Cubic meter	230.00			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	88.89	Per Cubic meter	4350.20			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	7.42	Per Cubic meter	1050.60			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	26.00	Each	380.70			
Total:-							
Percentage rate Quoted in figure							
Percentage rate Quoted in words							



 Executive Engineer,
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Shimla Mandi via Tattapani road km 115/000 to 135/000 (SH:- Construction of R/Wall at RD 134/780 to 134/794) Under PDNA

Estimated cost Rs. - 4,36,540/-
Earnest Money cost Rs.8800/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	60.97	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	92.76	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	9.38	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	24.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.A.W.D. Gohar

143

BILL OF QUANTITY

Name of work :- RRD on Chail Gohar Pandoh road km 0/00 to 24/00 (SH:- Construction of PCC R/Wall with Toe wall at RD 1/865 to 1/884.50) Under PDNA

Estimated cost Rs. - 4,87,427/-
Earnest Money cost Rs.9800/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	57.53	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	103.21	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	13.85	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	28.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY

Name of Work:- RRD on Kot Devidarh road km. 0/00 22/500 (SH:- C/o PCC R/wall at RD. 5/690 to 5/705 with parapets) .
 under PDNA

Estimated cost Rs. - 445881.00

Earnest Money cost Rs. - 9000.00

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.80	Per Cubic metre	230.00		
2	Providing and laying dowel br in foundation in hard roak including making hole for dowell bar and fixing 25 mm (twenty five millimetre) dia tor steel in cement with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	16.00	Each	948.65		
3	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	89.85	Per cubic metre	4350.20		
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	19.43	Per cubic metre	1050.60		
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	30.00	Each	380.70		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Divlsign
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Kot Devidarh road km 0/00 to 22/500 (SH:- Construction of PCC R/Wall at RD 14/820 to 14/830) Under PDNA					Estimated cost Rs. - 2,91,887/-	
					Earnest Money cost Rs.5900/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	30.50	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	62.94	Per Cubic meter	4350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	8.00	Per Cubic meter	1050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	7.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

127


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Kot Devidarh road km 0/00 to 22/500 (SH:- Construction of PCC & wire crate B/Wall at RD 1/315 to 1/340) Under PDNA						
					Estimated cost Rs. - 4,81,531/-	
					Earnest Money cost Rs.9700/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	143.88	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	45.00	Per Cubic meter	4350.20		
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10% of laps laid with boulders apron weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	75.60	Per Cubic meter	3078.30		
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	19.00	Per Cubic meter	1050.60		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY

Name of work: RRD on Jachh to Lot road km 0/00 to 6/300 (SH:- Construction of PCC R/Wall at Rd 4/795 to 1/805, Under PDNA)

Estimated cost Rs. - 1,93,190/-

Earnest Money cost Rs.3900/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.80	Per Cubic meter	230.00	3,634.00	Rupees Three Thousand Six Hundred Thirty Four Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	41.44	Per Cubic meter	4,350.20	1,80,272.00	Rupees One Lakh(s) Eighty Thousand Two Hundred Seventy Two Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	6.30	Per Cubic meter	1,050.60	6,619.00	Rupees Six Thousand Six Hundred Nineteen Only
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause	7.00	Each	380.70	2,665.00	Rupees Two Thousand Six Hundred Sixty Five Only
Total:-					1,93,190.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of Quantity approved for Rs. 1,93,190/- only.

Risali
Executive Engineer
Gonar Division
H.P.W.D. Bohar

BILL OF QUANTITY

Name of work :- RRD on Kot Devidarh road km 0/00 to 22/500(SH:- Construction of PCC R/Wall at Rd 8/660 to 8/675) Under PDNA

128

Estimated cost Rs. - 3,85,281/-
Earnest Money cost Rs.7800/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.50	Per Cubic meter	230.00	7,935.00	Rupees Seven Thousand Nine Hundred Thirty Five Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	80.35	Per Cubic meter	4,350.20	3,49,539.00	Rupees Three Lakh(s) Forty Nine Thousand Five Hundred Thirty Nine Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	17.85	Each	380.70	6,795.00	Rupees Six Thousand Seven Hundred Ninety Five Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	20.00	Per Cubic meter	1,050.60	21,012.00	Rupees Twenty One Thousand Twelve Only
Total:-					3,85,281.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of Quantity approved for Rs. 3,85,281/- only.

Executive Engineer.
Gohar Division
H.P.P.W.D. Gohar

(61)

BILL OF QUANTITY

Name of work :- RRD on Kot Devidarh road km 0/00 to 22/500 (SH:- Construction of PCC R/Wall at Rd 21/860 to 21/875) Under PDNA					Estimated cost Rs. - 3,29,640/-	Time - Two Month
					Earnest Money cost Rs.6600/-	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 u/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	31.65	Per Cubic meter	230.00	7,280.00	Rupees Seven Thousand Two Hundred Eighty Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	70.64	Per Cubic meter	4,350.20	3,07,298.00	Rupees Three Lakh(s) Seven Thousand Two Hundred Ninety Eight Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	10.35	Per Cubic meter	1,050.60	10,874.00	Rupees Ten Thousand Eight Hundred Seventy Four Only
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause	11.00	Each	380.70	4,188.00	Rupees Four Thousand One Hundred Eighty Eight Only
Total:-					3,29,640.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of Quantity approved for Rs. 3,29,640/- only

*Resdnt
Executive Engineer
Gopal D. Dasgupta
H.P.P.W.D. Gopani*

90

BILL OF QUANTITY

Name of work :- RRD on Kot Devidarh road km 0/00 to 22/500(SH:- Construction of PCC R/Wall at Rd 8/060 to 8/075) Under PDNA

Estimated cost Rs. -3,85,479/-

Earnest Money cost Rs.7800/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	34.73	Per Cubic meter	230.00	7,988.00	Rupees Seven Thousand Nine Hundred Eighty Eight Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	80.35	Per Cubic meter	4,350.20	3,49,539.00	Rupees Three Lakh(s) Forty Nine Thousand Five Hundred Thirty Nine Only
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	18.23	Each	380.70	6,940.00	Rupees Six Thousand Nine Hundred Forty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	20.00	Per Cubic meter	1,050.60	21,012.00	Rupees Twenty One Thousand Twelve Only
Total:-					3,85,479.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of Quantity approved for Rs. 385479/- only.

R.S. Singh
Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

60

BILL OF QUANTITY

5

15

Name of work :- RRD on Kukadigalu Saroa road km 0/00 to 8/00 (SH:- Construction of stone Masonry R/Wall at rd 4/300 to 1/320)

Estimated cost Rs. - 4,27,029/-

Earnest Money cost Rs.8600/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	22.55	Per Cubic meter	230.00	5,187.00	Rupees Five Thousand One Hundred Eighty Seven Only
2	Providing and laying cement concrete 1:6:12 (one cement : six sand twelve graded crushed stone aggregate 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	8.74	Per Cubic meter	4,150.60	36,276.00	Rupees Thirty Six Thousand Two Hundred Seventy Six Only
3	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	3.57	Per Cubic meter	4,820.10	17,208.00	Rupees Seventeen Thousand Two Hundred Eight Only
4	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704,1202 and 1204 (random rubble masonry in cement mortar : 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge complete in all respect.	29.21	Per Cubic meter	5,250.20	1,53,358.00	Rupees One Lakh(s) Fifty Three Thousand Three Hundred Fifty Eight Only
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge completer in all respect.	65.54	Per Cubic meter	3,150.60	2,06,490.00	Rupees Two Lakh(s) Six Thousand Four Hundred Ninety Only

5

6.	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads, lifts and carriage of materials and other incidentals as per direction of Engineer -in -Charge completer in all respect.	8.10	Per Cubic meter	1,050.60	8,510.00	Rupees Eight Thousand Five Hundred Ten Only
	Total:-				4,27,029.00	
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Bill of Quantity approved
for Rs. 4,27,029/- only.

R. Singh
Executive Engineer
Gohar Division
H.P.W.D. Gohar

DDMIA

32

15

2

BILL OF QUANTITY


Name of work :- RRD on Chail Moviseri road km 0/00 to 11/200 (SH:- Construction of PCC R/Wall at Rd 2/775 to 2/782)						Estimated cost Rs. - 2,05,691/-
						Earnest Money cost Rs.4200/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.62	Per Cubic meter	230.00	4,283.00	Rupees Four Thousand Two Hundred Eighty Three Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crushed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	43.93	Per Cubic meter	4,350.20	1,91,104.00	Rupees One Lakh(s) Ninety One Thousand One Hundred Four Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	5.46	Per Cubic meter	1,050.60	5,736.00	Rupees Five Thousand Seven Hundred Thirty Six Only
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	12.00	Each	380.70	4,568.00	Rupees Four Thousand Five Hundred Sixty Eight Only
Total:-					2,05,691.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of Quantity approved
for Rs. 2,05,691/- only

Executives Engr.
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Old Shimla Mandi road km 0/00 to 5/250 (SH:- Construction of PCC R/Wall at RD 2/415 to 2/425.60) Under PDNA					Estimated cost Rs. - 2,92,818/-	Earnest Money cost Rs.5900/-	Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.58	Per Cubic meter	230.00			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	59.89	Per Cubic meter	4350.20			
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	19.71	Per Cubic meter	1050.60			
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	21.00	Each	380.70			
Total:-							
Percentage rate Quoted in figure							
Percentage rate Quoted in words							


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

82

BILL OF QUANTITY

Name of work :- RRD on Kainad to Chattar road km 0/00 to 1/00 (SH:- Providing and laying CC Pavement from km 0/860 to 1/00) Under PDNA

Estimated cost Rs. - 4,79,030/-


Earnest Money cost Rs.9600/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	164.70	Per Cubic meter	230.00		
2	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	82.35	Per Cubic meter	1990.20		
3	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	54.90	Per Cubic meter	5058.20		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY

Name of work :- RRD on Maloh Kateru road km 0/00 to 14/250 (SH:- Providing and laying Interlocking Paver block 80 mm thick in km 9/905 to 10/00) Under PDNA					Estimated cost Rs. - 4,74,731/-	
					Earnest Money cost Rs.9500/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	29.45	Per Cubic meter	230.00		
2	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	29.45	Per Cubic meter	5050.20		
3	Providing and Laying of interlocking concrete Block pavements having thickness 80 mm. as per drawings and Technical Specification clause 1504. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer - in - charge .	285.00	Per Cubic meter	1120.10		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Maloh Kateru road km 0/00 to 14/250 (SH:-Repair of pot holes at various Rds Between km 6/00 to 14/250) Under PDNA					Estimated cost Rs. - 4,98,540/-	
					Earnest Money cost Rs.,10,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1.00	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405. (By manual means) including all leads, lifts of material and other incidentals as per direction of Engineer-in-Charge complete in all respect.	10.23	per Cubic metre	2,550.10		
2.00	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1516.70	per Square metre	21.15		
3.00	Providing, laying and rolling of open-graded premix carpet of 20 mm (twenty millimetre) thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type B as per Technical Specification Clause 508. with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1516.70	per Square metre	210.15		
4.00	Providing and laying seal coat sealing the void in a bituminous surface laid to the specified levels grade and cross fall using type B as per Technical Specification Clause 510 by Mechanical Means bitumen (S-90/ VG-10) as per direction and entire satisfaction of Engineer-in-Charge with in all leads, lifts and carriage of materials and other incidentals	1516.70	per Square metre	80.20		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

