



No. PW.CHD.CB.E-9/2025-

6762-64

Dated : 09/10/25


To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla, H.P.

Subject :- Publication of Tender Notice.


Sir,

Enclosed please find herewith the tender notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification vide Pr.Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May, 2021 and PBW(B)A(3)1/2020 dated 16th July, 2021 and even file dated 12.01.2023 as the work(s) mentioned in the tender notice is(are) urgent in nature and in public interest.


Executive Engineer,
Chopal Division,
HPPWD Chopal.

Copy forwarded for further necessary action to the :-

1. The Superintending Engineer, 04th Circle, HPPWD Shimla;
2. Computer Cell O/o the Executive Engineer, (IT Cell) Nigam Vihar Shimla-2.


Executive Engineer,
Chopal Division,
HPPWD Chopal.



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2024-

6662-6761

Dated : 09/10/25

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 22.10.2025 up to 04:00 PM
2. Date and time of issue of tender form : 22.10.2025 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 23.10.2025 11:00 AM
4. Date and time of opening of tender : 23.10.2025 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1.	Restoration of rain damages on KNDC road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 123/105 to 123/110)	98,029.00	2000.00	350.00	One month	Class D or above
2.	Restoration of rain damages on KNDC road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 119/930 to 119/940)	97256.00	2000.00	350.00	One month	Class D or above
3.	Restoration of rain damages on KNDC road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 119/950 to 119/960)	97,774.00	2000.00	350.00	One month	Class D or above
4.	Restoration of rain damages on KNDC road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 122/560 to 122/570)	97874.00	2000.00	350.00	One month	Class D or above
5.	Restoration of rain damages on Sailpab to Kupvi road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 119/980 to 119/990)	98776.00	2000.00	350.00	One month	Class D or above
6.	Restoration of rain damages on Sailpab to Kupvi road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 119/900 to 119/910)	98776.00	2000.00	350.00	One month	Class D or above
7.	Restoration of rain damages on Sailpab to Kupvi road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 120/0 to 120/005)	92069.00	2000.00	350.00	One month	Class D or above
8.	Restoration of rain damages on Sailpab to Kupvi road km 110/500 to 132/0 (SH:- C/O Wire crate R/Wall at RD 120/990 to 120/995)	92069.00	2000.00	350.00	One month	Class D or above
9.	Restoration of rain damages on Kupvi to Mashor road km 0/00 to 22/0 (SH:- C/O Wire crate R/Wall at RD 0/010 to 0/015)	99318.00	2000.00	350.00	One month	Class D or above
10.	Restoration of rain damages on Kupvi to Mashor road km 0/00 to 22/0 (SH:- C/O Wire crate R/Wall at RD 0/0 to 0/005)	99318.00	2000.00	350.00	One month	Class D or above


11.	Restoration of rain damages on Kupvi to Mashot road km 0/00 to 22/0 (SH:- C/O R/Wall at RD 1/735 to 1/744)	85587.00	1800.00	350.00	One month	Class D or above
12.	Restoration of rain damages on Sainikhad Dimmi Trahan road km 0/00 to 21/0 (SH:- C/O Wire crate B/Wall at RD 20/250 to 20/255)	94187.00	1900.00	350.00	One month	Class D or above
13.	Restoration of rain damages on Sainikhad Dimmi Trahan road km 0/00 to 21/0 (SH:- C/O Wire crate R/Wall at RD 20/265 to 20/275)	97874.00	2000.00	350.00	One month	Class D or above
14.	Restoration of rain damages on Trahan to Banah road km 0/00 to 11/285 (SH:- C/O B/Wall at RD 1/785 to 1/795)	94187.00	1900.00	350.00	One month	Class D or above
15.	Restoration of rain damages on Trahan to Banah road km 0/00 to 11/285 (SH:- C/O B/Wall at RD 1/805 to 1/815)	94187.00	1900.00	350.00	One month	Class D or above
16.	Restoration of rain damages on Trahan to Banah road km 0/00 to 11/285 (SH:- C/O B/Wall at RD 1/765 to 1/775)	94187.00	1900.00	350.00	One month	Class D or above
17.	Restoration of rain damages on Manjholi to Chanjah road km 0/00 to 11/0 (SH:- C/O B/Wall at RD 2/290 to 2/300)	94523.00	1900.00	350.00	One month	Class D or above
18.	Restoration of rain damages on Manjholi to Chanjah road km 0/00 to 11/0 (SH:- C/O B/Wall at RD 2/305 to 2/315)	94523.00	1900.00	350.00	One month	Class D or above

TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
12. The contractor/firm having necessary documents and past adequate experience shall be preferred.
13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. If any kind of holiday to be happened, the tender documents shall be sold/opened on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.

CERTIFICATE

It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-

1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs.98029
Earnest money :	Rs.2000
Time allowed :	One month

Time of work :- R/R damages on KNDC road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 123/105 to 123/110).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious materialand disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	8.25	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	1733
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90596
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.00	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	5700
Quoted rate in figure.				Total	98029
Quoted rate in words.					

DNIT No DD-144 For the year 2026
Draft schedule of quantities duly
approved 98029/- only
for Rs. 98029/- only


Executive Engineer
B & R Division
H&PWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Name of work :- R/R damages on KNDC road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 119/930 to 119/940).

Estimated cost :	Rs.97256
Earnest money :	Rs.2000
Time allowed :	One month

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	210.00	Rupees two hundred ten and paise zero only	Per cubic metre	2100
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paise zero only	Per Cubic Meter	90596
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.80	950.00	Rupees nine hundred fifty and paise zero only	Per Cubic Meter	4560
Quoted rate in figure.				Total	97256
Quoted rate in words.					

DNIT No. DL-148 of the year 25-26
Draft schedule of quantities duly
approved 92256/only
for Rs. 92256/only

Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

3

Line of work :- R/R damages on KNDC road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 119/950 to 119/960).

Estimated cost :	Rs.97774
Earnest money :	Rs.2000
Time allowed :	One month

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.20	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	1932
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2800.00	Rupees two thousand eight hundred and paisa zero only	Per Cubic Meter	87472
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.30	900.00	Rupees nine hundred and paisa zero only	Per Cubic Meter	8370
				Total	97774
Quoted rate in figure.					
Quoted rate in words.					

DNIT No. DL-143 For the year 25-26
Draft schedule of quantities duly
approved
for Rs. 9994/only


Executive Engineer
B & R Division
MPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Name of work :- R/R damages on KNDC road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 122/560 to 122/570).

Estimated cost :	Rs.97874
Earnest money :	Rs.2000
Time allowed :	One month

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.30	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	3003
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS: 280 and IS:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90596
3	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.50	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	4275
	Quoted rate in figure.				Total	97874
	Quoted rate in words.					

DNIT No. DL-141 For the year 25-26

Draft schedule of quantities duly

approved

for Rs. 99874/only

Executive Engineer

B & R Division

14PPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs.98776
Earnest money :	Rs.2000
Time allowed :	One month

name of work :- R/R damages on Sailpab to Kupvi road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 119/980 to 119/990).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	210.00	Rupees two hundred ten and paise zero only	Per cubic metre	2100
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paise zero only	Per Cubic-Meter	90596
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.40	950.00	Rupees nine hundred fifty and paise zero only	Per Cubic Meter	6080
Quoted rate in figure.				Total	98776
Quoted rate in words.					

DNIT No. 01-14 For the year. 25-26
Draft schedule of quantities duly
approved 98996/only
for Rs.

Executive Engineer
B & R Division
HDP/VID Chonai

DRAFT/SCHEDULED OF QUANTITY.

6

Name of work :- R/R damages on Sailpab to Kupvi road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 119/900 to 119/910).

Estimated cost :	Rs.98776
Earnest money :	Rs.2000
Time allowed :	One month

Description of item	Qty.	Rate	In words	Unit	Amount
		In figure			
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	10.00	210.00	Rupees two hundred ten and paiza zero only	Per cubic metre	2100
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paiza zero only	Per Cubic Meter	90596
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.40	950.00	Rupees nine hundred fifty and paiza zero only	Per Cubic Meter	6080
Quoted rate in figure.				Total	98776
Quoted rate in words.					

DNIT No. DL-13.9 For the year: 25-26
Draft schedule of quantities duly
approved
for Rs. 98776/- only

[Signature]
Executive Engineer
B & R Division
MPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.


7

Estimated cost :	Rs.92069
Earnest money :	Rs.2000
Time allowed :	One month

Time of work :- R/R damages on Sailpab to Kupvi road Km 110/00 to 132/00.
(SH :- C/O wire crate R/Wall at RD 120/00 to 120/005).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.15	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	1502
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.23	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90567
Quoted rate in figure.				Total	92069
Quoted rate in words.					

DNIT No. ~~01-138~~ For the year ~~25-26~~
Draft schedule of quantities duly
approved
for Rs. 92069/only


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

name of work :- R/R damages on Sailpab to Kupvi road Km 110/00 to 132/00.

(SH :- C/O wire crate R/Wall at RD 120/990 to 120/995).

Estimated cost :	Rs.92069
Earnest money :	Rs.2000
Time allowed :	One month

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.15	210.00	Rupees two hundred ten and paise zero only	Per cubic metre	1502
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.23	2900.00	Rupees two thousand nine hundred and paise zero only	Per Cubic Meter	90567
				Total	92069
Quoted rate in figure.					
Quoted rate in words.					

DNIT No. 01-138 For the year. 25-26
Draft schedule of quantities duly
approved 92069/only
for Rs. 92069/only

Executive Engineer
B&R Division
H&P&WD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs.99318
Earnest money :	Rs.2000
Time allowed :	One month

Time of work :- R/R damages on Kupvi to Mashot road Km 0/00 to 22/00.
(SH :- C/O wire crate R/Wall at RD 0/010 to 0/015).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.12	200.00	Rupees two hundred and paise zero only	Per cubic metre	5624
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2800.00	Rupees two thousand eight hundred and paise zero only	Per Cubic Meter	87500
Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.25	4955.20	Rupees four thousand nine hundred fifty five and twenty paise only	Per cubic metre	6194
Quoted rate in figure.				Total	99318
Quoted rate in words.					

DNIT No. 01-136 For the year. 25-26
Draft schedule of quantities duly
approved 99318/only
for Rs.

Executive Engineer
B & R Division
H.P.V.M.D. Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs. 99318
Earnest money :	Rs. 2000
Time allowed :	One month

Name of work :- R/R damages on Kupvi to Mashot road Km 0/00 to 22/00.

(SH :- C/O wire crate R/Wall at RD 0/00 to 0/05).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.12	200.00	Rupees two hundred and paise zero only	Per cubic metre	5624
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is: 4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2800.00	Rupees two thousand eight hundred and paise zero only	Per Cubic Meter	87500
Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.25	4955.20	Rupees four thousand nine hundred fifty five and twenty paise only	Per cubic metre	6194
Quoted rate in figure.				Total	99318
Quoted rate in words.					

DNIT No. 01.13.1 For the year 2020-21
Draft schedule of quantities duly

approved for Rs. 99318 only

Executive Engineer
B & R Division
HPPWD Chennai

DRAFT / SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 85587
Earnest Money	Rs. 1800
Time Allowed	Two Months

Name of work : R/R Damages on Kupvi to Mashot road Km 0/00 to 22/00.
(SH : C/O B/wall at RD 1/735 to 1/744).

Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.13	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	2967
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & viberated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.35	5200.00	Rupees five thousand two hundred and paisa zero only	Per cubic metre.	7020

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 94187
Earnest Money	Rs. 1900
Time Allowed	One Months

Name of work : R/R Damages on Sainj Khad to Dimmi Tarah road Km 0/00 to 21/00.

(SH : C/O wire crate B/wall at RD 20/250 to 20/255).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.10	210.00	Rupees two hundred ten and paise zero only	Per cubic metre.	3591
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paise zero only	Per cubic metre.	90596
					Total	94187
	Quoted rate in figure.					
	Quoted rate in words.					

DNIT No. DL-133 For the year 2025-26
Draft schedule of quantities duly

approved
of Rs. 94187/- only

[Signature]
Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

13

Estimated Cost	Rs. 97874
Earnest Money	Rs. 2000
Time Allowed	One Months

Name of work : R/R Damages on Sainj Khad to Dimmi Tarah road Km 0/00 to 21/00.

(SH : C/O R/Wall wire crate at RD 20/265 to 20/275).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.30	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	3003
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is. 280 and Is.4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre	90596

DRAFT/SCHEDULED OF QUANTITY.

14

Estimated Cost	Rs. 94187
Earnest Money	Rs. 1900
Time Allowed	One Months

Name of work : R/R Damages on Tarah Banah road Km 0/00 to 11/285.
(SH : C/O B/Wall at RD 1/785 to 1/795).

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.10	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre.	3591
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre.	90596
					Total	94187
	Quoted rate in figure.					
	Quoted rate in words.					

DNIT No. DL-131 For the year. 25-26
Draft schedule of quantities duly

approved
for Rs. 94187/- only

Ex-officio Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

15

Estimated Cost	Rs. 94187
Earnest Money	Rs. 1900
Time Allowed	One Months

Name of work : R/R Damages on Tarah Banah road Km 0/00 to 11/285.

(SH : C/O B/Wall at RD 1/805 to 1/815).

Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol. 1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.10	210.00	Rupees two hundred ten and paise zero only	Per cubic metre.	3591
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol. 1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paise zero only	Per cubic metre.	90596
					Total	94187
	Quoted rate in figure.					
	Quoted rate in words.					

DNIT No. DL-130 For the year 2025-26
Draft schedule of quantities duly

approved
for Rs. 94187/only


Executive Engineer
HPPWD Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

16

Estimated Cost
Rs. 94187
Earnest Money
Rs. 1900
Time Allowed
One Months

Name of work : R/R Damages on Tarah Banah road Km 0/00 to 11/285.
(SH : C/O B/Wall at RD 1/765 to 1/775).

Sl. No.	Description of item	Qty.	Rate		In words	Unit	Amount
			In figure				
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.10	210.00		Rupees two hundred ten and paisa zero only	Per cubic metre .	3591
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00		Rupees two thousand nine hundred and paisa zero only	Per cubic metre .	90596
						Total	94187
	Quoted rate in figure.						
	Quoted rate in words.						

DNIT No. For the year. 25-26
Draft schedule of quantities duly
approved
for Rs. 94187 only

Executive Engineer
B & R Division
PPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

17

Name of work : R/R Damages on Manjholi to Chanjha road Km 0/00 to 11/00. (SH : C/O wire crate B/wall at RD 2/290 to 2/300).		Estimated Cost		Rs. 94523		
		Earnest Money		Rs. 1900		
		Time Allowed		One Months		
Sl. No.	Description of item	Qty.	Rate In figure	In words	Unit	Amount
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.70	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre .	3927
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paisa zero only	Per cubic metre .	90596
					Total	94523
	Quoted rate in figure.					
	Quoted rate in words.					

DNIT No..... For the year... 25-26

Draft schedule of quantities duly

approved for Rs. 99523/only

Executive Engineer
B & R Division
MPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

8

Estimated Cost	Rs. 94523
Earnest Money	Rs. 1900
Time Allowed	One Months

Name of work : R/R Damages on Manjholi to Chanjha road Km 0/00 to 11/00.

(SH: C/O wire crate B/wall at RD 2/305 to 2/315).

Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount
			In figure			
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.70	210.00	Rupees two hundred ten and paise zero only	Per cubic metre .	3927
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts. as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.24	2900.00	Rupees two thousand nine hundred and paise zero only	Per cubic metre .	90596
					Total	94523

Quoted rate in figure.


Quoted rate in words.

DNIT No..... For the year 2025-26

Draft schedule of quantities duly

approved

for Rs. 94,523/-


 Executive Engineer
 B & R Division
 APPWD Chopal