



No. PW.CHD.CB.E-9/2025-

6865-67

Dated : 09/10/25


To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla, H.P.

Subject :- Publication of Tender Notice.


Sir,

Enclosed please find herewith the tender notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification vide Pr.Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May, 2021 and PBW(B)A(3)1/2020 dated 16th July, 2021 and even file dated 12.01.2023 as the work(s) mentioned in the tender notice is(are) urgent in nature and in public interest.


Executive Engineer,
Chopal Division,
HPPWD Chopal.

Copy forwarded for further necessary action to the :-

1. The Superintending Engineer, 04th Circle, HPPWD Shimla;
2. Computer Cell O/o the Executive Engineer, (IT Cell) Nigam Vihar Shimla-2.


Executive Engineer,
Chopal Division,
HPPWD Chopal.



Office 01783-260033
Email : ee-cho-hp@nic.in
No. PW.CHD.CB.E-9/2024-

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

6765-6864 Dated : 09/10/25

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 21.10.2025 up to 04:00 PM
2. Date and time of issue of tender form : 21.10.2025 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 22.10.2025 11:00 AM
4. Date and time of opening of tender : 22.10.2025 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1.	Restoration of rain damages on Nerwa to Bamta road km 0/00 to 23/0 (SH:- C/O Wire crate R/Wall at RD 16/060 to 16/070)	96,925.00	2000.00	350.00	One month	Class D or above
2.	Restoration of rain damages on Nerwa to Bamta road km 0/00 to 23/0 (SH:- C/O Wire crate R/Wall at RD 18/700 to 18/710)	99,085.00	2000.00	350.00	One month	Class D or above
3.	Restoration of rain damages on Nerwa to Bamta road km 0/00 to 23/0 (SH:- C/O Wire crate R/Wall at RD 2/110 to 2/120)	96,652.00	2000.00	350.00	One month	Class D or above
4.	Restoration of rain damages on Sainj Chopal Nerwa Fediz road km 59/00 to 77/0 (SH:- C/O PCC Protection wall under Police Station building Nerwa at RD 72/005 to 72/009.50)	99,980.00	2000.00	350.00	One month	Class D or above
5.	Restoration of rain damages on Khail to Shilikayan road km 0/500 to 4/0 (SH:- Hiring of Excavator cum Pock Lane/ L&T with breaker for removal of boulders and slips & dressing of road surface at RD 0/0 to 1/0 (as and when required) DNIT No: 109 DL for the year 2025-26	98,750.00	2000.00	350.00	One month	Class D or above
6.	R/R damages on various road in Nerwa-II section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of land slides/ debris etc. at various RDs) DNIT No:110DL for the year 2025-26	99,935.00	2000.00	350.00	One month	Class D or above
7.	R/R damages on various road in Nerwa-II section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of land slides/ debris etc. at various RDs) DNIT No: 111DL for the year 2025-26	99,935.00	2000.00	350.00	One month	Class D or above
8.	R/R damages on various road in Nerwa-II section under Shallu Sub-Division Nerwa (SH:- Hiring of Tipper for removal of land slides/ debris etc. at various RDs) DNIT No: 112DL for the year 2025-26	92,800.00	1900.00	350.00	One month	Class D or above


9.	Restoration of rain damages on Chopal Bodhana Bavi road km 0/00 to 5/0 (SH:- C/O Wire crate R/Wall at RD 1/818 to 1/823)	99,930.00	2000.00	350.00	One month	Class D or above
----	--	-----------	---------	--------	-----------	------------------

TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
12. The contractor/firm having necessary documents and past adequate experience shall be preferred.
13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. If any kind of holiday to be happened, the tender documents shall be sold/opened on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.


CERTIFICATE


It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-


1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division HPPWD Chopal



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD/OB.C-9/2025- 6765-6864 dated
09/10/25 are of urgent nature work(s).


Executive Engineer
Chopal Div. HPPWD/Chopal
On behalf of Governor of H.P.

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost	Rs. 96925
Earnest money	Rs. 2000
Time allowed	One month

Name of work - R/R damages on Nerwa to Bamta road Km 0/00 to 23/00.
(SH - C/O R/Wall wire crate at RD 16/060 to 16/070)

Sl. No.	Description of item	Qty.	Rate	In words	Unit	Amount	
			In figure				
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mtrs as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.00	195.00	Rupees one hundred ninety five and paise zero only	Per cubic metre	2730	
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.50	210.00	Rupees two hundred ten and paise zero only	Per cubic metre	1575	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is: 4826 in 100X100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2900.00	Rupees two thousand nine hundred and paise zero only	Per Cubic Meter	90625	
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10	950.00	Rupees nine hundred fifty and paise zero only	Per Cubic Meter	1995	
Quoted rate in figure.						Total	96925
Quoted rate in words.							

DNIT No. 01-137 For the year 2026
Draft schedule of quantities duly

approved 96925/only
for Rs.

Executive Engineer
B&R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

2


Estimated cost :	Rs. 99085
Earnest money :	Rs. 2000
Time allowed :	One month

Name of work :- R/R damages on Nerva to Bamta road Km 0/00 to 23/00.
(SH :- C/O R/Wall wire crate at RD 18/700 to 18/710)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mtrs as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.00	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	5460	
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.50	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	1575	
3	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90625	
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.50	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	1425	
Quoted rate in figure.						Total	99085
Quoted rate in words.							

DNIT No. ~~11-198~~ For the year ~~2016-17~~
Draft schedule of quantities duly approved

for Rs. 99085/- only


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

3

Estimated cost :	Rs 96652
Earnest money :	Rs 2000
Time allowed :	One month

Time of work - R/R damages on Nerwa to Bamta road 0/00 to 23/00.
(SH :- C/O R/Wall in wire crate at RD 2/110 to 2/120).

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mtrs as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.60	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	2457
Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.50	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	1575
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming IS. 280 and IS.4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90625
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	1995
Quoted rate in figure				Total	96652
Quoted rate in words.					

DNI No DL-135 For the year 25-26
Draft schedule of quantities duly approved
for Rs. 96652/only

Active Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

4

name of work :- R/R damages on Sainj Chopal Nerwa Fediz road Km 59/00 to 77/00.

(SH :- C/O PCC wall under Police station building Nerwa at RD 72/005 to 72/009.50).

Estimated cost :	Rs. 99980
Earnest money :	Rs. 2000
Time allowed :	One month

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by mechanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.90	5200.00	Rupees five thousand two hundred and paise zero only	Per cubic metre.	98280
Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST 18% or other taxes imposed by the Government	8.50	200.00	Rupees two hundred and paise zero only	Per running metre	1700
Quoted rate in figure.				Total	99980
Quoted rate in words.					

DNIT No DL-124 For the year... 25-26
 Draft schedule of quantities duly
 approved
 for Rs. 99980/- only

(Signature)
 Executive Engineer
 B & R Division
 MPPWD Chopal

DNT./SCHEDULE OF QUANTITIES.

Job No. 5

ESTIMATED COST:- 98,750/-

EARNEST MONEY:- RS. 2000/-

TIME ALLOWED:- 15 days

NAME OF WORK:- Restoration of rain damages on Khail to Shiljikayan road km 0/0 to 4/0
 (SH:- Hiring of Excavator-Cum- (PockLane/L&T with breaker) for removal of Boulders and slips & Dressing of road at RD 0/0 to 1/0 (As & When Required)

Sr.No	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of Excavator -cum-loader(Pock Lane / L&T) with 90-HP engine and lifting capacity of minimum 5000kgs including P.O.L. charges, shifting charges and other ancillary equipment as required of site of work for removal of boulders/slips in all kind of soil such as kanaker, moorun shingle boulder decomposed or soft variety of soil such as spade work pick work jumper work soft & hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stone from removal of slips shall have to be neatly staked along side on road burms. The work shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer- in-charge.	25.00	3950.00	Rupees Three Thousand Nine Hundred & Fifty Only	Per Hour	98750.00
Total						98750.00

Note :

1. POL charges and all bear and tear shall be born by the contractor/owner of machine.
2. The repair of machinery shall be done by the contractor.
3. Any damages or loss of Govt./ Private property during the course of work shall have to be made by the contractor.

DNT No DDI-19 For the year 2025-26
 Draft schedule of quantities duly approved
 for Rs. 98750/- only

(Signature)
 Assistant Engineer,
 Shailu Sub-Division,
 HPPWD Nerwa.

(Signature)
~~Executive Engineer~~
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Nerwa-II section under Shailu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 VOL.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

Shailu
Assistant Engineer
Shailu Sub-Division
H.P.P.W.D Nerwa

DMT No. DL-116/F for the year 25-26
Draft schedule of quantities duly
approved for Rs. 99935/- only

Shailu
HPPWD Chapter

DRAFT / SCHEDULED OF QUANTITY


Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Nerwa-II section under Shallu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Assistant Engineer
 Shallu Sub-Division
 H.P.P.W.D Nerwa

DNIT No. DL-111F of the year 25-28
 Draft schedule of quantities duly
 approved
 for Rs. 99935/- only


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY


Estimated Cost	Rs. 92800/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Nerwa-II section under Shallu Sub Division Nerwa.
(SH: Hiring of Tipper for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Tipper 5.5 cum capacity daily basis for eight hour daily in good condition including the charges of P.O.L Repair and maintenance and wages of driver/operator for lifting of excavated earth/stone slips, Drain and disposal of the same in all leads and lifts including carriage of material and as per HP PWD specification of 1990 Vol. I and as per the direction o Engineer-in-charge at site.	16.00	5800.00	Fifty Eight Thousand only	Per day	92800.00
	Quoted rate in figure.					
	Quoted rate in words.					
					Total	92800.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


 Assistant Engineer
 Shallu Sub-Division
 H.P.P.W.D Nerwa

DNIT No. DL-119 of the year. 2026
 Draft schedule of quantities duly
 approved
 for Rs. 92,800/-


 Executive Engineer
 B & R Division
 H.P.P.W.D Chopra

DRAFT/SCHEDULED OF QUANTITY.


name of work :- R/R damages on Chopal Bodhana Bavi road Km 0/00 to 5/00 ~~Under PWD~~

(SH :- C/O wire crate R/Wall at RD 1/818 to 1/823)

Estimated cost :	Rs. 99930
Earnest money :	Rs. 2000
Time allowed :	One month

Description of item	Qty.	Rate		Unit	Amount
		In figure	In words		
Earthwork by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains for all all kind of soil and ordinary rocks including dressing of sides ramming of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	19.88	210.00	Rupees two hundred ten and paisa zero only	Per Cubic Meter	4175
Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	31.25	2900.00	Rupees two thousand nine hundred and paisa zero only	Per Cubic Meter	90625
Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. Including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana toll tax, sale tax, GST or other taxes imposed by the Government.	5.40	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	5130
Quoted rate in figure:				Total	99930
Quoted rate in words:					

DNIT No DL-113 For the year 25-21
 Draft schedule of quantities duly
 approved
 for Rs. 99930/-


Executive Engineer
 B & R Division
 PWD Chopal