

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26 5744-52

Dated:- 16/10/25

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **28.10.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **27.10.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **27.10.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	R/R damages on Kotli-Kolka Chamyawal road km. 0/00 to 11/960 (SH:- C/o R/wall at rds 2/180 to 2/195) (under PDNA)	97,259/-	2000/-	1 Month	350/-
2	R/R damages on Galog Kunihar road km. 0/00 to 13/785 (SH:- C/o R/wall at rd 12/450 to 12/475) (under PDNA)	1,62,527/-	3300/-	1 Month	350/-
3	R/R damages on Galog Kunihar road km. 0/00 to 13/785 (SH:- C/o R/wall at rd 13/185 to 13/195) (under PDNA)	86,500/-	1800/-	1 Month	350/-
4	R/R damages on Galog Kunihar road km. 0/00 to 13/785 (SH:- C/o R/wall at rd 13/030 to 13/045) (under PDNA)	97,259/-	2000/-	1 Month	350/-
5	R/R damages on Kotli-Kolka Chamyawal road km. 0/00 to 11/960 (SH:- C/o B/wall at rds 5/660 to 5/680) (under PDNA)	1,26,844/-	2600/-	1 Month	350/-
6	R/R damages on Kotli-Kolka Chamyawal road km. 0/00 to 11/960 (SH:- C/o R/wall at rd 4/520 to 4/540) (under PDNA)	1,30,041/-	2700/-	1 Month	350/-

	R/R damages on Kotli-Kolka Chamyawal road km. 0/00 to 11/960 (SH:- C/o B/wall at rds 1/720 to 1/740) (under PDNA)	1,26,844/-	2600/-	1 Month	350/-
8	R/R damages on Kotli-Kolka Chamyawal road km. 0/00 to 11/960 (SH:- C/o R/wall at rds 6/150 to 6/165) (under PDNA)	97,259/-	2000/-	1 Month	350/-
9	R/R damages on Arki-Manju-Khanalag road km. 8/00 to 12/365 (SH:- C/o R/wall at rds 8/300 to 8/310) (under PDNA)	65,256/-	1400/-	1 Month	350/-
10	R/R damages on Arki-Manju-Khanalag road km. 8/00 to 12/365 (SH:- C/o R/wall at rds 8/855 to 8/870) (under PDNA)	97,884/-	2000/-	1 Month	350/-
11	R/R damages on Arki-Manju-Khanalag road km. 8/00 to 12/365 (SH:- C/o R/wall at rds 8/825 to 8/840) (under PDNA)	98,141/-	2000/-	1 Month	350/-
12	R/R damages on Arki-Manju-Khanalag road km. 8/00 to 12/365 (SH:- C/o R/wall at rds 9/600 to 9/615) (under PDNA)	97,884/-	2000/-	1 Month	350/-
13	R/R damages on Arki-Manju-Khanalag road km. 8/00 to 12/365 (SH:- C/o R/wall at rds 9/105 to 9/115) (under PDNA)	65,432/-	1400/-	1 Month	350/-
14	Restoration of drain damages on Jabal Manlogkalan Ukhoo Panjali Jainagar road km. 0/00 to 24/765 (SH:- C/o RCC Hume Pipe culvert at rd 24/075 with wing walls) (under PDNA 2023)	4,99,922/-	10,000/-	1 Month	350/-
15	R/R damages on link road to Vill. Namol km. 0/0 to 1/270 under PDNA 2023 (SH:- C/o R/wall at 0/075 to 0/081)	1,59,719/-	4000/-	1 Month	350/-
16	R/R damages on Sayawan Rinvi Behli road km. 0/0 to 1/360 under PDNA 2023 (SH:- C/o R/wall at 0/320 to 0/340)	1,30,735/-	3000/-	1 Month	350/-
17	R/R damages on Hardevpura Banwan road km. 0/0 to 4/170 under PDNA 2023 (SH:- C/o R/walls at rds 2/790 to 2/805, 3/180 to 3/190 and 3/810 to 3/820) under PDNA -2023	2,26,698/-	5,000/-	1 Month	350/-
18	Restoration of drain damages on Jabal Manlogkalan Ukhoo Panjali Jainagar road km. 0/00 to 24/765 (SH:- C/o R/walls at rds 12/415	4,38,091/-	9,000/-	1 Month	350/-

	to 12/430, 12/570 to 12/580, 7/935 to 17/945 and 22/790 to 22/820) (under PDNA 2023)				
19	Restoration of drain damages on Jabal Manlogkalan Ukhoo Panjali Jainagar road km. 0/00 to 24/765 (SH:- C/o R/walls at rds 0/105 to 0/125, 1/760 to 1/770, 2/575 to 2/597, 3/3885 to 3/900 and 4/300 to 4/315) (under PDNA 2023)	4,80,811/-	10,000/-	1 Month	350/-
20	Restoration of drain damages on Jabal mann bawasi Gamberpul road km. 0/00 to 8/500 (SH:- C/o R/walls at rds 0/100 to 0/120, 2/885 to 2/905, 5/285 to 5/300, 6/135 to 6/150 and 8/415 to 8/430) (under PDNA 2023)	4,80,811/-	10,000/-	1 Month	350/-
21	Restoration of drain damages on Jmli Jainagar road portion km. 6/500 to 16/200 (SH:- C/o R/walls at rds 7/972 to 7/990, 10/405 to 10/455 and 14/085 to 14/095) (under PDNA 2023)	4,81,668/-	10,000/-	1 Month	350/-
22	Restoration of drain damages on Maloun Kushri road km. 0/00 to 15/00 (SH:- C/o R/walls at rds 1/180 to 1/195, 1/795 to 1/810 and 7/485 to 7/495) (under PDNA 2023)	3,06,164/-	6,500/-	1 Month	350/-
23	R/R damages on Bania Devi Sewra road km. 0/0 to 3/000 under PDNA 2023 (C/o R/wall at rd 0/510 to 0/530 & 2/520 to 2/545)	2,67,636/-	6,000/-	1 Month	350/-
24	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o wire crate at rd 17/280 to 17/295)	4,50,072/-	10,000/-	1 Month	350/-
25	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o wire crate at rd 15/160 to 15/175)	4,99,494/-	10,000/-	1 Month	350/-
26	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o B/wall at rd 13/420 to 13/429)	99,213/-	2,000/-	1 Month	350/-
27	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o wire crate at rd 17/915 to 17/930)	3,57,539/-	8,000/-	1 Month	350/-
28	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o wing wall at rd 17/940 to 17/945)	1,46,512/-	3,000/-	1 Month	350/-
29	R/R damages on Kanda Ladvi Kunihar road km. 9/000 to 23/190 under PDNA 2023 (SH:- C/o	2,39,228/-	5,000/-	1 Month	350/-

	wire crate at rd 23/020 to 23/040)				
30	R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road portion road km. 0/0 to 8/0 under PDNA 2023 (SH:- C/o R/wall at rd 5/629 to 5/639)	3,45,906/-	7,000/-	1 Month	350/-
31	R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road portion road km. 0/0 to 8/0 under PDNA 2023 (SH:- C/o R/wall at rd 5/160 to 5/175)	4,34,380/-	9,000/-	1 Month	350/-
32	R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road portion road km. 0/0 to 8/0 under PDNA 2023 (SH:- C/o R/wall at rd 5/629 to 5/639)	3,45,906/-	7,000/-	1 Month	350/-
33	R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road portion road km. 0/0 to 8/0 under PDNA 2023 (SH:- C/o R/wall at rds 5/180 to 5/190, 52/795 to 52/805 & 55/205 to 22/225)	3,58,378/-	8,000/-	1 Month	350/-
34	R/R damages on Talab (Rau Khad) Behli road km. 0/0 to 2/170 under PDNA 2023 (SH:- C/o R/wall at rd 0/090 to 0/120, 0/590 to 0/600 & 0/610 to 0/630)	3,70,884/-	8,000/-	1 Month	350/-
35	R/R damages on Talab (Rau Khad) Behli road km. 0/0 to 2/170 under PDNA 2023 (SH:- C/o R/wall at rd 0/960 to 0/990 & 1/080 to 1/110)	3,83,660/-	8,000/-	1 Month	350/-
36	R/R damages on Talab (Rau Khad) Behli road km. 0/0 to 2/170 under PDNA 2023 (SH:- C/o R/wall at rd 01/240 to 1/255 & 1/480 to 1/500)	2,33,039/-	5,000/-	1 Month	350/-
37	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 0/300 to 0/308) (under PDNA)	1,03,445/-	2,069/-	2Months	350/-
38	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 5/100 to 5/112) (under PDNA)	1,57,224/-	3,144/-	2 Months	350/-
39	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 4/440 to 4/448) (under PDNA)	1,03,955/-	2,069/-	2 Months	350/-

40	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 3/410 to 3/418) (under PDNA)	1,03,445/-	2,069/-	2 Months	350/-
41	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 2/320 to 2/332) (under PDNA)	1,59,348/-	3,187/-	2 Months	350/-
42	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 1/750 to 1/758) (under PDNA)	75,069/-	1,501/-	2 Months	350/-
43	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 2/650 to 2/658) (under PDNA)	1,03,873/-	2,077/-	2 Months	350/-
44	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 1/300 to 1/308) (under PDNA)	1,04,735/-	2,095/-	2 Months	350/-
45	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 0/110 to 0/122.25) (under PDNA)	2,64,589/-	5,292/-	2 Months	350/-
46	R/R damages on Bhararighat Ali Bhurjani road km. 0/00 to 6/00 (SH:- C/o R/wall at rd 0/420 to 0/437) (under PDNA)	3,67,840/-	7,357/-	2 Months	350/-
47	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 2/140 to 2/416.25) (under PDNA)	1,03,793/-	2,076/-	2 Months	350/-
48	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 2/900 to 2/908) (under PDNA)	1,03,955/-	2,079/-	2 Months	350/-
49	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 1/210 to 1/216) (under PDNA)	76,939/-	1,539/-	2 Months	350/-
50	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 0/710 to 0/717) (under PDNA)	1,50,496/-	3,010/-	2 Months	350/-
51	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 7/895 to 7/902.90) (under PDNA)	1,31,937/-	2,639/-	2 Months	350/-
52	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 6/315 to 6/322.50) (under PDNA)	1,56,676/-	3,134/-	2 Months	350/-

53	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 5/620 to 5/628) (under PDNA)	1,03,955/-	2,079/-	2 Months	350/-
54	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 3/650 to 3/658) (under PDNA)	1,04,368/-	2,087/-	2 Months	350/-
55	R/R damages on Dohra Danga Kothi Jamogi road km. 0/00 to 5/00 (SH:- C/o B/wall at rd 3/045 to 3/090) (under PDNA)	2,92,139/-	5,843/-	2 Months	350/-
56	R/R damages on Sunhani Bashyana Falodan Kangridhar road km. 0/00 to 8/240 (SH:- C/o R/wall at rd 7/090 to 7/102) (under PDNA)	1,55,614/-	3,112/-	2 Months	350/-
57	R/R damages on Bathalang Jawara to Dharail road km. 0/00 to 0/615 (SH:- C/o Edge wall at rds 0/175 to 0/195) (under PDNA)	1,27,337/-	2,600/-	2 Months	350/-
58	R/R damages on Bathalang Jawara to Dharail road km. 0/00 to 0/615 (SH:- C/o Edge wall at rds 0/145 to 0/1165) (under PDNA)	1,29,295/-	2,600/-	2 Months	350/-
59	R/R damages on Bathalang Jawara to Dharail road km. 0/00 to 0/615 (SH:- C/o Edge wall at rds 0/085 to 0/105) (under PDNA)	1,23,047/-	2,600/-	2 Months	350/-
60	Restoration of Rain Damages in Darla Sub-Division (SH:- Hiring of Tipper for removal of slips in various roads under Darla Section Job No-3)	97,500/-	2,000/-	15 Days	350/-
61	Restoration of Rain Damages in Darla Sub-Division (SH:- Hiring of Tipper for removal of slips in various roads under Darla Section Job No-1)	97,500/-	2,000/-	15 Days	350/-
62	Restoration of Rain Damages in Darla Sub-Division (SH:- Hiring of JCB for removal of slips in various roads under Darla Section Job No-6)	99,000/-	2,000/-	15 Days	350/-
63	Restoration of Rain Damages in Darla Sub-Division (SH:- Hiring of JCB for removal of slips in various roads under Darla Section Job No-5)	99,000/-	2,000/-	15 Days	350/-
64	R/R damages on Galog Kunihar road km. 0/00 to 13/785 (SH:- C/o R/wall at rd 12/900 to 12/915) (under PDNA)	97,259/-	2,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2025-26- 5744-52

Dated:- 16/10/25

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.

Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 64(Sixty four) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Kotli-Kolka Chamayawall Road Km 0/00 to 11/960 . (SH:- C/O R/wall at Rds 2/180 to 2/195.) (Under PDNA)

Estimated Cost: -Rs97259/- only

Earnest Money :-Rs2000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words	4		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise forty only		P.Cum.	1440
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORO clause 802.803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	9.72	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	2666
						Total	97259

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Galog Kunihar Road Km 0/00 to 13/785 . (SH:- C/O R/wall at Rds12/450 to 12/475.) (Under PDNA)

Estimated Cost:-Rs162527/- only
Earnest Money :-Rs3300/-only
Time :- One Month

S No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	16.50	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	2828
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5 10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	31.25	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	137206
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts, and as per the direction of Engineer-In- Charge	15.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	18050
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	16.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4443
					Total	162527

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY				Estimated Cost -Rs.86500/- only	
Name of Work -R/R Damages on Galog Kunihar Road Km 0/00 to 13/785 . (S/H- C/O R/wall at				Earnest Money -Rs.1800/- Only	
Rs.13/185 to 13/195) (Under PDNA)				Time :- One Month	

S. No.	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words	4		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer-In- Charge	8.60	171.40	Rupees One hundred seventy one and paise forty only		P. Cum.	1474
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORO clause 802,803, 1202 & 1203 . P.C.C. nominal mix 1 to 10 (1 cement 5 sand 10 aggregates-40mm)including carriage of materials at all leads and lifts and as per the direction of Engineer-In- Charge	16.90	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P. Cum.	74201
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3 & 8 including carriage of materials in all leads, lifts, and as per the direction of Engineer-In- Charge	7.20	1203.30	Rupees one thousand two hundred three and paise thirty only		P. Cum.	8664
4	Providing and laying 100mm dia metre PVC pipe for wherp holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	7.88	274.25	Rupees two hundred seventy four and paise twenty five only		P. Rmt	2161
Total							86500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
AND Division HPWD
AND

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Galog Kunihar Road Km 0/00 to 13/785 . (SH:- C/O R/wall at Rds13/030 to 13/045.) (Under PDNA)

Estimated Cost :-Rs97259/- only

Earnest Money :-Rs2000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise fourty only		P.Cum.	1440
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802.803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	9.72	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	2666
						Total	97259

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Kolli-Kolka Channayawal Road Km 0/00 to 11/060 , (S.I.E. C/O B/wall at Rd55/060 to 5/630.) (Under PDNA)

Estimated Cost -Rs.126844/- only

Estimated Money -Rs.2000/- only

Time - One Month

Sl. No	Sub head and items of work	Qty	Figure	Rate In	Unit	Amount
				Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 302.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all heads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MCRD	13.60	171.40	Supers One hundred seventy one and paise forty only	P.Cum.	2331
2	Specification directed by Engineer In Charge					
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MCRD clause 402,403, 1202 & 1203, P.C.C. nominal mix 1 to 10 (1 cement to sand 10 aggregates 40mm)including cartage of materials in all heads and lifts and as per the direction of Engineer In Charge	27.60	4390.60	Supers four thousand three hundred ninety and paise sixty only	P.Cum.	121161
3	Providing and laying 100mm dia m/c 15VC pipe for whseep holes complete of approved quality including cartage of material within all heads, lifts and as per the direction of Engineer In Charge	12.15	274.25	Supers two hundred seventy four and paise twenty five only	P.Foot	3332
					Total	126844

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
And Divisional P.P.V.M.D
Aiki

Journal of Work, Life & Stress, 2013, Vol. 29, No. 1, 1-10
DOI: 10.1080/07447147.2013.751111

Estimated Cost: £16,000/£ only
Estimated Monthly: £1,270/£ only
Time - One Month

Qty	Figure	Rate In Words	Unit	Amount
12.20	171.40	Bagasse One hundred seventy one and paise twenty only	P 6000	2001
25.00	4300.00	Bagasse four hundred three hundred ninety and paise sixty only	P 6000	112300
0.60	1203.30	Bagasse one hundred two hundred three and paise thirty only	P 6000	11552
14.50	274.25	Bagasse two hundred seventy four and paise twenty five only	P 6000	3000
		Total		120041

1990-1991

100

1. $\frac{1}{2} \log 2$
2. $\frac{1}{2} \log 2$
3. $\frac{1}{2} \log 2$
4. $\frac{1}{2} \log 2$
5. $\frac{1}{2} \log 2$
6. $\frac{1}{2} \log 2$
7. $\frac{1}{2} \log 2$
8. $\frac{1}{2} \log 2$
9. $\frac{1}{2} \log 2$
10. $\frac{1}{2} \log 2$

SCHEDULE OF QUANTITY				Estimated Cost -Rs126844/- only	
Name of Work:-R/R Damages on Koli-Kolka Chamayawai Road Km 0/00 to 11/960 . (SH:- C/O B/wall at Rds1/720 to1/740.) (Under PDNA)				Earnest Money :-Rs2500/-Only	
				Time :-One Month	

S No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	13.60	171.40	Rupees One hundred seventy one and paise fourty only	P. Cum.	2331
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1 5 10 (1 cement :5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	27.60	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P. Cum.	121181
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	12.15	274.25	Rupees two hundred seventy four and paise twenty five only	P. Rmt	3332
					Total	126844

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Kotli-Kolka Chamayawal Road Km 0/00 to 11/960 . (SH:- C/O R/wall at Rds 6/150 to 6/165.) (Under PDNA)

Estimated Cost :-Rs97259/- only

Earnest Money :-Rs2000/-Only

Time :-One Month

S No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1440
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	9.72	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	2666
					Total	97259

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Arki-Manju-Khanalg Road Km 8/00 to 12/365 . (SH:- C/O R/wall at Rds 8/300 to 8/310.) (Under PDNA)

Estimated Cost:-Rs65256/- only

Earnest Money :-Rs1400/-only

Time :- One Month

S No	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing , removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer-In- Charge	5.60	171.40	Rupees One hundred seventy one and paise fourty only		P.Cum.	960
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORO clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand: 10 aggregates-40mm)including carriage of materials in all leads and lifts, and as per the direction of Engineer-In- Charge	12.50	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	54883
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3 & including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	6.00	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	7220
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	8.00	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	2194
						Total	65256

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Arki-Manju-Khanalg Road Km 8/00 to 12/365 . (SH:- C/O R/wall at Rds 8/855 to 8/870.) (Under PDNA)

Estimated Cost -Rs97884/- only

Earnest Money -Rs2000/-Only

Time :-One Month

S No	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words	4		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise forty only		P.Cum.	1440
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	12.00	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	3291
						Total	97884

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Atki-Manju-Khanalg Road Km 8/00 to 12/365. (Sft:- C/O R/wall at Rds 8/825 to 8/840.) (Under PDNA)

Estimated Cost Rs.98141/- only
 Earnest Money Rs.29140/- only
 Time - One Month

S No	Sub head and items of work	Qty	Figure	Rate In Words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer-In- Charge	9.90	171.40	Rupees One hundred seventy one and paise forty only	P.Cum	1687
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawings and technical specifications MORO clause 802,803, 1202 &1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	12.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3291
					Total	98141

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
 Atki Division HPPWD
 Atki

SCHEDULE OF QUANTITY

Name of Work -K/R Damages on Atki-Manju-Khanaly Road Km 8/00 to 12/365 . (SH- C/O R/wall at Rds 9/600 to 9/615.) (Under PDNA)

Estimated Cost -Rs/7884/- only

Earned Money -Rs/2000/- Only

Time :-One Month

S No	Sub head and items of work	Qty	Figure	Rate In	Unit	Amount
				Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 205.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MOIRD Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1440
2	Providing and laying concrete for plain /reinforced cement in open foundation complete as per drawings and technical specifications MOIRD clause 802,803, 1202 & 1203 , P.C.C, nominal mix 1:5:10 (1 cement :5 sand :10 aggregates-40mm)including cartilage of materials in all leads and lifts and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204,3 & 3 including cartilage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheel holes complete of approved quality including cartilage of material within all leads, lifts and as per the direction of Engineer-In- Charge	12.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3291
					Total	97884

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer

Atki Division HPPWD

Atki

SCHEDULE OF QUANTITY						Estimated Cost -Rs65432/- only	
Name of Work:-R/R Damages on Arki-Manju-Khanalg Road Km 8/00 to 12/365 . (SH:- C/O B/wall at Rds 9/105 to 9/115.) (Under PDNA)						Earnest Money :-Rs1400/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words			
1	2		3	4		5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	5.20	171.40	Rupees One hundred seventy one and paise fourty only		P.Cum.	891
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	14.20	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	62347
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	8.00	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	2194
						Total	65432

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of ruin Damages on Jabal Manlogkalan Ukhho Panjati jainagar road km 0/00 to 24/765. (Sh : Construction of Rcc Hume Pipe culvert at Rd 24/075 with wing walls . Under PDNA 2023.

Estimated Cost :- Rs 4,99,922.00

Earnest money :- Rs 10,000.00

Time: one months

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
1	2	3	In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	72.50	Cum	171.40	Per cubic metre	12427.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	79.05	Cum	4390.60	Per cubic metre	347077.00
3.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire satisfaction of Engineer-in -Charge.	15.00	cum	3881.55	Per cubic metre	58223.00
1.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	54.00	Rmt	274.25	Per running metre	14810.00

5.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	56.00	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	67385.00
						Total	499922.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words

col
Executive Engineer
Arki Division (B&R)
HP. PWD, Arki.

NOTIFICATION OF QUANTITY

Name of work :- R/R damages on Link Road to Village Nannal Km 0/0 to 1/270 under PDNA
2023 (SI:-C/O R/ Wall at 0/075 to 0/081)

Estimated Cost :- Rs 1,29,719.00
Earned money :- Rs 4,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Unit	Rate		Amount
				In figure	In words	
1	Earthwork in excavation for structures as per drawing and technical specification clause 802.1 including setting out construction of shoring and bracing, removal of stumps and other obstructions materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and back filling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MCHD specification and as per the direction of Engineer-In-Charge.	15.66	Cum	171.40	Propees One Hundred Seventy One and Forty paise Only	2684.60
2.00	Providing and laying plain cement concrete 1:2:10 (one cement two five sand two ten graded crushed stone aggregate 40 millimetre forty millimetre nominal size for plain reinforced concrete in open foundation complete as per drawings and technical specifications clause 802.803, 1202 & 1203 and curing complete including the cost of form work and cartings of materials in all leads lifts as per the direction of Engineer-In-Charge.	34.01	Cum	4390.60	Propees Four Thousand Three Hundred Thirtly paise Only	149324.60
3.00	Providing and laying scaphoria in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm cone hundred millimetre dia PVC pipes extending through the full width of the structures with slope of 1:0.25 (1) towards drawing face complete as per drawings and technical specifications MCHD clause 614.702, 1204.3.7 including cartings of materials within all leads and lifts as per the direction of Engineer-In-Charge.	12.54	Foot	274.25	Propees Two Hundred Seventy Four and Twenty five paise Only	3439.60
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MCHD clause 1204.3.8 including cartings of materials within all leads lifts and as per the direction of Engineer-In-Charge.	3.55	Cum	1203.30	Propees One Thousand Two Hundred Three and Thirtly paise Only	4271.60
			Total			159719.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

For
Engineer In Charge
AM Division, PDNA
AMM

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Sayawan Rinvi Behli Road Km 0/0 to 1/360 under PDNA
2023 (SH:-C/O R/ Wall at 0/320 to 0/340)

Estimated Cost :- Rs 1,30,735.00
Earnest money :- Rs 3,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	12.79	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	2192.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement iso Five sand iso ten graded crushed stone aggregate 40 millimetre) forty millimetre nominal size for plain/reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge	27.77	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	121927.00
3.00	Providing and laying weepholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred millimetre dia PVC pipe extending through the full width of the structures with slope of 1 in 20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge	11.40	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3126.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge	2.90	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	3490.00
						Total	130735.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division (B&R)
H.P. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-R/R damages on HardevPura Banwan Road Km 0/0 to 4/170 under PDNA 2023 (SH:-Construction of R/walls at rds 2/790 to 2/805,3/180 to 3/190 and 3/810 to 3/820) Under PDNA-2023

Estimated Cost :- Rs 2,26,698.00
Earnest money :- Rs 5,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge.	22.19	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre 3803.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre/ forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	48.18	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre 211539.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	19.38	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre 5315.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.02	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre 6041.00
					Total	226698.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jabal manlogkalan Ukhoo Panjali Jainagar road km 0/00 to 24/765. (Sh : Construction of R/Walls at rds 12/415 to 12/430, 12/570 to 12/580, 17/935 to 17/945 and 22/790 to 22/820) under PDNA 2023

Estimated Cost :- Rs 4,38,091.00
Earnest money :- Rs 9,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3	4	5	6	7
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (1) Ordinary Rock (1) Up to 3 m. depth.	34.76	Cum	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5958.00
2.00	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 Cement concrete 1:5:10 40 mm nominal size.	89.89	Cum	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	394671.00
3.00	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm diameters P.V.C. pipe extending through the full width of the structures with slope of 1 (V):20 (H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.	38.14	Rmt	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	10460.00
4.00	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 an i/c all leads and lifts. (a) Granular materials.	22.44	Cum	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	27002.00
					Total	438091

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jabal manlogkalan Ukhoo Panjali Jainagar road km 0/00 to 24/765. (Sh :Construction-of R/Walls at rds 0/105 to 0/125,1/760 to 1/770,2/575 to 2/597,3/885 to 3/900 and 4/300 to 4/315) under PDNA 2023

Estimated Cost :- Rs 4,80,811.00

Earnest money :- Rs 10,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (1) Ordinary Rock (1) Up to 3 m. depth.	31.30	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5365.00
2.00	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 Cement concrtene 1:5:10 40 mm nominal size.	98.87	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	434099.00
3.00	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm diameters P.V.C. pipe extending through the full width of the structures with slope of 1 (V):20 (H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.	42.48	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	11650.00
4.00	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 an i/c all leads and lifts. (a) Granular materials.	24.68	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	29697.00
						Total	480811.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Jabal mann bawasi Gamberpul road km 0/00 to 8/500. .(Sh :Construction-of R/Walls at rds 0/100 to 0/120,2/885 to 2/905,5/285 to 5/300,6/135 to 6/150 and 8/415 to 8/430) under PDNA 2023

Estimated Cost :- Rs 4,80,811.00
Earnest money :- Rs 10,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1							
1.00	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal up to a lead of 50 meters dressing of sides and bottom and back filling in trenches with excavated suitable materials. (1) Ordinary Rock (1) Up to 3 m. depth.	31.30	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5365.00
2.00	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 Cement concere 1:5:10 40 mm nominal size.	98.87	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	434099.00
3.00	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm diameters P.V.C. pipe extending through the full width of the structures with slope of 1 (V):20 (H) towards drawing face complete as per drawing and technical specification Clauses 614,709,1204.3.7.	42.48	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	11650.00
4.00	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 an i/c all leads and lifts. (a) Granular materials.	24.68	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	29697.00
						Total	480811.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Atki Division (B&R)
HP. PWD. Atki.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jamli Jainagar road portion km 6/500 to 16/200.(Sh :Construction-of R/Walls at rds 7/972 to 7/990,10/405 to 10/455 and 14/085 to 14/095) under PDNA 2023

Estimated Cost :- Rs 4,81,668.00
Earnest money :- Rs 10,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge.	36.30	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6222.00
2.00	Providing and laying Plain cement concrete 1:3:10 (one cement iso Five sand iso ten graded crushed stone aggregate 40 millimetre forty millimetre) nominal size for plain/reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	98.87	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	434099.00
3.00	Providing and laying masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):2.0 (1) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3,7 including carriage of materials within all leads lifts as per the direction of Engineer-In-Charge.	42.48	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	11650.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3,8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	24.68	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	29697.00
	Total						481668.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Bania Devi Sewra Road Km 0/0 to 3/000 under PDNA 2023
(SH-C/O R/ Wall at 0/510 to 0/530&2/520 to 2/545)

Estimated Cost :- Rs 2,67,636.00
Earnest money :- Rs 6,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1							
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of sumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge.	26.10	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4474.00
2.00	Charge Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre/ forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	56.68	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	248859.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	26.22	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	7191.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.91	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	7112.00
						Total	267636.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under PDNA 2023 (SH:-C/O Wire Crate at RD 17/280 to 17/295)

Estimated Cost :- Rs 4,50,072.00
Earnest money :- Rs 10,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including scieting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	24.22	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4151.00
2.00	Providing and Laying of boulder apron laid in wire crate with 4 mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100 mm mesh(wovendiagonally) i.e. 10% extra for laps and joint with stone boulder weighing not less than 25 kg each as per drawingv and technical specifications clause 1301 complete, complete as per HP. PWD specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	148.44	Cum	3004.05	Rupees Three Thousand Four and Five paise Only	Per cubic metre	445921.00
						Total	450072.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
RRI Division, HPPWD
Arif

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Maloun Kushri road km 0/00 to 15/00..(Sh
:Construction-of R/Walls at rds 1/180 to 1/195,1/795 to 1/810 and 7/485 to 7/495) under PDNA
2023

Estimated Cost :- Rs 3,06,164.00
Earnest money :- Rs 6,500.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	2						
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge.	24.33	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4170.00
2.00	Charge Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre) forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	62.91	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	276213.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	25.12	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	6889.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	15.70	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	18892.00
						Total	306164.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under PDNA 2023 (SH:-C/O Wire Crate at RD 15/160 to 15/175)

Estimated Cost :- Rs 499,494.00
Earnest money :- Rs 10,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	3	4		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	38.44	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6589.00
2.00	Providing and Laying of boulder apron laid in wire crate with 4 mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100 mm mesh(wovendiagonally) i.e. 10% extra for laps and joint with stone boulder weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete. complete as per HP. PWD specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-In-Charge.	164.08	Cum	3004.05	Rupees Three Thousand Four and Five paise Only	Per cubic metre	492905.00
						Total	499494.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
KMD Division, HPWD
Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under PDNA 2023 (SI-C/O B/ Wall at RD 13/420 to 13/429)

Estimated Cost :- Rs 99,213.00
Earnest money :- Rs 2,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	14.42	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	2472.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre) forty millimetre nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	21.79	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	95671.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(V):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	3.90	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	1070.00
						Total	99213.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Artd Division, HPPWD
Artd

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under PDNA 2023 (SH:-C/O Wire Crate at RD 17/915 to 17/930)

Earnest money :- Rs 8,000.00

Sr. No.	Sub Head and Items of Work	Qty.	Rate	Unit	Amount
---------	----------------------------	------	------	------	--------

Quoted Rate Percentage in Figures

en
Executive Engineer
Ard Division, HPPMD
Ard —

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under
PDNA 2023 (SH:-C/O Wing Wall at RD 17/940 to 17/945)

Estimated Cost :- Rs1,46,512.00
Earnest money :- Rs 3,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge.	20.25	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3471.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre (forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	30.95	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	135889.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	9.80	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	2688.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	3.71	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	4464.00
						Total	146512.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

led
Executive Engineer
Arki Division, HPPWD
Arki

NAME OF WORK:- R/R damages to Kanda Ladvi Kunihar Road Km 9/000 to 23/190 under PDNA 2023 (SH:-C/O Wire Crate at RD 23/020 to 23/040)

Earnest money :- Rs 5,000.00

Time: One month

Sr. No.		Sub Head and Items of Work		Qty.		Rate		Unit	Amount	
1		2		3		In figure		In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	26.56	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4552.00			
2.00	Providing and Laying of boulder apron laid in wire crate with 4 mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100 mm mesh(wovendiagonally) i.e. 10% extra for laps and joint with stone boulder weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete, complete as per HP. PWD specifications of 1990 volume-1 including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-In-Charge.	78.12	Cum	3004.05	Rupees Three Thousand Four and Five paise Only	Per cubic metre	234676.00			
								Total	239228.00	

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division, HPWD
Arki *J*

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion
Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O R/wall at RD 5/629 to 5/639)

Estimated Cost :- Rs 3,45,906.00
Earnest money :- Rs 7,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	27.00	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4628.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	69.60	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	305586.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	53.80	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	14755.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	17.40	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	20937.00
						Total	345906.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

b R
Executive Engineer
Work Division, HPPWD
Amr

SCHEDULE OF QUANTITY

Name of work :-R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion
Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O R/wall at RD 5/160 to 5/175)

Estimated Cost :- Rs 4,34,380.00
Earnest money :- Rs 9,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	3	4	5	6
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	69.37	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	11890.00
2.00	Providing and Laying of boulder apron laid in wire crate with 4 mm dia G.I. wire confirming to IS 280 and IS 4826 in 100 mm x100 mm mesh(wovendiagonally) i.e. 10% extra for laps and joint with stone boulder weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete. complete as per HP. PWD specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge.	140.64	Cum	3004.05	Rupees Three Thousand Four and Five paise Only	Per cubic metre	422490.00
						Total	434380.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY

Name of work :-R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion
Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O R/wall at RD 5/629 to 5/639)

Estimated Cost :- Rs 3,45,906.00
Earnest money :- Rs 7,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
1	2	3	In figure	In words	6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	27.00	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4628.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre/ forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	69.60	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	305586.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slope of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	53.80	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	14755.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	17.40	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	20937.00
					Total		345906.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arti Division, HPPWD
Arti

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion
Km 39/00 to 56/200 UNDER PDNA 2023 (SH:- (SH:-C/O R/ Wall at RD 5/180 to 50/190,52/795 to 52/805 & 55/205 to 55/225)

Estimated Cost :- Rs 3,58,378.00
Earnest money :- Rs 8,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	28.08	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4813.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge	73.69	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	323543.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204,3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge	45.50	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	12478.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	14.58	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	17544.00
Quoted Rate Percentage in Figures						Total	358378.00
Quoted Rate Percentage in Words							

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :-R/R damages on Talab (Rau Khad) Behli Road Km 0/0 to 2/170 under PDNA
2023 (.SH:-C/O R/wall at RD 0/090 to 0/120 ,0/590 to 0/600 & 0/610 to 0/630)

Estimated Cost :- Rs 3,70,884.00
Earnest money :- Rs 8,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	30.14	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5166.00
2.00	Charric Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre/ forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge	76.98	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	337988.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with stop of 1(v),20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge	39.73	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	10896.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	13.99	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	16834.00
						Total	370884.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY

Name of work :-R/R damages on Talab (Rau Khad) Behli Road Km 0/0 to 2/170 under PDNA
2023 (SH:-C/O R/wall at RD 0/960 to 0/990 & 1/080 to 1/110)

Estimated Cost :- Rs 3,83,660.00
Earnest money :- Rs 8,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	31.52	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5403.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	80.48	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	353355.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with stop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	41.79	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	11461.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	11.17	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	13441.00
						Total	383660.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Executive Engineer
Artd Division, HPPWD
Artd

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Talab (Rau Khad) Behli Road Km 0/0 to 2/170 under PDNA
2023 (S.H.-(SH-C/O R/wall at RD 1/240 to 1/255 & 1/480 to 1/500)

Estimated Cost :- Rs 2,33,039.00
Earnest money :- Rs 5,000.00
Time: One month

Sub Head and Items of Work		Qty.		Rate		Unit	Amount
Sr. No.				In figure	In words	6	7
1	2	3					
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	19.18	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	3287.00
2.00	Charge Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	49.01	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	215183.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	23.29	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	6387.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	6.80	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	8182.00
						Total	233039

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

Ans
Executive Engineer
A&D Division, HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost:-103445/-	
Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 0/300 to 0/308) (PDNA)						Earnest Money:-2069/-	
						Time:-Two Months	
S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4		5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.40	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2125	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91676	
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.28	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6353	
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291	
Total						103445	

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY						Estimated Cost:-157224/-	
Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 5/100 to 5/112) (P.D.N.A)						Earnest Money:-3144/-	
						Time:-Two Months	
S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4		5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	17.28	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2962	
2	Providing and laying concrete for plain/reinforced concrete open foundation complete as per drawings and technical specificationsMORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	31.32	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	137514	
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	9.36	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	11263	
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	20.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	5485	
Total						157224	

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Word

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY						Estimated Cost:-103955/-	
Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 4/440 to 4/448) (P D N H)					Earnest Money:-2069/-		
					Time:-Two Months		
S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4		5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.00	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2057	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91676	
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.76	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6931	
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291	
Total						103955	

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 3/410 to 3/418) (P D N H)

Estimated Cost:-103445/-

Earnest Money:-2069/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.4	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2125
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91676
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.28	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6353
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						103445

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer

HPPWD (B&R) Division

Arki

SCHEDULE OF QUANTITY						Estimated Cost:-159348/-
Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 2/320 to 2/332) (P.D.N.H.)						Earnest Money:-3187/-
						Time:-Two Months
S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	14.52	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2488
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	31.32	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	137513
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	11.52	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	13862
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	20.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	5485
Total						159348

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O B/Wall at Rd 1/750 to 1/758) (P.D.N.A)

Estimated Cost:-75069/-

Earnest Money:-1501/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	17.12	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2934
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	15.68	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	68844
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	0	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	0
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						75069

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY						Estimated Cost:-103873/-	
Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 2/650 to 2/658) (P D N A)						Earnest Money:-2077/-	
						Time:-Two Months	
S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4		5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	11.53	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	1975	
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specificationsMORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninty and sixty paise only	P.cum.	91676	
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.76	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6931	
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291	
Total						103873	

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 HPPWD (B&R) Division
 Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 1/300 to 1/308) (P D M A)

Estimated Cost:-104735/-
Earnest Money:-2095/-
Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	16.56	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2838
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91675
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.76	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6931
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						104735

Quated Rate Percentage in figure

Quated Rate Percentage in words



Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd /110 to 0/122.25) (P D N A)

Estimated Cost:-264589/-

Earnest Money:-5292/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	38.46	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	6592.044
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	54.27	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	238277.86
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	9.55	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	11491.515
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	30.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	8227.5
Total						264589

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



Executive Engineer

HPPWD (B&R) Division

Arki

SCHEDULE OF QUANTITY

Name Of Work :- R/R damages on Bhararighat Ali Bhurjani road km 0/00 to 6/00 (SH:- C/O R/Wall at Rd 0/420 to 0/437) (P D N A)

Estimated Cost:-367840/-

Earnest Money:-7357/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	51.85	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	8887.09
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	75.31	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	330656.09
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	13.26	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	15955.758
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	45.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	12341.25
Total						367840

Quoted Rate Percentage in Figure

Quoted Rate Percentage in ~~Figure~~ Words

Executive Engineer
 HPPWD (B&R) Division
 Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O
R/Wall at Rd 2/410 to 2/416.25) (PDNA)

Estimated Cost:-103793/-
Earnest Money:-2076/-
Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	13.50	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2314
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	21.13	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	92773
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	4.5	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	5415
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						103793

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Estimated Cost:-103955/-

Earnest Money:-2079/-

Time:-Two Months

Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O

R/Wall at Rd 2/900 to 2/908) (PDNA)

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.00	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2057
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91676
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.76	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6931
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						103955

Quoted Rate Percentage in Figure
quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :- R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 1/210 to 1/216) (PDNA)

Estimated Cost:-76939/-

Earnest Money:-1539/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	9.66	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	1656
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	15.66	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	68757
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	3.6	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	4332
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	8.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	2194
Total						76939

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :- R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 0/710 to 0/717) (P.D.N.H.)

Estimated Cost:-150496/-

Earnest Money:-3010/-

Time:- Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	21.35	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	3659
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	31.01	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	136153
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.46	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6570
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	15.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	4113.75
Total						150496

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Word

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Estimated Cost:-131937/-

Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 7/895 to 7/902.90) (P D N A)

Earnest Money:-2639/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	17.06	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2924
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	26.7	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	117229
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.69	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6847
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	18.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	4937
Total						131937

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH--C/O R/Wall at Rd 6/315 to 6/322.50) (P.D.N.A)

Estimated Cost:-156678/-

Earnest Money:-3134/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4		5	6
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	21.53	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	3690
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	32.12	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	141026
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	6.52	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	7846
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	15.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	4114
Total						156676

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



Executive Engineer

HPPWD (B&R) Division

Arki

SCHEDULE OF QUANTITY

Name Of Work :-R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O

Estimated Cost:-103955/-
Earnest Money:-2079/-

R/Wall at Rd 5/620 to 5/628) (PPNA)

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.00	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	2057
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1.5:10(1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91676
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	5.76	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	6931
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	3291
Total						103955

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

1028

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :- R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 3/650 to 3/658) (PDNA)

Estimated Cost:-104368/-
Earnest Money:-2087/-
Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer-In-Charge	11.04	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	1892
2	Providing and laying concrete for plain/reinforced concrete open foundation complete as per drawings and technical specifications MORO clause 302.303, 1202 & 1203 P.C.C nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	20.88	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	91576
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	6.24	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	7505
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	12.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Pmt.	3291
Total						104368

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Estimated Cost:-292139/-

Name Of Work :-R/R damages on Dohra Danga Kothi Jamogi Road km0/00 to 5/00 (SH:- C/O C/O B/Wall at

Earnest Money:-5843/-

RD 3/045 to 3/090) (P.D.N.A)

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	48.20	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	8261
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802.803, 1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	61.97	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	272085
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	0	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	0
4	Providing and laying 100mm dia meter PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	43.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	11793
Total						292139

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY

Name Of Work :- R/R damages on Suhani Bashyana Falodan Kangridhar road km 0/00 to 8/240 (SH:- C/O R/Wall at Rd 7/090 to 7/102) (PDNA)

Estimated Cost:-155614/-

Earnest Money:-3112/-

Time:-Two Months

S No.	Sub head and items of work	Quantity	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	18.00	171.4	Rupees one hundred seventy one and forty paise only	P.cum.	3085
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202&1203 P.C.C. nominal mix 1:5:10 (1 cement : 5 sand : 10 aggregates-40mm) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	31.32	4390.6	Rupees four thousand three hundred ninety and sixty paise only	P.cum.	137514
3	Back filling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In-Charge	7.92	1203.3	Rupees one thousand two hundred three and thirty paise only	P.cum.	9530
4	Providing and laying 100mm dia meter PVC pipe for wheel holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In-Charge	20.00	274.25	Rupees two hundred seventy four and twenty five paise only	P.Rmt.	5485
Total						155614

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
HPPWD (B&R) Division
Arki

SCHEDULE OF QUANTITY			Estimated Cost: -Rs1,27,337/- only	
Name of Work:-R/R Damages on Bathalang Jawara to Dharail road Km 0/00 to 0/615 . (SH:- C/o Edge wall at Rds 0/175 to 0/195.) (Under PDNA)			Earnest Money :-Rs <u>2 Lacs</u> only	
			Time :-Two Months	

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.00	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1885
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	25.60	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	112399
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	7.20	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	8664
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	16.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4388
					Total	127337

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Bathalang Jawara to Dharail road Km 0/00 to 0/615 . (SH:- C/o Edge wall at Rds 0/145 to 0/165.) (Under PDNA)

Estimated Cost :-Rs1,29,295/- only

Earnest Money :-Rs2600/-Only

Time :-Two Months

S. No.	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	14.00	171.40	Rupees One hundred seventy one and paise forty only		P.Cum.	2399.6
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	25.60	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	112399.4
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3,8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	8.40	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	10107.7
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	16.00	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	4388.0
						Total	129295

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD

Arki

SCHEDULE OF QUANTITY

Estimated Cost -Rs1,23,047/- only

Earnest Money :-Rs2600/-Only

Time :-Two Months

Name of Work:-R/R Damages on Bathalang Jawara to Dharail road Km 0/00 to 0/615 . (SH:- C/o
Edge wall at Rds 0/085 to 0/105.) (Under PDNA)

S No	Sub head and items of work	Qty.	Figure	Rate In		Unit	Amount
				Words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	12.00	171.40	Rupees One hundred seventy one and paise fourty only		P.Cum.	2056.8
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802, 803, 1202 & 1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	25.60	4390.60	Rupees four thousand three hundred ninety and paise sixty only		P.Cum.	112399.4
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	6.00	1203.30	Rupees one thousand two hundred three and paise thirty only		P.Cum.	7219.8
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	5.00	274.25	Rupees two hundred seventy four and paise twenty five only		P.Rmt	1371.3
						Total	123047

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer

Arki Division HPPWD

Arki

SCHEDULE OF QUANTITY							Estimated Cost: -Rs97500/- only
Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Various Roads Under Darla Section Job No-3							Earnest Money :-Rs2000/-only
							Time :-Fifteen Days
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4	5	6	
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machinerries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred and fifty only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs97500/- only	
Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Various Roads Under Darla Section Job No-1						Earnest Money :-Rs2000/-only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machinerries . Any accident and other damages to be the private and govt. property occur during the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred and fifty only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

Estimated Cost: -Rs99000/- only

Earnest Money :-Rs2000/-only

Time :-Fifteen Days

S. No	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1			3		4	5	6
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
	Total						99000

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99000/- only
Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of JCB for removal of slips in Various Roads Under Darla Section Job No-5)						Earnest Money :-Rs2000/-Only
						Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	
				Figure	Words		Amount
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611)including cartage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Galog Kunihar Road Km 0/00 to 13/785 . (SH:- C/O R/wall at Rds12/900 to 12/915.) (Under PDNA)

Estimated Cost :-Rs97,259/- only

Earnest Money :-Rs2000/-only

Time :-07m1Month

S No	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.40	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1440
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	82324
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts, and as per the direction of Engineer-In- Charge	9.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	10830
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	9.72	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rml	2666
					Total	97259

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki