

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26 6003-11

Dated:-22/10/2025


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **30.10.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **29.10.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **29.10.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.


Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of rain damages on Shimla Kunihar Ramshear Nalagarh road portion km. 38/600 to 47/0(SH:-Construction of RCC hume pipe culvert 900mmmm diameter at Rd 42/340 with wing walls under PDNA	4,89,694/-	10,000/-	1 Month	350/-
2.	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road portion km. 17/500 to 26/0(SH:-C/o RCC hume pipe culvert 900mm diameter at Rd 23/360 with wing walls under PDNA	4,79,032/-	10,000/-	1 Month	350/-
3	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road portion km. 17/500 to 26/0(SH:-C/o RCC hume pipe culvert 900mm diameter at Rd 23/280 with wing walls under PDNA	4,38,757/-	10,000/-	1 Month	350/-
4	Restoration of rain damages on Loharghat to Bhiunkhari road km. 0/0 to 15/0(SH:-C/o RCC hume pipe culvert 90mm dia at RD 14/330(ii)R/R on Kohu Sour Bhiunkhari road	4,79,095/-	10,000/-	1 Month	350/-

	km. 0/0 to 11/800(SH:-C/o RCC HPC at RD 5/060)Under PDNA				
5	Restoration of rain damages on Jabal Manlogkalan Ukhoo Panjali Jainagar road km. 0/0 to 24/765(SH:-C/o RCC hume pipe culvert 900mm diameter at Rd 22/730(ii)R/R damages on Jamli Jainagar road portion km. 6/500 to 16/200(SH:-C/o RCC HPC at RD 13/165)Under PDNA	4,79,095/-	10,000/-	1 Month	350/-
6	Restoration of rain damages on Shimla Kunihar Ramshear Nalagarh road portion km. 38/600 to 47/0(SH:-Construction of RCC hume pipe culvert 900mm diameter at Rd 49/465 & 49/540 with wing walls)Under PDNA	4,79,095/-	10,000/-	1 Month	350/-
7	C/o link road Shivghatti to Bajheri km. 0/0 to 1/500(SH:-Formation cutting at RDs 0/720 to 0/806.90)Deposit	99,948/-	2000/-	2 Month	350/-
8	Restoration of rian damages on Bagga Hawanikol road km. 0/0 to 6/0(SH:-C/o R/wall in km. 2/430 to 2/438)Under PDNA	1,24,741/-	2500/-	2 Month	350/-
9	Restoration of rain damages on Bagga Hawanikol road km. 0/0 to 6/0(SH:-C/o R/wall in km. 2/040 to 2/048)Under PDNA	1,25,223/-	2500/-	2 Month	350/-
10	R/R damages on Shimla Kunihar Ramshear Nalagarh road portion km. 38/600 to 47/0 under PDNA(SH:-C/o B/wall at RD 46/030 to 46/050)	2,38,761/-	5000/-	1 Month	350/-
11	Restoration of rain damages o n various roads under Kunihar Sub-Division under Mann section(SH:-Hiring of JCB for removal of slips in various reaches/locations etc.	99,000/-	2000/-	1 Month	350/-
12	R/R damages on Arki Sub-Division HP,PWD, Arki Piplughat Section (SH:- Hiring of Tipper for Carriage of slips/debries etc) Job No.-5	98,800/-	2000/-	15 Days	350/-
13	R/R damages on Arki Sub-Divn. HPPWD Arki under Piplughat Section (SH:- Removal of slips/dressing of road by hiring of JCB) Job No.9	99,000/-	2000/-	15 Days	350/-
14	R/R damages on Arki Sub-Divn. HPPWD Arki under Piplughat Section (SH:- Removal of slips/dressing of road by hiring of JCB) Job No.8	99,000/-	2000/-	15 Days	350/-

15	R/R damages on Arki Sub-Divn. HPPWD Arki under Piplughat Section (SH:- Removal of slips/dressing of road by hiring of JCB) Job No.7	99,000/-	2000/-	15 Days	350/-
16	R/R damages on Arki Sub-Divn. HPPWD Arki under Piplughat Section (SH:- Hiring of Tipper for carriage of slips/debries etc.) Job No.4	98,800/-	2000/-	15 Days	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.



Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2025-26- 6003-11

Dated:- 22/10/25

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 16(Sixteen) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Shimla Kunihar Ramsehar Nalagarh road portion km 38/600 to 47/00.(Sh :Construction-of Rcc Hume Pipe culvert 900 mm diameter at Rd 42/340 with wing walls .Under PDNA

Estimated Cost :- Rs 4.89,694.00


Earnest money :- Rs 10,000.00

Time: one months

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	66.79	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	11448.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	7.85	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	38113.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	12.61	Cum	5291.95	Rupees Five Thousand Two Hundred Ninety One and Ninety Five paise Only	Per cubic metre	66731.00
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	10.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	38816.00
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	71.54	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	314104.00

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	32.30	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	8858.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	9.66	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	11624.00
						Total	489694.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Shallaghat Arki Kuniyar Barotiwalla road portion km 17/500 to 26/00.(Sh :Construction-of Rcc Hume Pipe culvert 900 mm diameter at Rd 23/360 with wing walls .Under PDNA

Estimated Cost :- Rs 4.79,032.00


Earnest money :- Rs 10,000.00

Time: one months

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	In figure	In words		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	54.77	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	9388.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.42	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	31170.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	20.98	Cum	5291.95	Rupees Five Thousand Two Hundred Ninety One and Ninety Five paise Only	Per cubic metre	111025.00
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	20.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	77631.00
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	54.08	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	237444.00

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	20.90	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	5732.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.52	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6642.00
						Total	479032.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Shallaghat Arki Kunihar Barotiwalla road portion km 17/500 to 26/00.(Sh :Construction-of Rcc Hume Pipe culvert 900 mm diameter at Rd 23/280 with wing walls .Under PDNA

Estimated Cost :- Rs 4,38,757.00

Earnest money :- Rs 10,000.00


Time: one months

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3			6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	56.39	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	9665.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	7.73	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	37531.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	12.61	Cum	5291.95	Rupees Five Thousand Two Hundred Ninety One and Ninety Five paise Only	Per cubic metre	66731.00
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	10.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	38816.00
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	62.68	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	275203.00

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	15.20	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	4169.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.52	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6642.00
						Total	438757.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Loharghat to Bhiunkhary road km 0/00 to 15/00.(Sh :Construction-of Rcc Hume Pipe culvert 900 mm diameter at Rd14/330) ii) R/R/d on Kohu Sour Bhiunkhary road km 0/00 to 11/800.(Sh:-C/o RCC HPC at Rd 5/060)Under PDNA

Estimated Cost :- Rs 4.79,095.00


Earnest money :- Rs 10,000.00

Time: one months

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	54.77	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	9388.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.42	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	31170.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	20.98	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	111088.00
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	20.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	77631.00
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	54.08	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	237444.00

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	20.90	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	5732.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.52	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6642.00
						Total	479095.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.


SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages onJabal Manlogkalan Ukhoo Panjali Jainagar road km 0/00 to 24/765.(Sh :Construction-of Rcc Hume Pipe culvert 900 mm diameter at Rd 22/730) ii) R/R/d on Jamli Jainagar road portion km 6/500 to 16/200.(Sh:-C/o RCC HPC at Rd 13/165)Under PDNA							Estimated Cost :- Rs 4.79,095.00	
							Earnest money :- Rs 10,000.00	
							Time: one months	
Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount		
1	2	3	In figure	In words	6	7		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	54.77	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	9388.00	
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.42	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	31170.00	
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	20.98	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	111088.00	
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	20.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	77631.00	
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	54.08	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	237444.00	

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	20.90	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	5732.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.52	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6642.00
						Total	479095.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Divisjon (B&R)
HP. PW. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Shimla Kunihar Ramsehar Nalagarh road portion km 38/600 to 47/00.(Sh :Construction-of Rec Hume Pipe culvert 900 mm diameter at Rd 49/465 &49/540 with wing walls
.Under PDNA

Estimated Cost :- Rs 4,79,095.00


Earnest money :- Rs 10,000.00

Time: one months

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		1	2	In figure	In words		
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	54.77	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	9388.00
2.00	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203. P.C.C. 1:4:8 40 mm nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.42	Cum	4855.20	Rupees Four Thousand Eight Hundred Fifty Five and Twenty paise Only	Per cubic metre	31170.00
3.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	20.98	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	111088.00
4.00	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108. (C) 900 mm dia. including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	20.00	cum	3881.55	Rupees Three Thousand eight Hundred eighty one and fifty Five paise Only	Per cubic metre	77631.00
5.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	54.08	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and sixty Only	Per cubic metre	237444.00

6.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	20.90	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	5732.00
7.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.52	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6642.00
						Total	479095.00

Quoted Rate Percentage in Figures
Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:- C/o Link Road Shivghatti to Bajheri Km 0/00 to 1/500 (SH:-Formation Cutting at Rds 0/720 to 0/806.90.) (Deposit)

Estimated Cost: -Rs99948/- only

Earnest Money :-Rs2000/-Only

Time :- Two Months

S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution , etc. and to protect stability of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in -Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut material in specified manner, treading, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 11.23 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundred only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	561.35	Per. Cum.	178.05	Rupees one hundred seventy eight and paise five only .	99948
					Total	99948

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki

DRAFT SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Bagga hawanikol road km 0/000 to 6/000 (SH:- C/o R/wall in km
2/430 to 2/438) (under PDNA)

Estimated Cost: -Rs 1,24,741/- only

Earnest Money : Rs 2500/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	16.24	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	2784.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	26.40	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	115912.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	4.32	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	5198.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	847.00
						Total	124741.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

DRAFT SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Bagga hawanikol road km 0/000 to 6/000 (SH:- C/o R/wall in km 2/040 to 2/048) (Under PDNA)					Estimated Cost: -Rs 1,25,223/- only		
					Earnest Money : Rs 2600/-Only		
					Time -Two Months		
S.N	Sub head and items of work	Qty.	Rate		Unit	Amount	
1	2	3	In figure	In words	6	7	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	15.68	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	2688.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	26.40	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	115912.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	4.80	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	5776.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	847.00
						Total	125223.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of work :-R/R damages on Shimla Kunihar Ramshehar Nalagarh Road portion Km 38/600 to 47/000 UNDER PDNA (SH:-C/O B/wall at RD 46/030 to 46/050)

Estimated Cost :- Rs 2,38,761.00

Earnest money :- Rs 5,000.00

Time: One month

Sr.No	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	40.14	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6880.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	51.88	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	227784.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v) 20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	14.94	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	4097.00
						Total	238761.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

-sd-

Executive Engineer
Arki Division (B&R)
HP PWD Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Mann section.(Sh-Hiring of JCB for removal of slips in various reaches/locations etc.)

Estimated Cost :- Rs 99,000.00


Earnest money :- Rs 2,000.00

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	2					6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hour s	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
						Total	

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY						Estimated Cost: 98800.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Piplughat Section						Earnest Money: 2000.00	
(SH:- Hiring of Tipper for carriage of slips/ debris etc) Job No. 5						Time Period: 15 Days	
S. No	Description of Item	Qty		Rate		Unit	Amount
		3		In figures	In words	6	7
1	Hiring of Tipper for removal of land slide and debris with minimum capacity of 5.50 cum per trip and minimum working 6.00 (Six) hours per day. The contractor/ owner of the tipper shall bear the expenses of P.O.L charges, repair of machineries any type of accident and other damages to the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed with in all leads, lifts and as per direction of Engineer in charge.	152.00	Hour	650.00	Rupees Six hundred fifty and paise nil	Per Hour	98800.00
	Total=						98800.00
Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


Executive Engineer
Arki Division (B&R)
HPPWD Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99000.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Piplughat Section						Earnest Money: 2000.00	
(SH:- Removal of slips/dressing of road by hiring of JCB) Job No 9						Time Period: 15 Days	
S. No	Sub head and items of work	Qty		Rate		Unit	Amount
		3		In figures	In words	6	7
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause 302.3.5 and 1611 including carriage of materials upto all leads, lifts and as per direction of Engineer in charge.	99.00	Hour	1000.00	Rupees one thousand and paise nil only	Per Hour	99000.00
	Total=						99000.00
Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99000.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Piplughat Section						Earnest Money: 2000.00	
(SH:- Removal of slips/dressing of road by hiring of JCB) Job No. 8						Time Period: 15 Days	
S. No	Sub head and items of work	Qty		Rate		Unit	Amount
1	2	3		In figures	In words	6	7
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause 302.3.5 and 1611 including carriage of materials upto all leads, lifts and as per direction of Engineer in charge.	99.00	Hour	1000.00	Rupees one thousand and paise nil only	Per Hour	99000.00
	Total=						99000.00
Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99000.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Piplughat Section						Earnest Money: 2000.00	
(SH:- Removal of slips/dressing of road by hiring of JCB) Job No. 7						Time Period: 15 Days	
S. No	Sub head and items of work	Qty		Rate		Unit	Amount
		3		In figures	In words	6	7
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause 302.3.5 and 1611 including carriage of materials upto all leads, lifts and as per direction of Engineer in charge.	99.00	Hour	1000.00	Rupees one thousand and paise nil only	Per Hour	99000.00
	Total=						99000.00
Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY						Estimated Cost: 98800.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Piplughat Section						Earnest Money: 2000.00	
(SH:- Hiring of Tipper for carriage of slips/ debris etc) Job No. 4						Time Period: 15 Days	
S. No	Description of Item	Qty		Rate		Unit	Amount
1	2	3		In figures	In words	6	7
1	Hiring of Tipper for removal of land slide and debris with minimum capacity of 5.50 cum per trip and minimum working 6.00 (Six) hours per day. The contractor/ owner of the tipper shall bear the expenses of P.O.L charges, repair of machineries any type of accident and other damages to the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed with in all leads, lifts and as per direction of Engineer in charge.	152.00	Hour	650.00	Rupees Six hundred fifty and paise nil	Per Hour	98800.00
	Total=						98800.00
	Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.						

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki