

**Himachal Pradesh
Public works Department
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **01-11-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. **on 31-10-2025.** The applications for issue of tender forms will be received **up to 2.00 P.M. on 30-10-2025.**

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- Providing and supplying AIO computer system and UPS for Dhanotu Sub-Division)Under Telecom deposit)Job No.I	94760	1900	Two Months
2	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- Providing and supplying AIO computer system and UPS for Dhanotu Sub-Division)Under Telecom deposit)Job No.II	94760	1900	Two Months
3	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- Providing and supplying AIO computer system and UPS for Dhanotu Sub-Division)Under Telecom deposit)Job No.III	94760	1900	Two Months
4	RRD on Maloh Kateru road km 6/00 to 14/250(SH:- removal of slips in various RDs)	97660	2000	Two Months
5	Restoration on link road from Dol to Sekhra road km 0/00 to 4/00 (SH:- Restoration of rain cuts, and Removal of slips between km. 0/00 to 4/00)	99264	2000	Two Months
6	RRD on Bhalana to Namana Road km. 0/00 to 7/00 (SH:- Construction of PCC R/wall , at RD 0/160 to 0/165.60) Telecom Deposit	98544	2000	Two Months

7	RRD on various road in store section under Gohar Sub-division (SH:- Herring of JCB for removal of slips /debris, dressing of berms in various road under store section)	99000	2000	Two Months
8	RRD on various road in store section under Gohar Sub-division (SH:- Herring of JCB for removal of slips /debris, dressing of berms in various road under Jachh section)	99000	2000	Two Months
9	SDF/2025/59 R/O Road Jayog to Nalwad km. 0/00 to 2/00 (SH:- Herring of JCB for maintenance of earthen shoulders and removal of slips at various RDs in km. 1/00 to 2/00) GP Tunna	59400	1200	Two Months
10	SDF/2025/557, Repair of road chail Chowk to Kukrigaloo via Lambidhar chowkkkri Samih Mandogaloo Kamlon and Riyul Bagra Km. 0/00 to 7/00(SH:- Herring of JCB for removal of slips, dressing of Berms and construction of unlined drain) Job No. 1	99000	2000	Two Months
11	A/R & M/O on HPPWD Rest House Gohar at Bassa Tehsil Chachyot Distt. Mandi HP (SH:- Providing and laying painting work)	83769	1700	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated

23-10-2025

No. PW-GHR-Tender/NIT/2025

5776-86

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.

4. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

B. Saini
Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

BILL OF QUANTITY


me of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- Providing and suplying AIO computer system and UPS for Dhanotu Sub Division) under Telecom Deposit) Job No.1

Estimated cost Rs. - 94,760/-

Earnest Money cost Rs. 1900/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and installation of Lenovo idea centre AIO intel core i7 13620H 27" FHD IPS 3-Side Edgeless All-in- One Desktop (16GB/1TB SSD/Win 11/office 21/5.0MP+IR Camera/3Wx2 HHarman Speakers/wireless EOS Keyboard & Mouse) FOHM003EIN with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer- In-Charge	1.00	Each	92,000.00		
2	Providing and installation of UPS-600VA (as per proforma bill attechd) for with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer-In- Charge	1.00	Each	2,760.00		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Line of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- Providing and suplying AIO computer system and UPS for Dhanotu Sub Division under Telecom Deposit) Job No.II

Estimated cost Rs. - 94,760/-
Earnest Money cost Rs. 1900/-
Time - Two Month


SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and installation of Lenovo idea centre AIO intel core i7 13620H 27" FHD IPS 3-Side Edgeless All-in- One Desktop (16GB/1TB SSD/Win 11/office 21/5.0MP+IR Camera/3Wx2 Harman Speakers/wireless EOS Keyboard & Mouse) FOHM003EIN with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer- In-Charge	1.00	Each	92,000.00		
2	Providing and installation of UPS-600VA (as per proforma bill atatched) for with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer-In- Charge	1.00	Each	2,760.00		
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- Providing and suplying AIO computer system and UPS for Dhanotu Sub Division) under Telecom Deposit) Job No.III	Estimated cost Rs. - 94,760/-
	Earnest Money cost Rs. 1900/-
	Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and installation of Lenovo idea centre AIO 13th Gen core i5-13420H 24" FHD IPS (16GB/512GB SSD/Window 11/office 24/3Wx2 Harman Speakers/wireless EOS Keyboard & Mouse, cloud gray) FOHNOOPHIN All-in-one desktop with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer- In-Charge	1.00	Each	71,300.00		
2	Providing and installation of UPS-600VA (as per proforma bill attached) for with in warranty period as per Lenovo company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer-In- Charge	1.00	Each	2,760.00		
3	Providing and installation of Canon PIXMA Mega tank G3780 All-in-one inktank Colour Printer with Duplex with 2 years standard warranty (as per proforma bill attached) for with in warranty period as per Canon company period (as per Performa bill attached) with in guaranty period including of all tax / accessory fitting and installation charges in this office & as per direction and satisfaction of Engineer-In- Charge	1.00	Each	20,700.00		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer.
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

name of work :- RRD on Maloh Kateru road km 6/00 to 14/250 (SH:- Removal of slips in various RD's)

Estimated cost Rs. 97,666/-

Earnest Money cost Rs. 2000/-


Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	928.38	Per Cubic meter	105.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- Restoration on Link road from Dol to Sekhra road km 0/00 to 4/00 (SH:- Restoration of rain cuts, and Removal of slips between km 0/00 to 4/00)					Estimated cost Rs. 99,264/-	Earnest Money cost Rs. 2000/-
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 300 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902, as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	256.57	per Cubic metre	181.35		
2	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	501.28	Per Cubic meter	105.20		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY


Line of work :- RRD on Bhalana to Namana road km 0/00 to 7/00 (SH:- Construction of PCC R/Wall, at Rd 0/160
0/165.60) Telecom Deposit

Estimated cost Rs. - 98,544/-

Earnest Money cost Rs.2000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount	
					with all taxes including GST in Rs. P	with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.21	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	21.36	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause	8.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on various road in Store section under Gohar Sub - Division (SH:- Herring of JCB for removal of slips/debris , dressing of berms in various road under Store section) .					Estimated cost Rs. - 99000/-	Earnest Money cost Rs.2,000/-	
					Time - Two Month		
Sr. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00			
	Percentage rate Quoted in figure						
	Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Executive
 Gohar Division
 H.P.P.W.D. Gohar


135

BILL OF QUANTITY


Name of work :- RRD on various roads under Gohar Sub Division (Sl:- Hiring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various roads under Jachh Section) .				Estimated cost Rs. -	99000.00	
				Earnest Money cost Rs. -2000.00		
				Time - Two Month		
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00	99000.00	Rupees Ninety Nine Thousand Only
					99000.00	

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Assistant Engineer,
 Gohar Sub-Division,
 HP: PWD Gohar

Bill of Qty. attached for Rs. 99,000/- only


 Executive Engineer
 Gohar Division
 M.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/59 R/O Road Jayog to Nalwad Km 0/0 to 2/0 (SH:- Hiring of JCB for maintenance of earthen shoulders and removal of slips at various RDs 1/00 to 2/000) GP Tuna					Estimated cost Rs.	₹ 59,400.00
					Earnest Money cost	₹ 1,200.00
					Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	54.00	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

108

BILL OF QUANTITY

Name of work :- SDF/2025/557, Repair of road Chail Chowk to Kukrigaloo via Lambidhar Chowkkri Samih Mandogaloo Kamlon and Riyul Bagra km 0/00 to 7/00 (SH:- Herring of JCB for removal of slips, dressing of berms and construction of unlined drain) Job No. I					Estimated cost Rs. - 99,000/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
Sr. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00	99000.00	Rupees Ninety Nine Thousand Only
					99000.00	

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.

Bill of Quantity approved for Rs. 99,000/- only.

H Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

(62)

BILL OF QUANTITY

of work :- A/R & M/O on HPPWD Rest House Gohar at Bassa Tehsil Chachyot Distt. Mandi H.P (SH:- Providing and laying painting work etc.)

Estimated cost Rs. - 83,769/-

Earnest Money cost Rs.17,00/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary including carriage of material within all leads, lifts and other incidental charges complete with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	208.92	Per Square meter	12.25		
2	Providing and applying white cement based putty of average thickness 1 mm (one milimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of material within all leads, lifts and other incidental charges complete and as per direction of the Engineer-In-Charge.	208.92	Per Square meter	93.60		
3	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	208.92	Per Square meter	41.15		
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	263.88	Per Square meter	103.75		
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	26.87	Per Square meter	98.90		
6	French spirit polishing : Two or more coats on old works including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	139.90	Per Square meter	115.60		

Supply and fixing Plastic curtain rods 25 mm (twenty five millimetre) dia with in all hardware and lifts and other incidentals and as per the direction of the Engineer-in Charge.	44.20	Per Running meter	155.00		
Total:-					
Percentage rate Quoted in figure					
Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 M.P.W.D. Gohar

98