

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Scaled Item rate / percentage rate tender are hereby Invited on Form No. 6 & 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 28-10-2025 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 28-10-2025 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender:- 30-10-2025 at 10.30 AM.
4. Date of opening of Tender:- 30-10-2025 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	C/O R/wall to protect the community Hall road at Katoh (SH:-C/O R/wall from Community hall side) (VKV/2024/311)	3,88,002/-	8000/-	Two Months	Rs. 350/-	Class-D
2	A/R&M/O various road under sub Division HPPWD Bhoranj Division (SH:-P/F road stud at various road) (section Bhareri)	99,050/-	2000/-	Two Months	Rs. 350/-	Class-D
3	A/R & M/O various road under sub Division HPPWD Bhoranj Division (SH:- P/F Rumble strip at various road) (Section Bhareri)	99,600/-	2000/-	Two Months	Rs. 350/-	Class-D
4	Repair of link road Kehlwin to Bedu-Badhar via thatwani High School Tehsil Bhoranj Distt. Hamirpur (SH:- ROFD, R/wall at RD 0/468 to 1/253) (NDF/2023/637/R/O/Repair)(DC Deposit)	4,99,114/-	10000/-	Two Months	Rs. 350/-	Class-D
5	Repair & Restoration of old hamirpur to jahu road portion Bassi Chowk to Tal Shri Ram Chander Marg (NDF/2023/633) (SH:- C/O R/wall at RD 0/055 to 0/064.60) (DC Deposit)	28,580/-	10000/-	Two Months	Rs. 350/-	Class-D
6	R/M of Samirpur to Bakkar khad via Matlana km 0/00 to 5/500. (SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip)	99,503/-	2000/-	Two Months	Rs. 350/-	Class-D
7	R/M of Sangrohi to BakkarKhad via Bhuana km 0/00 to 3/700 (SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip)	99,519/-	2000/-	Two Months	Rs. 350/-	Class-D
8	Repair/Restoration on Lajhyani to Bhalwani via Kalyal, Barthwan Road km	98,986/-	2000/-	Two Months	Rs. 350/-	Class-D

	0/00 to 5/00 (SH:- C/O R/wall at RD 4/760 to 4/764) (PDNA)					
9	Repair and Maintenance on Dasmal to kot kangri Road km 0/00 to 3/500 (SH:- C/O R/wall at RD 1/910 to 1/917)	99,867/-	2000/-	Two Months	Rs. 350/-	Class-I
10	R/R Damage on link road from Town Bharari to Balet via Gharan Road (SH:- C/O R/wall at RD 0/320 to 0/327)	98,599/-	2000/-	Two Months	Rs. 350/-	Class-I
11	R/R damages on link road from Town Bharari to Balet via Ghroun. (SH:- C/O V-shape Drain & Side Berms)	97,760/-	2000/-	Two Months	Rs. 350/-	Class-I
12	R/M of link road Piplidhar to upper Tella km 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder)	99,950/-	2000/-	Two Months	Rs. 350/-	Class-I
13	R/M of link road pipidhar to upper Tella km 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder)	99,908/-	2000/-	Two Months	Rs. 350/-	Class-I
14	R/M of link road pipidhar to upper Tella km 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder)	99,992/-	2000/-	Two Months	Rs. 350/-	Class-I
15	A/R & M/O Bhareri Bhaur via Badehar road km 0/00 to 2/00 (SH:- Providing and installation of crash barrier at various portion between km 0/00 to 1/00) PDNA	4,73,850/-	9500/-	Two Months	Rs. 350/-	Class-I
16	Restoration of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/750 (SH:- Repair of existing causeway at various RD's 5/455 to 5/465, 5/525 to 5/535, 5/570 to 5/760, 5/790 to 5/800, 6/090 to 6/110, 6/225 to 6/235, 6/380 to 6/387) (Under PDNA)	4,98,220/-	10000/-	Two Months	Rs. 350/-	Class-I
17	Restoration of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/750. (SH:- Repair of existing causeway at various RD's 4/170 to 4/180, 4/440 to 4/470, 5/270 to 5/306, 5/415 to 5/422=77 mtr.) (under PDNA)	4,98,220/-	10000/-	Two Months	Rs. 350/-	Class-I
18	Restoration of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/750 (SH:- Restoration of road surface by filling available from excavated earth in various RD's) (PDNA)	4,99,764/-	10000/-	Two Months	Rs. 350/-	Class-D
19	Restoration of Awahdevi Bagwara Gharan Dera Parol road km 0/00 to 9/750 (SH:- Restoration of road surface by filling available from excavated earth in various RD's) (PDNA)	4,99,694/-	10000/-	Two Months	Rs. 350/-	Class-D
20	Restoration on link road to Baroh via Bajroh km 0/00 to 2/00 (SH:- Repair of pot hole in km 0/00 to 2/00 (Chamboh Section) (under PDNA)	4,99,548/-	10000/-	Two Months	Rs. 350/-	Class-D
21	C/O Shed in the compound of co-operative society G.P. Dhamrol (VKV/2024/622)	2,87,920/-	6000/-	Two Months	Rs. 350/-	Class-D
22	Restoration on Dadu-Chatrial road km 0/00 to 1/250 (SH:- Repair of Pot Hole at various RDs) (Under PDNA)	4,99,625/-	10000/-	Two Months	Rs. 350/-	Class-D
23	C/O Panjot Dhariyara road km 0/00 to 4/500 (ii) C/O link road Dharoun to	98000/-	2000/-	Two Months	Rs. 350/-	Class-D

	Dharyara km 0/00 to 0/900 under HPPWD Sub-Division Samirpur HPPWD Samirpur. (SH:- Providing & manufacturing sign Board (Dho Section))					
24	C/O link road Dho to Dho road Km 0/00 to 2/00 (ii) C/O Patta Awah Devi road Km 10/00 to 17/500 under HPPWD Sub Division Samirpur HPPWD Samirpur (SH:- Providing & manufacturing sign Board. (Dho Section))	98000/-	2000/-	Two Month	Rs. 350/-	Class-D
25	A/R & M/O various road under Sub Division HPPWD Bhoranj Division (SH:- P/F road stud at various road) (section Bhareri)	99400/-	2000/-	Two Month	Rs. 350/-	Class-D
26	A/R & M/O various road under Sub Division HPPWD Bhoranj Division (SH:- P/F road stud at various road) (section Bhareri)	99750/-	2000/-	Two Month	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(I) No Violation of social distancing.

(II) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2025- 9868 - 9908

Dated:- 16-10-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj, Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

Job-1

NAME OF WORK:- C/O R/Wall to protect the Community Hall road at Katoh.(SH:- C/O R/Wall from community hall side.) (vkv/2024/311)

Estimated Cost Rs 3,22,002/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	41.71	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	81.93	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	40.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.23	Per Cubic Meter			
Total						
Terms and Condition:-						
1.Work shall be executed as per PWD specification.						

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Job-2

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Various road under sub Division H.P.P.W.D Bhoranj Division (SH:- P/F road stud at various road). (Section Bhareri)

Estimated Cost
Earnest Money
Time

Rs 99,050/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing of road stud 100x100mm (one hundred into one hundred millimetres) size Yellow 11M Molded Shank RPM (ABS body) with one side Yellow and one side Red resistant to corrosive effect of salt and grit fitted with lense reflectors installed in concrete or asphaltic surface by drilling holes 30mm (thirty) millimetres upto a depth of 600mm (six hundred) millimetres and bedded in a suitable bituminous grout or epoxy mortar all as per BS:873 (Part4) 1973 as per direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are excluding GST and inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	283.00	Each			
	Terms and Condition:-					

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.P.W.D Bhoranj



Job-3

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various road under sub Division H.P.P.W.D Bhoranj Division .(SH:- P/F Rumble strip at various road). (Section Bhareri)

Estimated Cost
Earnest Money
TimeRs 99,600/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing & fixing rumble strips cover with premix bituminous Carpet, 25mm (twenty five milimetre) height at centre & 500x125mm (five hundred into one hundred twenty five milimetre) dimension (weight 3.80 kg per running meter brand H2 load bearing capacity 20-60 tons) placed across the road adjacent to each other made of plastic with interlocking sub unit make it bind perfectly in one from bump. The bump is pre-coloured (Black-Yellow) and UV stabilised.Each sub unit stubbed with good quality reflective glass beads on other side including carriage of material within all leads and lifts and other incidentals. The rates are excluding GST and inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	120.00	Each			
	Terms and Condition:-					
	1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
H.P.P.W.D Bhoranj

Job-4

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair of Link road kehlwin to Bedu-Badhar via thathwani High School Teh. Bhoranj Distt. Hamirpur. (SH:- ROFD, R/Wall at RD 0/468 TO 1/253) (NDF/2023/637/R/O/Repair) (D.C Deposit)

Estimated Cost Rs 499114/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required lines, grades with cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in-Charge at site according to the MORD technical specification clause 302,1602,1603 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus un-useful material to acquired width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. A recovery of useful stone for 71.30 cubic metre @ Rs. 300/- (Rupees three hundred only) per cubic metre amounting to Rs. 21390/-only shall be effected on pro-rata basis in each running bill from this item. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1426.04	Per Cubic Meter			
	Total					
	Terms and Condition:-					
	1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Restoration of Old hamirpur to Jahu road portion Bassi Chowk to Tal Shri Ram Chander Marg (NDF/2023/633).(SH:- C/O R/Wall at RD 0/055 to 0/064.60) (DC Deposit)

Estimated Cost
Earnest Money
Time

Rs 498680/-
Rs. 10000/-
2 month

Sr.No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	60.13	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	107.22	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Maikana, toll tax,sale tax or other taxes imposed by the Government.	32.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.84	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

Job-6

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Ramprur to Bakkar Khad via Matiana km. 0/00 to 5/500.
(SH:- Maintenance of earthen shoulder, unlined surface drain and Removal of slip.)

Estimated Cost
Earnest Money
Time

Rs. 99503/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	841.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	147.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.60 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1011 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	200.00	Per cubic metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Sangroh to Bakkar Khad via Bhuana km. 0/00 to 3/700.
(SH:- Maintenance of earthen shoulder ,unlined surface drain and Removal of slip.)

Estimated Cost
Earnest Money
Time

Rs. 99519/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	866.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines, grades, level and dimensions. Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	325.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	141.75	Per cubic metre			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HDPWD Bhoranj

Job-8

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair / Restoration on Lajhyani to Bhalwani via kalyal, Barthwan Road km 0/00 to 5/00.(SH:- C/O R/Wall at RD 4/760 to 4/764)
(PDNA)

Estimated Cost
Earnest Money
Time

Rs 92926/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.12	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.97	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

Job-9

NAME OF WORK:- Repair and Maintenance on Dasmal to Kot Kangri Road km. 0/00 to 3/500.(SH:- C/O R/Wall at RD 1/910 to 1/917)

Estimated Cost
Earnest Money
Time

Rs 99257/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.32	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded , crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	22.08	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
Hd PWD Bhoranj

SCHEDULE OF QUANTITY

J-6b-10


NAME OF WORK:- R/R Damage on link road from Town Bharari to Balet via Gharan Road.(SH:- C/O R/Wall at RD 0/320 to 0/327)

Estimated Cost
Earnest Money
Time

Rs 98599/-
Rs. 2000/-
2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structing and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.55	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.95	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.66	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bharanj Division
 HR PWD Bharanj

Job-4

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages on link road from Town Bharari to Balet via Ghroun . (SH:- C/O V-Shape Drain & Side Berms.)

Estimated Cost
Earnest Money
Time

Rs 97760/-
Rs. 2000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.75	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.08	Per cubic metre			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.62	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bharanj Division
 HP PWD Bharanj

Job-12

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of link road Piplidhar to upper Tella km. 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder,)

Estimated Cost Rs 99,950/-
 Earnest Money Rs. 2000/-
 Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.74	Per Cubic metre			
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	116.80	Per Cubic metre			
3	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	431.50	Per square metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
 Bhoranj Division
 Hq. PWD Bhoranj



Job-13

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of link road Pipldhar to upper Tella km. 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder.)

Estimated Cost
Earnest Money
TimeRs. 99,902/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.74	Per Cubic metre			
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	116.80	Per Cubic metre			
3	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	431.00	Per square metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj

SCHEDULE OF QUANTITY

Job-14

NAME OF WORK:- R/M of link road Piplidhar to upper Tella km. 0/00 to 0/900 (SH:- Repair of pot holes & Maintenance of earthen shoulder,)

Estimated Cost
Earnest Money
Time

Rs 99,992/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone screening/binding material to fill up the interstices of coarse aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.74	Per Cubic metre			
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	116.80	Per Cubic metre			
3	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularation on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	432.00	Per square metre			
Total						
Terms and Condition:-						
1. Work shall be executed as per PWD specification.						

Executive Engineer
Bhoranj Division
HNPWD Bhoranj

Job-15

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Bhareri Bhour via Badehar road km. 0/00 to 2/00.(S.H :- Providing and installation of crash barrier at various portion between Km 0/00 to 1/00.) PDNA

Estimated Cost
Earnest Money
Time

473250
Rs. 935550/-
Rs. 20000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size i/c ereing W metal beam crash barrier comprising 3 mm thick corrugated sheet metal beam rail 70 cm (seventy centimeter) above the ground level fixed on ISMC series channel vertical post 150x75x5 mm spaced 2 mtr. Centre to centre 1.80 mtr. Height 1.010 meter below ground/road level and steel parts or fitment to be galvenised by hot dip process , all fitting to confirm to IS 1367 , metal beam rail to be fixed on the vertical posts with a spacer of channel section 150x75x5 mm 330 m long complete as per clause 810 as per the direction of the Engineer-in-charge Including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	121.50	Per running metre			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D. Bhoranj



SCHEDULE OF QUANTITY

Job-16

NAME OF WORK:-Restoration of Awahdevi Bagwara Gharan Dera Parol road km. 0/00 to 9/750.

(SH:- Repair of existing causeway at various RD'S 5/455 to 5/465, 5/525 to 5/535, 5/750 to 5/760, 5/790 to 5/800, 6/090 to 6/110, 6/225 to 6/235, 6/380 to 6/387= 77 mtr.) (Under PDNA)

Estimated Cost Rs. 498220/-

Earnest Money Rs. 10000/-

Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.95	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.95	Per Cubic Meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

SCHEDULE OF QUANTITY

Job-17

NAME OF WORK:-Restoration of Awahdevi Bagwara Gharan Dera Parol road km. 0/00 to 9/750.

(Sit:- Repair of existing causeway at various RD'S 4/170 to 4/180, 4/440 to 4/470, 5/270 to 5/306, 5/415 to 5/422= 77 mtr.) (Under PDNA)

Estimated Cost

Rs. 438220/-

Earnest Money

Rs. 10000/-

Time

2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.95	Per cubic metre			
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	42.95	Per Cubic Meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj



Job-18

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awahdevi bagwara Gharan Dera Parol road km. 0/00 to 9/750.
(SH:- Restoration of road surface by filling available from excavated earth in various RD'S) (PDNA)

Estimated Cost
Earnest Money
Time

Rs 499764/-
Rs. 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	752.00	Per square metre			
2	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. all kind of soil as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1753.80	Per Cubic Meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj



Job-19

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Awahdevi bagwara Gharan Dera Parol road km. 0/00 to 9/750.
(SH:- Restoration of road surface by filling available from excavated earth in various RD'S) (PDNA)

Estimated Cost
 Earnest Money
 Time

Rs 499594/-
 Rs. 10000/-
 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	144.00	Per square metre			
2	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with $\frac{1}{2}$ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr. all kind of soil as per direction of Engineer-in-Charge, including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1957.00	Per Cubic Meter			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer
 Shoranji Division
 PWD Bhorani

Job-20

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration on link road to Baroh via Bajroh km 0/00 to 2/00 (SH:- Repair of Pot Hole in km 0/00 to 2/00) (Chamboh Section) (Under PDNA)

Estimated Cost
Earnest Money
Time

Rs 4,99,542/-
Rs. 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1273.40	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone sscreening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	17.88	Per cubic meter			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H&P WD Bhoranj

SCHEDULE OF QUANTITY

Job-21

NAME OF WORK:- C/O Shed in the Compound of Co-operative Society G.P. Dhamrol (VKV/2024/622)

Estimated Cost
Earnest Money
Time
Rs 2,87,920/-
Rs. 6000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, blasting work, in dry of saturated condition upto any depth and including pumping and bailing out water when required including stacking serviceable and un serviceable material separately as directed and returning the stacked soil in 15 cm (fifteen centimeter) layer by when required into plinth side of foundation consolidation each deposited layer by ramming and watering and then the disposing of all surplus unserviceable excavated earth within all leads and lifts as directed by the Engineer-in-Charge and including entire carriage of materials in all leads and lifts disposed materials to be neatly leveled. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.972	Per cubic meter			
2	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying priming coat of approved steel primer all complete. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2137.48	Per kilogramme			
3	Providing corrugated G.S Sheet roofing including vertical/ curved surface fixed with polymer coated Jor L Hooks, bolts and nuts 8 mm diameter with bitumen and GI Limpet washers or with GI limpet washers filled with white lead 0.63 mm thick with zinc coating not less than 275 gm/ m ² entire carriage of material within all leads and lifts and other incidentals. including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	108.64	Per Square meter			
4	Providing ridges or hips of width 60mm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete. 12.4.2 0.63mm thick with zinc coating not less than 275gm/m. including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.90	Per square meter			
TOTAL						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P. PWD Bhoranj

Job-22

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration on Dadu-Chatral road km. 0/00 to 1/250 . (SH:- Repair of Pot Hole at various RDs.) (Under PDNA)

Estimated Cost
Earnest Money
Time

Rs 499625-
Rs. 100000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1161.49	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam spedification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	35.43	Per cubic meter			
Total						

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.PWD Bhoranj



Job-23

Draft Schedule of Quantity

Estimated Cost :- 98000.00

Earnest Money:- 2000.00

Time: - 3 months

Name of Work:- C/O Panjot Dhariyara road Km.0/0 to 4/500. (ii) C/O link road Dharoun to Dhariyara Km 0/0 to 0/900 under HPPWD Sub- Division Samirpur HPPWD Samirpur .
(SH:-Providing & manufacturing sign Borad) (DHS Section)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lifts.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

Executive Engineer
HPPWD Division
Bharanj.

Job-24

Draft Schedule of Quantity

Estimated Cost :- 98000.00

Earnest Money:- 2000.00

Time:- 3 months

Name of Work:- C/O link road Dho to Doh road. Km. 0/00 to 2/00 (ii) C/O Patta Awah Devi road Km 10/0 to 17/500 under HPPWD Sub- Division Samirpur HPPWD Samirpur
(SH:-Providing & manufacturing sign Borad) (Dho Section)

Sr. No.	Description of items work	Qty	Unit	Rate In fig.	In words	Amount
1.	Providing and manufacturing steel fabrication of sign boards size following dias make of M.S sheet 1.60mm thickness with MS pipe 32mm dia. The height of board should not be less than 2430mm and size 4x3 including, welding, priming single coat complete in all respect and to the entire satisfaction of Engineer in Charge.	20	Each			

TERMS AND CONDITIONS:

1. The work will be carried out as per PWD specification and to the entire satisfaction of the Engineer in charge.
2. The rates shall be inclusive with all taxes and carriage of material in all leads and lift.
3. Nothing will be paid for rejected work/material.
4. The material shall be used of ISI marked/reputed make.

Executive Engineer
HPPWD Division
Bhoranj.

Job-25

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various road under sub Division H.P.P.W.D Bhoranj Division .(SH:- P/F road stud at various road). (Section Bharenj)

Estimated Cost
Earnest Money
Time
Rs 99,400/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing of road stud 100x100mm (one hundred into one hundred millimetres) size Yellow 11M Molded Shank RPM (ABS body) with one side Yellow and one side Red resistant to corrosive effect of salt and grit fitted with lense reflectors installed in concrete or asphaltic surface by drilling holes 30mm (thirty) millimetres upto a depth of 600mm (six hundred) millimetres and bedded in a suitable bituminous grout or epoxy mortar all as per BS:873 (Part4) 1973 as per direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are excluding GST and inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	284.00	Each			
Terms and Condition:-						

1. Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
H.P.P.W.D Bhoranj

Job-26

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various road under sub Division H.P.P.W.D Bhoranj Division .(SH:- P/F road stud at various road). (Section Bharerl)

Estimated Cost
Earnest Money
TimeRs 99,750/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing of road stud 100x100mm (one hundred into one hundred millimetres) size Yellow 11M Molded Shank RPM (ABS body) with one side Yellow and one side Red resistant to corrosive effect of salt and grit fitted with lense reflectors installed in concrete or asphaltic surface by drilling holes 30mm (thirty) millimetres upto a depth of 600mm (six hundred) millimetres and bedded in a suitable bituminous grout or epoxy mortar all as per BS:873 (Part4) 1973 as per direction of the Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are excluding GST and inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government.	285.00	Each			
Terms and Condition:-						

1.Work shall be executed as per PWD specification.



Executive Engineer
Bhoranj Division
H.P.W.D Bhoranj

