

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

E-Mail id-ee-bil2-hp@nic.in
Phone No.01978-222550

SHORT TERM TENDER NOTICE

Sealed items rates tender for the following works are hereby invited by the Executive Engineer, Bilaspur Division No.II, HP. PWD., Bilaspur (H.P) from the eligible contractors of the appropriate class registered in HP.PWD., as per revised enlistment rules so as to reach in the office undersigned on 09.10.2025 upto 10.30AM and will be opened on the same day at 11.00AM in the presence of intending contractors. The tender application will be received in this office alongwith cash payment on account of cost of tender form and the tender form can be had from this office on dated 08.10.2025 upto 12.30 PM. and will be sale on the same day at 4.00P.M.The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued to contractor on production of proof of enlistment, GST and Pan No.etc. Conditional tender and tender received without earnest money will be rejected straightway. The offer of the tender shall be kept open for 45 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	Restoration of Rain Damages on link road Mathi to Sakali road Km.0/00 to 4/240(SH:-Hiring of Excavator cum rock breaker, Excavator cum loader/JCB & Tipper for removal of at RD.0/600 to 0/600) for the year 2025-26 Job No.26.	Rs.99,670/-	Rs.2,000/-	Rs.350/-	One Month
2	Restoration of Rain Damages on link road Mathi to Sakali road Km.0/00 to 4/240(SH:-Hiring of Excavator cum rock breaker, Excavator cum loader/JCB & Tipper for removal of at RD.0/600 to 4/240) for the year 2025-26 Job No.27.	Rs.99,914/-	Rs.2,000/-	Rs.350/-	One Month
3	Restoration of Rain Damages on various road under Namhol Sub-Division(Jukhala Section) (SH:-Hiring of Excavator cum loader/JCB & Tipper for removal of slips and dressing of berms, clearance of drain at various RDs) for the year 2025-26 Job No.12.	Rs.99,360/-	Rs.2,000/-	Rs.350/-	One Month
4.	Restoration of Rain Damages on various road under Namhol Sub-Division(Kharsi Section) (SH:-Hiring of Excavator cum loader/JCB & Tipper for removal of slips and dressing of berms, clearance of drain at various RDs) for the year 2025-26 Job No.13.	Rs.99,360/-	Rs.2,000/-	Rs.350/-	One Month
5	Restoration of Rain Damages on various road under Namhol Sub-Division(Namhol Section) (SH:-Hiring of Excavator cum loader/JCB & Tipper for removal of slips and dressing of berms, clearance of drain at various RDs) for the year 2025-26 Job No.11.	Rs.99,360/-	Rs.2,000/-	Rs.350/-	One Month
6	Restoration of Rain Damages on Namhol Bahadarpur road Km.0/00 to 10/200 (SH:- Construction of 900mm dia Hume pipe culverts at RD.2/325)	Rs.67,341/-	Rs.1,400/-	Rs.350/-	Three Months
7	Restoration of Rain Damages on Chandigarh Mandi Manali road Km.86/00 to 127/00(SH:- Hiring of Hydraulic Excavator(210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD.99/752 to 99/758)For the year 2025-26 Job No.46	Rs.99,571	Rs.2,000/-	Rs.350/-	One Month
8	Restoration of Rain Damages on Chandigarh Mandi Manali road Km.86/00 to 127/00(SH:- Hiring of Hydraulic Excavator(210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD.99/758to 99/765)For the year 2025-26 Job No.47	Rs.99,571	Rs.2,000/-	Rs.350/-	One Month
9	Restoration of Rain Damages on Chandigarh Mandi Manali road Km.86/00 to 127/00(SH:- Hiring of Hydraulic Excavator(210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD.97/655to 97/662)For the year 2025-26 Job No.48	Rs.99,571	Rs.2,000/-	Rs.350/-	One Month
10	Restoration of Rain Damages on Chandigarh Mandi Manali road Km.86/00 to 127/00(SH:- Hiring of Hydraulic Excavator(210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD.97/662to 97/670)For the year 2025-26 Job No.49	Rs.99,571	Rs.2,000/-	Rs.350/-	One Month

Certified that tenders are being called for due to exigencies of works in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No.II, HP.PWD, Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate of each item both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/NBT/CB/Tender-State/EA-1/2025-

7949-56

Copy forwarded to the following for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD, Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HP.PWD., Hamirpur.
3. The Superintending Engineers,10th Circle, HP. PWD., Bilaspur.
4. The Executive Engineers (IT) O/o Engineer-in-Chief, HP.PWD., Shimla through email-ecict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HP.PWD web portal.
5. The Assistant Engineer,HP.PWD., Sub-Division Swarghat/ No.III Bilaspur.
6. Drawing Branch in this office/ Notice Board.

Dated:-

03/10/2025

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

Executive Engineer,
Bilaspur Divn.No.II,
HP-PWD, Bilaspur.

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,670 /-Only.
 Earnest Money:- Rs.= 2,000/-Only.
 Time:- One Month.

Name of work :- Restoration of Rain Damages on link road Mathli to Sakali road km 0/00 to 4/240 (SH):- Hiring of Excavator cum rock breaker ,Excavator cum loader/JCB & Tipper for removal of slips at Rd 0/00 to 0/600) For the Year 2025-26 Job No.-26

S No.	Description of items.	Quantity		Rate In		Unit	Amount
		3	4	In Figure	In words.		
1	2 Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer-in -Charge i/c P.O.L charges and other establishment required at site i.e operator, cleaner and staff and incidental charges i/c stacking of serviceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in-charge. The rate includes octori, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Hours	5	6	7 Per Hours	8
2	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	50.00	Hours			Per Hours	
3	Providing one number Tipper in good condition, on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-in-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.1	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
2.2	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							


 Executive Engineer,
 Bilaspur Division No. 2,
 HR PWD, Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,914 /-Only.
 Earnest Money:- Rs.= 2,000/-Only.
 Time:- One Month.

Name of work :- Restoration of Rain Damages on link road Mathi to Sakali road km 0/00 to 4/240 (SH):- Hiring of Excavator cum rock breaker ,Excavator cum loader/JCB & Tipper for removal of slips at Rd 0/600 to 4/240) For the Year 2025-26 Job No.-27

S No.	Description of items.	Quantity			Rate In		Unit	Amount
		3	4	5	In Figure	In words.		
1	2 Hiring of Excavator cum rock breaker for removal of rocks in all kind of rocks such as soft or hard rock complete as per direction Engineer -in -Charge i/c P.O.L charges and other establishment required at site i.e operator, cleaner and staff and incidental charges i/c stacking of serviceable material and disposal of un serviceable material in all lead and lifts as per direction and instruction of Engineer-in- charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.00	Hours		6	7	8	
2	Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	69.00	Hours			Per Hours		
3	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Hours			Per Hours		
Terms and Condition:-								
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge							
2	The one number Excavator cum rock breaker will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
2.1	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
2.2	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period							
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work							
Total								


 Executive Engineer,
 Bilaspur Division No. 2,
 HA PWD, Bilaspur (M.P.)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,360/-Only.
 Earnest Money:- Rs.= 2,000/-Only.
 Time:- One Month.

Name of work :- Restoration of Rain damages on various road under Namhol Sub-Division(Jukhala Section) (SH):- Hiring of Excavator cum loader/JCB & Tipper for removal of slips and dressing of berms, clearance of drain at Various RDs) For the Year 2025-26 Job No.-12

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		3	4	In Figure	In words.		
1	2 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. 2 Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Hours	5	6	7	8
Terms and Condition:- 1 The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge 2 The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery i) The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery 3 No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period 4 The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work Total							

Executive Engineer,
 Bilaspur Division No. 2,
 HR PWD., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated Cost:- Rs.=99,360/-Only.
 Earnest Money:- Rs.= 2,000/-Only.
 Time:- One Month.

Name of work :- Restoration of Rain damages on various road under Namhol Sub-Division(Kharsi Section) (SH:- Hiring of Excavator cum loader/JCB & Tipper for removal of slips and dressing of berms, clearance of drain at Various RDs) For the Year 2025-26 Job No.-13

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		3	4	In Figure	In words.		
1	2 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Hours	5	6	7	8
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							

Executive Engineer,
 Bilaspur Division No.2,
 HR PWD, Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Name of work:- Restoration of Rain damages on various road under Namhol Sub-Division(Namhol Section) For the Year 2025-26 Job No.-11
 and dressing of berms, clearance of drain at Various RDs)

Estimated Cost:- Rs.=99,360/-Only.
 Earnest Money:- Rs.= 2,000/-Only.
 Time:- One Month.

Sr No. Description of items.

Sr No.	Description of items.	Quantity			Rate In		Unit	Amount
		3	4	5	In Figure	In words.		
1	2 Providing one number Excavator cum loader/JCB in good condition on hire bases at site of work for removal of slip. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Hours		6	Per Hours	8	
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	54.00	Hours			Per Hours		
Terms and Condition:-								
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge							
2	The one number Excavator cum loader/JCB will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery							
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period							
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work							
Total								


 Executive Engineer,
 Bilaspur Division No. 2,
 HR PWD, Bhaspur (H.P.)

SCHEDULE OF QUANTITY.


Estimated cost:- Rs.67,341/-Only.

Earnest Money :- Rs.1,400/-

Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Namhol Bahadarpur road km 0/00 to 10/200 (SH:- Construction of 600 mm dia Hume pipe culverts at RD 2/325)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount
			Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All kind of soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 18.23	4 cubic metre	5 Per cubic metre	6 Per cubic metre	7 7
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge.The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.03	Cubic Metre		Per Cubic Metre	
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:3:6 (one Cement : Three coarse sand : six graded stone aggregate 20 mm (Twenty millimeter) nominal size) including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.34	Cubic metre.		Per Cubic Metre	
5	Providing and laying non-pressure NP3 class (Medium duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (One cement :Two fine sand) including testing of joints etc. complete 600 mm (Six Hundred Millimeter) dia. R.C.C. pipe including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.00	Running Meter		Per Running Meter	
Total:-						


 Executive Engineer,
 Bilaspur Division No. 2,
 HR PWD, Bilaspur (H.P.).

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.=99,571 /-Only. Earnest Money:- Rs.= 2,000/-Only. Time:- One Month.					
		Name of work :- Restoration of Rain damages on Chandigarh Mandi Manali road km 86/00 to 127/00 (SH:- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD 99/752 to 99/758) For the Year 2025-26 Job No.-46					
Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		3	4	In Figure	In words.		
1	2 Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) for breaking rock, loading in tippers and disposal with any lift, trimming bottom and side slopes in accordance with requirements of lines, graeds and cross-sections as per technical Specification clause 302.3.5, including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Hours	5	6	7 Per Hours	8
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate, soil, mud, boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Hours			Per Hours	
	Terms and Condition:-						
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Hydraulic Excavator (210TATA Hitechi or its equivalent) will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.						
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
	Total						


 Executive Engineer,
 Bilaspur Division No. II,
 H.P. P.W.D., Bilaspur (I.P.)

SCHEDULE OF QUANTITY.		Estimated Cost:- Rs.=99,571 /-Only.
		Earnest Money:- Rs.= 2,000/-Only.
		Time:- One Month.


Name of work :- Restoration of Rain damages on Chandigarh Mandi Manali road km 86/00 to 127/00 (SH):- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD 99/758 to 99/765) For the Year 2025-26 Job No.-47

Sr No.	Description of items.	Quantity		Rate In		Unit	Amount
		In Figure	In words.	In Figure	In words.		
1	2 Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) for breaking rock, loading in tippers and disposal with any lift, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per technical Specification clause 302.3.5. including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The rate includes octori, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3	4 Hours	5	6	7 Per Hours	8
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octori, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00	Hours			Per Hours	
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Hydraulic Excavator (210TATA Hitechi or its equivalent) will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.						
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							


 Executive Engineer,
 Bilaspur Division No. II,
 H.P. P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

		Estimated Cost:- Rs.=99,571 /-Only.			
		Earnest Money:- Rs.= 2,000/-Only.			
		Time:- One Month.			
Name of work :- Restoration of Rain damages on Chandigarh Mandi Manali road km 86/00 to 127/00 (SH:- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD 97/655 to 97/662) For the Year 2025-26 Job No.-48					
Sr No.	Description of items.	Quantity	Rate In In words.	Unit	Amount
1	2 Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) for breaking rock, loading in tippers and disposal with any lift, trimming bottom and side slopes in accordance with requirements of lines, graeds and cross-sections as per technical Specification clause 302.3.5. including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 20.00 Hours	5 6	7 Per Hours	8
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate , soil , mud , boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octori, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00 Hours		Per Hours	
Terms and Condition:-					
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge				
2	The one number Hydraulic Excavator (210TATA Hitechi or its equivalent) will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.				
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery				
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period				
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work				
Total					


Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur(I.P.)

SCHEDULE OF QUANTITY.							Estimated Cost:- Rs.=99,571 /-Only.
							Earnest Money:- Rs.= 2,000/-Only.
							Time:- One Month.
Name of work :- Restoration of Rain damages on Chandigarh Mandi Manali road km 86/00 to 127/00 (SH:- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) & Tipper for removal of slips at RD 97/662 to 97/670) For the Year 2025-26 Job No.-49							
Sr No.	Description of items.	Quantity	Rate In In Figure	Rate In In words.	Unit	Amount	
1	2 Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) for breaking rock, loading in tippers and disposal with any lift, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per technical Specification clause 302.3.5. including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 20.00	5	6	7 Per Hours	8	
2	Providing one number Tipper in good condition. on hire basis having capacity of 5.5 cum or 10 tonne per trip for carriage of material i.e aggregate, soil, mud, boulders etc with in all leads and lifts as per direction of Engineer-In-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.00			Per Hours		
Terms and Condition:-							
1	The work will be executed as per HPPWD specification and as per the direction of Engineer-in-charge						
2	The one number Hydraulic Excavator (210TATA Hitechi or its equivalent) will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery.						
i)	The One Number Tipper will be engaged on per hours bases working at site of work including cost of POL establishment and other repair charges of the side machinery						
3	No extra charges will be payable to the contractor for any type of loss/repair of machinery during corresponding period						
4	The contractor will be fully responsible for any loss/damages to any private /Govt. Property during the execution of work						
Total							


Executive Engineer,
Bilaspur Division No. II,
HP. PWD., Bilaspur(H.P.)