



Tel.01899-299219.

eepwd-chowari@hp.gov.in

No. PWD-CHW/Tender /2025-26-

To

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

6142-6200

Dated:- 10/10/2025


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,


Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.


Executive Engineer,
Chowari Division,
HPPWD, Chowari.



Tel.01899-299219.
cepwd-chowari@hp.gov.in

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Sealed percentage/item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Chowari Division, HPPWD, Chowari on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons: -

- 2 Date of issued/sale of tender form against **17.10.2025**
3. Cash payment (nonrefundable). **18.10.2025**

The tender shall be received upto **11.00 AM** on **18.10.2025** and will be opened on the day of **18.10.2025 at 12.00 PM** in the presence of intending Contractor or their authorized representative who may like to be present. The tender can be had from this office against cash payment as shown below (Nonrefundable) during the working hours on **17.10.2025**.

The Earnest Money in the shape of National Saving Certificate/Deposit at call/Time deposit/Account/in any Post Office/Nationalized Bank in HP duly pledged in favour of Executive Engineer, Chowari Division, HPPWD, Chowari must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons: -

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1	Restoration of rain damage on Ghatasanipul to Bholag road km 0/00 to 7/360 (SH:- Hiring of excavator cum loader for removal of slips in between km 2/500 to 4/500)	97650.00	2000.00	Rs. 350/-	One Month	Class-D & C
2	Restoration of rain damage on Ghatasanipul to Bholag road km 0/00 to 7/360 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/0 to 2/300)	97650.00	1100.00	Rs. 350/-	One Month	Class-D & C
3	Restoration of rain Damage on link road from Parchhore to village Naddal km 0/00 to 3/500 (SH:- Hiring of excavator cum loader for removal of slips in km 0/00 to 2/00)	97650.00	2000.00	Rs. 350/-	One Month	Class-D & C
4	Restoration of rain Damage on link road from Parchhore to village Naddal km 0/00 to 3/500 (SH:- Hiring of excavator cum loader for removal of slips in km 2/500 to 4/00)	97650.00	2000.00	Rs. 350/-	One Month	Class-D & C
5	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 20/500 to 23/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C

6	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 23/00 to 24/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & G
7	Restoration of rain damage on Chowari to Kainthly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 1/00 to 3/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
8	Restoration of rain damage on Kuther Saila road km 0/00 to 3/720 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/500 to 3/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
9	Restoration of rain damage on Shahpur Sihunta Chowari road km 40/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 48/00 to 49/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
10	Restoration of rain damage on link road to village Fakrodu km 0/00 to 2/700 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/00 to 2/700)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
11	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/00 to 2/500).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
12	Restoration of Rain damage on Patka to Dalhousie road Km. 32/0 to 45/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 38/500 to 42/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
13	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 17/00 to 21/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
14	Restoration of Rain damage on Patka to Dalhousie road Km. 32/0 to 45/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 33/00 to 38/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
15	Restoration of rain damage on Chowari to Kainthly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 3/300 to 5/600)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
16	Restoration of rain damage on Hunera to Kahri Kothi road km 0/00 to 2/400 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/00 to 2/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
17	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 TO 25/00 (SH:- Hiring of Poclairn for removal of slips in between Km. 18/610 to 20/00).	99765.00	2000.00	Rs. 350/-	One Month	Class-D & C

18	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 TO 25/00 (SH:- Hiring of Poclain for removal of slips in between Km. 18/100 to 18/600).	99765.00	2000.00	Rs. 350/-	One Month	Class-D & C
19	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 15/390 to 16/200)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
20	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 16/300 to 17/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
21	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 17/00 to 17/500)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
22	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 17/600 to 18/100)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
23	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 14/300 to 16/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
24	Restoration of Rain damage on Chowari Mandhiar Gagahar Baloh Fagot road Km. 0/0 to 13/330 (SH:- Hiring of Excavator cum loader for removal of slips in between Km.0/0 to 2/500).	97650.00	2000.00	Rs. 350/-	One Month	Class-D & C
25	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 13/300 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/0 to 5/00).	98790.00	2000.00	Rs. 350/-	One Month	Class-D & C
26	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/0 to 5/00).	98790.00	2000.00	Rs. 350/-	One Month	Class-D & C
27	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/800 to 4/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
28	Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 13/300 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/500 to 7/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
29	Restoration of rain damage on Chowari to Kainthly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 5/00 to 7/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C

30.	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 24/500 to 25/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
31	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 21/500 to 23/500).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
32	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/00 to 12/000).	498750.00	10000.00	Rs. 350/-	One Month	Class-D & C
33	Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 12/500 to 18/500).	498750.00	10000.00	Rs. 350/-	One Month	Class-D & C
34	Restoration of rain damage on Shahpur Sihunta Chowari road km 40/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 49/00 to 52/500)	498750.00	10000.00	Rs. 350/-	One Month	Class-D & C
35	Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 23/500 to 32/00).	498750.00	10000.00	Rs. 350/-	One Month	Class-D & C
36	Restoration of Rain damage on Chowari Mandhiar Gagahar Baloh Fagot road Km. 0/0 to 13/330 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 8/700 to 13/300).	498300.00	10000.00	Rs. 350/-	One Month	Class-D & C
37	Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Poelain for removal of slips in between km 20/00 to 21/00)	99765.00	2000.00	Rs. 350/-	One Month	Class-D & C
38	Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Poelain for removal of slips in between km 27/00 to 28/00)	99765.00	2000.00	Rs. 350/-	One Month	Class-D & C
39	Restoration of rain Damage on Siharu to Sandhara Road Km. 0/00 to 4/820 (SH:- Hiring of excvator cum loader for removal of slips in km 2/00 to 4/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
40	Restoration of rain Damage on Siharu to Sandhara Road Km. 0/00 to 4/820 (SH:- Hiring of excvator cum loader for removal of slips in km 0/00 to 2/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
41	Restoration of Rain damage on bagdhar to Chhanui Road Km. 0/00 to 3/600 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C

42	Restoration of Rain damage on Dhundiara to Kehlu Road Km. 0/00 to 1/880 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/880).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
43	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 25/00 to 27/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
44	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 27/00 to 29/00)	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
45	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 29/00 to 31/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
46	Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 31/00 to 33/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
47	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 33/00 to 35/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
48	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 35/00 to 37/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
49	Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810(SH:- Hiring of Excavator cum loader for removal of slips in between Km. 37/00 to 40/810).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
50	Restoration of Rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
51	Restoration of Rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/00 to 6/00).	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
52	Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of excavator cum loader for removal of slips in between km 6/00 to 7/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
53	Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of excavator cum loader for removal of slips in between km 7/00 to 8/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C

54	Restoration of Rain damage on Dentha Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/260).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C ₁
55	Restoration of Rain damage on Dentha Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/650 to 3/400).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
56	Restoration of Rain damage on Dentha Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 3/0 to 4/00).	99900.00	2000.00	Rs. 350/-	One Month:	Class-D & C
57	Restoration of Rain damage on Dentha Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 1/100 to 2/600).	99900.00	2000.00	Rs. 350/-	One Month	Class-D & C
58	Restoration of rain Damage on Samote to Drmnallah road km 0/00 to 12/430 (SH:- Hiring of Breaker in km 2/500 to 4/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
59	Restoration of rain Damage on Samote to Drmnallah road km 0/00 to 12/430 (SH:- Hiring of Breaker in km 4/090 to 5/00)	98700.00	2000.00	Rs. 350/-	One Month	Class-D & C
60	Restoration of Rain damage on Thakoli Dungru Via Mandrala Khera road km 0/00 to 4/280 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/00).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
61	Restoration of Rain damage on Thakoli Dungru Via Mandrala Khera road km 0/00 to 4/280 (SH: - Construction of Retaining wall at RD. 1/525 to 1/530 and U-shape drain at RD. 1/525 to 1/585)	98272.00	2000.00	Rs. 350/-	One Month	Class-D & C
62	Restoration of rain damage on Balana to Gola road km 0/00 to 9/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 1/0 to 5/500)	477750.00	10000.00	Rs. 350/-	One Month	Class-D & C
63	Restoration of Rain damage on Shaheed Jagdish Chand link road Bassa to Village Gatta km 0/00 to 3/720 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/110 to 2/950).	99750.00	2000.00	Rs. 350/-	One Month	Class-D & C
64	Restoration of Rain damage on Garnota to Bhont road Km. 0/0 to 5/480 (SH: - Removal of formation deficiency in between Km. 3/240 to 4/950)	98456.00	2000.00	Rs. 350/-	One Month	Class-D & C
65	Restoration of Rain damage on Garnota to Bhont road Km. 0/0 to 5/480 (SH: - Removal of formation deficiency in between Km. 1/270 to 2/900)	90548.00	1800.00	Rs. 350/-	One Month	Class-D & C

66	Restoration of Rain damage on Tundi Dharoon road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/500 to 3/600).	97650.00	2000.00	Rs. 350/-	One Month	Class- D & C
67	Restoration of Rain damage on Tundi Dharoon road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/900 to 5/800).	97650.00	2000.00	Rs. 350/-	One Month	Class- D & C
68	Restoration of Rain damage on Patka to Hathidhar road Km. 0/0 to 10/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/550 to 2/100).	97650.00	2000.00	Rs. 350/-	One Month	Class- D & C
69	Restoration of Rain damage on Patka to Hathidhar road Km. 0/0 to 10/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 4/00 to 5/600).	97650.00	2000.00	Rs. 350/-	One Month	Class- D & C
70	Restoration of Rain damage on Patka to Dadriyara road Km. 0/0 to 14/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 9/500 to 11/200).	99750.00	2000.00	Rs. 350/-	One Month	Class- D & C
71	Restoration of Rain damage on Patka to Dadriyara road Km. 0/0 to 14/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/500 to 8/00).	98700.00	2000.00	Rs. 350/-	One Month	Class- D & C
72	Restoration of Rain damage on Godra to Suini road Km. 0/0 to 3/150 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/500).	99750.00	2000.00	Rs. 350/-	One Month	Class- D & C
73	CONSTRUCTION OF LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- C/O B/WALL AT RD 0/202 TO 0/208.50)	98116.00	2000.00	Rs. 350/-	One Month	Class- D & C
74	CONSTRUCTION OF LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- C/O B/WALL AT RD 0/702 TO 0/712)	99508.00	2000.00	Rs. 350/-	One Month	Class- D & C

- 1 The tender forms will not be issued to those Contractors whose performance is not found satisfactory.
- 2 The Contractor should have executed two similar types of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within list five year.
- 3 GST No/Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.

(Signature)
Executive Engineer,
Chowari Division,
HPPWD, Chowari.


1

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 97650.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chatasanipul to Bholog road km 0/00 to 7/360 (SH:- Hiring of excavator cum loader for removal of slips in between km 2/500 to 4/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	93.00	1050.00	Ruppes One Thousand Fifty Only	Per Hours	97650.00
Total: -						97650.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


Executive Engineer
Chowari Division
HP PWU Chowari


SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Ghatasaniplu to Bholog road km 0/00 to 7/360 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/0 to 2/300)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	93.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	97650.00
Total:-						97650.00

Rate quoted in (%) Above / Below
 Rate quoted in (%) in Words


Executive Engineer
 Chowari Division
 HP PWD Deewari

3

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 97650.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of rain Damage on link road from Parchhore to village Naddal km 0/00 to 3/500 (SH:- Hiring of excavator cum loader for removal of slips in km 0/00 to 2/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government	93.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	97650.00
Total: -						97650.00

Rate quoted in (%) Above / Below

Rate quoted in (%) in Words


Executive Engineer
Chowari Division
HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain Damage on link road from Parchhore to village Naddal km 0/00 to 3/500 (SH:- Hiring of excavator cum loader for removal of slips in km 2/500 to 4/00)

Estimated Cost:- Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government	93.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	97650.00
Total:-						97650.00

Rate quoted in (%) Above / Below

Rate quoted in (%) in Words



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunahatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 20/500 to 23/00).

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD
 Chayari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 23/00 to 24/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chowari to Kaintly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 1/00 to 3/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Total:-						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Kuthar Salla road km 0/00 to 3/720 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/500 to 3/00)

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00	
Rate quoted in (%) Above / Below						Total: -	99750.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Shahpur Sihunta Chowari road km 40/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 48/00 to 49/00)

Estimated Cost: - Rs. 99750.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Gogayari

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on link road to village Fakrodu km 0/00 to 2/700 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/00 to 2/700)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00	
Rate quoted in (%) Above / Below						Total: -	99750.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/00 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						99750.00


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 32/0 to 45/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 38/500 to 42/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Gokhari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 17/00 to 21/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00
Total:-						99750.00
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 32/0 to 45/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 33/00 to 38/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupess One thousand five hundred only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chowari to Kainthly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 3/300 to 5/600)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Total:-						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Hunera to Kahri Kothi road km 0/00 to 2/400 (SH:- Hiring of excavator cum loader for removal of slips in between km 0/00 to 2/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00	
Rate quoted in (%) Above / Below						Total: -	99750.00
Rate quoted in (%) in Words							


 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 99765.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunhatdi road km 15/390 TO 25/00 (SH:- Hiring of Poclain for removal of slips in between Km. 18/610 to 20/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Poclain for removal of slips /Debris/Boulder all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the Poclain owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royality ,malakana toll tax sale tax or any other taxes imposed by the Government.	27.00	3695.00	Rupees Three Thousand Six Hundred Ninety Five Only	Per Hours	99765.00
Total:-						99765.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99765.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 TO 25/00 (SH:- Hiring of Poclain for removal of slips in between Km. 18/100 to 18/600).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Poclain for removal of slips /Debris/Boulder all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the Poclain owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malikana toll tax sale tax or any other taxes imposed by the Government.	27.00	3695.00	Rupes Three Thousand Six Hundred Ninety Five Only	Per Hours	99765.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						99765.00



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnahatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 15/390 to 16/200)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 16/300 to 17/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, mlalkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00	
Rate quoted in (%) Above / Below						Total: -	98700.00
Rate quoted in (%) in Words							


 Executive Engineer
 Chowari Division
 HP PWD Chowari


SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 17/00 to 17/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borre by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, mlalkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road km 15/390 to 25/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 17/600 to 18/100)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royality ,malkana toll tax sale tax or any other taxes imposed by the Government .	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 14/300 to 16/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Ruppes One thousand five hundred only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari Mandhiar Gagahar Baloh Fagot road Km. 0/0 to 13/330 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	93.00	1050.00	Rupees One thousand five hundred only	Per Hours	97650.00
Total: -						97650.00
Rate quoted in (%) Above /Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Jagari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98790.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Chowari Mandhhar Baloh Fagot road Km. 0/0 to 13/300 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/0 to 5/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	89.00	1110.00	Rupees One thousand five hundred only	Per Hours	98790.00
Total: -						98790.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 0/0 to 5/00).

Estimated Cost: - Rs. 98790.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	89.00	1110.00	Rupees One thousand five hundred only	Per Hours	98790.00
Total: -						98790.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/800 to 4/00).

Estimated Cost :- Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00	
Rate quoted in (%) Above / Below							
Rate quoted in (%) in Words						Total :-	99750.00



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari Mandhiar Baloh Fagot road Km. 0/0 to 13/300 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/500 to 7/00).

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One thousand five hundred only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Chowari to Kainthly road km 0/00 to 12/570 (SH:- Hiring of excavator cum loader for removal of slips in between km 5/00 to 7/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total:-						98700.00



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunuhatti road Km. 15/390 to 25/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 24/500 to 25/00).

Estimated Cost:- Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 21/500 to 23/500).


Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any Leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/00 to 12/000).

		Estimated Cost:- Rs. 498750.00		Earnest Money :- Rs. 10000.00			
		Time Limit :-		One Month.			
Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	475.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	498750.00	
Rate quoted in (%) Above / Below						Total: -	498750.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari to Jot road Km. 0/00 to 23/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 12/500 to 18/500).

Estimated Cost: - Rs. 498750.00
 Earnest Money :- Rs. 10000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government	475.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	498750.00
Total: -						498750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 498750.00
 Earnest Money :- Rs. 10000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Shahpur Situnta Chowari road km 40/00 to 53/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 49/00 to 52/500)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	475.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	498750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						498750.00



 Executive Engineer
 Chowari Division
 HP PWD, Anayari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Patka to Dalhousie road Km. 14/0 to 32/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 23/500 to 32/00).

Estimated Cost: - Rs. 498750.00
 Earnest Money :- Rs. 10000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	475.00	1050.00	Rupess One Thousand Fifty Only	Per Hours	498750.00
Total: -						498750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD, Bhojvari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Chowari Mandhjar Gagahar Baloh Fagot road Km. 0/0 to 13/330 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 8/700 to 13/300).

Estimated Cost: - Rs. 498300.00
 Earnest Money :- Rs. 10000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	242.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	254100.00
2	Hiring of tipper having capacity 10.50 (ten decimal five Zero) cubic metre for carriage of all type material up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private property or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	220.00	1110.00	Rupees One thousand five hundred only	Per Hours	244200.00
Total: -						498300.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


(Signature)
 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Poclain for removal of slips in between km 20/00 to 21/00)

Estimated Cost:- Rs. 99765.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Poclain for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	27.00	3695.00	Three thousand six hundred ninety five	Per Hours	99765.00
Total:-						99765.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Poclain for removal of slips in between km 27/00 to 28/00)

Estimated Cost: - Rs. 99765.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of Poclain for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	27.00	3695.00	Three thousand six hundred ninety five	Per Hours	99765.00	
Rate quoted in (%) Above / Below						Total: -	99765.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 HP PWD
 Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain Damage on Siharu to Sandhara Road Km. 0/00 to 4/820 (SH:- Hiring of excavator cum loader for removal of slips in km 2/00 to 4/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Ruppes one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chewari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain Damage on Siharu to Sandhara Road Km. 0/00 to 4/820 (SH:- Hiring of excavator cum loader for removal of slips in km 0/00 to 2/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, CHOWARI

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on bagdhar to Chhanui Road Km. 0/00 to 3/600 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	99750.00
Total:-						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Dhundiara to Kehlul Road Km. 0/00 to 1/880 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/880).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 25/00 to 27/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	95.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD
 Chawari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 27/00 to 29/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 29/00 to 31/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of excavator cum loader for removal of slips in between km 31/00 to 33/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnuhatti Road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 33/00 to 35/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner . The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnahati Road Km. 25/00 to 40/810 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 35/00 to 37/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malakana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD
 Sanjhi

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nurpur Sanjhi Nallah Lahru Tunnahatti Road Km. 25/00 to 40/810(SH):- Hiring of Excavator cum loader for removal of slips in between Km. 37/00 to 40/810).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum Loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 2/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or an accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rates including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) In Words						



 Executive Engineer
 Chowari Division
 HP PWD Dehvari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/00 to 6/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 98700.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of excavator cum loader for removal of slips in between km 6/00 to 7/00)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any Leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total: -						98700.00



 Executive Engineer
 Chowari Division
 HP PWD GORAKH.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Nanikhad to Samleu Road Km. 0/00 to 30/585 (SH:- Hiring of excavator cum loader for removal of slips in between km 7/00 to 8/00)

Estimated Cost:- Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees one Thousand & Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Ghogaeri

SCHEDULE OF QUANTITY


Estimated Cost: - Rs. 99750.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Dentha Morthu Joha road Km. 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/260).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00
Total:-						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Dentha Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/650 to 3/400).

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malakana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00	
Rate quoted in (%) Above / Below						Total: -	99750.00
Rate quoted in (%) in Words							


 Executive Engineer
 Chowari Division
 HP PWD Bhopal

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Dentha Morthu Johna road Km. 0/0 to 4/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 3/0 to 4/00).

Sr. No.		Descriptions of Item	Qty.	Rate		Unit	Amount
				In fig.	In words		
1		Hiring of tipper having capacity 5.50 (five decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases .The fuel and operational staff for truck will be provided by the owner .The repair and spare ,watch &ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.	180.00	555.00	Rupess One thousand five hundred only	Per Hours	99900.00
		Rate quoted in (%) Above / Below					
		Rate quoted in (%) in Words				Total: -	99900.00

Estimated Cost: - Rs. 99900.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.


(Signature)
 Executive Engineer
 CHOWARI Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99900.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Denthra Morthu Jolna road Km. 0/0 to 4/00 (SH:- Hiring of Tipper for shifting of muck / debris in between Km. 1/100 to 2/600).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 5.50 (five decimal five Zero) cubic metre for carriage of all type maerial up to any leads and lifts as per direction and entire satisfaction of Engineer in charge. Any loss to public/private poperty or any accident etc happened during the course of said period shall be absolute responsibility of the trucker owner which shall be fully compensated by the contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch & ward of machine also borne by the contractor /Owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge.	180.00	555.00	Rupees One thousand five hundred only	Per Hours	99900.00
Total: -						99900.00
Rate quoted in (%) Above / Below Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Solan

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain Damage on Samote to Drmmallah road km 0/00 to 12/430 (SH:- Hiring of Breaker in km 2/500 to 4/00)

Estimated Cost: - Rs. 98700.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator with Breaker for hard rock chiseling, wedging out rock (where blasting is prohibited) disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	42.00	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Per Hours	98700.00
Total:-						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Deogarh

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain Damage on Samnole to Drmmallah road km 0/00 to 12/430 (SH:- Hiring of Breaker in km 4/090 to 5/00)

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator with Breaker for hard rock chiseling, wedging out rock (where blasting is prohibited) disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	42.00	2350.00	Rupees Two Thousand Three Hundred Fifty Only	Per Hours	98700.00
Total: -						98700.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Thakoli Dungeeru Via Mandrala Khera road km 0/00 to 4/280 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/00 to 1/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One thousand five hundred only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari


SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Thakoli Dungru Via Mandrala Khera road km 0/00 to 4/280 (SH: - Construction of Retaining wall at RD. 1/525 to 1/530 and U-shape drain at RD. 1/525 to 1/585)

Estimated Cost: - Rs. 98272.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In Fig.	In word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	7.15	559.10	Rupees Five Hundred Fifty Nine And Paise Ten Only	Per Cubic Metre	3998.00
2	Providing and laying mechanical mixed and vibrated concrete for plain / reinforced grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in foundation etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depth and any quantum of water including removal of slush which many arise at the time of laying under water complete for all heights / depths includes the cost of form work complete as per drawing and M.O.R.D technical specifications clause 802, 803, 1202 and 1203 or as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.20	6024.20	Rupees Six Thousand Twenty Four And Paise Twenty Only	Per Cubic Metre	25302.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.10	4720.30	Rupees Four Thousand Seven Hundred Twenty And Paise Thirty Only	Per Cubic Metre	61836.00

4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government	10.00	411.00	Rupees Four Hundred Eleven Only	Each	4110.00
5	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including the octori, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.10	1440.90	Rupees One Thousand Four Hundred Forty And Paise Ninety Only	Per Cubic Metre	3026.00
				Total: -		98272.00
				Rate quoted in (%) Above / Below		
				Rate quoted in (%) in Words		



 Executive Engineer
 Chowari Division
 HP PWD, Dehra

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damage on Balana to Gola road km 0/00 to 9/00 (SH:- Hiring of excavator cum loader for removal of slips in between km 1/0 to 5/500)

Estimated Cost: - Rs. 477750.00
 Earnest Money :- Rs. 9600.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government	455.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	477750.00
Total: -						477750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Shaheed Jagdish Chand link road Bassa to Village Gatta km 0/00 to 3/720 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 1/110 to 2/950).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Ruppes One Thousand Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Sawai

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98456.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work: - Restoration of Rain damage on Garnota to Bhont road Km. 0/0 to 5/480 (SH: - Removal of formation deficiency in between Km. 3/240 to 4/950)

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORC technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Recovery of stone 90.21/- cubic metre @ Rs. 300/- only (at the rate of Rupees three hundred) only per cubic metre shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases.	318.37	309.25	Rupees Three Hundred Nine And Paise Twenty Five Only	Per Cubic Metre	98456.00
Total: -						98456.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Prakash
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damage on Garnota to Bhont road Km. 0/0 to 5/480 (SH: - Removal of formation deficiency in between Km. 1/270 to 2/900)

Estimated Cost: - Rs. 90548.00
 Earnest Money :- Rs. 1800.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual / mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rock, hard rock chiseling, wedging out rock (where blasting is prohibited) and their intermediate classification of soil complete including setting out true to the required lines, grades, width, cutting and trimming of side slopes and levels as shown on the drawings and as directed by Engineer-in-Charge at site, according to the MORC technical specification clause 302, 1603.1 and 1603.2 and sorting out useful materials and stacking the same within in all leads and lifts in acquired width of road and transportation of un-useful materials for filling in roadways camber, embankments for grade improvements and disposal of all surplus materials to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means alongwith its leveling fine dressing and carriage of machineries, materials, tools, equipments and safety measures and other incidentals necessary to complete the work by mechanical means and / labour if required. Recovery of stone 82.96/- cubic metre @ Rs. 300/- only (at the rate of Rupees three hundred) only per cubic metre shall be effected from the contractor running bills on pro-rata basis as per actual quantity executed. Any loss to the public/ private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases.	292.80	309.25	Rupees Three Hundred Nine And Paise Twenty Five Only	Per Cubic Metre	90548.00
Total: -						90548.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD, Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Tundi Dharoon road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 2/500 to 3/600).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any heigh and depth as per the direction & satisfaction of Engineer-In-Charge .Any loss to public/private poperty or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner .the fuel & operationa staff for machine will be provided by the owner .The repair & spare watch & ward of machine also be borne by the contractor/owner.The daily log book will be maintained at site ,which should be duly verified by the Engineer -in-Charge.The rate including the octroi,royalty ,malkana toll tax sale tax or any other taxes imposed by the Government.	93.00	1050.00	Rupes One Thousand Fifty Only	Per Hours	97650.00
Total: -						97650.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Tundi Dharoon road Km. 0/0 to 8/700 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 3/900 to 5/800).

Estimated Cost:- Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government	93.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	97650.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						
Total:-						97650.00



 Executive Engineer
 Chowari Division
 HP PWD/Chowari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Patka to Hathidhar road Km. 0/0 to 10/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/550 to 2/100).

Estimated Cost: - Rs. 97650.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operationa staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	93.00	105,000	Rupees One Thousand Fifty Only	Per Hours	97650.00	
Rate quoted in (%) Above / Below						Total: -	97650.00
Rate quoted in (%) in Words							



 Executive Engineer
 Chowari Division
 HP PWD, Chongari

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damage on Patka to Hathidhar road Km. 0/0 to 10/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 4/00 to 5/600).

Estimated Cost:- Rs. 97650.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. the fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi,royalty, malkana toll tax sale tax or any other taxes imposed by the Government.	93.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	97650.00
Total:-						97650.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Choshi

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dadriyara road Km. 0/0 to 14/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 9/500 to 11/200).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting /widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 98700.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Patka to Dadriyara road Km. 0/0 to 14/00 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 5/500 to 8/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	98700.00
Total: -						98700.00
		Rate quoted in (%) Above / Below				
		Rate quoted in (%) in Words				



 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 99750.00
 Earnest Money :- Rs. 2000.00
 Time Limit :- One Month.

Name of work:- Restoration of Rain damage on Godra to Sunni road Km. 0/0 to 3/150 (SH:- Hiring of Excavator cum loader for removal of slips in between Km. 0/0 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB/Excavator cum loader for removal of slips or for cutting/widening work of road in all kinds of soil & disposing of all excavated earth or unserviceable materials from the road surface upto any leads & lifts and upto any height and depth as per the direction & satisfaction of Engineer-In-Charge. Any loss to public/private property or any accident etc happened during the course of said period/execution shall be absolute responsibility of the JCB/Excavator owner. The fuel & operation staff for machine will be provided by the owner. The repair & spare watch & ward of machine also be borne by the contractor/owner. The daily log book will be maintained at site, which should be duly verified by the Engineer -in-Charge. The rate including the octroi, royalty, Malkana toll tax sale tax or any other taxes imposed by the Government.	95.00	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
Total: -						99750.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HP PWD Chowari

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- C/O BWALL AT RD 0/202 TO 0/208.50)

Estimated Cost: - Rs. 98116.00
Earnest Money :- Rs. 2000.00
Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount	
			In fig.	In words			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government	9.73	559.10	Rupees Five Hundred Fifty Nine And Paise Ten Only	Per Cubic Metre	5440.00	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1.5:1:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (Forty millimetre) nominal size in or under water and curingcomplete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depth including the cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	18.46	4819.95	Rupees Four Thousand Eight Hundred Nineteen And Paise Ninety Five Only	Per Cubic Metre	88976.00	
3	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia meters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.00	411.10	Rupees Four Hundred Eleven And Paise Ten Only	Each	3700.00	
Rate quoted in (%) Above / Below						Total: -	98116.00
Rate quoted in (%) in Words							

(Signature)
Executive Engineer
Chowari Division
HPPWD Chowari

SCHEDULE OF QUANTITY


NAME OF WORK :- CONSTRUCTION OF LINK ROAD TO VILLAGE FAKRODU KM 0/00 TO 2/700 (SH:- C/O B/WALL AT RD 0/702 TO 0/712)

Estimated Cost: - Rs. 99508.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (Surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax or any other taxes imposed by the Government.	28.10	559.10	Rupees Five Hundred Fifty Nine And Paise Ten Only	Per Cubic Metre	15711.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 25 Kg (twenty five kilogramme) each as per drawing technical specifications Clause 1301 and as per direction of Engineer-In-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.34	3065.00	Rupees Three Thousand Sixty Five Only	Per Cubic Metre	83797.00
Total: -						99508.00
Rate quoted in (%) Above / Below						
Rate quoted in (%) in Words						


 Executive Engineer
 Chowari Division
 HPPWD, Chyawari