

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2025-26-

7187

Dated:- 17-10-2025

To,


The Executive Engineer
IT Cell Nirman Bhawan Nigam Vihar
HP PWD Shimla

Subject: _

Regarding NIT for uploading on HP PWD website .


Enclosed please find herewith the Notice inviting tender Notice along with schedule of quantity for uploading on HP PWD website. This is for your kind information and necessary action at your end please.

Encls:- 10 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2025-26-7188-7202 Dated:-17-10-2025 are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **29-10.2025** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **28.10.2025** up to **4:00 P.M** and the application for issue of tender form shall be received on **27.10.2025** up to **12:00 noon**. The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Repair of Female Surgical Ward at Dr. R.P. Govt. Medical college Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing ceiling sheet, steel work, W.s. & S.I. etc. In Near Trauma Ward).	58583.00	1200.00	One Months
2	Balance work of Girls Hostel in Dr. R.P. G. M.C at Tanda in Tehsil & Distt. Kangra HP Deposit Work (SH: Providing and fixing wire mesh doors and aluminium work etc).	99937.00	2000.00	Two Months
3	Repair of Female Surgical ward at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra Hp Deposit Work (SH: Providing and fixing tiles work).	70850.00	1450.00	One Months
4	Construction of aluminium partition in Deptt. Of Community Medicine Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit work (SH: Providing and fixing aluminium work).	83044.00	1700.00	One Months
5	Repair of Anatomy Department in Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP deposit work (SH: Providing and laying tile work etc).	49977.00	1000.00	One Months
6	Repair to Internal roads on Dr. R.P. Govt. Medical College at Tanda in Distt. Kangra HP deposit work (SH: Repair of both side ducts slab etc).	99935.00	2000.00	Two months
7	Repair of Female Surgical Ward at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP deposit Work (SH: Painting and Distempering work etc).	99154.00	2000.00	One Months
8	Construction of Check post Type-III qtr. Near Dharoon khad at Dr. R.P. Govt. Medical College Tanda in Distt Kangra HP Deposit Work(SH: Providing and fixing prepainted steel sheet , steel work and BP Shet etc).	96974.00	1950.00	One Months
9	Repair of Oncology Department in Dr. R.P. Govt. Medical College Tanda in Distt. Kangra HP Deposit Work (SH: Providing and fixing Gypsm Board Ceiling etc).	75405.00	1550.00	One Months
10	Construction of Ambulance road to the House of Sh. Jagdish Chand and Ram Kumar in Ward No3 G.P. Chakban Gheen in Distt. Kangra HP Deposit work (SH: Providing and laying Grading -III and cement concrete pavement in km 0/200 to 0/268 SDP/2021/1152).	199598.00	4000.00	Two months

Terms & Conditions:-

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.


HIMSUCHANA AVAM & JAN SAMPARK


(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2025-26- **7188-7202** Dated/ **17-10-2025**

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Director, Information & Publications Department, H.P. Shimla.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.


Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan


Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan


SCHEDULE OF QUANTITY

ESTIMATED COST :- **RS. 56533.00**
 EARNINGS MONEY :- **RS. 1200.00**
 TIME LIMIT : **ONE MONTH**

NAME OF WORK :- Repair of Female Surgical Ward at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and fixing ceiling sheet, steel work, W.S. & S.I. etc. in Near Trauma Ward.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 6 mm (Six millimetres) thick Cement fiber board plain multipurpose cement board (Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately) as per IS: 14862. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	3	4	5	6	7
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	98.89			Per Square metres	
3	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	3			Per Kilograms	
4	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	3			Each	
5	Providing and fixing 10 litre capacity - white P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	4			Each	
6	Providing and fixing Stainless Steel A ISI 304 (18/8) Kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : Kitchen sink with drain board 510x1040 mm bowl depth 225 complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	1			Each	
7	Providing and fixing 20 mm nominal outer dia Pipe Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, 1/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	20.00			Per Running metres	
8	Providing and fixing 15 mm nominal bore with 45 cm length unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	5			Each	
9	Providing and fixing Flexible pipe 40 mm dia P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	4			Each	

10	Providing and fixing 600mm x 450 mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. Sheet or plywood sheet and fixed to wooden plugs with C.P. Brass screws and washers complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	2 Numbers			Each	
11	Providing and fixing 15mm nominal bore chromium plated ISI marked No. 8934 fancy bit tap E58 or equivalent complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	8 Numbers			Each	
12	Providing and fixing 15mm diameters brass angle valve without nuts as per approved drawing and design directed by the Engineer-Incharge complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	5 Numbers			Each	
TOTAL :-						



 Executive Engineer
 HP PWD Division
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99937.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Balance work of Girls Hostel in Dr. R.P.G.M. College at Tanda in Tehsil & Distr. Kangra (H.P.) Deposit work
SUB-HEAD :- Providing and fixing wire mesh doors and aluminium work etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Anodised aluminium for shutters of doors, windows and ventilators (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC15) complete as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	3 155.10 Kilo grams	4	5	6 Per Kilo-gram	7
2	Providing and fixing 12mm (Twelve millimetres) thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	4.35 Square metres			Per Square metre	
3	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm (zero point six three millimetre)all complete. and as directed by the Engineer-Incharge, including carriage of materials within all leads, lifts and other incidentals.	17.85 Square metres			Per square metre	
TOTAL :-						


 Executive Engineer,
 H.P.P. WD., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 70850.00
EARNEST MONEY :- Rs. 1450.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- Repair of Female Surgical Ward at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)

SUB-HEAD :- Providing and fixing tiles work.

S. No.	Description of Items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 1st quality ceramic glazed floor tiles of size 300x450mm (Three hundred into four hundred fifty millimetres) conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.Providing and fixing 1st quality ceramic glazed floor tiles of size 300x450mm conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	54.50 Square meters			Per Square metres	
TOTAL :-						7

Executive Engineer
HP PWD Division
Tanda at Nagrota Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST - **RS. 83044.60**
 EARNEST MONEY :- **RS. 1/00.00**
 TIME LIMIT : **ONE MONTH**

NAME OF WORK :- Construction of aluminium partition in Deptt. of Community Medicine Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and fixing aluminium work.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) complete as directed by Engineer-In-charge, including entire carriage of material within all leads, lifts and other incidentals.	111.40 3			Per Kilogram	7
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC15) complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	13.80			Per Kilogram	
3	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	20.00			Per Square metres	
4	Providing and fixing 300x16 mm aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with nuts and screws etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	1.00			Each	
5	Providing and fixing 200x10mm size aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	2.00			Each	
6	Providing and fixing 125 mm aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	2.00			Each	

7	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	1.00 Numbers		Each	
8	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	1.00 Numbers		Each	
TOTAL :-					



 Executive Engineer
 HP PWD Division
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 49977.00
 EARNEST MONEY :- Rs. 1000.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Repair of Anatomy Department in Dr. R. P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and laying water proofing, C.C. work and tile work etc.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and laying 600x600 mm (Six hundred into six hundred millimetres) size vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	37.02	Square meters		Per Cubic metre	
TOTAL :-						


 Executive Engineer,
 HP PWD Division,
 Tanda at N/Bagwan.


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 9995.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Repair to Internal Roads on Dr. R. P. Govt. Medical College at Tanda in Dist. Kangra (H.P.) (DEPOSIT WORK).

SUB-HEAD :- Repair of both side Ducts slab etc;

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	3		5	6	7
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more complete as per drawing and HP.PWD technical specifications and as directed by Engineer-Incharge including carriage of material within all leads, lifts and other incidentals.	52.00			Per kilo-gram	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 99154.00
EARNEST MONEY :- Rs. 2000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- Repair of Female Surgical Ward at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Painting and distemping work etc.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Removing dry or oil bound distemper water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	910.50 Square meters			Per Square metres	
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	273.15 Square meters			Per Square metres	
3	Wall painting two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as directed by Engineer- In-charge, including entire carriage of material within all leads, lifts and other incidentals.	910.50 Square meters			Per Square metres	
TOTAL :-						

Executive Engineer
HP PWD Division
Tanda at Nagrota Bagwan.

Schedule of Quantity

ESTIMATED COST: - ₹ 96974.00
 EARNEST MONEY: - ₹ 1950.00
 TIME LIMIT: ONE MONTH

Name of Work:- Construction of Check post Type-III Qtr. Near Dharoon Khad at Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
Sub Head:- Providing and fixing prepainted steel sheet, steel work and BP Sheet etc.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 0.60mm (Zero point sixty millimetres) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidental.	5.93 Square metres			Per Square metre	
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	735.64 Kilograms			Per Kilogram	
3	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.80 Running metres			Per Running metres	
4	Providing and fixing plain multipurpose cement board (High pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid separately) 6 mm (Six millimetres) thick Cement fiber board as per IS: 14862 complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	4.34 Square metres			Per Square metre	
5	Providing and fixing M.S. BP Sheet 1.66mm to 20mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as directed by the Engineer-in-charge including entire carriage of materials within all leads, lifts and other incidentals.	3.58 Square metres			Per Square metre	
Total:-						


Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 75405.00
 EARNEST MONEY :- Rs. 1500.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Repair of Oncology Department in Dr. R.P. Govt. Medical College Tanda in Distt. Kangra (H.P.) (Deposit Work)
SUB-HEAD :- Providing and fixing Gypsum Board Ceiling etc. (Part-II)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 12.5 mm (Twelve point five millimetres) thick square edge PVC Laminated Gypsum Tile of size 595x595 mm (Five hundred ninety five into five hundred ninety five millimetres) made of Gypsum plasterboard, manufactured from natural gypsum as per IS 2095 part I and laminated with white 0.16mm (Zero point sixteen millimetres) thick fire retardant PVC film on the face side and 12 micron metalized polyester on the back side with all edges sealed with the face side PVC film which goes around and wraps the edges and is bonded to the edges and the back side metalized polyester film so as to make the tile a completely sealed unit complete as directed by Engineer-In-charge, including entire carriage of material within all leads, lifts and other incidentals.	45.70 Square meters			Per Square metres	
TOTAL :-						



 Executive Engineer,
 HP PWD Division,
 Tanda at N/Bagwan.

Schedule of Quantity

ESTIMATED COST :- ₹ 199598.00
 EARNEST MONEY :- ₹ 4000.00
 TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of Ambulance road to the House of Sh. Jagdish Chand and Ram Kumar in Ward No-3 in G.P. Chakhan Gheer in Distt. Kangra (H.P.), Deposit work.
 SUB HEAD :- Providing and laying Grading-III and cement concrete pavement in Km 0/200 to 0/268 (SDP/2021/1152)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimeters) nominal size at the rate of 0.22 cum (zero point two two cubic metres) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 and as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals.	8.55			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimeters) nominal size complete as per HPPWD technical specification and within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer-in-charge.	30.60			Per cubic metre	
TOTAL :-						


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan.