

Offline

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PWD-Dal/TA/Tender /2025-26 **4794-96**
To

Dated: -08-10-25


The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject: - Publishing of Tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of Himachal Pradesh letter No. PBW-(B) A9 (3)1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest.

DA/ As above.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Copy forwarded to the Superintending Engineer, 7th Circle, HPPWD, Dalhousie for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer, (IT Cell) Nigam Bihar Shimla-2 for information and further necessary action.

Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Offline

"NOTICE INVITING TENDERS"

Sealed Item rate tender(s) on PWD from No 6 & 7/8 are hereby invited by the Executive Engineer, Dalhousie Division, HPPWD, Dalhousie on behalf of the Governor of HP for the following works from the approved and eligible contractor/firm of appropriate Class enlisted in HPPWD as per the latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tender. The undersigned reserves the right to reject any or all the tender without assigning any reasons:-

1. Date of receipt of application for the tender Form a /w requisite documents:- ~~14~~ 10.2025 onward (between 2:00 p.m.to 4:30.p.m.)
2. Date of issue/sale of tender form against Cash payment (non refundable). ~~14~~ 10.2025.

The tender shall be received up to 3:00 PM on ~~14~~ 10.2025 and will be opened on the same day at 3:30 PM in the presence of intending Contractor or their authorized representative who may like to be present. The tender will be sold by this office against cash payment as shown below (Non refundable) during the working hours on ~~14~~ 10.2025


The Earnest Money in the shape of National Saving Certificate/FDR of any Bank in HP duly pledged in favour of Executive Engineer, Dalhousie Division, HPPWD, Dalhousie must accompany with each application. Conditional tender and the tender received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserve the right to accept or reject the tender without assigning any reasons:-

S. No.	Name of work	Estimated cost	Earnest Money	Cost of tender	Time Limit	Class
1.	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 5/00 to 10/00).	99910.00	2000.00	350.00	One Month	D & C
2.	Restoration of rain damage on Samah to Hadila road Km. 0/0 to 5/510 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 0/00 to 5/510).	99910.00	2000.00	350.00	One Month	D & C
3	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 0/00 to 5/00).	98880.00	2000.00	350.00	One Month	D & C
4	Restoration of rain damage on Kheri to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of slips beteen Km. 0/0 to 3/00).	98880.00	2000.00	350.00	One Month	D & C
5	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 10/00 to 14/00).	97850.00	2000.00	350.00	One Month	D & C
6	Restoration of rain damage on Thandapani to Mandiar road Km. 0/0 to 0/0 to 4/620 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 0/0 to 4/620).	98880.00	2000.00	350.00	One Month	D & C

7	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 35/00 to 39/600).	99910.00	2000.00	350.00	One Month	D & C
8	Restoration of rain damage on Kheri to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of slips beteen Km. 3/0 to 6/00).	99910.00	2000.00	350.00	One Month	D & C
9	Restoration of Rain damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SH: - Providing and Laying WBM G-III in Km. 2/500 to 5/500).	99453.00	2000.00	350.00	One Month	D & C
10	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 14/00 to 17/00).	98880.00	2000.00	350.00	One Month	D & C
11	Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/243.60 to 10/244.80).	94675.00	2000.00	350.00	Two Months	D & C
12	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tipper for Sifting of Muck/Debris at RD. 0/0 to 5/00).	98790.00	2000.00	350.00	One Month	D & C
13	Restoration due to Digging of road by Jal Shakti vibhag on Kholpukhar to Rikhnalli road Km. 0/0 to 9/700 (SH: - Construction of PCC Drain at RD. 1/760 to 1/935).	98652.00	2000.00	350.00	Two Months	D & C
14	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tractor with trolley for Sifting of Muck/Debris at RD. 5/0 to 10/00).	98500.00	2000.00	350.00	One Month	D & C
15	Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/241.20 to 10/242.40).	94711.00	2000.00	350.00	Two Months	D & C
16	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tractor with trolley for Sifting of Muck/Debris at RD. 10/0 to 20/00).	99000.00	2000.00	350.00	One Month	D & C
17	Restoration of Rain damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SH: - Providing and Laying WBM G-III in Km. 0/0 to 2/500).	92775.00	2000.00	350.00	Two Months	D & C
18	Restoration of rain damage on Brangal Wangal Mandoh road Km.	99601.00	2000.00	350.00	One Month	D & C

	0/0 to 39/600 (SH: - Removal of Slips in Km. 22/00 to 26/00).					
19	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in wire crate at RD. 35/825 to 35/830).	99008.00	2000.00	350.00	One Month	D & C
20	Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/248o 10/249.20).	94723.00	2000.00	350.00	Two Months	D & C
21	Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in wire crate at RD. 35/830 to 35/835).	99382.00	2000.00	350.00	One Month	D & C

1. The tender forms will not be issued to those Contractors whose performance is not found satisfactory. .
2. GST No. Earnest Money Tender Form cost, copy of enlistment should be accompanied with application.
3. Application without all documents will not be entertained.
4. Proxy application will not be entertained.


 Executive Engineer,
 Dalhousie Division,
 HPPWD, Dalhousie.


No. PWD/TA/Tender /2025-26

4797-4847

Dated:- 06.10.2025


Copy forwarded to the following for information and necessary action please:-

- 1 Engineer-in-Chief, HPPWD, Shimla.
- 2 All the Chief Engineer in HPPWD.
- 3 All SEs/EE in HPPWD.
- 4 All AEs/Contractor under this Division.
- 5 Deputy Commissioner, Chamba
- 6 BDO Bhattiyat.
- 7 Sub Divisional Magistrate/Tehsildar Dalhousie.
- 8 Notice Board of this office.


 Executive Engineer,
 Dalhousie Division,
 HPPWD, Dalhousie


Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:-4794-96 dated.08-10-25 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Certificate

Certified that the tenders called vide this office letter No. PWD-
/TA/Tender /2025-26:-4794-96 dated.08-10-25 is emergent nature and in Public
interest.


Executive Engineer,
Dalhousie Division,
HPPWD, Dalhousie.

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 5/00 to 10/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the	97.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Job No. 02 TS No. 62

Estimated Cost: - Rs.	99910.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Samah to Hadila road Km. 0/0 to 5/510 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 0/00 to 5/510).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	98880.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 0/00 to 5/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	98880.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Kheri to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of slips beteen Km. 0/0 to 3/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer,
 Dalhousie Division,
 NPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	97850.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 10/00 to 14/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the	95.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Engineer
 Dalhousie Division,
 HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 98880.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Thandapani to Mandiar road Km. 0/0 to 0/0 to 4/620 (SH: - Hiring of Excavator cum loader for removal of slips in Km. 0/0 to 4/620).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99910.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 35/00 to 39/600).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of Qty.

Estimated Cost: - Rs.	99910.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Kheri to Bhunad road Km. 0/0 to 9/230 (SH: - Hiring of JCB for removal of slips between Km. 3/00 to 6/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	97.00			Per Hour	
	Total					

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


 Executive Engineer
 Dalhousie Division,
 HPPWD Dalhousie

Schedule of Qty.

Estimated Cost: - Rs. 99453.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SH: - Providing and Laying WBM G-III in Km. 2/500 to 5/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing, spreading and compacting 75 mm (Seventy five millimeter) thick stone aggregate size 53mm to 22.4 mm (fifty three millimetre to twenty two point four millimetre) Grading-III , 75mm (seventy five millimetre) consolidated thick to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 KN static roller to proper grade and camber, applying and brooming stone screening such as moorum or gravel at the rate of 0.22 (zero point two two cubic metre) per ten square metre to fill up the interstices of course aggregate, watering and compating to the required density as per MORD technical specifications clause No. 405 an including carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty ,Malkana, toll tax,GST or any other taxes imposed by the Government.	26.33			Per Cubic Metre	
2	Providing and applying prime coat with Bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90-1.2 kg/sqm using mechanical means as per Technical specification Clause 502 or as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rate including the octori, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	351.00			Per Square Metre	
					Total: -	

Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs.	98880.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of JCB for removal of slips in Km. 14/00 to 17/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of JCB / Excavator cum loader for cutting / widening work of road or removal of slips in all kinds of soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts upto any heights and depth as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the JCB / Excavator Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for machine will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	96.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division.
NPAWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 94675.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/243.60 to 10/244.80).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	6.89			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	17.86			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.16			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	4.00			Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 98790.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tipper for Sifting of Muck/Debris at RD. 0/0 to 5/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of tipper having capacity 10.50 (Ten decimal five zero) cubic meter for carriage all type material upto any leads and lifts as per direction and entire satisfactions of Engineer-in-charge. Any loss to the public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute responsibility of the trucker Owner which shall have to be fully compensated by the Contractor in all cases. The fuel and operational staff for truck will be provided by the owner. The repair and spare, watch and ward of machine also be borne by the Contractor / Owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	89.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 98652.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage due to Digging of road by Jal Shakti vibhag on Kholpukhar to Rikhnalli road Km. 0/0 to 9/700 (SH: - Construction of PCC Drain at RD. 1/760 to 1/935).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	21.88			Per Cubic Metre	
2	Providing and laying Mechanically mixed and vibrated concrete for plain cement concrete nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 40 millimetre (forty millimetre nominal size on ground or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structure including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of wate including removal of slush which may arise at the time of laying concrete complete for all heighths / depths including the cost of form work complete in drain as per drawing and M.O.R.D technical specifications section 800, 900 and 1200 or as directed by Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	14.44			Per Cubic Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 98500.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tractor with trolley for Sifting of Muck/Debris at RD. 5/0 to 10/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Tractor with trolley for disposing and transporting of surplus excavated material and shifting of any type of construction of materail in all leads and lifts as per direction and entire satisfactions of Engineer-in-charge. Any loss of public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of Owner of the machinery which shall have to be compensated by the Contractor in all cases. The fuel and operational staff have be compensated by the contractor in all cases.The fuel and operational staff for machine will be provided by the owner as his own cost and repair, watch of ward of machine will be also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	197.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost :- Rs. 94711.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrighat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/241.20 to 10/242.40).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	7.29			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all hights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	17.86			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	1.91			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	4.00			Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 99000.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month


Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Hiring of Tractor with trolley for Sifting of Muck/Debris at RD. 10/0 to 20/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Tractor with trolley for disposing and transporting of surplus excavated material and shifting of any type of construction of materail in all leads and lifts as per direction and entire satisfactions of Engineer-in-charge. Any loss of public / private property or any accident etc. happened during the course of hiring period /execution shall be the absolute respoonsibility of Owner of the machinery which shall have to be compensated by the Contractor in all cases. The fuel and operational staff have be compensated by the contractor in all cases.The fuel and operational staff for machine will be provided by the owner as his own cost and repair, watch of ward of machine will be also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, toll tax, sale tax GST or any other taxes imposed by the Government.	198.00			Per Hour	
					Total	

Note - 1) The physical progress of machine will also be measured while submitting the bill for payment. It is ensured that working progress of machine should be not be less than the amount to be paid.

Note - 2) No deviation shall be allowed in any case.

Note -3) Subject of availbity of funds


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 92775.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of Rain damage on Lahar to Sangrain road Km. 0/0 to 5/500 (SH: - Providing and Laying WBM G-III in Km. 0/0 to 2/500).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Providing, spreading and compacting 75 mm (Seventy five millimeter) thick stone aggregate size 53mm to 22.4 mm (fifty three millimetre to twenty two point four millimetre) Grading-III , 75mm (seventy five millimetre) consolidated thick to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 KN static roller to proper grade and camber, applying and brooming stone screening such as moorum or gravel at the rate of 0.22 (zero point two two cubic metre) per ten square metre to fill up the interstices of course aggregate, watering and compating to the required density as per MORD technical specifications clause No. 405 an including carriage of materials within all leads and lifts and other incidentals. The rate is inclusive of octroi, royalty ,Malkana, toll tax,GST or any other taxes imposed by the Government.	24.56			Per Cubic Metre	
2	Providing and applying prime coat with Bitumen emulsion (SS-1)on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90-1.2 kg/sqm using mechanical means as per Technical specification Clause 502 or as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax,GST, sale tax or other taxes imposed by the Government.	327.50			Per Square Metre	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie


Schedule of qty.

Job No. 18 TS 81

Estimated Cost: - Rs.	99601.00
Earnest Money :- Rs.	2000.00
Time Limit :-	One Month

Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Removal of Slips in Km. 22/00 to 26/00).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in all type of rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611. or as directed by Engineer-in Charge. The rate including the octroi, royalty , Malkana, Toll tax, sale tax GST or any other taxes imposed by the Government.	797.57			Per Cubic Metre	
					Total:-	


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.


Estimated Cost: - Rs. 99008.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in wire crate at RD. 35/825 to 35/830).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	20.28			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.25			Per Cubic Metre	
					Total: -	


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie

Schedule of qty.

Estimated Cost: - Rs. 94723.00

Earnest Money :- Rs. 2000.00

Time Limit :- Two Months

Name of work: -Restoration of Rain damage on Dalhousie Jandrightat Chamba via Kohlari road Km. 0/0 to 11/040 (SH: - Construction of PCC Retaining wall at RD. 10/248 to 10/249.20).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government.	7.07			Per Cubic Metre	
2	Providing and Laying plain cement concrete 1:5:10 (one cement isto five sand isto ten graded) crushed stone aggregate 40 mm (forty millimetre) nominal size mechanically mixed and vibrated in foundation for all type structure complete for all heights / depth including curing and cost of form work complete in all respect as per the drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in-Charge. The rate including the octroi, royalty, Malkana, Toll tax, sales tax , GST or any other taxes imposed by the Government.	17.86			Per Cubic Metre	
3	Back filling with granular material behind abutments, return walls, wing walls and retaining walls complete as per drawings and MORD technical specification clause 1204.3.8 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	2.09			Per Cubic Metre	
4	Providing Weepholes in brick masonry / stone masonry / plain / re-inforced concrete abutment, wing wall, return wall, retaining walls with 100 mm (one hundred millimetre) dia Metres, PVC pipe Finolex/Vigor/Ashirvad/Astral etc exetnding through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty) horizontal towards drawing face complete as per drawing and tecnical specification clause 614, 709, 1204.3.7 and as per direction of Engineer-In-Charge including carriage of materails with in all leads, lifts and other incidentals. The rates are inclusive of the octori, royalty, Malkana, Toll tax, sale tax GST or other taxes imposed by the Government.	4.00			Each	
					Total: -	

Executive Engineer
Dalhousie Division,
HPPWD Dalhousie

Schedule of qty.


Estimated Cost: - Rs. 99382.00

Earnest Money :- Rs. 2000.00

Time Limit :- One Month

Name of work: -Restoration of rain damage on Brangal Wangal Mandoh road Km. 0/0 to 39/600 (SH: - Construction of Retaining wall in wire crate at RD. 35/830 to 35/835).

Sr. No.	Descriptions of Item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150 mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including octroi royalty Malkhana Toll tax sale tax , GST or other taxes imposed by the Government	20.95			Per Cubic Metre	
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four milimetre) dia G.I wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighting not less than 40 Kg (forty kilograme) each as per drawing technical specifications Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, sales tax, GST or any other taxes imposed by the Government.	31.25			Per Cubic Metre	
					Total: -	


Executive Engineer
Dalhousie Division,
HPPWD, Dalhousie