

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DEH/CB/TENDER/2024-25-
To

6835-60

DATED: 13/10/25

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject :- Tender Notice.

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PW) to the Govt. of HP vide No. PBW(B)A(3)1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:-As above

Executive Engineer,
HPPWD Division,
Dehra.

Copy forwarded to the following:-

1. The FC-Cum Secy.(PW) to the Govt. of HP.Shimla-2.
2. The Engineer-in-Chief, HPPWD., Shimla.
3. The Chief Engineer(KZ) HP.PWD. Dharamshala.
4. The Superintending Engineer, Circle HP.PWD. Dehra.
5. All the Executive Engineer under North Zone.
6. All the Assistant Engineer under Dehra Division.
7. The Deputy Commissioner Kangra at Dharamshala.
8. The SDM/Tehsil/President MC Dehra.
9. The BDO Dehra /Pragpur/ Nagrota Surian.
10. Notice Board.
11. All the Head of Branches.
12. All the Contractors working under Dehra Division.

Executive Engineer,
Dehra Division HP.PWD.,
Dehra.

H. P. P.W.D. TENDER

Sealed percentage rate tenders on the form 6&8 are invited by the Executive Engineer Dehra Division HPPWD., Dehra on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|----------------------------------|
| 1. Date and time of receipt of application for tender form: | 21.10.2025 upto 12.00 Noon |
| 2. Date and time of issue of tender form: | 21.10.2025 12:00 Noon to 5.00 PM |
| 3. Date and time of receipt of tenders: | 23.10.2025 upto 10.30AM |
| 4. Date and time of opening of tenders: | 23.10.2025 at 11.00 AM |

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dehra Division HPPWD Dehra must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
01	A/R & M/O Non-Residential Building HPPWD Dehra in District Kangra (H.P.) (SH: Aluminium Work, Distempering, Plastering and Painting etc.).	Rs. 99,974.00	Rs.2,000/-	One Month	Rs.350/-
02	A/R & M/O Non-Residential Building HPPWD Dehra in District Kangra (H.P.) (SH: Providing & Fixing Wall Paper, Edge Wall and Bed).	Rs. 99,650.00	Rs.2,000/-	Three Months	Rs.350/-
03	A/R & M/O Non-Residential Building at Hanuman Chowk at Dehra in District Kangra (H.P.) (SH: C/o Path and Aluminium Work etc.).	Rs. 99,302.00	Rs.2,000/-	One Month	Rs.350/-
04	Restoration of Rain Damages on Bankhandi Haripur Road KM 0/0 to 8/00 (SH: Repair to Plaster etc.).	Rs. 99,852.00	Rs.2,000/-	One Month	Rs.350/-
05	Restoration of Rain Damages on Bankhandi Haripur Road KM 0/0 to 8/00 (SH: Furniture Work etc.).	Rs. 99,824.00	Rs.2,000/-	One Month	Rs.350/-
06	Construction of link road from Masroor to Ghariar via Othra KM 0/0 to 4/00 (SH: Hiring of Excavator-cum-Loader for removal of formation deficiency and slips for formation cutting at RD 1/100 to 2/00) Deposit.	Rs. 99,360.00	Rs.2,000/-	One Month	Rs.350/-
07	A/R & M/O Various Roads under HPPWD Sub Division Dehra in Distt. Kangra (H.P.) (SH: Painting & Writing on KM Stones, Culverts, Bridges Sign Board and Rain Shelters etc.) Section: Dehra.	Rs. 99,830.00	Rs.2,000/-	Three Months	Rs.350/-
08	Construction of link road from Masroor to Ghariar via Othra KM 0/0 to 4/00 (SH: Hiring of Excavator-cum-Loader for removal of formation deficiency and slips for formation cutting at RD 0/300 to 1/100) Deposit.	Rs. 99,268.00	Rs.2,000/-	One Month	Rs.350/-
09	Restoration of Rain Damages on Bankhandi Haripur Road KM 0/0 to 8/00 (SH: Repair to Plaster, Aluminium Work, Steel Work & Painting etc.) under PDNA.	Rs. 99,254.00	Rs.2,000/-	One Month	Rs.350/-
10	Preparation of Forest Diversion case under FRA, 2006 for construction of link road in Dehra Sub Division 1.) Ambulance road from Transformer to Dhanotu Balla Road in G.P. Dhaliara KM 0/00 to 0/159 KM.	Rs. 40,795.00	Rs.1,000/-	Six Months	Rs.350/-
11	A/R & M/O Non-Residential Building HPPWD Dehra in District Kangra (H.P.) (SH: Aluminium Work, Steel Work etc.).	Rs. 99,189.00	Rs.2,000/-	One Month	Rs.350/-
12	Hydraulic Data of 25.00mtr. Span Bridge over Gumrehar Khad at RD 0/650 on link road Kundli Har to Nauri via Andrari Mandeli Road (SH: Preparation of Hydraulic Data).	Rs. 60,000.00	Rs.2,000/-	One Month	Rs.350/-
1	The contractors/firms should possess the following documents (Photocopy to be attached):				
(i)	Latest renewal of enlistment.				
(ii)	PAN (Permanent Account No.)				
(iii)	Registration under HP GST/ (TIN No.).				
(iv)	EPF (Employee Provident Fund Account No.)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	If any of the date mentioned above happened/to be Gazetted Holidays the same shall be processed on next working day.				
4	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
5	The Contractor will have to submit an application for issue of tender that he has not more than two works in hand.				
6	The next tender will be issued only after completion of previous works in hand.				
7	The offer of the tender shall remain valid upto 30 days after the opening.				

Executive Engineer,
HPPWD Division Dehra,
Distt Kangra H.P.
on behalf of Governor of Himachal Pradesh

Exigency Certificate

It is certified that the tenders invited vide this office NIT No.....68.35-60.....dated....13/10/2025 are of emergent nature of work and in public interest.

Place:

Dated:

Executive Engineer,
HPPWD Division,
Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99974.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- A/R & M/O to non Residential Building HPPWD at Dehra (SH-Aluminium work, Distempering, plastering and painting etc)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and applying 15mm (fifteen millimeters) thick cement plaster with cement mortar 1:4 (one cement isto four sand) in single coat on rough side of brick/concrete/ stone walls for interior plastering up to all floor level including arises, internal rounded angles, chamfers and/or rounded angles in all girth and finished even and smooth as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Royalty, Malkhana, Octroi, GST, Toll Tax, GST, Sales tax or any other taxes imposed by the Government.	95.92 Square metre	200.45	Rupees Two Hundred And Paise Forty Five Only	Per Square metre	19,227.00
2	Distempering with 1st quality Acrylic distemper (ready mixed) having VOC content less than 50gm/litre of approved brand and manufacture (two or more coats) of required shade on new work over and including water thinnable priming coat with cement primer to give an even shade complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	95.92 Square metre	56.25	Rupees Fifty Six And Paise Twenty Five Only	Per Square metre	5,396.00
3	Providing and fixing 6mm thick commercial ply conforming to IS 1328 BWR type plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden/steel frame work, complete as per direction of Engineer-in-charge (Frame work shall be paid for separately complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	47.34 Square metre	530.00	Rupees Five Hundred Thirty Only	Per Square metre	25,090.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mired and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P.brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	70.50 Kilogram me	560.00	Rupees Five Hundred Sixty Only	Per Kilogram	39,480.00
5	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) (Cost of aluminium snap beading shall be paid in basic item) complete as per the architectural drawings and the directions of engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	6.48 Square metre	612.95	Rupees Six Hundred Twelve And Paise Ninety Five Only	Per Square metre	3,972.00
6	Painting two or more coat on wood work with Deluxe Multi Surface Paint of required shade applied @ 0.90ltr/10 sqman under coat of primer applied @ 0.75 ltrs/10 sqm complete including cost of priming coat complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax GST or any other taxes imposed by the Government.	41.16 Square metre	94.30	Rupees Ninety Four And Paise Thirty Only	Per Square metre	3,881.00
7	Providing and fixing 300x16mm (Three hundreded into Sixteen millimetres) nominal size aluminium sliding door bolts ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with nuts and screws etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing design and as directed by the Engineer-in-charge The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.00 Number	65.00	Rupees Sixty Five Only	Each	390.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Providing and fixing 200x10mm (two hundred into Ten millimetres) nominal size Brass Tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with nuts and screws etcetera. complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	18.00 Number	56.00	Rupees Fifty Six Only	Each	1,008.00
9	Providing and fixing 125x34x24 mm (one hundred twenty five into thirty four into twenty four millimetre) weighing not less than 23 (twenty three) gms size of bright finished PTMT Brass handles with screws complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	18.00 Number	85.00	Rupees Eighty Five Only	Each	1,530.00
Total						99,974.00
%Above/below						
Quotted percentage in Figures						
Quotted percentage in words						

Rate of quantity checked and approved for Rs. 99,974.86/- only

Executive Engineer,
Debra Division,
CHP/PWD Dehra

193

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs.99650.00
 Earnest Money :-Rs. 6000.00
 Time Limit :- Three Month.

Name of work:- A/R & M/O to non Residential Building HPPWD at Dehra (SH:-Providing and fixing Wall Paper, Edge wall and Bed CC ~~for approach road~~)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	11.64 Cubic meter	290.00	Rupees Two Hundred Ninety Only	Per Cubic meter	3,463.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour), upto all leads and lift as directed by Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals and as directed by the Engineer-in-charge. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	11.60 Cubic meter	900.00	Rupees Nine Hundred Only	Per Cubic meter	10,440.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (foury millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORD technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	11.20 Cubic meter	4050.00	Rupees Four Thousand Fifty Only	Per Cubic meter	45,360.00
4	Providing and fixing skirting with HD Wall Paper Flakes balancing lamination and edges to be saled with edge bending tape 2.00 mm thick of approved brand with necessary fixing arrangements etc. all complete upto all floor level as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	72.12 Square meter	560.00	Rupees Five Hundred Sixty Only	Per Cubic meter	40,367.00
Total						99,650.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

BID of quantity checked and approved for Rs. 99,650.00/- only.

Executive Engineer,
Dehra Division,
BIPWD Dehra

203

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99302.00
 Earnest Money :-Rs. 2,000.00
 Time Limit :- One Month.

Name of work:- A/R & M/O to non Residential Building at Hanuman Chowk Dehra HPPWD at Dehra (SH:-Construction of Path & Aluminium work, etc)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and back filling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORD Technical Specification clause 305.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	4.52 Cubic Metre metre	290.00	Rupees Two Hundred Ninety Only	Per Cubic Metre metre	1,311.00
2	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification clause 1604.7 and section 300 as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	16.54 Cubic Metre metre	900.00	Rupees Nine Hundred Only	Per Cubic Metre metre	14,886.00
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP, PWD specification. 150 mm (One fifty millimetre) spread thickness (finished work including materials and labour), upto all leads and lift as directed by Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals and as directed by the Engineer-in-charge. The rate is inclusive of Octroi, Royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	16.70 Cubic Metre metre	900.00	Rupees Nine Hundred Only	Per Cubic Metre metre	15,030.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M-10 (M-Ten) nominal mix 1:3:6 (One cement is to three sand is to six graded crushed stone aggregate 40mm (Forty millimeter) nominal size), on ground or under water in open foundation for all type of structure and the like etcetera complete including pumping or bailing out water, dewatering (surface/sub soil water) including removal of slush which may arise at time of laying concrete for all heights/depths and any quantum of water, including cost of form work and curing complete for 14 (fourteen) days and as per drawing and MORD Technical specification section 800, 900 and 1200 and as per entire satisfaction and directions of Engineer-in-charge, including carriage of materials within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, GST, Toll tax or any other taxes imposed by the Government.	12.78 Cubic Metre metre	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic Metre metre	63,261.00
5	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg (thirty six to eight kilogram) and door width from 701 mm to 1000 mm) (seven hundred one to one thousand millimetre), with double speed adjustment with necessary accessories and screws etcetera complete including carriage of material within all leads, lifts and other incidentals and further as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	5.00 Number	962.75	Rupees Nine Hundred Sixty Two And Paise Seventy Five Only	Each	4,814.00
		Total				99,302.00
		%Above/below				
		Quotted percentage in Figures				
		Quotted percentage in words				

*Bigo of quantity checked and approved
for Ro. 99,302.00/- only*

Executive Engineer,
Dehra Division,
HPPWD Dehra

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,852.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Restoration of Rain damages on Bankhandi Haripur Road Km. 0/00 to 8/00 (H.P) (SH:- Repair to Plaster etc.) ~~UNDER PDNA~~

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to plaster of thickness 12mm (Twelve millimetre) to 20mm (Twenty millimetre) in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	52.20 Square metre	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square metre	20,867.00
2	Providing and laying Vitrified tiles in 600x600mm (Six hundred millimetre) (thickness to be specified by manufacturer), Mat finished with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 20mm (Twelve millimetre) thick bed of cement mortar 1:4 (One cement isto Four coarse sand) jointing with grey cement slurry @ 3.3 kg/ sqm (Three point three kilogram per square metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	27.59 Square metre	1360.70	Rupees One Thousand Three Hundred Sixty And Paise Seventy Only	Per Square metre	37,542.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Providing and laying 600x1200mm (Six hundred into twelve hundred millimetres) full body matt finish Ceramic tiles of Resille /Johnson/ Rak/Nitico/Kajaria (Eternity)/ AGL / Simpolo / Somany /Orient & Bell as per approved shade and design of the office and thickness to be specified by manufacturer), with water absorption less than 0.08% (Zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12mm (Twelve millimetre) thick bed of cement mortar 1:3 (One cement isto Three coarse sand) jointing with grey cement slurry @ 3.3 Kilogram/ Square metre (Three point three kilogram per suare metre) including grouting the joint with white cement and matching pigments etcetera complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications, drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	30.14 Square metre	1375.00	Rupees One Thousand Three Hundred Seventy Five Only	Per Square metre	41,443.00
TOTAL						99,852.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

*Receivable Bill of 94 units checked
4/10/2024/10/24 99852/-*

AS
Executive Engineer,
Dehra Division,
HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,824.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Restoration of Rain daamges on Bankhandi Haripur Road Km. 0/00 to 8/00 (H.P) (SH:- Furniture work etc.) ~~UNDER PDA~~

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	116.25 Kilogram me	560.00	Rupees Five Hundred Sixty Only	Per Kilogram me	65,100.00
2	Providing and fixing 12mm (Twelve milimetres) thick (both Side) prelaminated water proof particle board in matt finish flat pressed three layer or graded wood particle board conforming to IS: 12823 as per of Action Tesa / Century / Greenlam / Merinolam / Kitlam / Vista approved shade Grade I Type II, in paneling fixed in aluminium/wood doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetera complete as per architectural drawings and directions of Engineer-in-Charge including entire carriage of materials within all leads, lifts and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the G	4.50 Square metre	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Square metre	5,625.00
3	Providing and fixing fly-proof stainless steel grade 304 wire gauge, to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia. 0.50 mm all complete With 12 mm Aluminium steel U beading all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	7.74 Square metre	892.65	Rupees Eight Hundred Ninety Two And Paise Sixty Five Only	Per Square metre	6,909.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
10	Providing and applying white cement (Birla white/JK) /based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	89.42 Square metre	95.00	Rupees Ninety Five Only	Per Square metre	8,495.00
TOTAL						99,392.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

*Percent 24119 Quantity checked
Approved Rs. 99392/-*

*Executive Engineer,
Dehra Division,
HPPWD Dehra.*

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,360.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Construction of on link road from Masroor to Ghariyar via Othra km. 0/00 to 4/00(SH:- Hiring of JCB Excavator Cum Loader for Removal of formation deficiency & Slips for formation cutting from RD.1/100 to 2/000).DEPOSIT

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of excavator cum loader on through rate basis for removal of slips and removal of formation deficiency in all kinds of soil from road formation, removal of slips, berms dressing, clearing of drains etc. complete in all respect as per direction of the Engineer-in-Charge including all leads lifts. The cost of lubricant diesel etc be borne by the contractor.	2160.00 Cubic Metre	46.00	Rupees Forty Six Only	Per Cubic Metre	99,360.00
	Total					99,360.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Team & Conditions:-

- 1 Hire charges shall be quoted per hour rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
- 3 Hire charges also including insurance of machinery and department shall not be responsible for and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 The minimum amount of work done should be not less 1.80cum Per hour. i.e. excavation 0.60 cum for drain and 1.20cum side cutting (0.75x0.80%)+(6.00x20%).

Percentage Bill of Quantity checked
Approved Rs. 29360/-

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

PERCENTAGE BILL OF QUANTITY

Name of Work: A/R & M/O Various roads under Dehra Sub Division (SH:- Painting and Writing on Km. Stone, Culverts, bridges Sign boards & Rain Shelter etc in Dehra Section)

Estimated Cost: Rs. 99830/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month.

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Removing old paint from Steel and other metal surfaces and making the surface even with hand scraping complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	23.60	Rupees Twenty Three And Paise Sixty Only	Per square metre	566.00
2	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	23.92 Square metre	90.00	Rupees Ninety Only	Per square metre	2153.00
3	Painting two coats (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	75.64 Square metre	90.00	Rupees Ninety Only	Per square metre	6808.00
4	Writing letter in figures of any surface with black Japan Paint (stops, commas, hyphens and the like not to be measured and paid separately) as per drawings and Technical Specification Clause 1701 complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	21000.00 Per Cm height per letter	2.95	Rupees Two And Paise Ninety Five Only	Per centimetre height per letter	61950.00
5	Painting index hands normal size or arrows (up to 40 cm long) on any surface with Black Japan complete as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	280.00 Figure	59.50	Rupees Fifty Nine And Paise Fifty Only	Per figure	16660.00
5	Finishing wall with water proofing cement paint of approved brand and manufacture (Nerolac Surfsh/Apex exterior) and of approved shade on decorated wall surfaces (two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, other foreign matter and sand paped smooth including applying of putty as required for making the surface smooth complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	98.61 Square metre	70.00	Rupees Seventy Only	Per square metre	6903.00
7	Write washing with lime on two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	416.58 Square metre	11.50	Rupees Eleven And Paise Fifty Only	Per square metre	4791.00
TOTAL						99830.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Percently 134402 quantity checked

Approved by A

99830/-

Executive Engineer,
HPPWD Dehra,
Division Dehra.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 99,268.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Construction of link road from Masroor to Gharivar via Othra km. 0/00 to 4/00(SH:- Hiring of JCB Excavator Cum Loader for Removal of formation deficiency & Slips for formation cutting from RD. 0/300 to 1/100). DEPOSIT

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Deployment of hydraulic excavator 0.90cum fitted with rock breaker on through rate basis for making drains and side cuttings in Hard rock (Where blasting is prohibited) as per direction of the Engineer in charge including disposal of excavated rock/material within any leads and lifts as directed by the Engineer-in-Charge. The cost of lubricant diesel etc operator will be borne by the contractor.	2158.00 Cubic Metre	46.00	Rupees Forty Six Only	Per Cubic Metre	99,268.00
	Total					99,268.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

Team & Conditions:-

- 1 Hire charges shall be quoted per Cubic Metre rate.
- 2 Hire charges shall be include all expenses including fuel lubricat establishment major and repair over hauling replacement of equipment if required.
- 3 Hire charges also including insurance of machinery and department shall not be responsible for and fatal and non fatal accident.
- 4 Hire charges shall be include local and other taxes including tax if any imposed by the Govt.
- 5 The minimum amount of work done should be not less 1.80cum Per hour. i.e. excavation 0.60 cum for drain and 1.20cum side cutting (0.75x0.80%)+(6.00x20%).

Executive Engineer,
 Dehra Division,
 DHPWD Dehra.

2460

*Per cent Bill of Quantity
 Corrected 21/02/2014*

PERCENTAGE BILL OF QUANTITY


Estimate Cost :- Rs. 99,254.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Restoration of Rain daamges on Bankhandi Haripur Road Km. 0/00 to 8/00 (H.P) (SH:- Repair to Plaster , Aluminium work, Steel Work & Painting etc.) UNDER PDNA

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to plaster of thickness 12mm (Twelve millimetre) to 20mm (Twenty millimetre) in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	52.20 Square metre	399.75	Rupees Three Hundred Ninety Nine And Paise Seventy Five Only	Per Square metre	20,867.00
2	Providing and fixing plain M.S. grills of required patterns in steel frames of window etc. with M.S grill made of 10mm (ten millimeter) M.S square bar welded to 6mmx12mm (six millimeter into twelve millimeter) M.S. flat, round bars bolts and nuts or screws complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including of Toll Tax Sales tax, GST or any other taxes imposed by the Government.	30.00 Kilogram me	176.45	Rupees One Hundred Seventy Six And Paise Forty Five Only	Per Kilogram me	5,294.00
3	Providing and fixing anodized aluminium work in frames/shutter of Jindal/Hindalco for door and window ventilators and partitions wall frames extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/ Neoprene felt etcetra Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically where ever required including cleat angle, aluminium snap beading for glazing/paneling C.P. brass/stainless steel screws all complete as per architectural drawing specifications, design and the direction of Engineer-in-Charge. The rate is inclusive for carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	27.00 Kilogram me	512.00	Rupees Five Hundred Twelve Only	Per Kilogram me	13,824.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
4	Distempering with oil bound washable distemper of (Nerolac/Asian/Dulux/Berger) approved brand and manufacture (two or more coats) of required shade on new work over and including water thinnable priming coat with cement primer to give an even shade complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	89.42 Square metre	96.85	Rupees Ninety Six And Paise Eighty Five Only	Per Square metre	8,660.00
5	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 k g/10 sqm) all complete and as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, Toll tax, GST or any other taxes imposed by the Government.	78.85 Square metre	55.00	Rupees Fifty Five Only	Per Square metre	4,337.00
6	Brick masonry work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (Seven point Five) in super structure in Cement mortar 1:6 (One cement isto Six coarse sand) complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, GST and any other taxes imposed by the Government.	3.68 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	21,344.00
7	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.31 Square metre	525.00	Rupees Five Hundred Twenty Five Only	Per Square metre	10,138.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
8	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) Nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) in or under water in open foundation for all types of structure and the like in Catchpit flooring etcetera, including cost of form work and curing complete as per drawing and MORD technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depts and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.55 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	14,790.00
TOTAL						99,254.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						


 Executive Engineer,
 Dehra Division,
 HPPWD Dehra.

SCHEDULE OF QUANTITY

Estimated Cost : 40795/-
Earnest Money : 850/-
Time Limit : SIX MONTH

Name of Work:- Preparation of forest diversion case under FRA, 2006 for the construction of link road in Dehra Sub Division 1. Ambulance road from Transformer to Dhanotu Balla Road in G.P. Dhallara Km 0/00 to 0/159 Km.

(SH:- Preparation of Forest Diversion Case under FRA, 2006)

Sr. No.	Description of item	Qty.	RATES IN		Unit	Amount
			Figures	Words		
1.	Preparation of KML File, Topo Sheet Map, Alternative Map and Geo Referenced Digital map of proposed land. Preparation of 3 number of proposal folders including Reclamation Plan, Cost Benefit Analysis, Muck Management, complete in all respect. Assistance to User Agency to attend the queries and clarification sought by Forest Department. The Rates are inclusive of all equipment within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax, Sale Tax or other taxes imposed by the Government.	1	40000	Forty Thousand only	Each	40000
2.	Preparation of revenue paper for land acquire in the project, Layout Plan of the Project, Khasra wise detail of forest and non-forest both, enumeration list, village wise beneficiary information and Joint Inspection Report. The rate including octroi, royalty, Malkana toll tax, Sale tax or other taxes imposed by the Government.	0.159	5000	Five Thousand only	Per Km	795
						40795

Bill of Quantity checked and approved for Rs 40,795/- only
Executive Engineer
H.P.P.W.D. Division
Dehra - 177101

PERCENTAGE BILL OF QUANTITY

ESTIMATED COST:- Rs. 99,189.00
EARNEST MONEY Rs. 2,000.00
TIME LIMIT : One Month

NAME OF WORK:- A/R & M/O to non Residential Building HPPWD at Dehra (SH:-Aluminium work, Steel work etc)

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 12mm (Twelve millimetre) thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, with decorative lamination on both side, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetera complete including carriage of materials in all leads and lift as per direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, GST and any other taxes imposed by the Government.	26.00 Square metres	1050.30	Rupees One Thousand Fifty And Paise Thirty Only	Per square metre	27,308.00
2	Providing and fixing 15mm (Fifteen millimetre) dia nominal bore G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etcetera Internal work-Exposed on wall complete as per architectural drawings including carriage of material within all leads, lifts and other incidentals, as per approved specifications drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.38 Running metre	298.25	Rupees Two Hundred Ninety Eight And Paise Twenty Five Only	Per Running metre	710.00
3	Providing and fixing 100mm (One hundred millimetre) dia high pressure PVC Finolux/Relpipe (Reliance) /Vecus Type B spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etcetera complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	4.40 Running metre	350.00	Rupees Three Hundred Fifty Only	Per Running metre	1,540.00
4	Providing and fixing 75mm (Seventy five millimetre) dia high pressure PVC Finolux/Relpipe (Reliance) /Vecus Type B spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etcetera complete including entire carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	2.61 Running metre	225.00	Rupees Two Hundred Twenty Five Only	Per Running metre	587.00
5	Providing and fixing 100mm (one hundred millimeters) aluminium handles make of pilot/sheel or equivalent anodized transparent or dyed to required colour and shade with necessary screws etcetera complete as per HPPWD specifications and as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Octroi, toll tax, GST or any other taxes imposed by the Government.	56.00 Numbers	68.00	Rupees Sixty Eight Only	Each	3,808.00

Sr. No.	Description of items	Quantity		Rate		Unit	Amount
		3	4	5	6		
1	2						7
6	Providing and fixing 250mmx10mm (Two hundred fifty into Ten millimetres) size arch make (corrosion resistant) or equivalent stainless steel 304 grade tower bolt (barrel type) with screws etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	49.00	Numbers	115.00	Rupees One Hundred Fifteen Only	Each	5,635.00
7	Providing and fixing 250x16mm (Two hundred fifty into Sixteen millimetres) arch make (corrosion resistant) or equivalent stainless steel 304 grade sliding door bolt with nuts and screw etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	6.00	Numbers	265.35	Rupees Two Hundred Sixty Five And Paise Thirty Five Only	Each	1,592.00
8	Providing and fixing bright finished floor door stopper of Godrej Cat no. 8564 with rubber cushion, necessary brass screws etcetera to suit shutter thickness etcetera complete, including carriage of material within all leads, lifts and other incidentals and as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	7.00	Numbers	247.50	Rupees Two Hundred Forty Seven And Paise Fifty Only	Each	1,733.00
9	Providing and fixing 150mm (One hundred fifty millimeters) size oxidized mild steel hooks and eyes complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Octroi, toll tax, GST or any taxes imposed by the Government.	8.00	Numbers	95.00	Rupees Ninety Five Only	Each	760.00
10	Providing for steel reinforcement of Tata/Sail for Reinforced Cement Concrete work including straightening, cutting, bending, placing in position and binding all complete upto all floor level Thermo-Mechanically Treated bars of grade Fe-500D or more etcetera complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkhana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	116.00	Kilogram	125.00	Rupees One Hundred Twenty Five Only	Per kilogram	14,500.00

Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			In fig	In words		
1		3				
11	Providing and fixing anodized aluminium work of Jindal/Hindalco for door and window ventilators and partitions wall frames extruded built up standard tubular and other sections of approved make conforming to IS:733 and IS:1285 anodized transparent or dyed to required shade according to IS:1868 (Minimum anodic coating of grade AC 15) fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions at top, bottom and sides with required PVC/ Neoprene felt etcetra Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically where ever required including cleat angle, aluminium snap beading for glazing/paneling C.P. brass/stainless steel screws all complete as per architectural drawing specifications, design and the direction of Engineer-in-Charge. The rate is inclusive for carriage of material within all leads, lifts and other incidentals. The rate is inclusive of Octroi, Royalty, Malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	36.00 Kilogram me	630.00	Rupees Six Hundred Thirty Only	Per Kilogram me	22,680.00
12	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm) (Cost of aluminium snap beading shall be paid in basic item) complete as per the architectural drawings and the directions of engineer-in-charge . including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, GST, toll tax or any taxes imposed by the Government.	15.05 Square metre	832.95	Rupees Eight Hundred Thirty Two And Paise Ninety Five Only	Per Square metre	12,536.00
13	Providing and laying cement concrete 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimeters) nominal size) mechanically mixed and curing complete up to all floor level complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00 Cubic metre	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic metre	5,800.00
TOTAL :-						99,189.00
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,
Delhra Division,
HP.PWD., Dehra

Per cent by Bill of quantities checked & approved
for Rs 99,189/-

202

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs. 60,000.00
 Earnest Money :- Rs. 2,000.00
 Time Limit :- One Month.

Name of Work:- Hydraulic Data of 25.00mtr span Bridge over Gumreher khad at RD. 0/650 on Link Road Kundli Har to Nauri via Andrari Mandeli Road. (SH :- Preparation of Hydraulic Data

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Preparation of Hydraulic data complete in all respect in manuscript form and submission of the same in higher office for approval. If any correction/amendment has desired by the head office the same may be corrected as desired and directed by the Engineer-in-Charge and higher office complete in all respect. After approval of the hydraulic data from the higher office, the same will be submitted in fair shape to this office in two numbers of copies and payment shall be made after the approval of the same by the higher office. The rate shall be inclusive of all taxes imposed by the Government.	1.00 Number	60000.00	Rupees Sixty Thousand Only	Each	60,000.00
	Total					60,000.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Bill of Quantity checked and approved for Rs. 60,000/- only.

Executive Engineer,
 Dehra Division,
 HPPWD Dehra.