

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

\*\*\*\*\*

No. PWCB/CB-GA/Tender/2025-26-

12519-618

Dated:- 21/10/25

To


The Executive Engineer (IT Cell ),  
Nigam Bihar, Himachal Pradesh Shimla-2.  
cc-pwd-hp@nic.in

**Subject: - Publication of Tender Notice**

Sir,

Enclosed please find herewith notice of various work as given in the tender inviting tender for uploading on departmental website as per notification Pr. Secy( PW) to the Govt. of Himachal Pradesh letter No. PBW ( B) A ( 3 ) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the works mentioned in the tender Notice are urgent nature and public interest. .


Your's Faithfully,

  
Executive Engineer,  
Bharmour Division,  
HP.PWD, Bharmour

DA/As above.

**Copy forwarded to the following for information please :-**

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, Kangra Zone, HP.PWD.Dharamshala.
3. Deputy Commissioner Chamba District Chamba.
4. All the Superintending Engineers/Executive Engineer in HPPWD
5. All the Assistant Engineer under Bharmour Division.
6. Additional District Magistrate Bharmour.
7. The Superintendent of Police Chamba.
8. Labour Officer Chamba.
9. Notice Board of this office

  
Executive Engineer,  
Bharmour Division,  
HP.PWD, Bharmour

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
SHORT TERM NOTICE INVITING TENDERS

Sealed percentage rate tenders on from 6 & 8 are hereby invited by the Executive Engineer, Bharmour Division, HP.PWD. Bharmour on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

**Date and time of receipt of application for tender form- 24.10.2025 up to 1.00 PM**

**Date and time of issue/Sale of tender form- 24.10.2025 at 2:00 PM to 04:30 PM**

**Date and time of receipt of tender form-25.10.2025 up to 11:30 AM**

**Date and time of opening tender form- 25.10.2025 at 3:30 PM**

The tender form can be had from the office of the Executive Engineer against Cash (Non-refundable). The earnest money should be in the shape of Fixed Deposit duly pledged in favour of the Executive Engineer Bharmour Division HPPWD Bharmour must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for 75 days. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.

Sr. No.	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of tender form (Rs.)	Class	Completion period
1	2	3	4	5	6	7
1	Restoration of rain damage under Barmour sub Division ( SH:- Hiring of JCB for removal of slips at various Rd's	492000	10000	350/-	C & D	Three Month
2	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (SH:- Removal of slips and boulder at various Rds.	499257	9985	350	C & D	Three Month
3	Restoration of rain damage on Patti to Khund road km 0/00 to 3/300 (SH:- Removal of slips and boulder at various Rds.	492188	3 Month	350	C & D	Three Month
4	Restoration of rain damage on Patti to Khund road km 0/00 to 3/300 (SH:- Removal of slips and boulder at various Rds.	497376	9947	350	C & D	Three Month
5	Restoration of rain damage on various road under Bharmour Sub Division ( SH:- Hiring of JCB for removal of slips at various Rds	498150	10000	350	C&D	Three Month
6.	Restoration of rain damage under Garola Sub Division ( SH:- Hiring or Tipper	499000	10000	350	C&D	Three Month
7.	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of crawler for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
8	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of crawler for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
9	Restoration of rain damage on various road under Rakh	147600	2952	350	C&D	Three



	Sub Division (SH:- Hiring of JCB for removal of slips at various RDs.					Month
10.	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tipper for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
11.	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tipper for removal of slips at various RDs.	99540	1990	350	C&D	Three Month
12.	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of crawler for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
13.	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tipper for removal of slips at various RDs.	99540	1990	350	C&D	Three Month
14	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tipper for removal of slips at various RDs.	99540	1990	350	C&D	Three Month
15	Restoration of rain damage on Sarehi Baloth road km 0/00 to 4/00 (SH:- Hiring of Tipper for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
16	Restoration of rain damage on Sarehi Baloth road km 0/00 to 4/00 (SH:- Hiring of Tipper for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
17	Restoration of rain damage on Sarehi Baloth road km 0/00 to 4/00 (SH:- Hiring of Tipper for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
18	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of crawler for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
19	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs.	499380	9987	350	C&D	Three Month
20	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs.	499380	9987	350	C&D	Three Month
21	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs.	498150	9963	350	C&D	Three Month
22	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of crawler for removal of slips at various RDs.	497700	9954	350	C&D	Three Month
23	Restoration of rain damage on Choori Bassu Kothi Nirkula road and link road to Village Sunara (SH:- Hiring of Crawler for removal of slips at various Rds	497700	9960	350	C&D	Three Month
24	Restoration of rain damage on Link road to Village Sunara km 0/00 to 3/00 (SH:- Hiring of JCB for removal of slips at various RDs.	400980	8019	350	C&D	Three Month
25	Restoration of rain damage on Bakani to Dharbeta road (SH:- Hiring of Tipper for removal of slips at various RDs.	300200	6004	350	C&D	Three Month
26	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tractor for removal of slips at various RDs.	300000	6000	350	C&D	Three Month
27	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tipper for removal of slips at various RDs.	150100	3002	350	C&D	Three Month
28	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs	301350	6027	350	C&D	Three Month
29	Restoration of rain damage on various road under Rakh	302400	6000	350	C&D	Three

*Handwritten signature*

	Sub Division (SH:- Hiring of Crawler for removal of slips at various RDs					Month
30	Restoration of rain damage on Gaithan Massu road km 0/00 to 4/500(SH:- Hiring of JCB for removal of slips at various RDs	400980	8000	350	C&D	Three Month
31	Restoration of rain damage on Link road to Village Jaintra and Galthan Massu road (SH:- Hiring of Crawler for removal of slips at various RDs	497700	9954	350	C&D	Three Month
32	Restoration of rain damage on Mehla Ukala road km 0/00 to 4/00 (SH:- Removal of slips at various Rds.	497511	9950	350	C&D	Three Month
33	Restoration of rain damage on Dunali Brehi road and Mandasa Matlog road SH:- Hiring of JCB for removal of slips at various RDs	499380	9987	350	C&D	Three Month
34	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs	499380	9987	350	C&D	Three Month
35	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs	499380	9987	350	C&D	Three Month
36	Restoration of rain damage on Gehra to Mandhara road (portion Gehra to Upper Jauwa km 0/00 to 4/400(SH:- Hiring of Crawler for removal of slips at various RDs	481950	9639	350	C&D	Three Month
37	Restoration of rain damage on Link road from Noan to Delpha via Rikhara i.e. leg to Vill Bhadour km 0/00 to 1/800 (SH:- Removal of slips at various Rds	252158	5043	350	C&D	Three Month
38	Restoration of rain damage on Samot to Sirna road km 0/00 to 1/500 (SH:- Removal of slips at various Rds	241658	4833	350	C&D	Three Month
39	Restoration of rain damage on Mehla Lakra Bandla road and Bandla to Rainpani road (SH:- Hiring of Crawler for removal of slips at various RDs	494550	9891	350	C&D	Three Month
40	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of JCB for removal of slips at various RDs	498150	9963	350	C&D	Three Month
41	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Tractor for removal of slips at various RDs	210000	4200	350	C&D	Three Month
42	Restoration of rain damage on various road under Rakh Sub Division (SH:- Hiring of Crawler for removal of slips at various RDs	497700	9954	350	C&D	Three Month
43	Restoration of rain damage on Bakani to Dharbeta road (SH:- Hiring of Crawler for removal of slips at various RDs	497700	9954	350	C&D	Three Month
44	Restoration of rain damage on Gehra Mandhara road (portion Gehra to Upper Jauwa km 0/00 to 4/400(SH:- Hiring of Crawler for removal of slips at various RDs	150060	3001	350	C&D	Three Month
45	A/R & M/O various road under Rakh Sub Division ( SH:- Hiring of Tractor for Shifting of Material	495000	10000	350	C&D	Three Month
46	Restoration of rain damage on under Rakh Sub Division ( SH:- Removal of Slips and boulder at various Rds	490105	10000	350	C&D	Three Month
47	Restoration of rain damage on Kandi to Mindra road km 0/00 to 6/215 (SH:- Removal of slips and boulder at various Rds.	225193	4503	350	C & D	Three Month
48	Restoration of rain damage on various road under Garola Sub Division ( SH:- Hiring of tractor for Shifting of Material	217600	4360	350	C&D	Three Month
49	Restoration of rain damage on various road under Garola Sub	421027	8420	350	C & D	Three

*de*

	Division (SH:- Removal of slips and boulder at various Rds.					Month
50	Restoration of rain damage on various road under Garola Sub Division (SH:- Removal of slips and boulder at various RDs	417899	8360	350	C & D	Three Month
51	Restoration of rain damage on various road under Garola Sub Division (SH:- Removal of slips and boulder at various RDs	348427	6970	350	C & D	Three Month
52	Restoration of rain damage on Kharamukh to Dhajji Mindra road Km 0/00 to 5/500 (SH:- Removal of slips and boulder at various RDs	229276	4585	350	C & D	Three Month
53	Restoration of rain damage on Dhakog to badgram road Km 0/00 to 20/500 (SH:- Removal of slips and boulder at various RDs	302174	6043	350	C & D	Three Month
54	Restoration of rain damage on Machhatter to Garima via Siur road Km 0/00 to 11/500 (SH:- Removal of slips and boulder at various RDs	330407	6610	350	C & D	Three Month
55	Restoration of rain damage on Pilli to Swai road Km 0/00 to 5/490 (SH:- Removal of slips and boulder at various RDs	253449	5068	350	C & D	Three Month
56	Restoration of rain damage on Beyoti to Sanj road Km 0/00 to 5/670 (SH:- Removal of slips and boulder at various RDs	235928	4720	350	C & D	Three Month
57	Restoration of rain damage on KSPA road Km 0/00 to 13/00 ( SH:- Removal of Slips and boulder at various Rds	495429	10000	350	C & D	Three Month
58	Restoration of rain damage on Dibri Ohra road Km 0/00 to 4/500 ( SH:- Removal of slips and boulder at various Rds	230851	4700	350	C&D	Three Month
59	Restoration of rain damage on Surge Shaft to Arki road KM 0/00 to 1/700 ( SH:- Removal of slips and boulder at various Rds	199772	4000	350	C&D	Three Month
60	Restoration of rain damage under Garola Sub Division ( SH:- removal of Slips and boulder at various Rds	499672	10000	350	C&D	Three Month
61	Restoration of rain damage on various road under Holi sub Division SH:-Hiring of Hydraulic Excavator (JCB)	499400	9988	350	C&D	Three Month
62	C/O Pnehruin Janni to Sanahan road Km Km 0/0 to 3/00 (SH:- C/O R/wall from RD 0/400 to 0/428	493550	10000	350	C&D	Three Month
63	Restoration of rain damage on link road to Village Kalmala ( SH:- C/O wire crate from RD 0/725 to 0/755.	477555	9600	350	C&D	Three Month
64	Restoration of rain damage on various road under Bharmour Sub Division ( SH:- Removal of slips at various RDs.	497277	9950	350	C&D	Three Month
65	Restoration of rain damage on Dhakog to Badgram road Km 0/00 to 6/215 ( SH:- Removal of Slips and boulder at various Rds's	225193	4500	350	C&D	Three Month
66	Restoration of rain damage on Sirdi to Ghared via sSuppa road Km 0/00 to 9/500 ( SH:- Removal of and boulder at various Rds.	497607	9960	350	C&D	Three Month
67	Restoration of rain damage on various road under Bharmour Sub Division ( SH:- Hiring of JCB for Removal of Slips at various Rds,s	488400	10000	350	C&D	Three Month
68	A/R & M/O Various road under Rakh Sub Division ( SH:- Hiring of	99600	10000	350	C&D	Three

*Handwritten signature or mark*

	Tractor for shifting of material					Month
69	Restoration of rain damage on Patti to Bharmani via Malkota road km 0/00 to 5/00 (under PDNA) (SH:- C/O R/Wall at PDNA RD 0/680 to 0/741 (portion 2/778 to 2/785.50.	409853	8197	300	C&D	Three Month
70	Restoration of rain damage on Patti to Bharmani via Malkota road km 0/00 to 5/00 (under PDNA) (SH:- C/O R/Wall at PDNA RD 0/680 to 0/741 (portion 2/786 to 2/793.	382333	7646	300	C&D	Three Month
71	Restoration of rain damage on Bharmour to Hadsar road km 0/0 to 12/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 11/135 to 11/485 portion 1/590 to 1/597.50	482976	9659	300	C&D	Three Month
72	Restoration of rain damage on Thalla to Chobia road km 0/00 to 13/500 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 13/00 to 13/050 portion 13/010 to 13/019.	496010	9920	300	C&D	Three Month
73	Restoration of rain damage on Hadsar to Chobia road km 0/00 to 9/500 (under PDNA) (SH:C/O- PCC R/Wall at PDNA RD 7/040 to 7/130 portion 5/360 to 5/365.	273586	5471	300	C&D	Three Month
74	Restoration of rain damage on Thalla to Chobia road km 0/00 to 13/500 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 12/500 to 12/530 portion 13/00 to 13/009	494853	9897	300	C&D	Three Month
75	Restoration of rain damage on Hadsar to Chobia road km 0/00 to 9/500 (under PDNA) (SH:C/O- PCC R/Wall at PDNA RD 7/040 to 7/130 portion 5/365 to 5/370	327507	6550	300	C&D	Three Month
76	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/840 to 4/860 portion 4/740 to 4/746.	464059	9281	300	C&D	Three Month
77	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/840 to 4/860 portion 4/747 to 4/754.	463391	9267	300	C&D	Three Month
78	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/840 to 4/860 portion 5/330 to 5/337.50.	485123	9702	300	C&D	Three Month
79	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 0/200 to 0/337 & 7/200 to 7/230 portion 10/506 to 10/513.50.	484558	9691	300	C&D	Three Month
80	Restoration of rain damage on Hadsar to Kugti road km 0/00 to 13/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 0/380 to 0/400, 1/020 to 1/045 & 1/400 to 1/425 portion 10/514 to 10/521.50.	485316	9706	300	C&D	Three Month
81	Restoration of rain damage on Thalla to Chobia road km 0/00 to 13/500 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/190 to 4/458 (portion 0/842 to 0/857 )	490818	9816	300	C&D	Three Month
82	Restoration of rain damage on Thalla to Chobia road km 0/00 to 13/500 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/190 to 4/458 (portion 0/858 to 0/871.50	490818	9820	300	C&D	Three Month
83	Restoration of rain damage on Thalla to Chobia road km 0/00 to 13/500 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 4/190 to 4/458 (portion 0/871 to 0/882.50)	491011	9820	300	C&D	Three Month
84	Restoration of rain damage on Bharmour to Badgram road km 0/00 to 26/00 (under PDNA) (SH:- C/O PCC R/Wall at PDNA RD 13/210 to 13/220, 18/790 to 18/810 & 23/960 to 23/980 portion 17/934 to 17/940.	466822	9336	350	C&D	Three Month
85	Special Repair of HRTC New Bus stand Patti at Bharmour Distt Chamba (SH:- Doors celing etc works.	94421	1888	350	C&D	Three Month
86	Restoration of rain damage on various road under Rakh Sub Division ( SH:- Hiring of JCB for Removal of slips at	498150	10000	350	C&D	Three Month

	Rds					
87	Restoration of rain damage on various road under Rakh Sub Division ( SH:- Hiring of Crawler for Removal of slips at various Rds	497700	10000	350	C&D	Three Month
88	Restoration of rain damage on various road under Rakh Sub Division ( SH:- Hiring of Crawler for Removal of slips at various Rds	497700	10000	350	C&D	Three Month
89	Restoration of rain damage on various road under Rakh Sub Division ( SH:- Hiring of JCB for Removal of slips at various Rds	498150	10000	350	C&D	Three Month
90	Restoration of rain damage on various road under Rakh Sub Division ( SH:- Hiring of JCB for Removal of slips at various Rds	498150	10000	350	C&D	Three Month


Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ Acknowledgement of GST Registration as per Condition No. 16(iii)/ and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected. 3. The offer shall remain valid up to 75 days.
4. The contractor should not have more than two contracts within Division at a time tender. If the contractor has already two works in hand then the tender not excepted at the time of opening of tender and the same will be rejected technical evaluations.
5. If the contractors found lowest more than two works during the opened of bid then two works awarded to contractor at the one time and then opportunity will be given to next lowest bidder.
6. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
7. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.
8. The tender documents shall be issued to only those contractors who do not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.
9. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.
10. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996- 38095 dated 13.03.2023.

  
Executive Engineer,  
Bharmour Division,  
HP.PWD; Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST                      Rs                      492000.00  
 EARNEST MONEY                      Rs                      10000.00  
 TIME LIMIT                              THREE MONTHS

**NAME OF WORK**                      Restoration of rain Damage Under Bharmour sub Division  
**SUB-HEAD :-**                              Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting / widening of road and removal of slips in all kind of soil and disposal of all excavated earth un- serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	410.00				Per Hours	
<b>Total :-</b>							


  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 499257.00  
 EARNEST MONEY : Rs 9985.14  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Hadsar to Kugti road Km 0/00 to 13/00  
**SUB-HEAD :-** Removal of slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government	4538.70			Cubic metres	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharmour Division,  
 SHPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497376.00  
 EARNEST MONEY : Rs 9947.52  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Patli to Khund road Km 0/00 to 3/300  
**SUB-HEAD :-** Removal of slips and boulder at various RD's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4521.60	Cubic metres			Per cubic metre	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 JHPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 492188.00  
 EARNEST MONEY : Rs 9843.76  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Patli to Khund road Km 0/00 to 3/300  
**SUB-HEAD :-** Removal of slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4687.50			Cubic metres Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 NPPWD Bharmour

## SCHEDULE OF QUANTITY

**Name of Work :- Restoration of rain damage on Various road under Bharmour Sub Division**

**E/COST:-498150/-**

**E/MONEY:-10000/-**

**TIME LIMIT:-1 MONTH**

S.No.	Description of Item	Quantity.	RATES		Unit	Amount (Rs.)
			Rate in Figure	Rate in Words		
1	Hiring of J.C.B./Excavator cum loader for cutting / widening of road and removal of slips in all kind of soil and disposal of all excavated earth un- serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B /Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	405.00	Per Hours		Per Hours	
<b>TOTAL AMOUNT=</b>						

  
**Executive Engineer**  
**Bharmour Division**  
**HPPWD, Bharmour**

SCHEDULE OF QUANTITY

**NAME OF WORK** Restoration of rain Damage Under Garola sub Division  
**SUB-HEAD :-** Hiring of tipper

**ESTIMATED COST** Rs 499000.00  
**EARNEST MONEY** Rs 10000.00  
**TIME LIMIT** THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government, come by the owner of the tractor	499.00	Hours		Per Hours	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 PAPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 497700.00  
 EARNEST MONEY : . . . . . Rs 9954.00  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Raksh Sub-Division  
**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount	
		Fig	Words	Fig	Words			
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all height's and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours			Per Hour		
<b>Total :-</b>								

  
 Executive Engineer,  
 Bharnour Division,  
 G.M.P.P.W.D Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 497700.00  
 EARNEST MONEY : . . . . . Rs 9954.00  
 TIME LIMIT . . . . . One Month

**NAME OF WORK** : Restoration of rain damage on Various road under Raksh Sub-Division

**SUB-HEAD** : - Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount	
		Fig	Words	Fig	Words			
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours			Per Hour		
<b>Total :-</b>								

  
 Executive Engineer,  
 Bharnour Division,  
 RPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST :                      Rs                      147600.00  
 EARNEST MONEY :                      Rs                      2952.00  
 TIME LIMIT                                      One Month

**NAME OF WORK** : Restoration of rain damage on Various road under Rakh Sub-division

**SUB-HEAD** : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	120.00	Hours			
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 RHPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of Tipper for removal of slips at various Rd's

Sl No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Makana, toll tax sale tax, GST or other taxes imposed by the Government.	630.00	Hours		Per Hour	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 99,540.00  
 EARNEST MONEY : Rs 1990.80  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD :-** Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	126.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharatour Division,  
 JHPPWD Bharatour

**SCHEDULE OF QUANTITY**

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

**ESTIMATED COST :** Rs 497700.00  
**EARNEST MONEY :** Rs 9954.00  
**TIME LIMIT** One Month

Sl. No.	Description of work	Quantity		RATES		Unit	Amount	
		Fig	Words	Fig	Words			
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours			Per Hour		
<b>Total :-</b>								

  
 Executive Engineer,  
 Bharnour Division,  
 PAPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 99540.00  
 EARNEST MONEY : Rs 1990.80  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	126.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 JHPWD Bharmour



**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Sarehi Baloth road km 0/00 to 4/00  
**SUB-HEAD :-** Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	630.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour



**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 497700.00  
 EARNEST MONEY : . . . . . Rs 9954.00  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Sarehi Baloth road km 0/00 to 4/00

**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un-serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours			Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharnour Division,  
 JIPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Raikh Sub-Division

**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow. Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period/ excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Matkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours		Per Hour	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 MPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 499380.00  
 EARNEST MONEY : Rs 9987.60  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-division  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/ private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 PAPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 499380.00  
 EARNEST MONEY : Rs 9987.60  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-division  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00	Hours		Per Hour	
<b>Total :-</b>						

  
 Engineer,  
 Bharmour Division,  
 HRPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 498150.00  
 EARNEST MONEY : Rs 9963.00  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Raksh Sub-division  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	405.00				Per Hour	
<b>Total :-</b>							

*AMT approved for Rs.*

  
 Executive Engineer,  
 Bharmour Division,  
 PAPPVD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00	Hours		Per Hour	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 PAPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 497700.00  
 EARNEST MONEY : . . . . . Rs 9954.00  
 TIME LIMIT . . . . . One Month

**NAME OF WORK** : Restoration of rain damage on Choori Bassu Kothi Nirakula road and Link road to village Sunara  
**SUB-HEAD** :- Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		Fig	RATES		Unit	Amount
			Hours		Words			
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow. Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	158.00					Per Hour	
<b>Total :-</b>								

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 400980.00  
 EARNEST MONEY : . . . . . Rs 8019.60  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Link road to Vill. Sunara Km 0/00 to 3/00  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
			Hours	Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	326.00				Per Hour	
<b>Total :-</b>							<b>400980.00</b>

  
 Executive Engineer,  
 Bharnour Division,  
 HPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 300200.00  
 EARNEST MONEY : Rs 6004.00  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Bakani Dharbeta road

**SUB-HEAD :-** Hiring of Tipper for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Tipper 10Cum/18 tonne capacity for disposing and transporting of surplus excavated material and shifting of any type of construction material in all leads as per directions and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of owner of the machinery which shall have to be compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner at his own cost and repair & spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	380.00	Hours			Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 JHPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 300000.00  
 EARNEST MONEY : Rs 6000.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD :-** Hiring of Tractor for shifting of material

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debris. Through mechanically from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	500.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 MPPWD Bharmour




**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 301350.00  
 EARNEST MONEY : Rs 6027.00  
 TIME LIMIT One Month

**NAME OF WORK** : Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD** : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	245.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 SHPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 302400.00  
 EARNEST MONEY : Rs 6048.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rds

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	96.00	Hours		Per Hour	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharnour Division,  
 MPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 400980.00  
 EARNEST MONEY : . . . . . Rs 8019.60  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Galthan Massu road Km 0/00 to 4/500  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	326.00	Hours			
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour




**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497511.00  
 EARNEST MONEY : Rs 9950.22  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Mehla UKla road Km 0/00 to 4/00

**SUB-HEAD :-** Removal of slips at Various Rds

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4738.20				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPVD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 499380.00  
 EARNEST MONEY : Rs 9987.60  
 TIME LIMIT One Month

**NAME OF WORK** : Restoration of rain damage on Dunali Brehni road and Mandasa Matlog road

**SUB-HEAD** : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00	Hours		Per Hour	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 499380.00  
 EARNEST MONEY : Rs 9987.60  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road Under Rakth Sub-Division  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of 406.00 soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00	Hours			Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 499380.00  
 EARNEST MONEY : Rs 9987.60  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road Under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	406.00	Hours		Per Hour	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharmour Division,  
 MPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 481950.00  
 EARNEST MONEY : Rs 9639.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Gehra to Mandhara road (Portion Gehra to Upper Jauwa Km 0/00 to 4/400)  
**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debries and boulders clear from the roads surface upto all height's and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	153.00	Hours			Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 252158.00  
 EARNEST MONEY : Rs 5043.16  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Link road from Noan to Delpha via Rikhara i.e. Leg to Vill Bhadour Km 0/00 to 1/800  
**SUB-HEAD :-** Removal of slips at Various Rds

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
			Hours	Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3.5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2401.50				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 241658.00  
 EARNEST MONEY : Rs 4833.16  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Samot to Sirma road Km 0/00 to 1/500  
**SUB-HEAD :-** Removal of slips at Various Rds

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3.5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2301.50			Hours	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 494550.00  
 EARNEST MONEY : . . . . . Rs 9891.00  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Mehla Lakra Bandla road and Bandla to rainpani road  
**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity		RATES		Unit	Amount	
		Fig	Words	Words	Words			
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	157.00	Hours			Per Hour		
<b>Total :-</b>								

  
 Executive Engineer,  
 Bharmour Division,  
 JHPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST :                      Rs                      498150.00  
 EARNEST MONEY :                      Rs                      9963.00  
 TIME LIMIT                                      One Month

**NAME OF WORK :** Restoration of rain damage on Various road Under Rakh Sub-Division

**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	405.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 SHPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 210000.00  
 EARNEST MONEY : Rs 4200.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD :-** Hiring of T tractor for shifting of material

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debris. Through mechanically from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	350.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 GHPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on Various road under Rakh Sub-Division

**SUB-HEAD :-** Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un-serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	158.00	Hours			
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 497700.00  
 EARNEST MONEY : Rs 9954.00  
 TIME LIMIT One Month

**NAME OF WORK** : Restoration of rain damage on Bakani to Dharbeta road

**SUB-HEAD** : - Hiring of Crawler for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Crawler Excavator cum Pocklane or JS 210 or equipment of slips debris and boulders clear from the roads surface upto all heights and depths in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth un- serviceable material from the road surface up to all heights and depths as per direction and entire satisfaction of Engineer-in-charge. The excavator at least 200 cum quantity for snow, Slips per hour. Any loss of public/ private property or any accident etc. happened during the course of hiring period /excavation shall be the absolute responsibility of the Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	158.00	Hours		Per Hour	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour


**SCHEDULE OF QUANTITY**

ESTIMATED COST . . . . . Rs 150060.00  
 EARNEST MONEY : . . . . . Rs 3001.20  
 TIME LIMIT . . . . . One Month

**NAME OF WORK :** Restoration of rain damage on Gehra Mandhara road (Portion Gehra to Upper Jauwa Km 0/00 to 4/400)

**SUB-HEAD :-** Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring of J.C.B./Excavator cum loader for cutting/ widening of road and removal of slips in all kind of soil and disposal of all excavated earth un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happened during the course of hiring period / executing shall be the absolute responsibility of the J.C.B./Excavator owner, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owner, repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	122.00				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 ANPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST                      Rs                      495000.00  
 EARNEST MONEY                    Rs                      10000.00  
 TIME LIMIT                              THREE MONTHS

**NAME OF WORK**                      A/R & M/G various road under Rakh Sub Division  
**SUB-HEAD**                              Hiring of Tractor for shifting of Material

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of tractor for shifting of material un-dressed stone muck/debris. Through mechanically from different reaches as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	825.00		Hours	Per Hours	
<b>Total :-</b>						

  
 Scientific Engineer,  
 Bharmaour Division,  
 APPWD Bharmaour

SCHEDULE OF QUANTITY

ESTIMATED COST                      Rs                      490105.00  
 EARNEST MONEY                      Rs                      1910.00  
 TIME LIMIT                              THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Under Rakh Sub division

**SUB-HEAD :-** Removal of slips and boulder at various Rd,s

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4455.50			Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharnour Division,  
 HPPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 225193.00  
 EARNEST MONEY : Rs 4503.86  
 TIME LIMIT **THREE MONTHS**

**NAME OF WORK :** Restoration of rain damage on Kandi to mindra road Km 0/00 to 6/215  
**SUB-HEAD :-** (Removal of slips and boulders at various RD's )

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	1958.20			Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 JHPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      217600.00  
 EARNEST MONEY      Rs      4352.00  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK** Restoration of rain Damage on Various road under Garola Sub Division  
**SUB-HEAD :-** Hiring tractor for shifting of material

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debrs. Through mechanically 320.00 from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	320.00	Hours			Per Hours	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

**NAME OF WORK :** Restoration of rain damage at various road under Garola Sub Division  
**SUB-HEAD :-** Removal of slips and boulders at Various Rds

**ESTIMATED COST .** Rs 421027.00  
**EARNEST MONEY :** Rs 8420.54  
**TIME LIMIT** One Month

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government	3661.10				Per Hour	
<b>Total :-</b>							

  
**Executive Engineer,**  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 417899.00  
 EARNEST MONEY : Rs 8357.98  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage at Various road under Garola Sub Division

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	3633.90	Cubic metres		Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 AHPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST . . . . . Rs 348427.00  
 EARNEST MONEY : . . . . . Rs 6968.54  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage at Various road under Garola Sub Division  
**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government	3029.80			Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 SHPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST . Rs 229276.00  
 EARNEST MONEY : Rs 4585.52  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Kharanmukh to Dhajji mindra road Km 0/00 to 5/500

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	1993.70			Per cubic metre	
<i>Total :-</i>						

  
 Executive Engineer,  
 Bharamour Division,  
 P.P.P.V.D Bharamour


SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 302174.00  
 EARNEST MONEY : Rs 6043.48  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Dhakog to Badgram road Km 0/00 to 20/500

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	Unit	Amount	RATES	
					Fig	Words
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government	2627.60	Cubic metres	Per cubic metre		
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 BHPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 330407.00  
 EARNVEST MONEY : Rs 6608.14  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Machhatter to Garima Via Siur road Km 0/00 to 1/1/500

**SUB-HEAD :-** Removal of slips and boulder at various RD's

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2873.10	Cubic metres		Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharnour Division,  
 APPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 253449.00  
 EARNEST MONEY : Rs 5068.98  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Pilli to Suai road km 0/00 to 5/490

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2203.90		Cubic metres	Per cubic mete	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharnour Division,  
 KMPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 235928.00  
 EARNEST MONEY : Rs 4718.56  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Beyoti to Sanj road km 0/00 to 5/670

**SUB-HEAD :-** Removal of slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	2051.55			Cubic metres	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      495429.00  
 EARNEST MONEY      Rs      10000.00  
TIME LIMIT      **THREE MONTHS**

**NAME OF WORK :** Restoration of rain damage on KSPA road Km 0/00 to 13/00

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4308.08	Cubic metres		Per cubic metre	
<b>Total :-</b>						

  
**Executive Engineer,**  
**Bharmour Division,**  
**HPPWD Bharmour**



**SCHEDULE OF QUANTITY**

ESTIMATED COST                      Rs                      199772.00  
 EARNEST MONEY                    Rs                      4000.00  
 TIME LIMIT                            THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Surge Shaft to Arki Road KM 0/00 to 1/700

**SUB-HEAD :-** Removal os slips and boulder at various RD's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Engineer-in-Charge. The rate including octroi, Makhana, toll tax, GST or other taxes imposed by the Government.	1737.15			Cubic metres Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour



**SCHEDULE OF QUANTITY**

ESTIMATED COST . Rs 499400.00  
 EARNEST MONEY : Rs 9988.00  
 TIME LIMIT One Month

**NAME OF WORK :** Restoration of rain damage on various roads under Holt Sub Division

**SUB-HEAD :-** Hiring of Hydraulic Excavator (JCB)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of Hydraulic Excavator having capacity of 0.9 cum (zero point nine) in working condition for removal of slips and boulders in all kind of soil including rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lift as per direction and entire satisfaction of Engineer-in-Charge as per day basis with 8(eight) hour per day and remove at least 25 cum quantity of slips per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner. Therepair and spare, watch and ward of excavator be borne by the contractor/owner. The daily logbook will be maintained at site, which should be verified by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	454.00			Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPVD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST . . . . . Rs 497277.00  
 EARNEST MONEY : . . . . . Rs 9945.54  
 TIME LIMIT . . . . . THREE MONTHS

**NAME OF WORK** Restoration of rain damage on various road under Bhammour Sub Division  
**SUB-HEAD :-** (Removal of slips at various RD's )

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government	4520.70			Per cubic metre	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bhammour Division,  
 HPPVD Bhammour




**SCHEDULE OF QUANTITY**

ESTIMATED COST : Rs 497607.00  
 EARNEST MONEY : Rs 9952.14  
 TIME LIMIT : One Month

**NAME OF WORK :** Restoration of rain damage on Sirdi to Ghared via Suppa road Km 0/00 to 9/500  
**SUB-HEAD :-** Removal of slips and boulders at Various Rds

Sl. No.	Description of work	Quantity	Hours	RATES		Unit	Amount
				Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5 m and lead upto 1000m as per technical specification 302.3 5 and 1611.1 as per the direction of Eengineer-in-Charge. The rate including octroi, Malkhana, toll tax, GST or other taxes imposed by the Government.	4523.70				Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 488400.00  
 EARNEST MONEY :- Rs 10000.00  
 TIME LIMIT THREE MONTHS

**NAME OF WORK** : Restoration of rain Damage on Bhamour Sub Division  
**SUB-HEAD** : - Hiring of JCB for removal of slips at various Rd's

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Hiring of JCB /Excavator cum loader for cutting /widening of road and removal of slips in all kinds of soil an disposal of all excavated earth up-un-serviceable material from the road surface up to all height and depths as per direction and entire satisfaction of Engineer-in-charge. Any loss to the public/private property or any incident etcetera happend during the course of hiring period/excavator owener, which shall to be fully compensated by the contractor in all cases. The fuel and operational staff for machine will be provided by the owener , repair and spare, watch and ward of the machine will also be borne by the contractor/owner. The daily log book will be maintained at site which shall be duly verified by the Engineer-in-charge. within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. .	407.00 Hour			Per Hours	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bhamour Division,  
 P.W.D., Bhamour

SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 99600.00  
 EARNEST MONEY : Rs 1992.00  
 TIME LIMIT : One Month

**NAME OF WORK :** A/R & M/O Various road under Rakh Sub-Division  
**SUB-HEAD :-** Hiring of Tractor for shifting of material

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
		Fig	Words	Fig	Words		
1	Hiring charge of tractor for shifting of material un-dressed stone muck/debrs. Through mechanically from different reaches as per the direction Engineer in Charge with in all leads and lifts and other incidentals including all mechanical and operational charges. The rate including octroi, royalty, Malkana, toll tax sale tax, GST or other taxes imposed by the Government.	166.00	Hours			Per Hour	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharnour Division,  
 GHPWD Bharnour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      409853.00  
 EARNEST MONEY      Rs      8197.06  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Partii to Bhamani via Malkona road Km 0/00 to 5/00 (Under PDNA)

**SUB-HEAD :-** C/o R/Wall at PDNA Rd 0/680 to 0/741 (Portion 2/778 to 2/785, 50)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) ches ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including cartage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.88 Cubic metres			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORP specifications Clause 802, 803, 1202 & 1203 1.4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including cartage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	55.35 Cubic metres			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including cartage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.53 Cubic metres			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including cartage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.00 Nos			Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bhamour Division,  
 HPPWD Bhamour



**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      482976.00  
 EARNEST MONEY      Rs      9659.52  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Bhamour to Hadsar road Km 0/0 to 12/00 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/Wall at PDNA RD 11/1/35 to 11/4/85 (Portion 1/590 to 1/597.50)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work, jumper work, blasting work (soft or hard rock) ches ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.18			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.33			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.98			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.00			Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bhamour Division,  
 HPPWD Bhamour



**SCHEDULE OF QUANTITY**

ESTIMATED COST                      Rs                      273586.00  
 EARNEST MONEY                      Rs                      5471.72  
 TIME LIMIT                                      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Hadsar to Chobia road km 0/00 to 9/500 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/Wall at PDNA RD 7/040 to 7/130 (Portions/360 to 5/365)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soiling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.85	Cubic metres		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	36.90	Cubic metres		Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.15	Cubic metres		Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.00	Nos		Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST                      Rs                      494853.00  
 EARNEST MONEY                      Rs                      9897.06  
 TIME LIMIT                                      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Thalla to chobia road Km 0/00 to 13/500 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/W/all at PDNA RD 12/500 to 12/530 (Portion 13/00 to 13/009)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work, jumper work, blasting work (soft or hard rock), chess ling saturated soling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.45			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement iso four sand iso eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.42			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	15.03			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	38.00			Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPVD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      327507.00  
 EARNEST MONEY      Rs      6550.14  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Hadsar to Chobha road km 0/00 to 9/500 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/Wall at PDNA RD 7/040 to 7/130 (Portions/5/360 to 5/365)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.46			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORP specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	44.28			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - In-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.12			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.00			Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- Rs 463391.00  
 EARNEST MONEY :- Rs 9267.82  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Hadsar to Kugdi road Km 0/00 to 13/00 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/Wall at PDNA RD 4/840 104/860 (Portion 4/747 to 4/754)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including cartage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.12			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including cartage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	63.06			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including cartage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.12			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1%. 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including cartage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.00			Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- Rs 485123.00  
 EARNEST MONEY :- Rs 9702.46  
 TIME LIMIT THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Hadsar to Kugti road Km 0/00 to 13/00 (Under PDNA)  
**SUB-HEAD :-** C/o PCC R/Wall at PDNA RD 4/840 to 4/860 (Portion 5/330 to 5/337.50)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount	
			Fig	Words			
1	Excavation in earth work in all kinds of soil such as pick work, jumper work, blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.40			Cubic metres	Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORC specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.33			Cubic metres	Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.78			Cubic metres	Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	32.00			Nos	Each	
<b>Total :-</b>							

  
 Executive Engineer,  
 Bharmour Division,  
 HPPW/D Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      490818.00  
 EARNEST MONEY      Rs      9816.36  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Thalia to Chobia road Km 0/00 to 13/500 (Under PDNA)  
**SUB-HEAD :-** (SH.- C/o PCC R/Wall at PDNA RD 4/190 to 4/458 (Portion 0/842 to 0/857))

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28.93	Cubic metres		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORO specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement six four sand six eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.01	Cubic metres		Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.74	Cubic metres		Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	36.00	Nos		Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPW/D Bharmour

SCHEDULE OF QUANTITY

ESTIMATED COST      Rs      490818.00  
 EARNEST MONEY      Rs      9816.36  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Thalia to Chobia road Km 0/00 to 13/500 (Under PDNA)  
**SUB-HEAD :-** (SH.- C/o PCC R/Wall at PDNA RD 4/190 to 4/458 (Portion 0/858 to 0/874.50)

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in earth work in all kinds of soil such as pick work jumper work blasting work (soft or hard rock) ches ling saturated soiling upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charges. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28.93			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORR specifications Clause 802, 803, 1202 & 1203 1.4.8 (One cement isto four sand isto eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.01			Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - In-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.74			Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	36.00			Each	
<b>Total :-</b>						


  
 Executive Engineer,  
 Bharmour Division,  
 HPPWD Bharmour

**SCHEDULE OF QUANTITY**

ESTIMATED COST      Rs      491011.00  
 EARNEST MONEY      Rs      9820.22  
 TIME LIMIT      THREE MONTHS

**NAME OF WORK :** Restoration of rain damage on Thalla to Chobia road Km 0/00 to 13/500 (Under PDNA)  
**SUB-HEAD :-** (SH - C/o PCC R/Wall at PDNA RD 4/190 to 4/458 (Portion 0/871 to 0/882.50)

Sl. No.	Description of work	Quantity	Unit	RATES		Amount
				Fig	Words	
1	Excavation in earth work in all kinds of soil such as pick work, jumper work, blasting work (soft or hard rock) chess ling saturated soil upto all depths and disposal of all surplus material as directed by the Engineer-in-Charge including carriage of material within all leads and lift and as per the direction of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	29.48	Cubic metres		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORP specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement 150 four sand 150 eight graded/crushed stone aggregate 20mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	65.01	Cubic metres		Per cubic metre	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.74	Cubic metres		Per cubic metre	
4	Providing weep holes in brick/ stone / plain reinforced concrete abutment, wing wall, return walls with 100 mm dia PVC pipe extending through the full width of the structure with slope of 1V: 20H towards drawing face complete as per drawing and technical specifications clauses 614, 709 and 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	36.00	Nos		Each	
<b>Total :-</b>						

  
 Executive Engineer,  
 Bharmour Division,  
 HPPVD Bharmour