

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed Percentage rates tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **24.10.2025 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM** & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **23.10.2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1.	RRD on Sain to Chhani road Km. 0/00 to 2/00/ (SH:- Improvement of gradient in Km 0/050 to 0/170). Under PDNA 2023	Rs 1,24,617.00	Rs 2,500.00	350	One Month
2.	R/R Damages on Deodhar Kheelgaloo road km. 0/00 to 24/500).(SH- C/O D/S toe wall and wing wall to 900mm dia RCC hume culvert at Rd 10/190 dia Under PDNA-2023	Rs 1,53,916.00	Rs 3,100.00	350	One Month
3.	RRD On Kun Galoo to Harizan Basti Padhar road km. 0/00 to 1/500.(SH- C/O 1200 mm dia rcc hume pipe culvert along with both side wing wall at Rd 0/290) Under PDNA	Rs 4,82,191.00	Rs 9,700.00	350	One Month
4.	RRD on Kun Galoo to Harizan Basti Padhar road km. 0/00 to 1/500. (SH- C/O 1200mm dia rcc Hume pipe culvert along with both side wing wall at Rd 1/330) Under PDNA	Rs. 4,80,635	Rs 9000.00	350	One Month
5.	RRD on Kun galo to Baroha Ropa Matyal road km. 0/00 to 2/800.(SH- C/O 1200 mm dia rcc Hume pipe culvert along with both side wing wall at Rd 1/170) Under PDNA	Rs 4,80,014.00	Rs 9,000.00	350	One Month
6.	RRD on Kun galoo to Harizan Basti Padhar road km. 0/00 to 1/500. (SH- C/O 1200MM dia rcc hume pipe culvert along with both side wing wall at Rd 0/870) Under PDNA	Rs 4,83,626.00	Rs 9,700.00	350	One Month
7.	RRD on Kun galoo to Harizan Basti Padhar road km. 0/00 to 1/500. (SH- C/O 1200mm dia RCC hume pipe culvert along with both side wing wall at Rd 0/694) Under PDNA	Rs 4,83,626.00	Rs 9,700.00	350	One Month
8.	RRD Damages on Jablahi Nallah to Barnota Karkoh road km. 0/00 to 5/500. (SH- C/o balance work of R/wall in wire crate at Rd 0/359 to 0/374.85) Under PDNA 2023	Rs 1,98,544.00	Rs 4,000.00	350	One Month
9.	RRD on Kun galoo to Harizan Basti Padhar road km. 0/00 to 1/500. (SH- C/O 1200MM dia RCC Hume pipe culvert along with both side wing wall at Rd 1/170) Under PDNA	Rs 4,80,014.00	Rs 9,600.00	350	One Month
10.	R.R. Damages on Kotli Kun Ka Tar road Km 70/600 to 85/00.(SH :- C/O U-shape drain in Km 84/800 to 84/840) Under PDNA-2023	Rs 2,02,401.00	Rs 4,100.00	350	One Month
11.	RRD on Kun Galoo to Harizan Basti Padhar road km. 0/00 to 1/500 (SH- C/O 1200mm Dia RCC Hume pipe culvert along with both side wing wall at Rd 0/680) Under PDNA	Rs 4,84,207.00	Rs 9,700.00	350	One Month
12.	R.R.Damages on Bindrawani Majhwar road km 0/00 to 19/800.(SH- C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at 14/470) under PDNA-2023	Rs 2,78,759.00	Rs 5,600.00	350	One Month
13.	RRD on Anna Kenchi to Kushmal road Km. 0/00 to 8/080/ (SH- C/O R/wall 6/450 to 6/457). Under PDNA 2023	Rs 3,01,342.00	Rs 6,100.00	350	One Month

14.	RRD on Khalanoo to Mahan road km. 0/00 to 2/800. (SH:- C/O R/Wall at Rd 2/630 to 2/640 Under PDNA 2023	Rs 2,83,405.00	Rs 5,700.00	350	One Month
15.	R/R Damages on Deodhar Kheelgaloo road km. 0/00 to 24/500).(SH- C/O wire crate R/wall with PCC Toe wall at RD. 18/290 to 18/305) (portion Batahar to Batahan) Under PDNA-2023).	Rs 3,01,605.00	Rs 6,100.00	350	One Month
16.	RRD on Khalanoo to Mahan road km. 0/00 to 2/800.(SH:- C/O PCC R/wall at Rd 0/920 to 0/935 Under PDNA 2023	Rs 4,62,230.00	Rs 9,300.00	350	One Month
17.	RRD Damages on Kun to Kot road km. 0/00 to 2/800. (SH- P/L interlocking paver at Rd 1/470 to 1/500). Under PDNA 2023	Rs 3,04,332.00	Rs 6,100.00	350	One Month
18.	R.R.Damages on Bindrawani Majhwar Road km 0/00 to 19/800.(SH- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 15/450) Under PDNA 2023)	Rs 3,21,881.00	Rs 6,500.00	350	One Month
19.	RRD on Bindrawani Majhwar road km 0/00 to 19/800 (SH- C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 16/380) Under PDNA 2023	Rs 3,24,769.00	Rs 6,500.00	350	One Month
20.	R.R.Damages on Bindrawani Majhwar road km 0/00 to 19/800. (SH- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 19/230) Under PDNA 2023)	Rs 3,26,817.00	Rs 6,600.00	350	One Month
21.	RRD on Kahlanoo to Mahan road km. 0/00 to 2/800. (SH:- C/O PCC R/Wall at Rd 2/670 to 2/680 under PDNA 2023)	Rs 2,18,526.00	Rs 4,400.00	350	One Month
22.	R.R.Damages on Bindrawani Majhwar road km. 0/00 to 19/800. (SH:- C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 15/650) Under PDNA 2023	Rs 3,72,565.00	Rs 7,500.00	350	One Month
23.	R.R.Damages on Bindrawani Majhwar road km. 0/00 to 19/800.(SH- C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 15/310) Under PDNA 2023)	Rs 3,81,797.00	Rs 7,700.00	350	One Month
24.	RRD on Khalanoo to Mahan road km. 0/00 to 2/800. (SH:- C/O PCC R/wall at Rd 1/115 to 1/130 under PDNA 2023	Rs 3,23,651.00	Rs 6,500.00	350	One Month
25.	R.R.Damages on Bindrawani Majhwar road km. 0/00 to 19/800. (SH-C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 17/800) Under PDNA 2023)	Rs 4,42,109.00	Rs 7,500.00	350	One Month
26.	RRD on Bindrawani Majhwar road km 0/00 to 19/800.(SH- C/O 900mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 14/230) Under PDNA 2023	Rs 4,42,109.00	Rs 8,900.00	350	One Month
27.	RRD on Khalanoo to Mahan road km. 0/00 to 2/800. (SH:- C/O wire crate R/wall at Rd 1/620 to 1/632 under PDNA 2023)	Rs 3,95,471.00	Rs 8,000.00	350	One Month
28.	R.R.Damages on Bindrabani Majhwar Kotmorse Moviseri road Km 0/00 to 19/800.(SH C/O wire crate R/wall at Rd 17/740 to 17/755) Under PDNA 2023	Rs 4,64,186.00	Rs 9,300.00	350	One Month
29.	RRD on Khalanoo to Mahan road km. 0/00 to 2/800. (SH:- C/O Wire Crate R/wall at Rd 1/600 to 1/615 Under PDNA 2023).	Rs 3,93,672.00	Rs 7,900.00	350	One Month
30.	RRD Damages on Roda Nallah Karkoh road km. 0/00 to 12/300. (SH- Construction of R/wall in PCC at RD. 6/140 to 6/152 and 6/315 to 6/327). Under PDNA 2023	Rs 4,72,935.00	Rs 9,500.00	350	One Month
31.	R.R Damages on Rada Nallah to Dhandal road km. 0/00 to 2/900).(SH- C/O V-shape drain at various Rds) Under PDNA-2023	Rs 4,76,531.00	Rs 9,600.00	350	One Month
32.	R.R.D on Khalanoo to Mahan road km. 0/00 to 2/800. (SH:- C/o wire crate R/wall at Rd 1/390 to 1/410 under PDNA 2023	Rs 3,67,502.00	Rs 7,400.00	350	One Month

CERTIFICATE

Certified that the work mentioned above under PDNA-2023 is of **urgent nature** and is **essential for public safety / restoration of infrastructure** damaged due to a natural disaster.

The work is being proposed in accordance with **Notification No. PWD-B-A0(3)/8/2025-300858 dated 09.10.2025**, issued by the **Government of Himachal Pradesh, Public Works Department**, which permits **offline tendering without press notice for works up to ₹5.00 lakh**.

Tender Notice – Terms & Conditions

The tender documents shall be issued only to those Contractors/Firms who submit the following documents along with their application:

1. Valid enlistment/registration of contractor in the appropriate class.
2. Permanent Account Number (PAN).
3. GST Registration Number.
4. Earnest money in the shape of National Saving Certificate/Time Deposit Account in any Post Office in Himachal Pradesh, or F.D.R. from any Nationalized Bank duly pledged in favour of the Executive Engineer, Mandi Division No. 2, HPPWD, Mandi H.P.
5. Earnest money and cost of tender form for the above works must be submitted along with the application for purchase of tender form. Applications received without earnest money and cost of tender form shall be summarily rejected.
6. The offer of the tender shall remain valid for 75 (seventy-five) days after the opening of the tender.
7. Ambiguous, telephonic, conditional tenders or tenders submitted by fax/e-mail shall not be considered and will be summarily rejected.
8. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reason.
9. If the date specified above happens to be a holiday, the tenders shall be processed on the next working day.
10. The Contractor/Firm must quote their rates both in words as well as in figures, failing which the Executive Engineer reserves the right to accept or reject any or all tenders.
11. Tender forms shall not be issued to those Contractors/Firms whose past performance is not found satisfactory or who have failed to complete previously awarded works within the stipulated period.
12. No contractor shall have more than two major works in hand at a time.
13. The work shall be completed by the Contractor within the stipulated period.

No.PW-MDII-CB NIT (off line) /2025-

11546-60

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A. E, S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

Dated: - 13 / 10 / 2025

Executive Engineer
Mandi Division No.II
HP.PWD Mandi

283

Estimated Cost :- 1,24,617/-
 Earnest Money:- 2,500/-
 Time:- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- RRD on Sain to Chhani road Km. 0/00 to 2/00/ (SH:- Improvement of gradient in Km 0/050 to 0/170). Under PDNA 2023

Contract No. :
 Name of the Bidder/
 Bidding Firm/
 Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	Item Description	NUMBER #	Quantity	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes including GST in Rs. p	NUMBER #	TOTAL AMOUNT With all Taxes excluding GST in Rs. p	TEXT #	TOTAL AMOUNT with all Taxes including GST in Words
1	2	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specification clause 1603.1 & 1603.2 sorting out useful/un useful materials and stacking the same in all leads and lift and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and leveling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required). Recovery for useful stone of 3,319 cubic metre @ Rs. 300/- per cubic metre amounting to Rs. 9,956/- only, shall be done on pro-rata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect. Including all leads and lift of materials and as per direction of Engineer-in-charge.	3	414.85	4	Per Cubic metre	5	300.39	6	1,24,617.00	7	Rupees One Lakh Twenty Four Thousand Six Hundred Seventeen Only
Total										1,24,617.00		Rupees One Lakh Twenty Four Thousand Six Hundred Seventeen Only

DNT amount approved for Rs 1,24,617/- only

Quoted Rate in Figures :
 Quoted Rate in words :

Executive Engineer,
 Mandi Division No. II,
 HP.PWD, Mandi

517

Estimated Cost Rs. 1,53,916/-
Earnest Money Rs. 3,100/-
Time: One month

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No-II HPPWD Mandi
Name of work : R/R Damages on Doodhar Kheedgaloo Road Km. 0/00 to 24/5001 (SH: C/O D/S toe wall and wing wall to 900 mm dia RCC hume culvert at Rd 10/190 dia Under PDNA-2023)

NUMBER #	TEXT #	PRICE SCHEDULE	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
S. No	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST In Words	

1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	3	Per Cubic Metre	609.90	6,819.00	Rupees Six Thousand Eight Hundred Nineteen Only
2	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3.61	Per cubic metre	5,792.25	20,910.00	Rupees Twenty Thousand Nine Hundred Ten Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	19.65	Per Cubic Metre	5,320.75	1,04,553.00	Rupees One Lakh Four Thousand Five Hundred Fifty Three Only
4	Providing weep holes in block masonry / stone masonry / plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals.	12.00	Each	365.00	4,380.00	Rupees Four Thousand Three Hundred Eighty Only
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	5.04	Per Cubic Metre	1,607.60	8,102.00	Rupees Eight Thousand One Hundred Two Only
6	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	2.50	Per Running metre	3,660.65	9,152.00	Rupees Nine Thousand One Hundred Fifty Two Only
Total					1,53,916.00	Rupees One Lakh Fifty Three Thousand Nine Hundred Sixteen Only

Quoted Rate in Figures :
Quoted Rate in words :

Boa amount approved for Rs 1,53,916/- only

2

Executive Engineer,
Mandi Division No. II,
HP, PWD, Mandi.

606

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Kun Galoo to Harizan Basti Padhar road Km. 0/00 to 1/500. (SH.- C/O 1200 MM DIA rec HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD
 0/290) under PDNA
 Contract No. :

Percentage of BoQ
 Estimated Cost :- 4.82,191/-
 Earnest Money :- 9700/-
 Time :- One Month

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	NUMBER #	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes including GST in Rs. p	TOTAL AMOUNT With all Taxes including GST in Rs. p	TEXT #	TOTAL AMOUNT with all Taxes including GST in Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per	3	4	Per Cubic Metre	5	609.10	6	7	Rupees Twenty Seven Thousand Three Hundred Twenty Four Only
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge	2.73		Per Cubic Metre		3883.50	16,062.00		Rupees Sixteen Thousand Sixty Two Only
3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar 1:4 (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge	10.99		Per cubic metre		7846.34	86,231.00		Rupees Eighty Six Thousand Two Hundred Thirty One Only
4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge	0.71		Per cubic metre		4790.80	3,401.00		Rupees Three Thousand Four Hundred One Only
5	Providing and laying 1200mm dia (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals	5.00		Per running metre		6707.20	33,536.00		Rupees Thirty Three Thousand Five Hundred Thirty Six Only
6	Providing and laying 1:6:12(One cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge	5.12		Per Cubic Metre		5026.90	25,738.00		Rupees Twenty Five Thousand Seven Hundred Thirty Eight Only

3

7	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Four Thousand Five Hundred Seventy
8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty Seven Only
9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3,7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of	6.00	Each	365.10	2,191.00	Rupees Two Thousand Hundred Ninety One Only
Total					4,82,191.00	Rupees Four Lakh Eighty Two Thousand One Hundred Ninety One Only
Quoted Rate in Figures :						
Quoted Rate in words:						

BO & approved for Rs 4,82,191/-

Executive Engineer,
Mandi Division No. II.,
H.P.W.D. Mandi.

607

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work : RRD on Kun galoo to Harizan Basti Padhar road Km. 0/00 to 1/500. (SH. C/O 1200 MM DIA rcc HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD
 1/330) under PDNA
 Percentage of BoQ

Estimated Cost :- 4,80,635/-
 Earnest Money:- 9,000/-
 Time:- One Month

Contract No. :

Name of the Bidding Firm/ Company :

Sl. No.	Item Description	PRICE SCHEDULE						
		NUMBER #	TEXT #	Quantity	Unit	NUMBER #	TOTAL AMOUNT	TEXT #
						Estimate Rate with all taxes including GST in Rs. P	With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST In Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per	2	3	4	5	6	7	
				Per Cubic Metre	609.10	25,533.00	Rupees Twenty Five Thousand Five Hundred Thirty	
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2	2	Per Cubic Metre	5883.50	16,297.00	Rupees Sixteen Thousand Two Hundred Ninety	
3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar 1:4 (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	3	Per cubic metre	7846.34	86,231.00	Rupees Eighty Six Thousand Two Hundred Thirty One Only	
4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4	4	Per cubic metre	4790.80	3,401.00	Rupees Three Thousand Four Hundred One Only	
5	Providing and laying 1200mm dia (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1408 including carriage of materials with in all leads, lifts and other incidentals	5	5	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Three Hundred Thirty Six Only	
6	Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts	6	6	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Seven Hundred Thirty	
7	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	7	7	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Thousand Four Five Hundred Seventy	

8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty Seven Only
9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of	6.00	Each	365.10	2,191.00	Rupees Two Thousand One Hundred Ninety One Only
Total					4,80,635.00	Rupees Four Lakh Eighty Thousand Six Hundred Thirty Five Only

Quoted Rate in Figures :
Quoted Rate in words:

Executive Engineer,
Mandi Division No.II.,
P.P.W.D. Mandi.

Rs. 4,80,635/-
for Rs. 4,80,635/-

618

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work : RRD on Kun galoo to Baroha Rop Matyal road Km. 0/00 to 2/800. (SH. C/O 1200 MM DIA rcc HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT Rd 1/170)

Percentage of BoQ

Estimated Cost :- 4,80,014/-
 Earnest Money:- 9,000/-
 Time:- One Month

PDMA

Name of the Bidder/ Bidding Firm/ Company :		PRICE SCHEDULE	
Contract No. :			

NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.			Quantity	Unit	Estimate Rate with all taxes excluding GST In Ra. P	TOTAL AMOUNT With all Taxes excluding GST In Ra. P	TOTAL AMOUNT with all Taxes excluding GST In Words	
1	2	Search work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	4	5	6	7	
			40.90	Per Cubic Metre	609.10	24,912.00	Rupees Twenty Four Thousand Nine Hundred Twelve Only	
2		Providing and laying 1.4:8:1 (One cement : four sand : eight graded stone aggregate 40mm [Forty millimetre nominal size] concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2.77	Per Cubic Metre	5883.50	16,297.00	Rupees Sixteen Thousand Two Hundred Ninety Seven Only	
3		Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar (1:4) (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge.	10.99	Per cubic metre	7846.34	86231.25	Rupees Eighty Six Thousand Two Hundred Thirty One Only	
4		Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	0.71	Per cubic metre	4799.80	3,401.00	Rupees Three Thousand Four Hundred One Only	
5		Providing and laying 1200mm dia (twelve hundred millimetre) reinforced concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	5.00	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Five Hundred Thirty Six Only	
6		Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm [Forty millimetre nominal size] concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	5.12	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Seven Hundred Eight Only	
7		Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge.	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Thousand Four Hundred Seventy Seven Only	
8		Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand Three Hundred Seventy Seven Only	

5

9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	6.00	Each	365.10	2,191.00	Rupees Thousand Hundred Ninety One Only	Two One
Total					4,80,014.00	Rupees Four Lakh Eighty Thousand Fourteen Only	

Quoted Rate in Figures :
Quoted Rate in words:

DHA amount approved for Rs. 4,80,014 only

Executive Engineer,
Mandi Division North,
MPPWD, Mandi.

608

Percentage of BOD

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Kun galoo to Harizan Basti Padnar road Km. 0/00 to 1/500. (SH. C/O 1200 MM DIA rec HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD
 0/870) under PDNA

Contract No. :

Estimated Cost :- 4 83 626/-
 Earnest Money :- 9,700/-
 Time :- One Month

Name of the Bidder/
 Bidding Firm/
 Company :

NUMBER # Sl. No.	TEXT # Item Description	PRICE SCHEDULE					TEXT # TOTAL AMOUNT with all Taxes including GST in Words
		NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Rs. p	NUMBER # TOTAL AMOUNT with all Taxes including GST in Rs. p	TEXT # TOTAL AMOUNT with all Taxes including GST in Words	
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per specifications Clause 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	46.83	Per Cubic Metre	609.10	28,524.00	Rupees Twenty Eight Thousand Five Hundred Twenty	
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specifications clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2.77	Per Cubic Metre	5883.50	16,297.00	Rupees Sixteen Thousand Two Hundred Ninety Seven Only	
3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar (1:4) (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge.	10.99	Per cubic metre	7846.34	86,231.00	Rupees Eighty Six Thousand Three Hundred Thirty One Only	
4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	0.71	Per cubic metre	4790.80	3,401.00	Rupees Three Thousand Four Hundred One Only	
5	Providing and laying 1200mm dia. (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals	5.00	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Hundred Thirty Six Only	
6	Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	5.12	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Hundred Thirty Eight Only	

6

8	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Thousand Five Hundred
9	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty Seven Only
	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of	6.00	Each	365.10	2,191.00	Rupees Two Hundred Ninety One Only
Total					4,83,626.00	Rupees Four Lakh Eighty Three Thousand Six Hundred Twenty Six

Quoted Rate in Figures :
Quoted Rate in words:

500 award for Rs 483626/-

Executive Engineer,
Mandi Division No. II,
H.P. PWD, Mandi.

609

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Kun galoo to Harizan Basti Padhar road Km. 0/00 to 1/500 (SH:- C/O 1200 MM DIA rec HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD
 0/694) under PDNA
 Percentage of BoQ
 Estimated Cost :- 4,83,626/-
 Earnest Money :- 9700/-
 Time :- One Month

Contract No. :
 Name of the Bidder/
 Bidding Firm/
 Company :

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. p	TOTAL AMOUNT With all Taxes including GST in Rs. p	TOTAL AMOUNT with all Taxes including GST in Words
Sl. No.	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per	46.83	Per Cubic Metre	609.10	28,524.00	Rupees Twenty Eight Thousand Five Hundred Twenty
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2.77	Per Cubic Metre	5883.50	16,297.00	Rupees Sixteen Hundred Ninety Seven Only
3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar (1:4) (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge.	10.99	Per cubic metre	7846.34	86,231.00	Rupees Eighty Six Thousand Two Hundred Thirty One Only
4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	0.71	Per cubic metre	4790.80	3,401.00	Rupees Three Thousand Four Hundred One Only
5	Providing and laying 1200mm dia (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause- 1108 including carriage of materials with in all leads, lifts and other incidentals	5.00	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Five Hundred Thirty Six Only
6	Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm and-curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	5.12	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Seven Hundred Thirty Eight Only

7

7	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Four Thousand Five Hundred Seventy
8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty Seven Only
9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of	6.00	Each	365.10	2,191.00	Rupees Two Hundred Ninety One Only
Total					4,83,626.00	Rupees Four Lakh Eighty Three Thousand Six Hundred Twenty Six

Quoted Rate in Figures :
Quoted Rate in words:

1502 approval for no 583626/-

Executive Engineer,
Mandi Division No. II.,
P.W.D. Mandi.

525

Contract No. : _____
 Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- R.R.Damages on Jablahi Nallah to Barnota Karkoh Road Km. 0/0 to 5/500. (SH:- C/O balance work of R/wall in wire
 crate at Rd 0/359 to 0/374.85). Under PDNA-2023

Percentage of BOQ _____
 Estimated Cost :- 1,98,544/-
 Earnest Money:- 4,000/-
 Time:- One Month

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns,
 else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. p	TOTAL AMOUNT with all Taxes excluding GST in Rs. p	TOTAL AMOUNT with all Taxes excluding GST in Words
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
1	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.	54.53	Per cubic metre	3,641.00	1,98,544.00	Rupees One Lakh Ninety Eight Thousand Five Hundred Forty Four
Total:-						Rupees One Lakh Ninety Eight Thousand Five Hundred Forty Four Only

800 approved for 1,98,544/-

[Signature]
 Executive Engineer,
 Mandi Division No.II,
 H.P.W.D. Mandi.

8

Estimated Cost :- 4,80,014/-
 Earnest Money:- 9600/-
 Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- RRD on Kun galoo to Harizan Basti Padhar road Km. 0/00 to 1/500. (SH:- C/O 1200 MM DIA rec HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD 1/170) under PDNA
 Percentage of BOD

Contract No. :
 Name of the Bidder/ Bidding Firm/ Company :

NUMBER # Sl. No.	TEXT # Item Description	PRICE SCHEDULE		NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Rs. P	NUMBER # TOTAL AMOUNT With all Taxes including GST in Rs. P	TEXT # TOTAL AMOUNT with all Taxes including GST in Words
		NUMBER #	TEXT #					
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305-1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per specifications Clause 305-1	2	3	40.90	Per Cubic Metre	609.10	24,912.00	Rupees Twenty Four Thousand Nine Hundred Twelve Only
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2	3	2.77	Per Cubic Metre	5883.50	16,297.00	Rupees Sixteen Thousand Two Hundred Ninety Seven Only
3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar (1:4) (One cement four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	4	10.99	Per cubic metre	7846.34	86,231.00	Rupees Eighty Six Thousand Three Hundred Thirty One Only
4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the direction of Engineer-in-charge.	4	5	0.71	Per cubic metre	4790.80	3,401.00	Rupees Three Thousand Four Hundred Only
5	Providing and laying 1200mm dia. (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals	5	6	5.00	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Three Hundred Thirty Six Only
6	Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	6	7	5.12	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Seven Hundred Thirty Eight Only
7	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	7	8	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Four Thousand Five Hundred Seventy

9

8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty Seven Only
9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3,7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer in charge.	6.00	Each	365.10	2,191.00	Rupees Two Thousand One Hundred Ninety One Only
Total					4,80,014.00	Rupees Four Lakh Eighty Thousand Fourteen Only
Quoted Rate in Figures :						
Quoted Rate in words:						

BOA approved for Mr. & Bhaiji
 G

Executive Engineer,
 Mandi Division No.11,
 P.W.D. Mandi.

580

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No-II HPPWD Mandi
 Name of work : R.R Damages on Kotli Kun Ka Tar road Km 70/600 to 85/00 (SH : C/O U-shape drain in Km 84/800 to 84/840) Under PDNA-2023

Estimated Cost :-2,02,401/-
 Earnest Money:-4,100/-
 Time:- One Month

PRICE SCHEDULE
 [This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only]

Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. p	TOTAL AMOUNT With all Taxes including GST in Rs. p	TOTAL AMOUNT with all Taxes including GST in Words	TEXT #
1		2					
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	12.00	Per cubic metre	609.90	7,319.00	Rupees Thousand Hundred Nineteen Only	7
3	Providing mechanically mixed and vibrated placed plain/reinforced concrete 1:2.5:5 (1 cement : 2 point five sand : 5 graded stone aggregate 20mm (Twenty millimetre) nominal size) in open foundations and curing complete as per drawing and MORC technical specification section 800, 1200 and clause 1604 including carriage of materials with in all leads, lifts and other incidentals as per the direction of Engineer-in-charge.	7.50	Per Cubic Metre	6,965.20	52,239.00	Rupees Fifty Thousand Hundred Thirty Nine Only	7
3	Providing Tor steel reinforcement for reinforced cement concrete work including bending, binding and placing in position and cost of binding wire complete upto floor all level including carriage of materials with in all leads, lifts and other incidentals or as per direction of Engineer-in-charge.	225.00	Per cubic metre	98.50	22,163.00	Rupees Twenty Thousand Hundred Sixty Three Only	7
5	Steel work welded-in-built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings framed guard bars, ladders, railing, brackets and similar works including carriage of materials with in all leads, lifts and other incidentals.	954.75	Per cubic metre	126.40	1,20,680.00	Rupees One Lakh Twenty Thousand Six Hundred Eighty Only	7
Total					2,02,401.00	Rupees Two Lakh Two Thousand Four Hundred One Only	

DA 1 amount approved for Rs. 202,401/- only

Quoted Rate in words:
 Quoted Rate in words:

Executive Engineer,
 Mandi Division No-II,
 H.P.W.D. Mandi.

Executive Engineer,
 Mandi Division No-II
 H.P.W.D. Mandi.

10

11

Percentage of BOD

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Kun galoo to Harizan Basti Padhar road Km. 0/00 to 1/500 (SH:- C/O 1200 MM DIA rec HUME PIPE CULVERT ALONG WITH BOTH SIDE WING WALL AT RD
 O/680) under PDNA

Estimated Cost :- 4,84,207/-
 Earnest Money:- 9700/-
 Time:- One Month

Contract No. :
 Name of the Bidder/
 Bidding Firm/
 Company :

PRICE SCHEDULE
 (The BOD template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns,
 The BOD template is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	SL No.	Item Description	NUMBER #	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	2	48.17	Per Cubic Metre	609.10	29,340.00	Rupees Twenty Nine Thousand Three Hundred Forty Only
2	2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	2.73	Per Cubic Metre	5883.50	16,062.00	Rupees Sixteen Thousand Sixty Two Only
3	3	Stone masonry in cement mortar in foundation complete as drawing and technical specification clauses 702, 704, 1202 and 1204 in cement mortar (1:4) (One cement : four sand) Coursed rubble masonry (2nd sort) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-charge.	4	10.99	Per cubic metre	7846.34	86,231.00	Rupees Eighty Six Thousand Two Hundred Thirty One Only
4	4	Providing and laying dry flooring with rubble stone as per drawing and technical specifications clause 1303.3 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	5	0.71	Per cubic metre	4790.80	3,401.00	Rupees Three Thousand Four Hundred One Only
5	5	Providing and laying 1200mm dia (twelve hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals	6	5.00	Per running metre	6707.20	33,536.00	Rupees Thirty Three Thousand Five Hundred Thirty Six Only
6	6	Providing and laying 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7	5.12	Per Cubic Metre	5026.90	25,738.00	Rupees Twenty Five Thousand Seven Hundred Thirty Eight Only

7	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar 1:6 (One cement : six sand) including carriage of materials with in all lead, lifts and other incidentals as per direction of Engineer-in-Charge.	27.84	Per Cubic Metre	6270.50	1,74,571.00	Rupees One Lakh Seventy Four Thousand Five Hundred Seventy
8	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in charge.	26.94	Per Cubic Metre	4199.60	1,13,137.00	Rupees One Lakh Thirteen Thousand One Hundred Thirty
9	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of	6.00	Each	365.10	2,191.00	Rupees Two Thousand One Hundred Ninety One
Total					4,84,207.00	Rupees Four Lakh Eighty Four Thousand Seven
Quoted Rate in Figures :						
Quoted Rate in words:						

Executive Engineer,
Mandi Division No.II.,
HP.PWD, Mandi.

773

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandl Division No.II HPPWD Mandl

Name of work :- R.R.Damages on Bindrabani Majhwar road Km 0/00 to 19/800,SH :- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 14/470) Under PDNA-2023

Estimated Cost :- 2,78,759/-
 Earnest Money:-56,00/-
 Time:- One Month


PRICE SCHEDULE
 [This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only]

Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	TEXT #	Quantity	Unit	Estimate Rate with all taxes including GST in Ru. p	TOTAL AMOUNT With all Taxes including GST in Ru. p	TOTAL AMOUNT with all Taxes including GST in Words	TEXT #
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	3	Per Cubic Metre	198.60	1,204.00	Rupees One Thousand Two Hundred Four	7
2	Earth work in excavation in all leads of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	59.05	Per cubic metre	609.90	36,015.00	Rupees Thirty Six Thousand Fifteen Only	
3	Providing and laying 15:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	26.48	Per cubic metre	5,320.70	1,40,892.00	Rupees One Lakh Forty Thousand Eight Hundred Ninety Two Only	
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	9.00	Per Tonne	6,451.75	58,066.00	Rupees Fifty Eight Thousand Sixty Six Only	
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00	Rupees Thirty Two Thousand Eight Hundred Fifty Eight Only	
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	10.00	Per Cubic Metre	365.00	3,650.00	Rupees Three Thousand Six Hundred Fifty Only	

12

7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	3.78	Per cubic metre	1,607.00	6,074.00	Rupees Six Thousand Seventy Four Only
	Total				2,78,759.00	Rupees Two Lakh Seventy Eight Thousand Seven Hundred Fifty Nine Only
Quoted Rate in words:						
Quoted Rate in words:						

BOB approved for Rs. 2,78,759/- only.


 Executive Engineer,
 Mandi Division No-II
 HP.PWD, Mandi.

582

Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST in Words
---------	------------------	----------	------	---	--	--

Estimated Cost :- 3,01,342/-
 Earnest Money :- 6,100/-
 Time :- One Month

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Anna Kanchi to Kushmal road Km. 0/00 to 8/080/ (SH:- C/O R/wall 6/450 to 6/457), Under PDVA 2023

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	20.02	Per Cubic Metre	609.90	12,210.00	Ruppes Twelve Thousand Two Hundred Ten Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	49.98	Per Cubic Metre	5311.65	2,65,476.00	Ruppes Two Lakh Sixty Five Thousand Four Seventy Six Only
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall, with 40mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing/face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	21.00	Each	365.30	7,671.00	Ruppes Seven Thousand Six Hundred Seventy Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	9.80	Per Cubic Metre	1631.10	15,985.00	Ruppes Fifteen Thousand Eighty Five Only
Total					3,01,342.00	Ruppes Three Lakh One Thousand Three Hundred Forty Two Only

DAVT amount approved for Rs. 3,01,342/- only

Executive Engineer,
 Mandi Division No. II,
 HP, PWD, Mandi

19

605

Percentage of BOQ

Estimated Cost :- 2,83,405/-
Earnest Money :- 5,700/-
Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
Name of work :- RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH: C/O PCC R/wall at Rd 2/630S to 2/640 under PDNA 2023)
Contract No. :

NUMBER #	TEXT #	Item Description	NUMBER #	Quantity	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes including GST in Rs. P	NUMBER #	TOTAL AMOUNT With all Taxes including GST in Rs. P	TEXT #	TOTAL AMOUNT with all Taxes including GST in Words
1	2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	19.80	4	Per Cubic Metre	5	609.10	6	12,060.00	7	Rupees Twelve Thousand Sixty Only
2	4	Providing and laying 1:5:10 (One-cement Five sand ten graded stone aggregate 40mm Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.		46.70		Per Cubic Metre		531.65		2,48,054.00		Rupees Two Lakh Forty Eight Thousand Fifty Four Only
3	4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204, 3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.		20.00		Each		365.30		7,306.00		Rupees Seven Thousand Three Hundred Six Only
4	4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.		9.80		Per Cubic Metre		1631.10		15,985.00		Rupees Fifteen Thousand Nine Hundred Eighty Five
Total										2,83,405.00		Rupees Two Lakh Eighty Three Thousand Four Hundred Five Only

Quoted Rate in Figures :
Quoted Rate in words :

BOQ approved Rs. 2,83,405/- only.

Executive Engineer,
Mandi Division No. II,
HPPWD, Mandi.

14

516

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work : R/R Damages on Doodhar Kheedgaoo Road Km. 0/00 to 24/500 (SH..C/O wire crate R/wall with PCC Toe wall at RD. 18/290 to 18/305) (portion Batahar to Batahar) under PDN42023

Percentage of BOQ

Estimated Cost Rs. 3,01,605/-
 Earnest Money Rs. 6,100/-
 Time:- One month

Name of the Bidder/ Bidding Firm/ Company :		PRICE SCHEDULE											
NUMBER #	TEXT #	Item Description	NUMBER #	QUANTITY	TEXT #	UNIT	NUMBER #	ESTIMATE RATE	NUMBER #	TOTAL AMOUNT	TEXT #	TOTAL AMOUNT	TEXT #
S. No								with all taxes including GST in Rs. P		with all Taxes including GST in Rs. P		including GST In Words	
1	2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	3	15.75	4	Per Cubic Metre	5	609.90	6	9,606.00	7	Rupees Nine Thousand Six Hundred Six Only	
2		Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.		18.75		Per Cubic Metre		5,320.75		99,764.00		Rupees Ninety Nine Thousand Seven Hundred Sixty Four Only	
3		Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals.		46.86		Per cubic metre		3,562.00		1,66,915.00		Rupees One Lakh Sixty Six Thousand Nine Hundred Fifteen Only	
4		Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.		15.75		Per Cubic Metre		1,607.60		25,320.00		Rupees Twenty Five Thousand Three Hundred Twenty Only	
Total										3,01,605.00		Rupees Three Lakh One Thousand Six Hundred Five	

BoQ amount approved for Rs. 3,01,605/- only

Executive Engineer,
 Mandi Division No.II
 HP,PWD, Mandi.

15

8

604

Percentage of BOQ

Estimated Cost :- 4,62,230/-
 Earnest Money :- 9,300/-
 Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH.- C/O PCC R/wall at Rd 0/920 to 0/935 under PDNA 2023)

Contract No. :

Name of the Bidder/
 Bidding Firm/
 Company :

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns. else the bidder's bid will be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes excluding GST in Rs. P	NUMBER # TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TEXT # TOTAL AMOUNT with all Taxes excluding GST In Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	30.70	Per Cubic Metre	517.65	15,892.00	Rupees Fifteen Thousand Eight Hundred Two Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (forty millimetre, nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802-803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	88.65	Per Cubic Metre	4612.00	4,08,854.00	Rupees Four Lakh Eight Thousand Hundred Fifty Four Only
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204, 3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	45.00	Each	322.00	14,490.00	Rupees Fourteen Thousand Four Hundred Ninety Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	16.65	Per Cubic Metre	1381.00	22,994.00	Rupees Twenty Two Thousand Nine Hundred
Total					4,62,230.00	Rupees Four Lakh Sixty Two Thousand Two Hundred Thirty Only

Quoted Rate in Figures : 30.0 approved
 Quoted Rate in words: Rs. 4,62,230/- only.

Executive Engineer,
 Mandi Division No. II,
 HPPWD, Mandi.

16

523

Contract No. : _____
 Name of the Bidder/ Bidding Firm/ Company : _____
 Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- R.R.Damages on Kun to Kot Road Km. 0/0 to 2/800. (SH.. P/L interlocking paver at Rd 1/470 to 1/500). Under PDNA-2023

Percentage of BoQ
 Estimated Cost :- 3,04,332/-
 Earnest Money:- 6,100/-
 Time:- One Month

PRICE SCHEDULE
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	NUMBER #	TOTAL AMOUNT WITH all Taxes including GST in Rs. P	NUMBER #	TOTAL AMOUNT WITH all Taxes including GST in Words
Sl. No.			Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P			
1	2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	4	5	6	7	
			15.00	Per cubic metre	5,620.40	84,306.00	Rupees Eighty Four Thousand Six Only	
2		Providing and laying 80mm (eighty millimetre) thick factory made cement concrete interlocking paver block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (fifty millimetre) thick compacted bed of coarse sand, filling the joints with line sand etc. all complete including carriage of materials with in all leads, lifts and other incidentals as per the direction of Engineer-in-charge.	150.00	Per Square metre	1,346.90	2,02,035.00	Rupees Two Lakh Two Thousand Thirty Five Only	
3		Providing concrete for plain/reinforced concrete 1:2:4 (1 cement : 2 sand : 4 graded stone aggregate 20mm (Twenty millimetre) nominal size) in open foundations and curing complete as per drawing and MORC technical specification section 800, 1200 and clause 1604 including carriage of materials with in all leads, lifts and other incidentals as per the direction of Engineer-in-charge.	2.43	Per Cubic Metre	7,403.75	17,991.00	Rupees Seventeen Thousand Nine Hundred Ninety One Only	
Total:-						3,04,332.00	Rupees Three Lakh Four Thousand Three Hundred Thirty Two Only	
Quoted Rate in words:								
Quoted Rate in words:								

BOQ. approved for Rs. 3,04,332/- only.

Executive Engineer,
 Mandi Division No.II,
 HPPWD, Mandi.

17

771

Percentage of BOD

Estimated Cost :- 3,21,881/-
Earnest Money:-6,500/-
Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandl Division No.II HPPWD Mandl
Name of work : R.R.Damages on Bindrabani Majhwar road Km 0/00 to 19/800,SH :- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 15/450 Under PDNA-2023

Name of the Bidder/ Bidding Firm/ Company : [This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns]

Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	Excavation in soft in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	7.20	Per Cubic Metre	198.60	1,430.00	Rupees One Thousand Four Hundred Thirty Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	60.37	Per cubic metre	609.90	36,820.00	Rupees Thirty Thousand Eight Hundred Twenty Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	32.90	Per cubic metre	5,320.70	1,75,051.00	Rupees One Lakh Seventy Thousand Fifty One Only
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	10.05	Per Tonne	6,451.75	64,840.00	Rupees Sixty Thousand Four Hundred Forty Only
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00	Rupees Thirty Thousand Eight Hundred Fifty Eight Only
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	10.00	Per Cubic Metre	365.00	3,650.00	Rupees Three Thousand Six Hundred Fifty Only

18

771

Tender Inviting Authority : Executive Engineer, Mandi Division No.11 Hippud Mandi
 Name of work : R.R Damages on Bindrabani Mahwar road Km 0/00 to 19/800 (SH : C/O 900 mm dia RCC hump pipe culvert alongwith both side wing wall at Rd at Rd 15/450) Under PDNA-2023

Percentage of BoQ

Estimated Cost :- 3,21,881/-
 Earnest Money:-6,500/-
 Time:- One Month

Name of the Bidder/ Bidding Firm/ Company :	PRICE SCHEDULE							
Sl. No.	NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
1	2		Excavation in soft in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	3	4	5	6	7
				7.20	Per Cubic Metre	198.60	1,430.00	Rupees One Thousand Four Hundred Thirty
2			Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	32.90	Per cubic metre	609.90	36,820.00	Rupees Thirty Eight Thousand Hundred Twenty
3			Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm [Forty millimetre nominal size] concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	10.05	Per Tonne	6,451.75	64,840.00	Rupees Sixty Four Thousand Hundred Forty Only
4			Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00	Rupees Thirty Two Thousand Hundred Fifty Eight Only
5			Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	10.00	Per Cubic Metre	365.00	3,650.00	Rupees Three Thousand Six Hundred Fifty Only
6			Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.					

18

7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.50	Per cubic metre	1,607.00	7,232.00	Rupees Thousand Hundred Only	Seven Thousand Thirty Two
	Total				3,21,881.00	Rupees Three Lakh Twenty One Thousand Eight Hundred Eighty One Only	
Quoted Rate in words:							
Quoted Rate in words:							

BDA approved for Rs. 3,21,881/- only.

[Signature]
 Executive Engineer,
 Mandi Division No-II
 Mandi, W.D. Mandi.

763

Percentage of BOQ

Estimated Cost :- 3,24,769/-
 Earnest Money:-6,500/-
 Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- RRD on Bindrabani Majhwar road Km 0/00 to 19/800 (SH :- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 16/380) under PDNA 2023)

PRICE SCHEDULE						
[This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns.]						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	8.02	Per Cubic Metre	198.60	1,593.00	Rupees One Thousand Five Hundred Ninety Three Only
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	62.09	Per Cubic Metre	609.90	37,869.00	Rupees Thirty Seven Thousand Eight Hundred Sixty Nine Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete in open foundations complete including formwork, work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	34.50	Per Cubic Metre	5,320.70	1,83,564.00	Rupees One Lakh Eighty Three Thousand Sixty Four Only
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and plinth curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	9.00	Per cubic metre	6,451.75	58,066.00	Rupees Fifty Eight Thousand Sixty Six Only
5	Providing and laying 900mm (nine hundred millimetre) dia reinforced cement concrete pipe IS class NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1106 including carriage of materials with in all leads, lifts and other incidentals or as per the entire satisfaction and direction of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.50	Per Running metre	4,381.00	32,858.00	Rupees Thirty Two Thousand Hundred Fifty Eight Only
6	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	13.00	Each	365.00	4,745.00	Rupees Four Thousand Seven Hundred Forty Five Only

19

7	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification (Granular material) including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government.	3.78	Per cubic metre	1,607.00	6,074.00	Rupees Six Thousand Seventy Four Only
Total					3,24,769.00	Rupees Three Lakh Twenty Four Thousand Seven Hundred Sixty Nine Only
Quoted Rate in words:						
Quoted Rate in words:						

BOR approved for Rs. 3,24,769 only.

[Signature]
 Executive Engineer,
 Mandi Division No-II
 P.P.W.D. Mandi.

769

Percentage of BOD

Estimated Cost :- 3,26,817/-
Earnest Money:-6,600/-

Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- R.R Damages on Bindrabani Majhwar road Km 0/00 to 19/800 (SH :- C/O 900 mm dia RCC hump pipe culvert alongwith both side wing wall at Rd at Rd 19/230) Under PDNA-2023

Name of the Bidder/ Bidding Firm/ Company : _____

(This BOD template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
		Quantity	Unit	Estimate Rate with all taxes including GST In Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P		TOTAL AMOUNT with all Taxes Including GST in Words
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	8.14	Per Cubic Metre	198.60	1,617.00		Rupees One Thousand Six Hundred Seventeen Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 905.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	61.93	Per cubic metre	609.90	37,771.00		Rupees Thirty Seven Thousand Seven Hundred Only
3	Providing and laying 1:5:10 (One cement : Five sand : Ten graded stone aggregate 40mm (Forty millimetres nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	34.50	Per cubic metre	5,320.70	1,83,564.00		Rupees One Lakh Eighty Thousand Three Hundred Sixty Four
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	9.00	Per Tonne	6,451.75	58,066.00		Rupees Fifty Eight Thousand Sixty Six Only
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00		Rupees Thirty Two Thousand Eight Hundred Fifty Eight Only
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	13.00	Per Cubic Metre	365.00	4,745.00		Rupees Four Thousand Seven Hundred Forty Five Only

7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.10	Per cubic metre	1,607.00	8,196.00	Rupees Thousand Hundred Ninety Six Only	Eight One Thousand Six Hundred
	Total				3,26,817.00	Rupees Three Lakh Twenty Six Thousand Eight Hundred Seventeen Only	
Quoted Rate in words:							
Quoted Rate in words:							

BOA approved for Rs. 3,26,817/- only.

[Signature]
 Executive Engineer,
 Mandi Division No-II
 J.P.W.D. Mandi.

605

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Khanoo to Mahan road Km. 0/00 to 2/800. (SH:- C/O PCC R/wall at Rd 2/670 to 2/680 under PDNA 2023)

Percentage of BoQ

Estimated Cost :- 2,18,526/-
 Earnest Money:- 4,400/-
 Time:- One Month

Name of the Bidder/ Bidding Firm/ Company :		PRICE SCHEDULE	
---	--	----------------	--

NUMBER #	Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
			Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words
1	1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	15.30	Per Cubic Metre	609.10	9,319.00	Nine Thousand Three Hundred Nineteen Only	7
2	2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	35.80	Per Cubic Metre	5311.65	1,90,157.00	Rupees One Lakh Ninety Thousand One Hundred Fifty Seven Only	7
3	3	Providing, weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face, complete as per drawing and technical specifications clause 614, 709, 1204, 3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	20.00	Each	365.30	7,306.00	Rupees Seven Thousand Three Hundred Six Only	7
4	4	Back-filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204, 3.8, Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	7.20	Per Cubic Metre	1631.10	11,744.00	Rupees Eleven Thousand Seven Hundred Forty Four Only	7
Total						2,18,526.00	Rupees Two Lakh Eighteen Thousand Five Hundred Twenty Six Only	

BoQ approved by *[Signature]* Rs. 2,18,526/- only.

Executive Engineer,
 Mandi Division No. II,
 HPPWD, Mandi.

767

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work : R.R Damages on Bindrabani Majhwar road Km 0/00 to 19/800.(SH : C/O 900 mm dia RCC hump pipe culvert alongwith both side wing wall at Rd at Rd 15/650) Under PDNA-2023

Estimated Cost :- 3,72,565/-
 Earnest Money:-7,500/-
 Time:- One Month

Name of the Bidder/ Bidding Firm/ Company : _____

[This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only]

PRICE SCHEDULE

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Rs. p	NUMBER # TOTAL AMOUNT With all Taxes including GST in Rs. p	TEXT # TOTAL AMOUNT with all Taxes including GST in Words
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	10.10	Per Cubic Metre	198.60	2,006.00	Rupees Two Thousand Six Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps, masonry deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	64.97	Per cubic metre	609.90	39,625.00	Rupees Thirty Nine Thousand Six Hundred Twenty Five Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	42.52	Per cubic metre	5,320.70	2,26,236.00	Rupees Two Lakh Twenty Six Thousand Two Hundred Thirty Six Only
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	9.00	Per Tonne	6,451.75	58,066.00	Rupees Fifty Eight Thousand Sixty Six Only
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00	Rupees Thirty Two Thousand Eight Hundred Fifty Eight Only
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	10.00	Per Cubic Metre	365.00	3,650.00	Rupees Three Thousand Six Hundred Fifty Only

7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	6.30	Per cubic metre	1,607.00	Total			3,72,565.00	Rupees Ten Thousand One Hundred Twenty Four Only
Quoted Rate in words:									
Quoted Rate in words:									

B.O.B. approved Rs. 3,72,565/- only.

[Signature]
 Executive Engineer,
 Mandi Division No-II
 P.W.D. Mandi.

788

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandl Division No.II HPPWD Mandl

Name of work :- R.R.Damages on Bindrabani Mehwar road Km 0/00 to 19/800, SH :- C/O 900 mm dia RCC hump pipe culvert alongwith both side wing wall at Rd at Rd 15/310 Under PDNA-2023

Estimated Cost :- 3,81,797/-
Earnest Money:-7,700/-
Time:- One Month

[This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns.]

Sl. No.	Item Description	NUMBER #	TEXT #	Quantity	Unit	NUMBER #	TEXT #	Estimate Rate with all taxes including GST in Rs. p	TOTAL AMOUNT with all Taxes including GST in Rs. p	NUMBER #	TEXT #
1	Excavation in soft hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	2	3	9.76	Per Cubic Metre	5	6	198.60	1,938.00	7	Rupees One Thousand Nine Hundred Thirty Eight Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	3	4	63.87	Per cubic metre	5	6	609.90	38,954.00	7	Rupees Thirty Eight Thousand Five Hundred Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	4	5	43.06	Per cubic metre	5	6	5,320.70	2,29,109.00	7	Rupees Two Lakh Twenty Nine Thousand One Hundred Nine Only
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	5	6	10.05	Per Tonne	5	6	6,451.75	64,840.00	7	Rupees Sixty Four Thousand Four Hundred Only
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	6	7	7.50	Per cubic metre	5	6	4,381.00	32,858.00	7	Rupees Thirty Two Thousand Eight Hundred Fifty Eight Only
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	7	8	13.00	Per Cubic Metre	5	6	365.00	4,745.00	7	Rupees Four Thousand Seven Hundred Forty Five Only

23

7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	5.82	Per cubic metre	1,607.00	9,353.00	Rupees Nine Thousand Three Hundred Fifty
Total					3,81,797.00	Rupees Three Lakh Eighty One Thousand Seven Hundred Ninety Seven Only
Quoted Rate in words:						
Quoted Rate in words:						

B.O.G. approved for Rs 3,81,797 only.

[Signature]
 Executive Engineer,
 Mandi Division No-II
 H.P.P.W.D. Mandi.

609

Estimated Cost :- 3,23,651/-
 Earnest Money :- 6,500/-
 Time :- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH:- C/O PCC R/wall at Rd 1/115 to 1/130 under PDNA 2023)

Contract No. :
 Name of the Bidder/ Bidding Firm/ Company :
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Rs. P	NUMBER # TOTAL AMOUNT With all Taxes including GST in Rs. P	TEXT # TOTAL AMOUNT with all Taxes including GST in Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	24.60	Per Cubic Metre	609.10	14,984.00	Rupees Fourteen Thousand Nine Hundred Eighty Four Only
2	Providing and laying 1:5-10 (One cement : five sand : ten graded stone aggregate 40mm forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	53.10	Per Cubic Metre	5311.65	2,82,049.00	Rupees Two Lakh Eighty Two Thousand Forty Nine Only
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204, 3.7 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	30.00	Each	365.30	10,959.00	Rupees Ten Thousand Nine Hundred Fifty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	9.60	Per Cubic Metre	1631.10	15,659.00	Rupees Fifteen Thousand Six Hundred Fifty Nine
Total					3,23,651.00	Rupees Three Lakh Twenty Three Thousand Six Hundred Fifty One Only

BOQ approved by *[Signature]* Rs. 3,23,651/- only.

Executive Engineer,
 Mandi Division No. II,
 HPPWD, Mandi.

21

790

Percentage of BQ

Estimated Cost :- 4,42,109/-
 Earnest Money:- 7,500/-
 Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
 Name of work :- R.R.Damages on Bindrahani Majhwar road Km 0/00 to 19/800 (SH :- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd at Rd 17/800) Under PDNA-2023

Name of the Bidder/ Bidding Firm/ Company : _____

(This BQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Rs. p	NUMBER # TOTAL AMOUNT With all Taxes including GST in Rs. p	TEXT # TOTAL AMOUNT with all Taxes including GST in Words
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	12.00	Per Cubic Metre	198.60	2,383.00	Rupees Two Thousand Three Hundred Eighty Three Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	67.17	Per cubic metre	609.90	40,967.00	Rupees Thousand Sixty Seven Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	53.22	Per cubic metre	5,320.70	2,83,168.00	Rupees Two Lakh Eighty Three Thousand Sixty Eight Only
4	Providing concrete for plain concrete in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 P.C.C. 1:3:6 (One cement : Three sand : Six Graded stone aggregate) Mechanically Mixed including carriage of materials with in all leads, lifts and other incidentals.	10.05	Per Tonne	6,451.75	64,840.00	Rupees Sixty Four Thousand Forty Only
5	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	4,381.00	32,858.00	Rupees Thirty Two Thousand Fifty Eight Only

25

6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	16.00	Per Cubic Metre	365.00	5,840.00	Rupees Five Thousand Eight Hundred Forty Only
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	7.50	Per cubic metre	1,607.00	12,053.00	Rupees Twelve Thousand Fifty Three Only
Total					4,42,109.00	Rupees Four Lakh Forty Two Thousand One Hundred Nine Only
Quoted Rate in words:						
Quoted Rate in words:						

BDO approved for Rs. 4,42,109 only.

[Signature]
Executive Engineer,

Mandi Division No-II

H.P.W.D. Mandi.

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100

(764)

Percentage of Boq

Estimated Cost :- 4,42,109/-
Earnest Money:-8,900/-
Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandl Division No.II HPEWD Mandl
Name of work :- RRD on Bindrabani Majhwar road Km 0/00 to 19/800 (SH :- C/O 900 mm dia RCC hume pipe culvert alongwith both side wing wall at Rd 14/230) under PDNA 2023)


PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns.						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST In Rs. P	TOTAL AMOUNT With all Taxes including GST In P	TOTAL AMOUNT with all Taxes including GST In Words
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper wrok including carriage of materials with in all leads, lifts and other incidentals.	12.00	Per Cubic Metre	198.60	2,383.00	Rupees Two Thousand Three Hundred Eighty Three Only
2	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	67.17	Per Cubic Metre	609.90	40,967.00	Rupees Thousand Hundred Sixty Seven Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	53.22	Per Cubic Metre	5,320.70	2,83,168.00	Rupees Eighty Thousand Hundred Sixty Eight Only
4	Providing concrete for plain concrete 1:3:5 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and plinth curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.05	Per cubic metre	6,451.75	64,840.00	Rupees Sixty Thousand Hundred Forty Only
5	Providing and laying 900mm (nine hundred millimetre) dia reinforced cement concrete pipe IS class NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (One cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1106 including carriage of materials with in all leads, lifts and other incidentals or as per the entire satisfaction and direction of Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.50	Per Running metre	4,381.00	32,858.00	Rupees Thirty Thousand Hundred Fifty Eight Only
6	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	16.00	Each	365.00	5,840.00	Rupees Five Thousand Eight Hundred Forty Only

(28)

7	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification (Granular material) including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge. The rate including Royalty, Malkhana, Octroi, toll tax, sales tax or any other taxes imposed by the Government.	7.50	Per cubic metre	1,607.00	12,053.00	Rupees Twelve Thousand Fifty Three Only
Total					4,42,109.00	Rupees Four Lakh Forty Two Thousand One Hundred Nine Only
Quoted Rate in words:						
Quoted Rate in words:						

BDA approved for Rs. 4,42,109 only.


 Executive Engineer,
 Mandi Division No-II
 MP-PWD, Mandi.

601

Estimated Cost :- 3,95,471/-
Earnest Money :- 8,000/-
Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. II HPPWD Mandi
Name of work : RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH:- C/O wire crate R/wall at Rd 1/620 to 1/632 under PDNA 2023)

Contract No. :

Name of the Bidder/
Bidding Firm/

Company :

PRICE SCHEDULE

NUMBER #	TEXT #	Item Description	NUMBER #	Quantity	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes including GST in Rs. P	NUMBER #	TOTAL AMOUNT With all Taxes including GST in Rs. P	NUMBER #	TOTAL AMOUNT with all Taxes including GST In Words
Sl. No.												
1	1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	32.16	4	Per Cubic Metre	5	609.10	6	19,589.00	7	Rupees Nineteen Thousand Five Hundred Eighty Nine Only
2	2	Providing and laying 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.		20.40		Per Cubic Metre		5311.65		1,08,358.00		Rupees One Lakh Eight Thousand Three Hundred Fifty Eight Only
3	3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.		68.28		Per cubic metre		3568.32		2,43,645.00		Rupees Two Lakh Forty Three Thousand Six Hundred Forty Five Only
4	4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204 3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals, as per direction and entire satisfaction of Engineer-in-charge.		14.64		Per Cubic Metre		1631.10		23,879.00		Rupees Twenty Three Thousand Eight Hundred Seventy Three Only
Total										3,95,471.00		Rupees Three Lakh Ninety Five Thousand Four Hundred Seventy One Only

BOB approved Rs. 395,471/- only

Executive Engineer,
Mandi Division No. II,
HPPWD, Mandi.

24

7775

Percentage of BOQ

Estimated Cost :- 4,64,186/-
Earnest Money:-9,300/-

Tender Inviting Authority : Executive Engineer, Mandl Division No.II HPPWD Mandl
Name of work : R.R.Damages on Bindrabani Majhwar Kormore Moviseri road Km 0/00 to 19/800 (SH : C/O wire crate R/wall at Rd 17/740 to 17/755) Under PDNA- Time:- One Month
2023

Name of the Bidder/ Bidding Firm/ Company : PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER # Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Unit	NUMBER # Estimate Rate with all taxes including GST in Ra. p	NUMBER # TOTAL AMOUNT With all Taxes including GST in Ra. p	TEXT # TOTAL AMOUNT with all Taxes including GST in Words
1	Excavation in soft in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	36.30	Per Cubic Metre	168.35	6,111.00	Rupees Six Thousand One Hundred Eleven Only
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	19.20	Per cubic metre	517.65	9,939.00	Rupees Nine Thousand Nine Hundred Thirty Nine Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stones) concrete of 40mm (Forty millimetre) nominal size concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	27.00	Per cubic metre	4,612.00	1,24,524.00	Rupees One Lakh Twenty Four Thousand Five Hundred Twenty Four Only
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming to IS:250 and IS:4826 in 150mmX150mm (one hundred fifty millimetre) into one hundred fifty millimetre mesh (woven diagonally including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each including cost of trimming for preparation of bed etc. as per drawing and technical specification clause 1301 as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	110.59	Per Cubic Metre	2,695.00	2,98,040.00	Rupees Two Lakh Ninety Eight Thousand Forty Only

28

5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	18.00	Per cubic metre	1,381.00	24,858.00	Rupees Twenty Four Thousand Eight Hundred Fifty Eight Only
Total					4,63,472.00	Rupees Four Lakh Sixty Three Thousand Four Hundred Seventy Two Only
Quoted Rate in words:						
Quoted Rate in words:						


 Executive Engineer,
 Mandi Division No-II
 HP.PWD. Mandi.

600

Estimated Cost :- 3,93,672/-
Earnest Money :- 7,900/-
Time :- One Month

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH:- C/O wire crate R/wall at Rd 1/600 to 1/615 under PDNA 2023)

Contract No. :

Name of the Bidder/
Bidding Firm/
Company :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	Unit	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.			Quantity			Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P		TOTAL AMOUNT with all Taxes including GST in Words
1	2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	27.60	4	Per-Cubic Metre	609.10	16,811.00	7	Rupees Sixteen Thousand Eight Hundred Eleven Only
2		Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	20.40		Per-Cubic Metre	531.65	1,08,358.00		Rupees One Lakh Eight Thousand Three Hundred Fifty Eight Only
3		Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	68.28		Per-cubic metre	3568.32	2,43,645.00		Rupees Two Lakh Forty-Three Thousand Six Hundred Forty Five Only
4		Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8 Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	15.24		Per Cubic Metre	1631.10	24,858.00		Rupees Twenty Four Thousand Eight Hundred fifty-Eight Only
Total							3,93,672.00		Rupees Three Lakh Ninety Three Thousand Six Hundred Two

Quoted Rate in Figures :
Quoted Rate in words :

BOQ approved for Rs. 393672 only.

Executive Engineer,
Mandi Division No. II,
HPPWD, Mandi.

29

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- R.R.Damages on Roda Nallahi Kakoh n Road Km. 0/0 to 12/300. (SH:- Construction of R/wall in PCC at R.D. 6/140 to 6/152 and 6/315 to 6/327). Under PDNA-2023

Estimated Cost :- 4,72,935/-
 Earnest Money:- 9500/-
 Time:- One Month

Contract No. :
 Name of the Bidder/ Bidding Firm / Company :
 (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

PRICE SCHEDULE

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST in Words
1	Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	31.68	Per Cubic Metre	517.65	16,399.00	Rupees Sixteen Thousand Three Hundred Ninety Nine Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	75.60	Per Cubic Metre	4,636.20	3,50,497.00	Rupees Three Lakh Fifty Thousand Four Hundred Ninety Seven Only
3	Providing and Erecting type-A "W" metal beam crash barrier comprising of 3mm (Three millimetre) thick corrugated sheet metal beam rail 70 cm (Seventy centimetre) above road/ground level fixed on ISMC series channel vertical post 150X75X5mm (one hundred fifty into seventy five into five millimetre) spaced 2m (Two metre) centre-to-centre 1.8m (one point eight metre) high 1.1 m (one point one metre) below ground/road level all steel parts and fittings to be galvanized by hot dip process all fitting to conform to IS: 1367 and IS: 1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150X75X5mm (one hundred fifty into seventy five into five millimetre) 300 mm (Three hundred millimetre) long complete as per clause 810 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	24.00	Per running Metre	2,765.00	66,360.00	Rupees Sixty Six Thousand Three Hundred Sixty Only
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals.	45.00	Each	322.00	14,490.00	Rupees Fourteen Thousand Four Hundred Ninety Only

30

Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	18.24	Per Cubic Metre	1,381.00	25,189.00	Rupees Twenty Five Thousand One Hundred Eighty Nine Only
Total:-					4,72,935.00	Rupees Four Lakh Seventy Two Thousand Nine Hundred Thirty
Quoted Rate in words:						
Quoted Rate in words:						

B & C approved for Rs. 472935/-


 Executive Engineer,
 Mandi Division No. II,
 P.W.D. Mandi.

(575)

Percentage of BOQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work : R.R Damages on Rada Nallah to Dhandal road Km 0/00 to 2/900 (ISH :: C/O V-shape drain at various Rds) Under PDNA-2023

Estimated Cost :: 4,76,531/-
Earnest Money:-9,600/-
Time:- One Month

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes including GST in Rs. P	TOTAL AMOUNT With all Taxes including GST in Rs. P	TOTAL AMOUNT with all Taxes including GST in Words	
1	2	3	4	5	6	7	
1	Earth-work-in-excavation for structures as per drawing and technical specifications Clause-305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50 m, dressing of sides and bottom and back filling in trenches with excavated suitable material in ordinary soil up to 3 m depth including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	84.00	Per Cubic Metre	609.90	51,232.00	Rupees Fifty One Thousand Hundred Thirty Two Only	
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and plinth curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	65.92	Per cubic metre	6,451.75	4,25,299.00	Rupees Four Lakh Twenty Five Thousand Hundred Ninety Nine Only	
Total					4,76,531.00	Rupees Four Lakh Seventy Six Thousand Five Hundred Thirty One Only	
Quoted Rate in words:							
Quoted Rate in words:							

BOQ approved for Rs. 4,76,531/- only.

Executive Engineer,
Mandi Division No-II
HPPWD, Mandi.

(31)

597

Estimated Cost :- 3,67,502/-
 Earnest Money:- 7,400/-
 Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
 Name of work :- RRD on Khalanoo to Mahan road Km. 0/00 to 2/800. (SH:- C/O wire crate R/wall at Rd 1/390 to 1/410 under PDNA 2023)

Percentage of BoQ

Sl. No.	Item Description	NUMBER #	Quantity	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes including GST in Rs. P	NUMBER #	TOTAL AMOUNT With all Taxes including GST in Rs. P	TEXT #	TOTAL AMOUNT with all Taxes including GST in Words
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3	24.75	4	Per Cubic Metre	5	609.10	6	15,075.00	7	Rupees Fifteen Thousand Seven Hundred Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	14.85	14.85	4	Per Cubic Metre	5	5311.65	6	78,878.00	7	Rupees Seventy Eight Thousand Eight Hundred Seventy Eight Only
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia. GI wire conforming to IS: 280 and IS: 4826 in 100mm X 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	67.50	67.50	4	Per cubic metre	5	3568.32	6	2,40,862.00	7	Rupees Two Lakh Forty Thousand Eight Hundred Sixty Two Only
4	Back filling behind abutment wing wall and return wall complete as per drawings and technical specification Clause-1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge.	20.04	20.04	4	Per Cubic Metre	5	1631.10	6	32,687.00	7	Rupees Thirty Two Thousand Eight Hundred Eighty
Total									3,67,502.00		Rupees Three Lakh Sixty Seven Thousand Five Hundred Two Only

Quoted Rate in Figures :
 Quoted Rate in words :
 BQA approved for Rs. 3,67,502 only.

32

Executive Engineer,
 Mandi Division No.II,
 H.P.W.D. Mandi.