

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NO.PW- GHD-EA-I- /Tender/2024-

9567-72 Dated:- 24-10-25

The Executive Engineer (IT-Cell),  
Nirman Bhawan Nigam Vihar Shimla-2  
Himachal Pradesh Shimla -2.  
Email:-ee-pwd-hp@nic.in

SUBJECT: -

Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 25.10.2025.

DA:-As above.

Executive Engineer,  
Ghumarwin, Division.  
HP.PWD. Ghumarwin  
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Chief Engineer (HZ) HP.PWD., Hamirpur.
2. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
3. All the Assistant Engineer, working under this Division
4. Notice Board of this office.

DA:- One No.

Executive Engineer,  
Ghumarwin, Division.  
HP.PWD. Ghumarwin.  
On behalf of Governor of Himachal Pradesh

**\*NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 01-11-2025 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 31-10-2025 up to 4.00 P.M and the application for issue of tender form shall be received on 31-10-2025 up to 1.00 PM. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Restoration of rain damages on various road under Sub-Division Ghumarwin (SH: Removal of slips, maintenance of earthen shoulder and drain in various road under Ghumarwin Sub-Division.	Rs.99368/-	Rs.2000/-	Rs.350/-	One Month
2.	Upgradation of Amarpur Hadsar Dahad Jamman Ghumarwin road km 0/000 to 7/100 in District Bilaspur HP(SH: Improvement passing places, R/walls, B/walls, CD work, GSB, WBM-II, tarring work side drain and parapets)(SH: Preparation of Detailed working estimate and DNIT).	Rs.96500/-	Rs.2000/-	Rs.350/-	One Month
3.	Restoration of rain damages on link road Auhar to Daryana Vijaypur via Kali Mata Mandir km 0/00 to 2/300(SH: C/on of R/wall at Rd 0/235 to 0/243.50).	Rs.97585/-	Rs.2000/-	Rs.350/-	One Month
4.	Restoration of rain damages on various road under Sub-Division Bharari (SH: Removal of slips, maintenance of earthen shoulder and drain in various roads under Sub-division Bharari (under CRF).	Rs.99644/-	Rs.2000/-	Rs.350/-	One Month
5.	Restoration of rain damages on various road under Sub-Division Bharari (SH: Removal of slips, maintenance of earthen shoulder and drain in various roads under Section Bharari-I (under CRF).	Rs.96588/-	Rs.2000/-	Rs.350/-	One Month
6.	Restoration of rain damages on Sumari to Lower Bhapral road in km 0/00 to 9/200 (SH: Removal of slips, maintenance of earthen shoulder and maintenance of unlined drain at various Rd's (under CRF).	Rs.98648/-	Rs.2000/-	Rs.350/-	One Month
7.	C/o Ambulance road in village Khungan from the House of Dharam Singh Rana to Palangri (Daaliyan Harizan Basti Mohal) (SH: C/o Edge wall at Rd 0/00 to 0/012(L/side) and P/L Cement concrete pavement at RD 0/130 to 0/157.60(Deposit Works under VKVNY).	Rs.199002/-	Rs.4000/-	Rs.350/-	One Month
8.	C/o Link road Khungan from the House of Rajesh Jaswal to House of Ram Lal Harizan Basti Mohal(SH: Constructiion of Edge wall at Rd 0/00 to 0/08)(R/Side) and P/L cement concrete pavement at Rd 0/00 to 0/125.60(Deposit Works under VKVNY).	Rs.499292/-	Rs.10000/-	Rs.350/-	One Month
9.	C/o Pucca and Ambulance road from link road Balhi to village Birring to the Hosue of Smt. Nikki Devi (SH: P/L cement concrete interlocking paver block at Rd 0/00 to 0/074(Deposit Work under SDP).	Rs.499432/-	Rs.10000/-	Rs.350/-	One Month

**Certificate:-** Certified that tenders are being called for due to exigencies of works (landslide and road sinking etc.) in the public interest.

**Terms and Conditions:-**

- The Contractor should produce a copy of enlistment/renewal letter at time of application.
- Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
- The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
- The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division, HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
- The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

Executive Engineer,  
 Ghumarwin Division  
 HP-PWD, Ghumarwin

### Draft Schedule of Quantity

Estimated Cost:- Rs. 99,368.00  
 Earnest Money:- Rs. 2,000.00  
 Time :- One Month

Name of Work:- Restoration of rain damages on various road under Sub-Division Ghumarwin HPPWD Ghumarwin (SH:- Removal of slps, Maintenance of earthen shoulder and drain in various roads under Ghumarwin Sub-division).

Sr. No.	Description Item	Quantity	Unit	In figure	In words	Amount
1	Removal of land slide/slps in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	542.00	Per cubic metre	120.00	Rupees One Hundred Twenty Only	65040
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	644.00	Per square metre	22.00	Rupees Twenty Two Only	14168
3	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification clause 1907 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1680.00	Per Running Metre	12.00	Rupees Twelve Only	20160
<b>Total:-</b>						<b>99,368.00</b>

*Draft Schedule of Quantity at Sr. No. 311 for the year 2025-26 approved for Rs. 99,368 /- only.*

Executive Engineer,  
 Ghumarwin Division,  
 HP, PWD, Ghumarwin,

## Draft Schedule of Quantity

**Name of Work:- Upgradation of Amarpur Hadsar Dahad Jamman Ghumarwin road Km 0/000 to 7/100 in District Bilaspur (HP) (Sh:- Improvement, passing places, R/walls, B/ walls C.D. work, GSB, WBM-II, WBM-III, tarring work, side drain and parapets)(SH:-Preparation of Detailed working estimate and DNIT).**

Estimated Cost:- Rs. 96,500.00

Earnest Money:- Rs. 2,000.00

Time :- One Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Preparation of Detailed working estimate and DNIT. If any correction/ ammendment desired by the head office the same may be corrected as desired and directed by the Engineer-In-Charge and complete in all respect. The rate shall including entire carriage of material with in all leads and lifts and other indental as directed by the Engineer-in-charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.000	Job	96500	Rupees Ninety Six Thousand Five Hundred Only	96500.00
<b>Total</b>						96500

*Draft Schedule of Quantity at Sr. No. 312 for the year 2025-26 approved for Rs. 96,500/- only.*

Executive Engineer,  
Ghumarwin Division,  
HP, PWD, Ghumarwin.

## Draft Schedule of Quantity

**Name of Work:- Restoration of rain damages on link road Auhar to Daryana Vijaypur via Kali Mata Mandir km 0/00 to 2/300(SH):- Construction of R/wall at Rd 0/235**

Estimated Cost:- Rs. 97,585.00  
 Earnest Money:- Rs. 2,000.00  
 Time :- One Month

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead.All kinds of soil as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	13	Per cubic metre	275.00	Rupees Two Hundred Seventy Five Only	3575.00
2	Providing and Laying cement concrete 1:5:10 nominal mix ( One Cement : five Sand : Ten graded crushed stone aggregate.) 40mm ( forty millimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curing complete . including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.88	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	89460.00
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre), dia PVC pipe white in colour extending through the full width of the structures with slop of 1(V) : 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 .as per direction of Engineer-In-Charge.The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Each	325.00	Rupees Three Hundred Twenty Five Only	4550.00
<b>Total</b>						<b>97585</b>

Draft Schedule of Quantity at Sr. No. 313 for the year 2025-26 approved for Rs. 97,585 /only.

Executive Engineer,  
 Ghumanwin Division,  
 HP, PWD, Ghumanwin.

## Draft Schedule of Quantity

		Estimated Cost:- Rs.		99,644.00		
		Earnest Money:- Rs.		2,000.00		
		Time :-		One Month		
<b>Name of Work:- Restoration of rain damages on various road under Sub-Division Ghumarwin HPPWD Ghumarwin (SH:- Removal of slips and Maintenance of earthen shoulder in various roads under Ghumarwin Section-II. Ghumarwin Sub-division).(Under CRF).</b>						
Sr. No.	Description Item	Quantity	Unit	In figure	In words	Amount
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	687.00	Per cubic metre	120.00	Rupees One Hundred Twenty Only	82440
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	782.00	Per square metre	22.00	Rupees Twenty Two Only	17204
<b>Total:-</b>						<b>99,644.00</b>

Draft Schedule of Quantity No. 299 for the year 2025-26 approved for Rs. 99,644/- only

  
 Executive Engineer,  
 Ghumarwin Division,  
 HP, PWD, Ghumarwin.

## Draft Schedule of Quantity

Estimated Cost:- Rs. 96,588.00

Earnest Money:- Rs. 2,000.00


Time :- One Month

**Work:- Restoration of rain damages on various road under Sub-Division Bharari (SH:- Removal of slips. Maintenance of earthen shoulder and rain in various roads under Section Bharari-I, Sub-division Bharari)-(Under CRF).**

Description Item

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	532.00	Per cubic metre	120.00	Rupees One Hundred Twenty Only	63840
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	678.00	Per square metre	22.00	Rupees Twenty Two Only	14916
3	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification clause 1907 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1486.00	Per Running Metre	12.00	Rupees Twelve Only	17832
<b>Total:-</b>						<b>96,588.00</b>

Draft Schedule of Quantity No 284 for  
The year 2025-26 approved for Rs 96,588/- only

  
**Executive Engineer,**  
 Ghumarwin Division,  
 HP, PWD, Ghumarwin.

## Draft Schedule of Quantity

**Name of Work:- Restoration of Rain damage on Sumari to Lower Bhapral road in km 0/00 to 9/200(SH):- Removal of slips, maintenance of Earthen shoulder and maintenance of unlined drains at various Rd's).(Under CRF).**

Estimated Cost:- Rs. 98,648.00

Earnest Money:- Rs. 2,000.00

Time :- One Month

**Description Item**

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	538.00	Per cubic metre	120.00	Rupees One Hundred Twenty Only	64560
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	686.00	Per square metre	22.00	Rupees Twenty Two Only	15092
3	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification clause 1907 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1583.00	Per Running Metre	12.00	Rupees Twelve Only	18996
<b>Total:-</b>						<b>98,648.00</b>

*Draft Schedule of Quantity No. 263 for the year 2025-26 approved for Rs. 98,648/- only.*

Executive Engineer,  
Ghumarwin Division,  
HP, PWD, Ghumarwin

## Draft Schedule of Quantity

**Name of Work:- C/o Ambulance road in village Khungan from the House of Dharam Singh Rana to Palangari (Daaliyan Harizan Basti Mohal) (SH:- Construction of Edge wall at Rd 0/00 to 0/012(L/side) and P/L cement concrete pavement at RD 0/130 to 0/157.60).(Deposit work).**

Estimated Cost:- Rs. 1,99,002.00

Earnest Money:- Rs. 4,000.00

Time :- Two Months

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Excavation in foundations, trenches etc., in earth work, lift upto 1.50 Metres stacking the excavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15cm. layers, when required in to plinths sides of foundations etc., consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.80	Per cubic metre	275.00	Rupees Two Hundred Seventy Five Only	2970.00
2	Providing and Laying cement concrete 1:5:10 nominal mix ( One Cement : five Sand : Ten graded crushed stone aggregate.) 40mm ( forty millimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curring complete . including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.72	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	97740.00
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 .as per direction of Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.00	Each	325.00	Rupees Three Hundred Twenty Five Only	3900.00
4	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, all lead and lift up to in All kinds of soil. with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	82.80	Per square metre	20.00	Rupees Twenty Only	1656.00
5	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.42	Per cubic metre	1550.00	Rupees One Thousand Five Hundred Fifty Only	19251.00

6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement : one point five coarse sand : three graded stone aggregate 20 mm (twenty milimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.35	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	73485.00
<b>Total</b>						<b>199002</b>

*Draft Schedule of Quantity No. 291 for the year 2025-26 approved for Rs. 1,99,002/- only.*

Executive Engineer,  
Ghumarwin Division,  
HP, PWD, Ghumarwin.  
*for*

## Draft Schedule of Quantity

<b>Name of Work:- C/o link road Khungan from the House of Rajesh Jaswal to House of Ram Lal Harizan Basti Mohal (SH:- Construction of Edge wall at Rd 0/00 to 0/08 (R side) and P/L cement concrete pavement at RD 0/00 to 0/125.60). (Deposit work).</b>	Estimated Cost:- Rs. 4,99,292.00	Time :- Two Months
<b>Description Item</b>	Earnest Money:- Rs. 10,000.00	

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Excavation in foundations, trenches etc., in earth work, lift upto 1.50 Metres stacking the excavated soil not more than 3 metres clear from the edge of the excavation and then returning the stacked soil in 15cm. layers, when required in to plinths sides of foundations etc., consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed with in a lead of 20 metres. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.20	Per cubic metre	275.00	Rupees Two Hundred Seventy Five Only	1980.00
2	Providing and Laying cement concrete 1:5:10 nominal mix ( One Cement : five Sand : Ten graded crushed stone aggregate.) and curing complete. including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.48	Per cubic metre	4500.00	Rupees Four Thousand Five Hundred Only	65160.00
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 .as per direction of Engineer-In-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	325.00	Rupees Three Hundred Twenty Five Only	2600.00
4	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, all lead and lift up to in All kinds of soil with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	376.80	Per square metre.	20.00	Rupees Twenty Only	7536.00
5	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	56.52	Per cubic metre	1550.00	Rupees One Thousand Five Hundred Fifty Only	87606.00

6	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5:3(One cement : one point five coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.10	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	334410.00
<b>Total</b>						<b>499292</b>

*Draft Schedule of Quantity No. 292 for the year 2025-26 approved for Rs. 4,99,292/- only.*

Executive Engineer,  
Ghumarwin Division,  
HP, PWD, Ghumarwin;

*[Signature]*

## Draft Schedule of Quantity

**Name of Work:- C/o Pucca and Ambulance road from link road Balhi to village Birring to the House of Smt. Nikki Devi (SHI-P/L cement concrete interlocking paver block at Rd 0/00 to 0/074). (Deposit work).**

Estimated Cost:- Rs. 4,99,432.00  
 Earnest Money:- Rs. 10,000.00  
 Time :- Two Months

Sr. No.	Description Item	Quantity	Unit	Rates		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.70	Per cubic metre	275.00	Rupees Two Hundred Seventy Five Only	6518.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to all level 1:4:8 (one Cement : four coarse sand : eight graded stone aggregate 40 mm nominal size) The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	22.57	Per Cubic Metre	4900.00	Rupees Four Thousand Nine Hundred Only	110593.00
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in - Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	225.70	Per square metre	1450.00	Rupees One Thousand Four Hundred Fifty Only	327265.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm (Twenty millimetre) nominal size) as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.88	Per cubic metre	6200.00	Rupees Six Thousand Two Hundred Only	55056.00
<b>Total</b>						<b>499432</b>

Draft Schedule of Quantity upto 31/0 for  
 the year 2025-26 approved for Rs 4,99,432/- only

Executive Engineer,  
 Ghumarwin Division,  
 HP, PWD, Ghumarwin.