

**Himachal Pradesh
Public works Department
Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **15-10-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **14-10-2025**. The applications for issue of tender forms will be received up to **2.00 P.M. on 13-10-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	SDF/2024/816 R/O Road Jayog to Nalwad Km. 0/00 to 2/00 (SH:- Hiring of JCB for removal of slips /debris, dressing of berms, clearance of drain etc. in various RDs) (Deposit Work)	99000	2000	Two Months
2	A/R & M/O on HPPWD Rest House Gohar at Bassa Tehsil Chachyot Distt. Mandi HP (SH:- Providing and laying Distempring work)	99395	2000	Two Months
3	RRD on Chail Moviseri road km. 0/00 to 11/200(SH:- Construction of PCC B/wall at RD 6/005 to 6/014.50)	98,598	2000	Two Months
4	Repari of Tilli Palas road km. 0/00 to 5/00(SH:- Construction of road side Parapets in various km. Deposit work at RD 0/200 to 0/350)	95,226	2000	Two Months
5	SDP/2023/978 R/O Link road Harizan Basti Port Thunagala Buthadhar km. 0/00 to 2/500 (SH:- Construction of crate work R/wall at RD 0/00 to 0/007.20) Deposit work	98,766	2000	Two Months
6	SDF/2025/59 R/O road Jayog to Nalwad Km. 0/00 to 2/00 (SH:- Hiring of JCB for maintenance of earthen shoulders, and removal of slips at various RDs in km. 1/00 to 2/00) G.P Shalla	59,400/-	1,200/-	Two Months

7	SDF/2025/501/ R/O Baniseri to Kaneti road Km. 0/00 to 5/700 & SDF/2025/503 R/O Jailpul to Saryach road km 0/00 to 5/700 (SH:- Hiring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)	99,300/-	2,000/-	Two Months
8	SDF/2025/499 R/O Baniseri to Kaneti road & SDF/2025/500 R/O Baniseri to Kaneti road km 0/00 to 4/00 (SH:- Hiring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various RDs)	99,000/-	2,000/-	Two Months
9	SDF/2025/505/ & SDF/2025/506 R/O Gani to Bhurani road km. 0/00 to 4/00 (SH:- Hiring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)	99,000/-	2,000/-	Two Months
10	SDF/2025/502 R/O Jailpul to Saryach road Km. 0/00 to 2/00 & SDF/2025/504 R/O Jachh Lot Katesh road km 0/00 to 3/500 (SH:- Hiring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)	99,330/-	2,000/-	Two Months
11	SDF/2025/347 R/O Chail Janjehli road Km. 0/00 to 9/200 (SH:- Hiring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs & Hiring of Tipper for carriage of debris/muck in various RDs))	99,000/-	2,000/-	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.


**Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.**

No. PW-GHR-Tender/NIT/2025!-5226-30

Dated - 06/10/2025

Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
1. The Superintending Engineer 1stCircle, HP.PWD Mandi.
2. **The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.**
3. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
4. The Block Development Officer Gohar.
5. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
6. Various contractors.
7. Notice Board/DB/AB.


Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

Name of work :- SDF/2024/816 R/O Road Jayog to Nalwad Km 0/0 to 2/0 (SH:- Hiring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various RDs) (Deposit Work)						BILL OF QUANTITY	
						Estimated cost Rs.	₹ 99,000.00
						Earnest Money cost	₹ 2,000.00
						Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	₹ 1,100.00			
Percentage rate Quoted in figure							
Percentage rate Quoted in words							

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.



 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- A/R & M/O on HPPWD Rest House Gohar at Bassa Tehsil Chachyoit Distt. Mandi H.P (SH:- Providing and laying Distempring work)

Estimated cost Rs. - 99,395/-
Earnest Money cost Rs.2,000/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Finishing walls with textured exterior paint of required shade : Old work (One or more coats) applied @ 1.82 ltr/10 sqm. including carriage of material within all leads, lifts and other incidental charges complete and as per direction of the Engineer-In-Charge.	1044.61	Per Square meter	95.15		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY


Name of work :- RRD on Chail Moviseri road km 0/00 to 11/200 (SH:- Construction of PCC B/Wall at Rd 6/005 to 6/014.50)

Estimated cost Rs. - 98,598/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.25	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	21.37	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	8.00	Each	380.70		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- Repair of Tilli Palas road km 0/00 to 5/00 (SH:- Construction of road side Parapets in various km) Estimated cost Rs. - 95,226/-
 Deposit work *at RD 0/200 to 0/350* Earnest Money cost Rs.2,000/-
 Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	21.89	Per Cubic meter	4350.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Repair
 Executive
 Gohar Division
 M.P.P.W.D. Gohar

26
BILL OF QUANTITY


Name of work :- SDP/2023/978 R/O Link road Harizan Basti Port Thunagala Butadhar km 0/00 to 2/500 (SH:- Construction of crate work R/Wall at Rd 0/00 to 0/007.20) Deposit work					Estimated cost Rs. - 98,766/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.37	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	6.75	Per Cubic meter	4350.20		
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to IS 280 and IS 4826 in 150 mm x 150 mm mesh (woven diagonally) including 10% of laps laid with boulders apron weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	20.74	Per Cubic meter	3078.30		
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	3.02	Per Cubic meter	1050.60		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY

Name of work :- SDF/2025/58 R/O Road Jayog to Nalwad Km 0/0 to 2/0 (SH:- Hiring of JCB for maintenance of earthen shoulders and removal of slips at various RDs in km. 0/00 to 1/00) GP Shalla					Estimated cost Rs.	₹ 59,400.00
					Earnest Money cost	₹ 1,200.00
					Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	54.00	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.



Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/59 R/O Road Jayog to Nalwad Km 0/0 to 2/0 (SH:- Hiring of JCB for maintenance of earthen shoulders and removal of slips at various RDs 1/00 to 2/000) GP Tuna				Estimated cost Rs.	₹ 59,400.00	
				Earnest Money cost	₹ 1,200.00	
				Time	Two Month	
Sl. No.	Description of work	No. or Qty.	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	54.00	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gohar District
 H.P.W.D. Gohar

BILL OF QUANTITY


Name of work :- SDF/2025/501 R/O Baniseri to Kaneti Road Km 0/0 to 5/700 & SDF/2025/503 R/O Jailpul to Saryach Road Km 0/0 to 5/700 (SH:- Herring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)

Estimated cost Rs.	₹ 99,330.00
Earnest Money cost	₹ 2,000.00
Time	Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.30	Per Hour	₹ 1,100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.



 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/499 R/O Baniseri to Kaneti Road & SDF/2025/500 R/O Baniseri to Kaneti Road Km 0/0 to 4/0(SH:- Herring of JCB for removal of slips/debris, dressing of berms, clearance of drain etc. in various RDs)					Estimated cost Rs.	₹ 99,000.00
					Earnest Money cost	₹ 2,000.00
					Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.



Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/505 & SDF/2025/506 R/O Gani to Bhurani road Km 0/0 to 4/0 (SH:- Herring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)					Estimated cost Rs.	₹ 99,000.00
					Earnest Money cost	₹ 2,000.00
					Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.



Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- SDF/2025/502 R/O Jailpul to Saryach Road Km 0/0 to 2/0 & SDF/2025/504 R/O Jachh Lot					Estimated cost Rs.	₹ 99,330.00
Katesh Road Km 0/0 to 3/500 (SH:- Herring of JCB for removal of slips/debris, maintenance of earthen shoulders, clearance of drain etc. in various RDs)					Earnest Money cost	₹ 2,000.00
					Time	Two Month
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.30	Per Hour	₹ 1,100.00		
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be duly verified by the Engineer-in-Charge.
- 2 The owner shall be liable for any type of accident, incident resulting in damage or loss to private or government-owned property.
- 3 Driver and POL will be provided by the owner.


Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

105