



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 31.10.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 29.10.2025 up to 10:00 A.M. to 12:00 P.M. and tender form can be had from this office on 30.10.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	R/o Restoration of Damages on jeepable link road Badoun to Almerah (Sub Head:- Construction of edge wall, retaining wall at Km. 0/700 to 0/707) Deposit SDF SID:SDF/2022/391).	Rs. 80,786/-	Rs. 1,600/-	Rs. 350/-	Class "D"	Three Months
2	A/R & M/O Various road under Joginder Nagar Sub Division No. II HPPWD Joginder Nagar (Ladruhin Section) (Sub Head:- Supplying and stacking of crushed/ broken stone agg. 20mm, 10mm to 12.5mm and sand for Patch work)	Rs. 94,825/-	Rs. 1,900/-	Rs. 350/-	Class "D"	One Month
3	A/R and M/O to Majharu Siyuri Kufu road Km. 0/0 to 0/300 (Sub Head:- Construction of U-shape drain and Providing steel grating over Drain at Rd. 0/120).	Rs. 19,390/-	Rs. 400/-	Rs. 350/-	Class "D"	One Month
4	Construction of Balotu Kharon Pando road Km. 0/0 to 1/050 (Sub Head:- Formation cutting in Km. 0/150 to 0/360 under BASP deposit scheme ID BSP/2023/1128).	Rs. 96,638/-	Rs. 1,900/-	Rs. 350/-	Class "D"	Two Months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
3. For on behalf of Governor of Himachal Pradesh the Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
7. The contractor shall be responsible for rectifying defects noticed within six months from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
8. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc. or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
9. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking he will get complete the works in hand before award of work with in schedule time.
10. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
11. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/permit.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033.

No. PW-JND-B&R-EA-I/NIT/Press/2025-26-

14788-837

Dated:- 14/10/25

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Account Branch in this office.
9. Notice Board.
10. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

DNIT/DRAFT SCHEDULE OF QUANTITY

Job -1

Name of Work : R/O Restoration of rain damages on Jeepable link road Badoun to Almerah (Sh:-C Construction of edge wall, retaining wall km.0/700 to 0/707) Deposit SDF SID: SDF/2022/391

Estimate Cost: **80786/-**
Earnest Money: **1600/-**
Time Limit : Three Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	3.71	Per cubic metre	609.90	Ruppes Six Hundred Nine And Paise Ninety Only	2,22
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights (depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	12.04	Per cubic metre	6,135.15	Ruppes Six Thousand One Hundred Thirty Five And Paise Fifteen Only	73,86

Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST	2.73	Per cubic metre	1,104.30	Rupees One Thousand One Hundred Four And Paise Thirty Only	3.0
4 Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1(v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614. 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Each	328.25	Rupees Three Hundred Twenty Eight And Paise Twenty Five Only	1.6
Total					80.7

*Draft schedule of quantities approved for
₹ 80,786/- (₹ Eighty thousand seven hundred
eighty six) only*

Executive Engineer
B & R Division HP.P.W.D.
Joginder Nagar

Draft Schedule of Quantity

Name of work:- A/R & M/O various roads under Joginder Nagar, Sub Division No. II HP. PWD, Joginder Nagar (Ladruhin Section)
 Sub Head: Supplying and stacking of crushed/broken stone agg 20mm, 10mm to 12.5mm and sand for patch work

Estimated Cost:- 94825.00
 Earnest Money:- 98800.00
 Time:- 2000.00 19.00.00
 One month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking of Crushed/broken stone aggregate Grading-II 63mm to 40mm (sixty three millimeter to forty millimeter) nominal size at site for wearing free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack along roadside as per PWD specification and as desired by the Engineer-In-Charge within all leads and lifts complete in all respects. The rate is inclusive of all taxes including GST levy by the Govt. time to time	8.00	2000.00	Rupees Two thousand Two hundred and paise nil only	Per cubic metre	16000.00
2	Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect	22.50	2250/- -2400.00	Rupees Two thousand Four hundred and paise nil only	Per cubic metre	50625.00 -54000.00
3	Supply and stacking of coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect	12.00	2350/- -2400.00	Rupees Two thousand Four hundred and paise nil only	Per cubic metre	28200.00 28800.00
		Total:-		98800.00		

*Draft schedule of quantity approved for ₹ 94825 only
 (i.e. Ninety four thousand eight hundred twenty five) only*

Assistant Engineer,
 B&R Sub Division No. II,
 HP. PWD, Joginder Nagar

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

Job 3

300

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O to Majharu Sivuri Kufru road km 0/0 to 0/300.
(SH-Construction of T-shape Drain & Providing steel grating over Drain at RD 0/120)


Estimate Cost: 19,390.00
Earnest Money: 400.00
Time Limit: One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R. Technical specification section 300 & 1600 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiselling and wedging out rock (where blasting is prohibited). All earth work in cutting excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber, super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge. hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness, and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	1.75	Per cubic metre	609.90	Rupees Six Hundred Nine & Paise ninety only	1,067.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete Grade M-10 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time including GST.	0.96	Per cubic metre	7,383.80	Rupees Seven Thousand Three Hundred Eighty Three and Paise Eighty only	7,088.00

300

3	Steel work welded in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rates are inclusive cost and carriage of materials with in all loads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time including GST.	75.00	Per Kilogramme	149.80	Rupees one Hundred Forty Nine and Paise Eighty Only.	11,230
Total						19,390

As per Schedule of quantity approved for ₹ 19,390.00/-
 & Nineteen thousand Three hundred ninety only.


 Executive Engineer
 B & R Division HP, P.W.D.
 Jodhpur Nagar

E.No - 229

Job - 4

32

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Balotu Kharon Pando road km.0/0 to 1/050. (Sh:-Formation cutting in km. 0/150 to 0/360 under BASP deposit scheme ID BSP/2023/1128)

Estimate Cost: 96,638.00
 Earnest Money: 1,900.00
 Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 16.03cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	400.87	Per cubic metre	241.07	Rupees Two Hundred Forty One And Paise Seven Only	96,638.00
Total						96,638.00

326

Draft Schedule Quantity checked and approved for
 (96,638) Ninety Six Thousand Six hundred Thirty-eight.

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)

E.No - 229

Job - 4

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: Construction of Balotu Kharon Pando road km.0/0 to 1/050. (Sh.-Formation cutting in km. 0/150 to 0/360 under BASP deposit scheme ID BSP/2023/1128)

Estimate Cost: 96,638.00
 Earnest Money: 1,900.00
 Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 16.03cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work contract. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time including GST.	400.87	Per cubic metre	241.07	Rupees Two Hundred Forty One And Paise Seven Only	96,638.00
Total						96,638.00

Draft Schedule Quantity checked and approved for
 (2-96,638) Ninety six Thousand Six hundred Thirty-eight.

Executive Engineer
 B&R Division, HPPWD
 Joginder Nagar (H.P.)