

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on **or 09.10.2025 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interesting contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM &** without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **08.10.2025.**

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1.	RRD on various roads under Kotli Sub Division HPPWD Kotli. (Gokhara Section) (SH:- Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders which can not be removed or lifted with JCB).	Rs 99,825	Rs 2,000	Rs. 350	One Month
2.	A/R and M/O various road under Mandi Sub Division No. IV HPPWD Mandi (Ganpati Section) (SH:-Hiring of Hydraulic Excavator (210 TATA Hitachi or its equivalent) 1.00/1.35 Cum capacity for removal of mucks and other debries) Job No-1	Rs 97,350	Rs 2,000	Rs. 350	One Month
3.	A/R and M/O various road under Mandi Sub Division No. IV HPPWD Mandi (Ganpati Section) (SH:-Hiring of Hydraulic Excavator (210 TATA Hitachi or its equivalent) 1.00/1.35 Cum capacity for removal of mucks and other debries) Job No-2	Rs 97,350	Rs 2,000	Rs. 350	One Month
4.	A/R and M/O on Link road to village Pajethi km 0/00 to 2/00 (SH:- Providing and applying 2.5mm (two point five millimeter) thick road marking strips in km 1/00 to 2/00) Hill and valley side)	Rs 78,000	Rs 1,600	Rs. 350	One Month
5.	RRD on various roads under Kotli Sub Division HPPWD Kotli.(Saigaloo Section) (SH:- Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders which can not be removed or lifted with JCB).	Rs 99,825	Rs 2,000	Rs. 350	One Month
6.	RRD on various roads under Mandi Sub Division no-IV HPPWD Mandi (Randhara Section) (SH:- Hiring of J.C.B for removal of slips and dressing of berms etc)	Rs 99,000	Rs 2,000	Rs. 350	One Month
7.	A/R and M/o various road under Mandi Sub Division No-IV HPPWD Mandi (Ganpati Section) (SH:- Hiring of Tipper for carriage of muck and other misc. materials) Job-II	Rs 99,000	Rs 2,000	Rs. 350	One Month
8.	A/R and M/o various road under Mandi Sub Division No-IV HPPWD Mandi (Ganpati Section) (SH:- Hiring of Tipper for carriage of muck and other misc. materials) Job-I	Rs 99,000	Rs 2,000	Rs. 350	One Month
9.	Special repair of District Attorney residence at jail road Mandi. Sub Head:- Construction of boundary wall	Rs 68,248	Rs 1,400	Rs. 350	One Month
10.	Annual repair and maintenance of nonresidential building Class-III at jail road Mandi Distt. Mandi (H.P.). Sub Head:-Providing and laying painting on wood and steel work etcetera	Rs 73,435	Rs 1,500	Rs. 350	One Month
11.	Annual repair and maintenance of residential building under Mandi Division No.II at Jail road Mandi Distt. Mandi (H.P.). Sub Head: Providing and fixing tile flooring and flooring mat works etc. in Type-IV Qtr. No.6).	Rs 94,145	Rs 1,900	Rs. 350	One Month

CERTIFICATE

It is certified that the above works are required to be carried out immediately, being of emergent nature and in the larger public interest.

Tender Notice – Terms & Conditions

The tender documents shall be issued only to those Contractors/Firms who submit the following documents along with their application:

1. Valid enlistment/registration of contractor in the appropriate class.
2. Permanent Account Number (PAN).

3. GST Registration Number.
4. Earnest money in the shape of National Saving Certificate/Time Deposit Account in any Post Office in Himachal Pradesh, or F.D.R. from any Nationalized Bank duly pledged in favour of the Executive Engineer, Mandi Division No. 2, HPPWD, Mandi H.P.
5. Earnest money and cost of tender form for the above works must be submitted along with the application for purchase of tender form. Applications received without earnest money and cost of tender form shall be summarily rejected.
6. The offer of the tender shall remain valid for 75 (seventy-five) days after the opening of the tender.
7. Ambiguous, telephonic, conditional tenders or tenders submitted by fax/e-mail shall not be considered and will be summarily rejected.
8. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reason.
9. If the date specified above happens to be a holiday, the tenders shall be processed on the next working day.
10. The Contractor/Firm must quote their rates both in words as well as in figures, failing which the Executive Engineer reserves the right to accept or reject any or all tenders.
11. Tender forms shall not be issued to those Contractors/Firms whose past performance is not found satisfactory or who have failed to complete previously awarded works within the stipulated period.
12. No contractor shall have more than two major works in hand at a time.
13. The work shall be completed by the Contractor within the stipulated period.

No.PW-MDII-CB NIT (off line) /2025-

10638-51

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A. E, S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies.

Executive Engineer
Mandi Division No. II
HP.PWD Mandi

Dated: 23/10

2025


Executive Engineer
Mandi Division No. II
HP.PWD Mandi

Name of work :- RRD on various roads under Kotli Sub Division HP PWD Kotli. (Gokhara Section)
 (SH:- Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders which can not be removed or lifted with JCB.)

percentage Rate SCHEDULE OF QUANTITY

Estimated Cost Rs.99,825-
 Earnest Money Rs. 2000/-
 Time :- One month.

No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	55.00	1815.00	Rupees One Thousand Eight Hundred Fifteen Only	Per day	99825.00
					Total	99825.00


 Executive Engineer,
 Mandi Division No-II
 HP.PWD. Mandi.

Percentage Rate SCHEDULE OF QUANTITY

A/R & M/O Various road under Mandi Sub Division No.IV HPPWD,Mandi (Ganpati Section)

(SH:- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum Capacity for removal of mucks and other debris) Job No.-1

Estimated Cost Rs. 97,350/-
 Earnest Money Rs. 2000/-
 Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) bucket capacity to be deployed for cutting/excavating including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge.	33.00	2950.00	Rupess Two Thousand Nine Hundred Fifty Only	Per Hour	97,350.00
					Total	97,350.00

Conditions:- Contractor should have his own machinery or he should have an agreement with the owner of the machinery.


Executive Engineer,
 Mandi Division No-II,
 HP.PWD, Mandi.

Percentage Rate SCHEDULE OF QUANTITY
A/R & M/O Various road under Mandi Sub Division No.IV HPPWD, Mandi (Ganpati Section)
 (SH:- Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum Capacity for
 removal of mucks and other debris) Job No.-II

Estimated Cost Rs. 97,350/-
 Earnest Money Rs. 2000/-
 Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Hydraulic Excavator (210TATA Hitechi or its equivalent) 1.00/1.35 Cum (one point zero zero/one point three five cubic metres) bucket capacity to be deployed for cutting/excavating including cost of fuel oil lubricants and wages of operating staff. Any repair/breakage during operation will be carried out by the Contractor/owner at his own risk and cost including shifting of machinery from one place to other place will be absolute responsibility of the Contractor. only actual working hours will be accounted for the payment earth cutting/removal of slips, excavation in all kinds of soil including loading in to tipper/trucks and disposal of all excavated earth in all leads and lifts to the entire satisfaction of the Engineer-in-charge.	33.00	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per Hour	97,350.00
	Total					97,350.00

Conditions:- Contractor should have his own machinery or he should have an agreement with the owner of the machinery.


 Executive Engineer,
 Mandi Division No-II,
 HP.PWD. Mandi.

Percentage Rate SCHEDULE OF QUANTITY

Name of work :-

AA/R & M/O on Link road to village Pajethi km 0/00 to 2/00 (SH :- Providing and applying 2.5 mm (two point five millimetre) thick road marking strips in km 1/400 to 2/00) Hill and valley side)

Estimated cost Rs. 78,000/-
Earnest Money Rs. 1,600/-
Time:- One month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Providing and laying of hot applied thermoplastic road marking paint compound 2.5mm (two point five millimetre) thick including reflectorising glass beads @ 250 grms. (two hundred fifty grams) per square metre area, thickness of 2.5 mm (two point five millimetre) is exclusive of surface applied a glass beads as per IRC 35. The finished surface is to be level, uniform and free from streaks and holes as per MORT&H specification clause 803 including all leads and lifts of materials, machinery by all modes of transportation and other incidental charges required to complete the job to the entire satisfaction of Engineer-in-charge, including carriage of materials with in all leads, lifts and other incidentals.	120.00	650.00	Rupees Six Hundred Fifty Only	Per Square metre	78,000.00
Total						78,000.00


 Executive Engineer,
 Mandi Division No-II,
 HP. PWD, Mandi.

Name of work :-

RRD on various roads under Kotli Sub Division HP PWD Kotli. (Saugaloo Section)
 (SH:- Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders which can not be removed or lifted with JCB.)

Percentage Rate SCHEDULE OF QUANTITY

Estimated Cost Rs. 99,825-
 Earnest Money Rs. 2000/-
 Time :- One month.

No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Hydraulic Excavator with rock breaker for breaking of large boulders from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	55.00	1815.00	Rupees One Thousand Eight Hundred Fifteen Only	Per day	99825.00
					Total	99825.00



Executive Engineer,
 Mandi Division No-II
 HP.PWD. Mandi.

%age rate of SCHEDULE OF QUANTITY

Name of work :- RRD on various roads under Mandi Sub Division no-IV HP PWD Mandi (Randhara Section)
(SH :- Hiring of J.C.B for removal of slips & dressing of berms etc.)

Estimated Cost Rs. 99,000/-
Earnest Money Rs. 2000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of J.C.B for removal of slips & dressing of berms etc and trimming of side slopes and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99,000.00
					Total	99,000.00



Executive Engineer,
Mandi Division No-II,
HP.PWD. Mandi.

Percentage Rate SCHEDULE OF QUANTITY

of work :- A/R & M/O various road under Mandi Sub Division No-IV HPPWD Mandi. (Ganpati Section)
 (SH:- Hiring of Tipper for carriage of muck and other misc. materials) Job-II

Estimated Cost Rs. 99,000/-
 Earnest Money Rs. 2000/-
 Time :- One month

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper on daily wages with P.O.L. and lubricants including driving staff of carriage of materials/removal of debris from road side up to all leads & lifts and as per direction and entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) during working day/Sunday/ Holiday any loss to the public/property or any accident etc. happened during the course of hiring period shall be the absolute responsibility by him in all cases. The repair and spare, watch and ward of the Tipper also be borne by the contractor/ owner. The daily log book shall be maintained at site which should be verified by the Engineer-in-charge.	33.00	3000.00	Rupees Three Thousand Only	Per day	99,000.00
Total						99,000.00


Engineer,
 Mandi Division No-II,
 HP.PWD. Mandi.


Percentage Rate SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various road under Mandi Sub Division No-IV HPPWD Mandi. (Ganpati Section)
 (SH:- Hiring of Tipper for carriage of muck and other misc. materials) Job-1

Estimated Cost Rs. 99,000/-
 Earnest Money Rs. 2000/-
 Time :- One month

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1		3	4	5	6	7
		33.00	3000.00	Rupess Three Thousand Only	Per day	99,000.00
					Total	99,000.00

Hiring of Tipper on daily wages with P.O.L. and lubricants including driving staff of carriage of materials/removal of debris from road side up to all leads & lifts and as per direction and entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) during working day/Sunday/ Holiday any loss to the public/property or any accident etc. happened during the course of hiring period shall be the absolute responsibility by him in all cases. The repair and spare, watch and ward of the Tipper also be borne by the contractor/ owner. The daily log book shall be maintained at site which should be verified by the Engineer-in-charge.


 Executive Engineer,
 Mandi Division No-II,
 HP.PWD, Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 68248.00
 Earnest Money:- Rs. 1400.00
 Time:- One Month

Name of work:- Special repair of District Attorney residence at jail road Mandi.
 Sub Head:- Construction of boundary wall.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Earth work in excavation for all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten squaremetre) on plan), including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	3 24 Cum.	233.10	Rupees Two Hundred Thirty Three and Paise Ten Only	Per cubic metre	755.00
2	Providing and laying in position reinforced cement concrete 1:5:10 (one cement five coarse sand ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) excluding the cost of centering, shuttering, in all works up to all floor level including curing complete within all leads and lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	3 24 Cum.	5044.60	Rupees Five Thousand Forty Four and Paise Sixty Only	Per cubic metre	16345.00
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor all level in cement mortar 1:3 (one cement : three sand) complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	36 00 Sqm	1300 25	Rupees One Thousand Three Hundred and Paise Twenty Five Only	Per square metre	46809.00
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in super structure above plinth level upto all level in all shapes and sizes in cement mortar 1:4 (one cement : four sand) complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	0 40 Cum.	10848.50	Rupees Ten Thousand Eight Hundred Forty Eight and Paise Fifty Only	Per cubic metre	4339.00
Total:-						68248.00


Executive Engineer,
 Mandi Division No. II,
 HP PWD Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 73435.00
 Earnest Money:- Rs. 1500.00
 Time:- One Month

Name of work:- Annual repair and maintenance of non residential building Class-III at jail road Mandi Dist. Mandi (H.P.).
 Sub Head:- Providing and laying painting on wood and steel work etcetera.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Painting wood work with Deluxe Multi Surface Paint of required shade two or more coat applied @ 0.90 ltr/10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.75 ltr/10 sqm (at the rate of zero point seven five litre per ten square metre) of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	203.09	136.70	Rupees One Hundred Thirty Six and Paise Seventy Only	Per square metre	27762.00
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade two or more coats applied @ 0.90 ltr/10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm (at the rate of zero point eight zero litre per ten square metre) of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	5.02	137.70	Rupees One Hundred Thirty Seven and Paise Seventy Only	Per square metre	691.00
3	Finishing walls with Acrylic Smooth exterior paint of required shade on old work (two or more coats applied @ 1.67 ltr/10 sqm (at the rate of one point sixty seven litre per ten square metre) including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	214.25	209.95	Rupees Two Hundred Nine and Paise Ninety Five Only	Per square metre	44982.00
Total:-						73435.00


 Executive Engineer,
 Mandi Division No.II,
 MP PWD, Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 94145.00
 Earnest Money:- Rs. 1900.00
 Time:- One Month

Name of work:- Annual repair and maintenance of residential building under Mandi Division No.11 at Jail road Mandi Dist. Mandi (H.P.).

Sub Head:- Providing and fixing tile flooring and flooring mat works etc. in Type-IV Qtr. No.6).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and laying Duro stone vetrified tiles (450mmx200mm x 8mm) (four hundred fifty into two hundred into eight millimetre) in grey/coloured of required shade in skirting risers of steps and dados on 12mm (twelve millimetre) thick cement mortar 1:3 (one cement . three sand) laid over and jointed with neat cement slurry finished with flush pointing in white cement mixed with pigment of required shade to match the shade of tiles complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge..	29.52	2743.45	Rupees Thousand Hundred Forty and Paise Only	Two Per square metre	80987.00
2	Providing and fixing flooring mat plain or coloured, carbed or mosaic/ metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) of superior quality complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.88	1331.75	Rupees Thousand Hundred Thirty and Paise Five Only	One Per square metre	13158.00
Total:-						94145.00


 Executive Engineer,
 Mandi Division No.11,
 NP PWD Mandi.