

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-NHD-GA-TENDER/2025-26 · 5081-82

Dated: 04/10/2025

To

The Executive Engineer,
IT Cell Nirman Bhawan Nigam Vihar,
HP,PWD Shimla-02 (H.P)..


Subject:-

Regarding uploading of NIT on HP,PWD website .

Please find enclosed herewith the tender notice for the works as given in the Notice inviting tender for uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of (H.P.) letter No. PBW(B)A(3) 1/2024 dated 03 Jan 2024. The work mentioned in the tender notice are urgent in nature and public interest.

This is for your kind information and necessary action at your end please.

Encl:-NIT & copy of schedule of quantity.



Executive Engineer,
National Highway Division
HP,PWD Hamirpur.

Copy to the Superintendent Engineer, National Highway Circle HP.PWD Shahpur for information please.

Executive Engineer,
National Highway Division,
HP,PWD Hamirpur.

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-NHD-GA-TENDER/2025-26 5081-82 Dated:- 04-10-2025 are urgent nature.


Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)



HIMACHAL PRADESH
Public Works Department

NOTICE INVITING TENDER

Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by Executive Engineer, NH Division, HPPWD, Hamirpur (H.P) from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on **15.10.2025** up to 11.00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received on dated **13.10.2025** up to 11:30 P.M. on cash payment of Rs. 350/- (Non-Refundable) and tender document will be issued on **14.10.2025** up to 1:00 P.M. If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.


Sr. No	Name of Work	Estimated cost	Earnest money	Time allowed	Class of Contractor
1	Restoration of Road damages on NH -503 Km 0/00 to 23/105 (Section Matour Dharmsala Macleodganj) (SH:- Construction of Sub grade at RD 21/030 to 21/060 and 21/900 to 21/925.(Deposit work).	99788.00	2000.00	One Month	Class-D
2	Restoration of Road damages on NH -503 Km 0/00 to 23/105 (Section Matour Dharmsala Macleodganj) (SH:- Construction of Sub grade at RD 18/920 to 18/940, 20/690 to 20/718 and 22/950 to 22/960.(Deposit work).	98719.00	2000.00	One Month	Class-D
3	Restoration of Road damages on NH -503 Km 0/00 to 23/105 (Section Matour Dharmsala Macleodganj) (SH:- Construction of Sub grade at RD 18/900 to 18/920 and 22/930 to 22/950.(Deposit work).	98719.00	2000.00	One Month	Class-D
4	Restoration of Road damages on NH -303 Km 0/00 to 39/0.(SH:-Removal of slips at various stretches).(Deposit work).	97192.00	2000.00	One Month	Class-D
5	Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmsala Macleodganj) (SH:- Construction of Edge wall and parapet at RD 18/260 to 18/267).(Deposit work).	99911.00	2000.00	One Month	Class-D
6	Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmsala Macleodganj) (SH:- Construction of Edge wall and parapet at RD 18/265.5 to 18/272.5).(Deposit work).	99911.00	2000.00	One Month	Class-D
7	Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmsala Macleodganj) (SH:- Excavation for foundation of R/wall in wire crate at km 14/613.2 to 14/640.(Deposit work).	99548.00	2000.00	One Month	Class-D
8	Restoration of road damages on NH- 70(03) at Km 58/400 to 114/00 (SH:- Hiring of excavator cum loader / Tipper in Km. 100/0 to 106/0. (Deposit work)	99900.00	2000.00	One Month	Class-D
9	Restoration of road damages on NH- 70(03) at Km 58/400 to 114/00 (SH:- Hiring of excavator cum loader / Tipper in Km. 106/0 to 114/0 . (Deposit work)	99900.00	2000.00	One Month	Class-D
10	Restoration of road damages on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of crate wire work at km. 58/780 to 58/785(LHS) (Deposit work)	92292.00	2000.00	One Month	Class-D
11	Restoration of road damages on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of crate wire work at km. 58/788 to 58/793(LHS) (Deposit work)	92292.00	2000.00	One Month	Class-D

12	Restoration of road damages on NH- 503 A. at Km 0/0 to 70/0 (SH:- Construction of V-shape drain at Km. 50/800 to 50/895 (Deposit work)	97185.00	2000.00	One Month	Class-D
----	---	----------	---------	-----------	---------

Draft notice inviting/ specification special conditions can be seen in this office on any working day, ambiguous/ conditional tenders shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application: -

1. A copy of valid enlistment and renewal certificate.2. A copy of GST.3 Earnest Money duly pledged in favour of Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage, the tender is liable to be rejected and action taken against contractor/firm.


Executive Engineer,
NH Division, HPPWD
Hamirpur.




DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmasala Macleodganj) (SH:-
Construction of Sub gradeat RD 21/030 to 21/060 and 21/900 to 21/925.(Deposit work).

Sr No.	Description of Item.	Qty.	Rate		Unit	Amount	Estimated	One Month
			In Figure	In Words			Cost:- Rs.	Amount
1	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2.The rate including Octroi, Royalty, Malkhana, toll tax, GST or other taxes imposed by the Govt. including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	266.10	375.00	Rupees three hundred seventy five and paise nil only	Per Cubic Metre	99788.00	2000.00	99788.00
G.Total						99788.00		

Draft schedule of Quantity checked and Approved for Rs 99788/- only


 Executive Engineer,
 National Highway Division,
 HP.PWD, Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmasala Macleodganj) (SH:- Construction of Sub gradeat RD 18/920 to 18/940, 20/690 to 20/718 and 22/950 to 22/960.(Deposit work).

Sr No.	Description of Item.	Qty.	Rate		Unit	Amount	Estimated
			In Figure	In Words			Cost:- Rs.
1	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2.The rate including Octroi, Royalty, Malkhana, toll tax, GST or other taxes imposed by the Govt. including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	263.25	375.00	Rupees three hundred seventy five and paise nil only	Per Cubic Metre	98719.00	98719.00
G.Total						98719.00	2000.00

D. Draft schedule of Quantity checked and Approved for Rs 98719/- only

had
Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)


DRAFT SCHEDULE OF QUANTITY

Old No-2

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmasala Macleodganj) (SH:- Construction of Sub gradeat RD 18/900 to 18/920 and 22/930 to 22/950.(Deposit work).

Sr No.	Description of Item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2.The rate including Octroi, Royalty, Malkhana, toll tax, GST or other taxes imposed by the Govt. including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	263.25	375.00	Rupees three hundred seventy five and paise nil only	Per Cubic Metre	98719.00
G.Total						98719.00

Draft schedule of quantity checked and approved for Rs 98719/- only


 Executive Engineer,
 National Highway Division,
 HP.PWD, Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -303 Km 0/00 to 39/0. (SH:- Removal of slips at various stretches) (Deposit work).

Estimated Cost:- Rs. 97192.00
 Earnest Money:- Rs. 2000.00
 Time Limit:- One Month

Sr No.	Description of Item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611. including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	830.70	117.00	Rupees One hundred seventeen and paise nil only	Per Cubic Metre	97192.00
G.Total						97192.00

Draft schedule of quantity checked and approved for Rs. 97192/- only

hpw

Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmasala Macleodganj) (SH:-

Construction of Edge wall and parapet at RD 18/260 to 18/267).(Deposit work).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount	Estimated
			In Figure	In Words			Cost:- Rs. :-
1	Plain cement concrete M15(M-Fifteen) nominal mix in foundation with crushed stone aggregate nominal size mechanically mixed placed in foundation and compacted by vibration including curing for 14 days from work with steel plates to give a fair finish centring shuttering, strutting propping and removal of the same including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	20.39	4900.00	Rupees four thousand Nine hundred and paise nil only	Per Cubic Metre	99911.00	2000.00
G.Total						99911.00	

Draft Schedule of Quantity checked and approved for Rs 99911/- duly


Spool
 Executive Engineer,
 National Highway Division,
 HP.PWD Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dharmasala Macleodganj) (SH:-
 Consti.uction of Edge wall and parapet at RD 18/265.5 to 18/272.5).(Deposit work).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount	Estimated
			In Figure	In Words			Cost:- Rs.
1	Plain cement concrete M15(M-Fifteen) nominal mix in foundation with crushed stone aggregate nominal size mechanically mixed placed in foundation and compacted by vibration including curing for 14 days from work with steel plates to givn a fair finish centring shuttering, strutting propping and removal of the same including carriage of materials upto all leads and lifts as per dirrection of the Engineer-in-charge.	20.39	4900.00	Rupees four thousand Nine hundred and paise nil only	Per Cubic Metre	99911.00	99911.00
G.Total						99911.00	99911.00

*Draft schedule of Quantity checked and
 Approved for Rs. 99911/- only*


 Executive Engineer,
 National Highway Division,
 HP.PWD, Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages on NH -503 Km 0/00 to 23/105(Section Matour Dhamsala Macleodgari) (SH:-
Excavation for foundation of R/wall in wire crate at km 14/613.2 to 14/640.(Deposit work).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount	Estimated	One Month
			In Figure	In Words			Cost:- Rs.	Time Limit:-
1	Earth work in excavation of foundation of structures as per drawing and technical specification,including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling with approved material.	497.74	200.00	Rupees two hundred and paise nil only	Per Cubic Metre	99548.00	2000.00	
G.Total						99548.00		

Draft schedule of quantity checked and approved for Rs. 99548/- Only,


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages on NH- 70(03) . at Km 58/400 to 114/00 (SH:- Hiring of excavator cum loader / Tipper in Km. 100/0 to 106/0. (Deposit work)

Sr No.	Description of item.	Qty.	Rate		Unit	Estimated Cost:- Rs.	One Month Amount
			In Figure	In Words			
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil i/c rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. The machine/JCB should work minimum 8:00 hours from 9:00 am to 5:00 pm daily and remove atleast 25 cum quantity of slips per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/Excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	59.00	1100.00	Rupees One thousand one hundred and paise nil only	Per Hours	64900.00	64900.00
2	Hiring of Tipper for carriage of debris/muck/unserviceable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of the Engineer-in-Charge. (9.00 am to 5.00 PM)	10.00	3500.00	Rupees three thousand five hundred and paise nil only	Per day	35000.00	35000.00
G.Total							99900.00

Drafts Schedule of Quantity checked and approved for Rs. 99900 only (Ninty nine thousand nine hundred only.)

For
Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

Name of work :- Restoration of road damages on NH- 70(03) . at Km58/400 to 114/00 (SH:- Hiring of excavator cum loader / Tipper in Km. 106/0 to 114/0 . (Deposit work)

DRAFT SCHEDULE OF QUANTITY

Sr No.	Description of item.	Qty.	Rate		Unit	Estimated Cost:- Rs.	One Month Amount
			In Figure	In Words			
1	Hiring of JCB/Excavator for removal of Slips and boulders in all kind of soil i/c rocky portion and saturated soil and disposing of all excavated earth or un-serviceable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. The machine/JCB should work minimum 8.00 hours from 9.00 am to 5.00 pm daily and remove atleast 25 cum quantity of slips per hour. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	59.00	1100.00	Rupees One thousand one hundred and paise nil only	Per Hours	64900.00	64900.00
2	Hiring of Tipper for carriage of debris/muck/unserviceable material from the various reaches of the road including all leads, lifts and unloading of material at suitable places as per entire satisfaction of the Engineer-in-Charge. (9.00 am to 5.00 PM)	10.00	3500.00	Rupees three thousand five hundred and paise nil only	Per day	35000.00	35000.00
G.Total							99900.00

Draft's schedule of quantity checked and approved for Rs 99900 only (Rupees Ninety Nine thousand nine hundred only.)

Executive Engineer,
National Highway Division,
HP.PWD., Haridwar (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of crate wire work at km. 58/780 to 58/785) (LHS) (Deposit work)

Estimated Cost:- Rs. 92292.00
 Earnest Money:- Rs. 2000.00
 Time Limit:- One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	15.63	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	3126.00
2	Providing and laying, of boulder apron laid in wire crates made with 4mm dia GI wire conforming to IS : 280 & IS : 4826 in 100 mm x 100 mm (Hundred into hundred millimetre)mesh (weaved diagonally) including 10 percent (Ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 kg (Twenty Five Kilogram) each including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	23.44	3700.00	Rupees Three thousand Seven hundred and paise nil only	Per Cubic metre	86728.00
3	Back filling with granular material wing walls, return walls and retaining walls complete as per drawing and MORT&H specifications clause 1204.3.8 and as per diretion of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	3.75	650.00	Rupees Six hundred fifty and paise nil only	Per Cubic metre	2438.00
G Total						92292.00

Drafts schedule of quantity checked and approved for Rs. 92292.00 (Rupees Ninety Two thousand Two hundred Ninety Two only)

Executive Engineer,
 National Highway Division,
 HP, PWD, Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages on NH- 503 A. at Km 0/0 to 70/00 (SH:- Construction of crate wire work at km. 58/788 to 58/793 (LHS) (Deposit work)

Sr No.	Description of Item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305 1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	15.63	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	3126.00
2	Providing and laying of boulder apron laid in wire crates made with 4mm dia GI wire conforming to IS : 280 & IS : 4826 in 100 mm x 100 mm (Hundred into hundred millimetre)mesh (weaved diagonally) including 10 percent (Ten percent) extra for laps and joints laid with stones boulders weithing not less than 25 kg (Twenty Five Kilogram) each including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	23.44	3700.00	Rupees Three thousand Seven hundred and paise nil only	Per Cubic metre	86728.00
3	Back filling with granular material wing walls, return walls and retaining walls complete as per drawing and MORT&H specifications clause 1204.3.8 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	3.75	650.00	Rupees Six hundred fifty and paise nil only	Per Cubic metre	2438.00
G.Total						92292.00

Doth's schedule of quantity checked and approved for Rs. 92292 only. (Rupees Ninety Two thousand Two Hundred Ninety Two only.)

Executive Engineer,
National Highway Division,
HP.PWD., Haridpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages on NH- 503 A. at Km 0/0 to 70/0 (SH:- Construction of V-shape drain at Km. 50/800 to 50/895 (Deposit work)

Estimated Cost:- Rs.	97185.00
Earnest Money:- Rs.	2000.00
Time Limit:-	One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm, (One hundred fifty millimetre) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi, royalty, Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	17.10	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	3420.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802, 803, 1202 and 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi, royalty, Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	19.95	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	93765.00
G.Total						97185.00

Drafts schedule of quantity checked and approved for Rs. 97185/only (Rupees ninety seven thousand one hundred eighty five only)

Executive Engineer,
National Highway Division,
HP.PWD., Haripur (HP)