

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed **percentage rate** tender on form No. 6 and 7/8 are hereby invited by the **Executive Engineer (NH) Division HPPWD Nahan** on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD, so as to reach in this office on **30-10-2025** up to 11:00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to **29-10-2025 04:00 PM**


The earnest money in the shape of FDR/TDR of any Bank in H.P. duly pledged in favour of Executive Engineer NH Division HP.PWD Nahan must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Eligible Class of contractor	Cost of Form
1	A/R & M/O to Kala Amb Paonta Sahib Dehradun road on NH-07 Km 46/00 to 103/00 (SH:- Laying of cement concrete paver block at Majra near median on taper portion towards Nahan side (LHS and Paonta Sahib side) (LHS) at RD 88.870.	99473/-	2000/-	01 Month	"C" & "D"	350/-
2	A/R & M/O to Kala Amb Paonta Sahib Dehradun road on NH-07 Km 46/00 to 103/00 (SH:- Laying of cement concrete paver block at Majra near median on taper portion towards Paonta side (RHS) at RD 88.870.	99566/-	2000/-	01 Month	"C" & "D"	350/-

CERTIFICATE:- It is certified that the tenders of above work are exigency/emergent nature and in public interest.

Terms & Conditions:-

1. The Contractors/Bidders must quoted their Permanent Income Tax Account Number/ GST number on the tender alongwith copy of the same be attached with the application.
2. The Contractors/Firms should attach copy of the Registration/Renewal with the application.
3. The contractor/bidders should quote his rates Both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firms should have to produce the details of works in hand in HP. PWD, and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any PWD Circle/ Division worth Rs. 1.00 Crore each.
8. The Contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The provision of guidelines issued vide the Principal Secretary (PW) to the Govt. of H.P, Shimla vide notification No. PBW (B) A (3) 1/2020-I dated Shimla-2 the 22nd July, 2020 and 07.10.2021 regarding adoption of CPWD work manual 2019 & other publication of CPWD in HPPWD and others as published by the Govt. from time to time Shall also be applicable.
11. The Executive Engineer reserve the right to reject any or all the tenders without assigning any reason.



Executive Engineer
NH Division HPPWD
Nahan
Tele No. 01702-222202

For & on behalf of Governor of Himachal Pradesh

No. PW/NHD-NHN/TA-Tender Notice/ 2023-24: 3552-67 dated:- 21-10-2025
Copy along with NIT is forwarded to the following for kind information and necessary action please:-

- 1 The Engineer in Chief HPPWD Nirman Bhawan, Niagam Bihar Shimla.
- 2 The Chief Engineer (NH) HPPWD Shimla please.
- 3 The Deputy Commissioner, Sirmour at Nahan please.
- 4 The Superintending Engineer (NH) Circle HPPWD Shimla.

- 5 The Executive Engineer (IT Cell), to the Engineer-in-Chief HPPWD, Nigam Vihar, HPPWD Shimla-2 alongwith Schedule of Quantity through (email) for taking necessary action in view of Principal Secretary (PW) to the H.P. notification No. PBW (B) A (3) dated 16 July, 2021 for uploading of Notice Inviting Tender on departmental website please.
- 6 The Sub-Divisional Magistrate Nahan/ Paonta Sahib/Pachhad please.
- 7 The District Panchayat Officer, Nahan please.
- 8 The Executive Officer, Municipal Committee Nahan/ Paonta Sahib please.
- 9 All the Assistant Engineer under this division to display on their respective Notice Boards.
- 10 Notice Board of this Office.


Executive Engineer
NH Division HPPWD
Nahan


2021-07-19 11:22

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O to Kahaamb Paonta Sahib Dehradun road on NH-07 km 46/00 to 103/00 (SH:- Laying of cement concrete paver block at Majra near median on taper portion towards Nahans side (LHS and paonta sahib side) (LHS) at RD 88.870.

Sr.No	Description of item/Sub Head	Quantity	Unit	Estimated cost :-		Total Amount	Total Amount in word
				Time Limit :- Earnest Money :-	Estimate Rate		
1	2	3	4	5	6	7	8
1	Earth work in excavation of foundation of structures as per drawing and technical specification as per clause 304 of Month Specification (latest revision), including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. Ordinary Soil Manual Means - stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	5.61	Per Cubic metre	361.35	2027.00	Rupees two thousand twenty seven	
2	Providing concrete for plain/reinforced concrete P.C.C grade M 10 (Ten) 1:3:6 (One cement :Three sand and six graded stone aggregate 40mm(Forty millimetre) nominal size) in open foundations complete as per drawings and technical specifications including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	5.43	Per Cubic metre	6071.45	32968.00	Rupees thirty two thousand nine hundred sixty eight only	
3	Providing and laying Plain Cement Concrete / Reinforced cement concrete in PCC M20 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	0.77	Per Cubic metre	6836.80	5264.00	Rupees five thousand two hundred sixty four only	
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks (80 mm thick) in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-charge.	36.21	Per Sqm	1635.30	59214.00	Rupees fifty nine thousand two hundred fourteen only	
Quoted Rate % (Percentage) in Figures		(+)/(-)			99473.00	Rupees ninety nine thousand four hundred seventy three only	
Quoted Rate % (Percentage) in Words							

The contractor shall procure all the materials conforming to MORT&H specification at his own risk and cost. All the rates inclusive of GST.


 Executive Engineer
 NH Division
 HPPWD Nahans

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O to Kalaamb Paonta Sahib Dehradun road on NH-07 km 46/00 to 103/00 (SH)- Laying of cement concrete paver block at Majra near median on taper portion towards paonta sahib side (RHS) at RD 88.870.

Sr.No	Description of Item/Sub Head	Quantity	Unit	Estimate Rate	Total Amount	Total Amount in word
1	Earth work in excavation of foundation of structures as per drawing and technical specification as per clause 304 of Month Specification (latest revision), including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. Ordinary Soil Manual Means, stacking the useful materials and disposal of unserviceable materials in all leads & lifts. Any loss to public/private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	5.73	Per Cubic metre	361.35	2071.00	Rupees two thousand seventy one
2	Providing concrete for plain/reinforced concrete P.C.C grade M10 (Ten) 1:3:6 (One cement : Three sand and six graded stone aggregate 40mm(Forty millimetre) nominal size) in open foundations complete as per drawings and technical specifications including all leads, lifts and carriage of materials as per the direction and entire satisfaction of the Engineer-in-charge.	5.54	Per Cubic metre	6071.45	33636.00	Rupees thirty three thousand six hundred thirty six only
3	Providing and laying Plain Cement Concrete / Reinforced cement concrete in PCC M20 Grade in open Foundation complete as per Drawing and technical specifications clause 1500.1700.2100, in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	0.50	Per Cubic metre	6836.80	3418.00	Rupees three thousand four hundred eighteen only
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks (80 mm thick) in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-charge.	36.96	Per Sqm	1635.30	60441.00	Rupees sixty thousand four hundred forty one only
Total :-					99566.00	Rupees ninety nine thousand five hundred SIXTY six only
Quoted Rate % (Percentage) in Figures		(+ / -)				
Quoted Rate % (Percentage) in Words						

The contractor shall procure all the materials conforming to MORT&H specification at his own risk and cost. All the rates inclusive of GST.


 Executive Engineer
 NH Division
 HPPWD Nahana

768.2