

Himachal Pradesh
Public Works Department

No. PWH/HD/CB/T-I/2025-26
To

6501-03

Dated: -18/10/2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP)


Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,
HPPWD Division Haroli,
Distt. Una (HP).

Certificate

Certified that the tenders for the works called vide this office letter
PWH/HD/CB/T-1/2025-26- 6501-03 dated 18/10/2025 are required to be carried out
immediately being emergent nature of work in public interest.


Executive Engineer,
Haroli Division, HPPWD
Haroli Dist. (Una HP).

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

“ NOTICE INVITING TENDERS ”

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Engineer, Haroli Division H.P. on behalf of Governor of H.P for the following works from the approved and contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. Undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: 25/10/2025 up to 10.30 (AM)
2. Date of issue/sale of tender forms against cash payment(non-refundable): 28/10/2025 up to 3.00 PM
3. Date of receipt of tenders: - 29/10/2025 up to 10.30 AM
4. Date of opening of tenders: - 29/10/2025 at 11.00 AM

Sr. No.	Name of work	Estimated cost	EMD	Time Limit	Cost of tender	Eligible class of contractor
1	2	3	4	5	6	7
1	Restoration of rain damages on Samnal to Laluwal road via Baliwal Km 0/00 to 15/930 (SH: C/o Breast wall at RD 0/180 to 0/200 RHS)	99146	2000/-	One Month	350/-	Class-C & D
2	Restoration of rain damages on Link Road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/o CC Pavement RD 2/580 to 2/602.50)	99620	2000/-	One Month	350/-	Class-C & D
3	Restoration of rain damage Una Jaijon road Km 0/0 to 23/00 (SH: C/o U-shape drain from 15/727 to 15/784 LHS)	99830	2000/-	One Month	350/-	Class-C & D
4	A/R & M/O on link road Old Haroli to Gugga Mandir Pajjal Yojna Haroli Km 0/0 to 2/240 (SH: P/L hot applied thermoplastic, P/F cat eyes Km 0/600 to 1/400)	99620	2000/-	One Month	350/-	Class-C & D
5	Restoration of rain damages on Link Road to village Bhoolgarh Km 0/0 to 2/600 (SH: C/o Retaining wall at RD 2/774.50 to 2/783.10 LHS)	99688	2000/-	One Month	350/-	Class-C & D
6	C/O Driving Training Track and Traffic Park at Rora Haroli Distt.Una (SH: Beautification & Grassing at Traffic Park) Deposit work Phase-IV	99976	2000/-	One Month	350/-	Class-C & D
7	Restoration of rain damage Una Jaijon road Km 0/00 to 23/00 (SH: C/o U-shape drain from RD 15/670 to 15/727 LHS)	99830	2000/-	One Month	350/-	Class-C & D
8	Restoration of rain damages on Polian Janani road Km 0/0 to 6/00 (SH: C/o Retaining wall RD 1/150 to 1/159.60 LHS)	99241	2000/-	One Month	350/-	Class-C & D

9	Restoration of rain damages on Link Road to village Bhoogarh Km 0/0 to 2/600 (SH: C/o CC Pavement RD 2/765 to 2/774.50 LHS)	98995	2000/-	One Month	350/-	Class C & D
10	C/O Driving Training Track and Traffic Park at Rora Haroli Distt.Una (SH: Beautification & Grassing at Traffic Park) Deposit work Phase-III	99976	2000/-	One Month	350/-	Class C & D
11	C/O Driving Training Track and Traffic Park at Rora Haroli Distt.Una (SH: Beautification & Grassing at Traffic Park) Deposit work Phase-V	98190	2000/-	One Month	350/-	Class C & D
12	Restoration of rain damages on link road Old Haroli road Gugga Mandir upto Pajjal Yojna HAROLI Km 0/0 to 2/140 RHS (SH: C/o U-shape drain at RD 2/100 to 2/130 RHS)	99254	2000/-	One Month	350/-	Class C & D
13	Restoration of rain damages on Polian Janani road Km 0/0 to 6/00 (SH: C/o Retaining wall RD 3/070 to 3/079.60 LHS)	99241	2000/-	One Month	350/-	Class C & D
14	A/R & M/O on Tahliwal Garshankar (HP Boundary) from Km 0/0 to 7/800 (SH: P/L Thermoplastic paint at RD 6/160 to 6/565)	63250	2000/-	One Month	350/-	Class C & D
15	Balance work for the C/o Community Park, Outdoor, Open gym at WNo.2 and 4 GP Dulehar (SH: Hill side cutting of extended portion of Park RD 0/028 to 0/032) Deposit work	99400	2000/-	One Month	350/-	Class C & D
16	Restoration of rain damages on link road Polian to Janani Km 0/0 to 6/00, L/R from Kuthar Beet to Jodian Km 0/00 to 1/800 & L/R to village Kuthar Beet from Una Jaijon road Km 0/0 to 2/500 (SH: Deployment of excavator cum loader & tractor for Treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	98100	2000/-	One Month	350/-	Class C & D
17	Restoration of rain damages on link road from Una Jaijon road to Gulaban da tobba Km 0/00 to 1/700 (SH: C/o CC Pavement RD 1/046 to 1/067.50)	99330	2000/-	One Month	350/-	Class C & D
18	Restoration of rain damage on link road to village Dharampur Km 0/00 to 2/250 (SH: C/o CC in berm at RD 0/50 to 0/150 Lhs & Edge wall 0/550 to 0/560 Bhs)	98895	2000/-	One Month	350/-	Class C & D
19	Restoration of rain damages on link road to village Naiyan Basti Baliwal road Km 0/0 to 1/500 (SH: P/L 80mm thick paver blocks at RD 0/400 to 0/409.70)	98463	2000/-	One Month	350/-	Class C & D
20	Restoration of rain damages on Umralli Singa road Km 0/0 to 6/550 (SH: P/L 60mm thick paver block in berms at RD 1/375 to 1/393.60 BHS)	99221	2000/-	One Month	350/-	Class C & D
21	C/o link road to Harijan Basti Dulehar (SH: C/o B/wall RD 0/719 to 0/744) Deposit work	99552	2000/-	One Month	350/-	Class C & D
22	Restoration of rain damage on link road to village Dharampur Km 0/00 to 2/250 (SH: C/o U-shape drain at RD 0/174.30 to 0/188.30)	99157	2000/-	One Month	350/-	Class C & D

23	Restoration of rain damages on link road to village Naiyan Basti Baliwal road Km 0/0 to 1/500 (SH: P/L 80mm thick paver blocks at RD 0/409 to 0/419.50)	99478	2000/-	One Month	350/-	Class-C & D
24	Restoration of rain damage on link road Labana Basti Ispur to Dera Baba Bharthari Damamian Km 0/0 to 5/580 in Pandoga section under Khad Sub Divn (SH: Hiring of excavator loader removal of debris/slips & C/o unlined drain etc.) Phase-III	99000	2000/-	One Month	350/-	Class-C & D
25	C/o Bus Stand Dulehar Tehsil Haroli Distt.Una (SH: C/o Ms sliding gate no.2) Phase-I	99172	2000/-	One Month	350/-	Class-C & D
26	C/o Bus Stand Dulehar Tehsil Haroli Distt.Una (SH: C/o Ms sliding gate no.2) Phase-II	99446	2000/-	One Month	350/-	Class-C & D
27	Restoration of rain damages on link road from Una Jaijon road to Gulaban da tobba Km 0/00 to 1/700 (SH: C/o CC Pavement RD 1/025 to 1/046)	97020	2000/-	One Month	350/-	Class-C & D
28	Restoration of rain damages on link road from Una Jaijon road to Gulaban da tobba Km 0/00 to 1/700 (SH: C/o U-shape drain at RD 1/061 to 1/085 Rhs & 900mm dia pipe at RD 1/085)	93535	2000/-	One Month	350/-	Class-C & D
29	Restoration of rain damages on Umrli Singan road km. 0/00 to 6/550(SH:-P/L 60mm thick paver blocks in berm at RD. 1/319.10 to 1/337.80 BHS)	99642	2000/-	One Month	350/-	Class-C & D
30	C/o link road from Nagnoli to SC Basti via Chaprian (SH: C/o B/wall in RD 0/958.50 to 0/977 RHS) Deposit work	99918	2000/-	One Month	350/-	Class-C & D
31	Restoration of rain damages on Una Rampur Haroli Jaijon Road 0/00 to 23/00(SH:-C/O R/wall at RD. 20/530 to 20/536.10 RHS)Deposit Work	99255	2000/-	One Month	350/-	Class-C & D
32	Restoration of rain damage on link Nagnoli ot village Nagnoli Km 0/0 to 5/600 (SH: Hiring of excavator cum loader & tractor for Treiming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season) Phase-III	99550/-	2000/-	One Month	350/-	Class-C & D
33	C/o link road from Nagnoli to SC Basti via Chaprian (SH: C/o B/wall in RD 0/977 to 0/990 & Edge wall at RD 0/916 to 0/934 RHS) Deposit work	99121	2000/-	One Month	350/-	Class-C & D
34	Restoration of rain damage on link road Polian to Janani Km 0/0 to 6/00 (SH: Deployment of excavator loader & tractor for Treiming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season) Phase-II	99200	2000/-	One Month	350/-	Class-C & D
35	C/o link road to Harijan Basti Dulehar (SH: C/o B/wall RD 0/694 to 0/719) Deposit work	99400	2000/-	One month	350/-	Class-C & D
36	Restoration of rain damages on Una Rampur Haroli Jaijon Road 0/00 to 23/00(SH:-C/O R/wall at RD. 20/512 to 20/518 RHS)Deposit Work	97657	2000/-	One Month	350/-	Class-C & D

37	C/o link road from Nagnoli to SC Basti via Chaprian (SH: C/o B/wall in RD 0/940 to 0/958.50 RHS) Deposit work	99977	2000/-	One Month	350/-	Class- C & D
38	Restoration of rain damage on link road to Harijan Basti Beetan to Village Beetan km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 1/128 to 1/146)Deposit Work	98535	2000/-	One Month	350/-	Class- C & D
39	Restoration of rain damages on lalual Gondpur Jaichand to Singan, Jhungian upto Punjab Boundary road km. 0/00 to 13/570(SH:-Removal of debris & desilting of Hume Khad at RD. 8/025)Phase-II	99300	2000/-	One Month	350/-	Class- C & D
40	A/R & M/O PWD Non-residential bldg. of HPPWD Haroli	99893	2000/-	One Month	350/-	Class- C & D
41	Restoration of rain damage on (i) link road to village Tholian at RD 0/0 to 2/090 (ii) Link road to village Nayian Basti Baliwal at RD 0/0 to 1/500 (iii) link road to village Nayian Rajputtan to Baliwal RD 0/0 to 1/600 under section Ghaluwal (SH: Hiring of excavator loader & tractor for Treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	99200	2000/-	One Month	350/-	Class- C & D
42	Restoration of rain damage on link road to Harijan Basti Beetan to Village Beetan km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 1/073 to 1/091)Deposit Work	98578	2000/-	One Month	350/-	Class- C & D
43	Restoration of rain damages on Una Rampur Haroli Jaijon Road 0/00 to 23/00(SH:-C/O R/wall at RD. 20/506 to 20/512 RHS)Deposit Work	97977	2000/-	One Month	350/-	Class- C & D
44	A/R & M/O PWD Non-residential bldg. of HPPWD Haroli	99806	2000/-	One Month	350/-	Class- C & D
45	Restoration of rain damage on link Nagnoli to HB via mohalla Brahmana Gujran Chaperian Km 0/0 to 3/345, link road to Nagnoli HB to Rajputtan mohalla Km 0/0 to 1/500, link road Panajwar Bathri to Jhikla Panjwar Km 0/0 to 2/550, link road to the house of Mehtab Singh Km 0/0 to 1/00 (SH: Hiring of excavator loader & tractor for Treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)Phase-III	99550	2000/-	One Month	350/-	Class- C & D
46	C/o Levelling work in Playground near GSSS Nangal Khurd mohalla Thai Nangal Khurd (Deposit Work)(SH: P/L Good earth material on top of play ground) Phase-I	99688	2000/-	One Month	350/-	Class- C & D
47	Restoration of rain damage on link road to Harijan Basti Beetan to Village Beetan km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 1/055 to 1/073)Deposit Work	98672	2000/-	One Month	350/-	Class- C & D
48	A/R & M/o PWD Non-residential bldg at Haroli (SH: P/F all in one HP-PC with i5, 16GB Ram, 1TB SD with Microsoft office in Chief Office Hamirpur Zone Hamirpur	92500	2000/-	One Month	350/-	Class- C & D

49	C/o Levelling work in Playground near GSSS Nangal Khurd mohalla Thai Nangal Khurd (Deposit Work)(SH: P/L Good earth material on top of play ground) Phase-II	99516	2000/-	One Month	350/-	Class-C & D
50	C/O Gramin sampark R/wall from link road to the house of Sh. Parveen Kumar Ward No.2 GP Pandoga (SH:-C/O R/wall)I Phase-I	99532	2000/-	One Month	350/-	Class-C & D
51	Restoration of rain damages on Jaijon Mod Bhai ka Mod upto tahliwal chowk km. 0/00 to 17/500 (SH:- Removal of debries & desilting of Kangar Khad causeway at RD. 3/795 to 3/830)Phase-I	99300	2000/-	One Month	350/-	Class-C & D
52	C/o Levelling work in Playground near GSSS Nangal Khurd mohalla Thai Nangal Khurd (Deposit Work)(SH: P/L Good earth material on top of play ground) Phase-III	99344	2000/-	One Month	350/-	Class-C & D
53	Restoration of rain damage on link road Polian to Janani Km 0/0 to 6/00 (SH: Deployment of excavator loader & tractor for Treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season) Phase-I	98100	2000/-	One Month	350/-	Class-C & D
54	Repair & Restoration work on Umrali Singan road km. 0/00 to 6/550 (SH:-P/L Steel Built up Section/frame over U-shape drain at RD. 2/770 to 2/798-RHS)Deposit Work	98781	2000/-	One Month	350/-	Class-C & D
55	Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No. 7 G.P. Badhera(SH:-C/O CC Pavement & Edge wall at RD. 0/008.80 to 0/017.50)Deposit Work	98492	2000/-	One Month	350/-	Class-C & D
56	Restoration of rain damages on Jaijon Mod Bhai ka Mod upto tahliwal chowk km. 0/00 to 17/500 (SH:- Removal of debries & desilting of Kangar Khad causeway at RD. 3/795 to 3/830)Phase-IV	99300	2000/-	One Month	350/-	Class-C & D
57	Restoration of rain damage on link road to Harijan Basti Beetan to Village Beetan km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 1/018 to 1/036)Deposit Work	98771	2000/-	One Month	350/-	Class-C & D
58	C/o Levelling work in Playground near GSSS Nangal Khurd mohalla Thai Nangal Khurd (Deposit Work)(SH: P/L Good earth material on top of play ground) Phase-IV	99856	2000/-	One Month	350/-	Class-C & D
59	Restoration of rain damage on link road village Singa to HP boundary Km 0/0 to 1/300 (SH: Hiring of excavator cum loader for C/o unlined drain, clearance of existing drain, removal of minor slips etc.) Phase-II	99000	2000/-	One Month	350/-	Class-C & D
60	C/O Gramin sampark from main to the house of Sh. Krishan Dutt Sharma GP Pandoga (SH:-C/O R/wall)I Phase-I	94940	2000/-	One Month	350/-	Class-C & D

61	Restoration of rain damage on link road to Harijan Basti Beetan to Village Beetan km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 1/036 to 1/054)Deposit Work	98512	2000/-	One Month	350/-	Class- C & D
62	Restoration of rain damage on link road Labana Basti Ispur to Dera Baba Bharthari Damamian Km 0/0 to 5/580 in Pandoga section under Khad Sub Divn (SH: Hiring of excavator loader & tractor for Treming of access soil in berm removal of slips & C/o unlined drain etc. in rainy season)	99550	2000/-	One Month	350/-	Class- C & D
63	Restoration of rain damages on lalual Gondpur Jaichand to Singan, Jhungian upto Punjab Boundary road km. 0/00 to 13/570(SH:-Removal of debries & desilting of Hume Khad at RD. 8/025)Phase-I	98200	2000/-	One Month	350/-	Class- C & D
64	Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at Khad GP Khad (SH:-C/O CC pavement & C/O R/wall-Phase-I) Deposit Work	99951	2000/-	One Month	350/-	Class- C & D
65	Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No. 7 G.P. Badhera(SH:-C/O CC Pavement & Edge wall at RD. 0/00 to 0/008.80)Deposit Work	99623	2000/-	One Month	350/-	Class- C & D
66	Repair & Restoration work on Umrli Singan road km. 0/00 to 6/550 (SH:-P/L Steel Built up Section/frame over U-shape drain at RD. 2/700 to 2/720-RHS)Deposit Work	99623	2000/-	One Month	350/-	Class- C & D
67	Balance work for the C/O Link road from the H/O Sh. Pawan Kaundal to Lower Badhera ward No. 5 G.P. Lower Badhera(Deposit Work)(SH:-P/L 60 mm thick paver blocks length =21.00 mtr.)Phase-I	98154	2000/-	One Month	350/-	Class- C & D
68	Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at Khad GP Khad (SH:-C/O CC pavement & C/O R/wall-Phase-II) Deposit Work	99654	2000/-	One Month	350/-	Class- C & D
69	Restoration of link road to Co-Operative society Haroli via GSSS Km. 0/00 to 2/225(SH:-C/O R/wall in RD. 1/380 to 1/406 RHS)	98973	2000/-	One Month	350/-	Class- C & D
70	Balance work for the C/O Link road from the H/O Sh. Pawan Kaundal to Lower Badhera ward No. 5 G.P. Lower Badhera(Deposit Work)(SH:-P/L 60 mm thick paver blocks length =21.00 mtr.)Phase-II	99089	2000/-	One Month	350/-	Class- C & D
71	Restoration of link road to Co-Operative society Haroli via GSSS Km. 0/00 to 2/225(SH:-P/L 80 mm thick paver block at RD. 1/430 to 1/445.50)	99605	2000/-	One Month	350/-	Class- C & D
72	Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at Khad GP Khad (SH:-C/O CC pavement & C/O R/wall-Phase-III) Deposit Work	99487	2000/-	One Month	350/-	Class- C & D

73	Restoration of link road to Co-Operative society Haroli via GSSS Km. 0/00 to 2/225(SH:-P/L 80 mm thick paver block at RD. 1/445.50 to 1/460.90)	98960	2000/-	One Month	350/-	Class-C & D
74	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/046 to 0/057)Deposit Work	98613	2000/-	One Month	350/-	Class-C & D
75	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/033 to 0/046)Deposit Work	98824	2000/-	One Month	350/-	Class-C & D
76	Restoration of rain damage on Una Rampur Haroli Jaijon road 0/00 to 23/00(SH:-C/O R/wall at RD. 20/518 to 20/524 RHS) Deposit Work	97497	2000/-	One Month	350/-	Class-C & D
77	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/020 to 0/033)Deposit Work	98531	2000/-	One Month	350/-	Class-C & D
78	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/070 to 0/083)Deposit Work	99687	2000/-	One Month	350/-	Class-C & D
79	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-P/L CC Pavement at RD. 0/353 to 0/367)	98821	2000/-	One Month	350/-	Class-C & D
80	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-P/L CC Pavement at RD. 0/339 to 0/353)	97354	2000/-	One Month	350/-	Class-C & D
81	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/135 to 0/145)Deposit Work	77923	2000/-	One Month	350/-	Class-C & D
82	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/057 to 0/070)Deposit Work	99118	2000/-	One Month	350/-	Class-C & D
83	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-P/L CC Pavement at RD. 0/325 to 0/339)	99188	2000/-	One Month	350/-	Class-C & D
84	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-P/L CC Pavement at RD. 0/297 to 0/350)*	99873	2000/-	One Month	350/-	Class-C & D
85	Restoration of rain damage on Una Rampur Haroli Jaijon road 0/00 to 23/00 (SH:-C/O R/wall at RD. 20/500 to 20/506 RHS)	97817	2000/-	One Month	350/-	Class-C & D
86	Restoration of rain damages on Panjwar Bathri road to Ispur Pathak Mohalla Kayaria Road km. 0/00 to 1/900,	98832	2000/-	One Month	350/-	Class-C & D

	L/R to Village Mohalla Tipperian km. 0/00 to 6/650(SH:-Repair of Rain cuts at Various RDs)					
87	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-Repair of old drain RD. 0/220 to 0/297))	98637	2000/-	One Month	350/-	Class-C & D
88	Restoration of rain damage on link road Butt to Butt Jagrian km. 0/00 to 1/700 (SH:-P/L CC Pavement at RD. 0/367 to 0/381)	99420	2000/-	One Month	350/-	Class-C & D
89	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/122 to 0/135)Deposit Work	98513	2000/-	One Month	350/-	Class-C & D
90	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/083 to 0/096)Deposit Work	98807	2000/-	One Month	350/-	Class-C & D
91	Restoration of rain damages on Link road Mohalla Jhangri Shiv Mandir Naun Ispur km. 0/00 to 2/395, link road Ispur to Pandoga via Kiarian km. 0/00 to 2/175, link road Petrol Pump Bhadsali to Una Hoshiarpur road to Pandoga Lower to Har Sainian Abadi Distt. Una HP km. 0/00 to 2/00, Link road to Village Pandoga km. 0/00 to 2/640)	99836	2000/-	One Month	350/-	Class-C & D
92	Restoration of rain damages on Link road Panjwar Bathri road to Behli Khad km. 0/00 to 3/040, Link road to Village Khad km. 0/0 to 2/240, Link road to Village Daulatpur km. 0/00 to 1/660) (SH:- Repair of Rain Cuts at various RD's)	99225	2000/-	One Month	350/-	Class-C & D
93	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/096 to 0/109)Deposit Work	99100	2000/-	One Month	350/-	Class-C & D
94	Repair and restoration of Gramin Sampark from Chhaliwala Temple to Jongpur road GP Gondpur Bula (SH:-C/O U-shape drain & P/L CC Pavement at RD. 0/109 to 0/122)Deposit Work	98220	2000/-	One Month	350/-	Class-C & D
95	Restoration of rain damages on Jaijon Mod Bhai ka Mod upto Tahliwal Chowk km. 0/00 to 17/500(SH:- Removal of debries & disilting of Kangar Khad causeway at RD. 3/795 to 3/830)Phase-III	99100	2000/-	One Month	350/-	Class-C & D
96	Restoration of rain damages on Samnal Naliwal road by providing R/wall at RD. 4/265 to 4/271.10 & P/L 900 mm dia RCC pipe)Deposit work	99819	2000/-	One Month	350/-	Class-C & D
97	Restoration of rain damages on Samnal Baliwal road by providing R/wall at RD. 4/257.50 to 4/265)Deposit work	99829	2000/-	One Month	350/-	Class-C & D

98	A/R & M/O Non-Residential building PWD Rest House at Haroli(SH:-Painting work to boundary wall etc.)	99603	2000/-	One Month	350/-	Class-C & D
99	Restoration of rain damages on link road Old Haroli road Gugga Mandir upto Pajjal Yojna HAROLI Km 0/0 to 2/140 RHS (SH: C/o U-shape drain at RD 2/130 to 2/160 RHS)	99334	2000/-	One Month	350/-	Class-C & D
100	Restoration of rain damages on Samnal Baliwal road by providing R/wall at RD. 4/250 to 4/257.50)Deposit work	99979	2000/-	One Month	350/-	Class-C & D
101	Restoration of rain damage on various roads under Haroli & T/wala Sub-Division HPPWD(SH:- Supplying and fixing of sign boards & writing)	99788	2000/-	One Month	350/-	Class-C & D
102	Restoration of rain damage on Panjwar Bathri road km. 0/00 to 34/00(SH:-Repair of Rain cuts at Various RDs from km. 2/00 to 9/00)	98520	2000/-	One Month	350/-	Class-C & D
103	C/o Boundary wall at HWC ward No.7 GP Pucca Pragan GP Pubowal (SH:-C/O Boundary wall Length=4.00 Mtr. & Steel gate)Phase-III	58589	1400/-	One Month	350/-	Class-C & D
104	Restoration of rain damage on link road to Harijan Basti Beetan to Village km. 0/00 to 1/300(SH:-C/O R/wall at RD. 1/00 to 1/018)Deposit Work	98611	2000/-	One Month	350/-	Class-C & D
105	Restoration of rain damage on link road to Harijan Basti Beetan to Village km. 0/00 to 1/300(SH:-C/O R/wall at RD. 1/091 to 1/109)Deposit Work	98407	2000/-	One Month	350/-	Class-C & D
106	Restoration of rain damage on link road to Village Sainsowal road km. 0/00 to 2/205 (SH:-C/O R/wall at RD. 1/740.80 to 1/744.90 RHS & C/O approach slab)	99526	2000/-	One Month	350/-	Class-C & D
107	Restoration of rain damage on link road to Village Sainsowal road km. 0/00 to 2/205 (SH:-C/O R/wall at RD. 1/730 to 1/740.80 RHS)	99294	2000/-	One Month	350/-	Class-C & D
108	Restoration of rain damage on link road to Harijan Basti Beetan to Village km. 0/00 to 1/300(SH:-C/O R/wall at RD. 1/146 to 1/164)Deposit Work	98611	2000/-	One Month	350/-	Class-C & D
109	Restoration of rain damage on link road Mohalla Kutta to Sant Dhanguwala km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 0/568 to 0/586)Deposit Work	98611	2000/-	One Month	350/-	Class-C & D
110	Restoration of rain damage on link road Mohalla Kutta to Sant Dhanguwala km. 0/00 to 1/300 (SH:-C/O R/wall at RD. 0/550 to 0/568)Deposit Work	98771	2000/-	One Month	350/-	Class-C & D
111	Restoration of rain damage on link road to Harijan Basti Beetan to Village km. 0/00 to 1/300(SH:-C/O R/wall at RD. 1/109 to 1/127)Deposit Work	98727	2000/-	One Month	350/-	Class-C & D
112	Repair & Restoration work on Umrli Singan road km. 0/00 to 6/550(SH:-C/O U-shape drain at RD. 2/796 to 2/822 RHS) Deposit work	98715	2000/-	One Month	350/-	Class-C & D

113	Repair & Restoration work on Umrli Singan road km. 0/00 to 6/550(SH:-P/L 300 mm dia RCC piupe at RD 2/822 to 2/872-RHS) Deposit work	99448	2000/-	One Month	350/-	Class C &
114	Restoration of rain damages on link road to Village Naiyan Basti Baliwal road km. 0/00 to 1/500(SH:-P/L 80 mm thick paver blocks at RD. 0/429.10 to 0/438.90)	99478	2000/-	One Month	350/-	Class C &
115	Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt. Una (HP) Deposit Work(SH:-Hill side cutting for extended portion of park RD. 0/020 to 0/024)	96600	2000/-	One Month	350/-	Class C &
116	Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt. Una (HP) Deposit Work(SH:-Hill side cutting for extended portion of park RD. 0/011 to 0/020)	99295	2000/-	One Month	350/-	Class C &
117	Restoration of rain damages Una Jaijon road 0/00 to 23/00(SH:-C/O R/wall at RD. 14/360 to 14/367-RHS)	99824	2000/-	One Month	350/-	Class C &
118	Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP. (SH:-C/O Ms sliding gate No.1)	97746	2000/-	One Month	350/-	Class C &
119	Restoration of rain damage on link road Lawana Basti Ispur to Dera Baba Bharthri Damamiyan km. 0/00 to 5/580 in Pandoga section under Khad Sub Divn (SH: Hiring of excavator loader for removal debries/slips & removal of slips & C/o unlined drain etc.)Phase-II	99000	2000/-	One Month	350/-	Class C &
120	C/O Gramin Sampark from main road to the house of Sh. Krishan Dutt Sharma GP Pandoga (SH:-P/L Paver block)	99475	2000/-	One Month	350/-	Class C &
121	Restoration of rain damages on Jaijon Mod Bhai ka Mod upto Tahliwal chowk km. 0/00 to 17/500(SH:- Removal of debries & of Kangar Khad causeway at RD. 3/795 to 3/830)Phase-II	99300	2000/-	One Month	350/-	Class C &
122	C/O Gramin sampark R/wall from link road to the house of Sh. Parveen Kumar Ward No.2 GP Pandoga (SH:-C/O R/wall)I Phase-II	60475	2000/-	One Month	350/-	Class C &
123	Restoration of rain damage on Una Rampur Haroli Jaijon road 0/00 to 23/00(SH:-C/O R/wall at RD. 20/524 to 20/530 RHS)Deposit Work	97657	2000/-	One Month	350/-	Class C &
124	C/o Boundary wall at HWC ward No.7 GP Pucca Pragan GP Pubowal (SH:-C/O Boundary wall Length=24.00 Mtr.)Phase-I Deposit Work	99675	2000/-	One Month	350/-	Class C &
125	C/o Boundary wall at HWC ward No.7 GP Pucca Pragan GP Pubowal (SH:-C/O Boundary wall Length=23.00 Mtr. & Steel gate)Phase-II	96971	2000/-	One Month	350/-	Class C &
126	C/O Link road from House of Champa Devi RD. 0/00 to 1/200(Deposit work) (SH:-C/O R/wall at RD. 1/177.20 to 1/182.90 RHS)	99290	2000/-	One Month	350/-	Class C &

127	C/O Link road from House of Champa Devi RD. 0/00 to 1/200(Deposit work) (SH:-C/O R/wall at RD. 1/182.90 to 1/188.60 RHS)	99130	2000/-	One Month	350/-	Class-C & D
-----	--	-------	--------	-----------	-------	-------------

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of an post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

SPECIAL CONDITION: -

The contractor should produce a copy of valid enlistment/renewal letter at the time of application

1. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
2. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
3. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happen to be local/gazetted holidays, the same shall be process on next date.
4. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their application a/w proof of ownership of machinery/legal tie up arrangement).
5. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
6. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer
HPPWD Division Haroli
Distt.Una(HP).Pin Code-177220
Email: ee-harolli-hp@hp.gov.in
On behalf of Governor of Himachal Pradesh

①

SCHEDULE OF QUANTITY

Sl. No.		Description of work	Quantity	Unit	RATE In		AMOUNT
					Figures	Words	
Name of Work:-Restoration of rain damages on Samnal to Laluwal road via Baliwal km. 0/00 to 15/930 (SH: C/O Breast wall at RD. 0/180 to 0/200 RHS)							
					Estimated Cost		99146/-
					Earmest Money		2000/-
					Time limit		One month
1		Earth work in excavation by mechanical means (Hydraulic excavator/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. includind carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.10	Cum	160.00	Rupees one hundred sixty only	3216
2		Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement: 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.10	Cum	3300.00	Rupees three thousand three hundred only	92730
3		Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	Each	160.00	Rupees one hundred sixty only	3200
					Total:		99146
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.9.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

2

Schedule of quantity

Name of work- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/700		Estimated Cost: Rs		₹ 99,620		
(Sh: C/O CC Pavement Rd. 2/580 to 2/ 602.50).		Time:-		One month		
S.NO	DESCRIPTION	Earnest Money:-				
		Qty	Unit	T.Rate	Rate in words	
1	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401	7.88	cum	1100.00	Rupees One Thousand One Hundred Only	8663
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.88	cum	3300.00	Rupees Three Thousand Three Hundred Only	25988
3	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads .The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.81	cum	5500.00	Rupees Five Thousand Five Hundred Only	64969
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99620
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

285

Schedule of Quantity

4

Estimated Cost: Rs. 99620
Earnest Money: Rs. 2000-
Time Limit: One Month

Name of work: A/R & M/O on ~~bank road~~ old Haroli road Gugga mandir Pajjal yojna Haroli 0/0 to 2/240 (SH: (SH: P/L hot applied thermoplastic, P/F cat eye Km 0/600 to 1/400)

Sr. No.	Sub-Head and Items of work	Quantity	Unit	Rates in		Amount
				Figures	Words	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes as per entire direction of Engineer-in - Charge including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, GST , sale tax or other taxes imposed by the Government.	18.00	Per Square	650.00	Rupees six hundred fifty only	11700
2	Providing and fixing cat eye make(3M) of size 100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretreite) or HP/High impact polystyrene) or ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 136.35 by tested in accordance with ASTM D4280. The slope of retro reflective surface shall be 35°/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge .including carriage of material within all leads and lifts .The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	314.00	Each	280.00	Rupees two hundred eighty only	87920
Note:-				Total		99620
1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

5

Schedule of quantity

Name of Work :- Restoration of rain damages on Link road to Village Boolgarh km. 0/00 to 2/600		Estimated Cost: Rs	Time:-	₹ 99,688		
(SH :- C/O Retaining wall at RD. 2/774.50 to 2/783.10 Lhs)		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.75	Cum	160.00	Rupees One Hundred Sixty Only	1720
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.94	Cum	3300.00	Rupees Three Thousand Three Hundred Only	92189
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	15.00	Each	160.00	Rupees One Hundred Sixty Only	2400
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	6.14	Cum	550.00	Rupees Five Hundred Fifty Only	3379
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total	99688
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.R.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs	₹ 99,976			
		Time:-	One month			
(SH: Beautification & Grassing at Traffic Park) (Deposit work) - Phase - IV		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water , including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.76	Cum	285.00	Rupees Two Hundred EightyFive Only	15322
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.76	Cum	880.00	Rupees Eight Hundred Eighty Only	47309
3	Rough dressing the trenched ground including breaking clods, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	17.00	Rupees Seventeen Only	1523
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	70.00	Rupees Seventy Only	6272
5	Fine dressing of the ground, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	35.00	Rupees ThirtyFive Only	3136

6

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.96	Cum	145.00	Rupees One Hundred FortyFive Only	1299
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions.including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	130.00	Rupees One Hundred Thirty Only	11648
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm. refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	80.64	Cum	167.00	Rupees One Hundred SixtySeven Only	13467
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99976
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


Executive Engineer,
H.P.P.W.D. Division Harohi
 Distt. Una (H.P.)

8

SCHEDULE OF QUANTITY									
Name of work : Restoration of rain damages on Polian Janani road Km 0/00 to 6/00 (SH: C/O retaining wall RD 1/150 to 1/159.60-LHS)									
S. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost	99241	2000	One month
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.06	Per cubic metre	160.00	Rupees One hundred sixty only				1290
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement : four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.98	Per cubic metre	3300.00	Rupees three thousand three hundred only				92334
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only				2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.14	Per cubic metre	550.00	Rupees Five hundred fifty only				3377
						Total:			99241
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Schedule of quantity

Name of Work :- Restoration of rain damages on Link road to Village Boogiarh km. 0/00 to 2/600		Estimated Cost: Rs	₹ 98,995			
		Time:-	One month			
(SH :- C/O Retaining wall at RD. 2/765 to 2/774.50 Lhs)		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge..including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.64	Cum	160.00	Rupees One Hundred Sixty Only	1702
2	Providing and laying in position concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	27.65	Cum	3300.00	Rupees Three Thousand Three Hundred Only	91229
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	17.00	Each Cum	160.00	Rupees One Hundred Sixty Only	2720
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government	6.08	Cum	550.00	Rupees Five Hundred Fifty Only	3344
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total		98995
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


Executive Engineer,
H.R.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 99,976		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.76	Cum	285.00	Rupees Two Hundred EightyFive Only	15322
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	53.76	Cum	880.00	Rupees Eight Hundred Eighty Only	47309
3	Rough dressing the trenched ground including breaking clods, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	17.00	Rupees Seventeen Only	1523
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	70.00	Rupees Seventy Only	6272
5	Fine dressing of the ground, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	89.60	Sqm	35.00	Rupees ThirtyFive Only	3136

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.96	Cum	145.00	Rupees One Hundred FortyFive Only	1299
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	89.60	Sqm	130.00	Rupees One Hundred Thirty Only	11648
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	80.64	Cum	167.00	Rupees One Hundred SixtySeven Only	13467
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99976
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :- C/O Driving Training Track and Traffic Park at Rora, Haroli Distt. Una.		Estimated Cost: Rs		₹ 98,190		
(SH: Beautification & Grassing at Traffic Park) (Deposit work) — PWA — V		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	285.00	Rupees Two Hundred EightyFive Only	15048
2	Supplying and stacking of good earth at site including cost of sludge, manure & including royalty and carriage upto any lead complete, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	52.80	Cum	880.00	Rupees Eight Hundred Eighty Only	46464
3	Rough dressing the trenched ground including breaking clods, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	17.00	Rupees Seventeen Only	1496
4	Uprooting weeds from the trenched area after 10 to 15 days of its flooding with water including disposal of uprooted vegetation, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	70.00	Rupees Seventy Only	6160
5	Fine dressing of the ground, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	88.00	Sqm	35.00	Rupees ThirtyFive Only	3080

(11)

6	Spreading of sludge, dump manure and/or good earth in required thickness as per direction of officer-in-charge (cost of sludge, dump manure and/ or good earth to be paid separately, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.80	Cum	145.00	Rupees One Hundred FortyFive Only	1276
7	Grassing with selection No. 1 grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn, free from weeds and fit for mowing including supplying good earth, if needed (the grass and good earth shall be paid for separately). In rows 5 cm apart in both directions including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	88.00	Sqm	130.00	Rupees One Hundred Thirty Only	11440
8	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludge or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20% : one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary, watering and finally fine dressing, leveling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and leveling as directed, within a lead of 50 m, lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately), including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	79.20	Cum	167.00	Rupees One Hundred SixtySeven Only	13226
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98190
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(3)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

13

SCHEDULE OF QUANTITY									
Name of work : Restoration of rain damages on Polian Janani road Km 0/00 to 6/00 (SH: C/O retaining wall RD 3/070 to 3/079.60-RHS)									
S. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost	99241		
				Figures	Words		Earnest Money	2000	One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.06	Per cubic metre	160.00	Rupees One hundred sixty only				1290
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement: four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	27.98	Per cubic metre	3300.00	Rupees three thousand three hundred only				92334
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only				2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.14	Per cubic metre	550.00	Rupees Five hundred fifty only				3377
						Total: 99241			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018									
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

14

Name of Work: A/R & M/O on Tahlwal Garshankar (HP Boundary) MDR-41 from km. 0/0 to 7/800
(SH; P/L Thermoplastic paint at Rd. 6/160 to 6/565)

		Estimated Cost: Rs		Time:-		
		One month		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	101.25	Sqm	600.00	Rupees Six Hundred Only	60750
2	Providing and fixing cat eye make)(3M) of size 100x20mm made of heavy duty body shall be molded dual shank ASA /Acyclic styrene acyloretreite) or HP/High impact polystyrene) ort ABS having electronically welded micro prismatic lens with abrasion resistant coating as approved by Engineer-in-charge. The road stud shall support a load of 13635 by tested in accordance with ASTM D4280.The slope of retro reflective surface shall be 35+/-5 degrees to base. The reflective panels on both side with at least 12cm. of each area side. The luminance intensity should be as per the specification ASTM as recommended in BS-8873 part 4 1973 as per approved sample and manufacture by the Engineer-in-charge.	10.00	Each	250.00	Rupees Two Hundred Fifty Only	2500
				Total		63250
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

145

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

15

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una HP. (Deposit work)		Estimated Cost: Rs			₹ 99,400
(SH: Hill side cutting for extended portion of park Rd. 0/028 to 0/032)		Time:-			One month
S.NO	DESCRIPTION	Earnest Money:-			2000
		Qty	Unit	T.Rate	Rate in words
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification 2014 clause 302, 1603 in association with other clauses. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhara ,toll tax,GST,labour cess or other taxes imposed by the Government..	710.00	Cum.	140.00	Rupees One Hundred Fourty Only
				Total	99400
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

16

Draft Schedule of quantity

		Estimated Cost: Rs	₹ 98,100			
		Time:-	One month			
		Earnest Money:-	2000			
		Rate in words	Amount			
<p>Name of work: -Restoration of rain damages on Link road Polian to Janani km. 0/00 to 6/00 , Link road from Kuthar Beet to Jodian Km. 0/00 to 1/800 & Link road to Village Kuthar from Una Jaijon Road Km. 0/00 to 2/500</p> <p>(SH: Deploymet of excavator Cum Loader & Trector for Treming of Access soil in berm Removal of slips & C/O unilind drain etc. in rainy season etc.)</p>						
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	P/ Hour	1100.00	Rupees One Thousand One Hundred Only	78100
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	Rupees Two Thousand Five Hundred Only	20000
					Total	98100
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						

182

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt Una (H.P.)

Schedule of quantity

Name of work : Restoration of rain damages on Link road from Una Jaizon road to Gulaban da Toba Km. 0/00 to 1/700

		Estimated Cost: Rs		₹ 99,330	
(Sh: C/O CC Pavement Rd. 1/046 to 1/067.50).		Time:-		One month	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.60	cum	3300.00	Rupees Three Thousand Three Hundred Only 28380
2	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	12.90	cum	5500.00	Rupees Five Thousand Five Hundred Only 70950
					Total 99330
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				
	Percentage quoted rate in figures				
	Percentage quoted rate in words				
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected				


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

X

18

Schedule of quantity

Name of work:- Restoration of rain damages On link road to Village Dharampur Km. 0/00 to 2/250 (SH: C/O CC in berm at Rd. 0/050 to 0/150 Lhs & Edge wall 0/550 to 0/560 Bhs).		Estimated Cost: Rs	₹ 98,895				
		Time:-	One month				
		Earnest Money:-	2000				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.50	CUM.	160.00	Rupees One Hundred Sixty Only	720	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	25.50	CUM.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	98175	
						Total:	98895
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/0212 dated 7.8.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)A(31/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of work :-Restoration of rain damages on link road to village Naiyan Basti Baliwal road km. 0/00 to 1/500)

19

Name of work :-Restoration of rain damages on link road to village Naiyan Basti Baliwal road km. 0/00 to 1/500)		Estimated Cost: Rs	Time:-	One month		
(SH: P/L 80 mm thick paver blocks at Rd. 0/400 to 0/409.70)		₹ 98,463		2000		
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:- Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	23.79	Cum.	160.00	Rupees One Hundred Sixty Only	3806.00
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5.60	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	21567.00
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.28	Cum.	1100.00	Rupees One Thousand One Hundred Only	8003.00
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.85	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	16005.00
5	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	48.50	Cum	850.00	Rupees Eight Hundred Fifty Only	41225.00
6	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana ,toll tax, GST, labour cess or other taxes imposed by the Government.	1.75	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	7857.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					
					Total	98463

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H P W D)

971

20

SCHEDULE OF QUANTITY									
Name of work :- Restoration of rain damages on Umrali Singan road km. 0/00 to 6/550(SH :- P/L 60mm thick paver blocks in berm at RD 1/375 to 1/393.60 BHS)									
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	Estimated Cost		
				Figures	Words		99221/-	2000/-	One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	19.63	cum	160.00	Rupess one hundred sixty only	3141			
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	7.55	cum	1100.00	Rupess one thousand one hundred only	8305			
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.	7.55	cum	3300.00	Rupess three thousand three hundred only	24915			
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	75.20	sqm	800.00	Rupess eight hundred only	60160			
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax, GST, labour cess or other taxes imposed by the Government.	0.60	cum	4500.00	Rupess four thousand five hundred only	2700			
Total -						99221			
1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PW(B)/(17)2/0212 dated 7.8.2018									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)


SCHEDULE OF QUANTITY

Name of work: C/O link road to Harijan Basti Dulehar (SH : C/O B/wall RD 0/719 to 0/744)- Deposit work

Estimated Cost 99552
Earnest Money 2000/-
Time limit One month

21

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	25.86	Per cubic metre	160.00	Rupees One hundred sixty only	4138
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.38	Per cubic metre	3300.00	Rupees three thousand three hundred only	93654
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete. as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One hundred sixty only	1760
					Total:	99552
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						



Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

22

Schedule of quantity

Name of work:- Restoration of rain damages On link road to Village Dharampur Km. 0/00 to 2/250 (SH: C/O U-Shape drain at RD. 0/174.3 to 0/188.30).		Estimated Cost: Rs		₹ 99,157		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.75	CUM.	160.00	Rupees One Hundred Sixty Only	2520
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	12.46	CUM.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	47971

3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.15	CUM.	5500.00	Rupees Five Thousand Five Hundred Only	825
4	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	531.56	Kg	90.00	Rupees Ninety Only	47841
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99157
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

23

Schedule of quantity

Name of work :- Restoration of rain damages on link road to village Naiyan Basti Baliwal road km. 0/00 to 1/500)

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Estimated Cost: Rs	
						One month	Amount
						Time:-	
						Earnest Money:-	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	24.03	Cum.	160.00	Rupees One Hundred Sixty Only	3846.00	2000
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 .including carriage of materials within all leads and lifts and other incidental. . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	5.66	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	21789.00	
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government.	7.35	Cum.	1100.00	Rupees One Thousand One Hundred Only	8085.00	
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 .including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.90	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	16170.00	
5	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	49.00	Cum	850.00	Rupees Eight Hundred Fifty Only	41650.00	
6	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.76	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	7938.00	
					Total	99478	
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>							

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

272

24

SCHEDULE OF QUANTITY						
					Estimated Cost	99000
					Earnest Money	2000/-
					Time limit	One month
Name of work : Restroation of rain damages on link road Lawana Basti Ispur to Dera Baba Bharthri Damamiyan KM 0/0 TO 5/580 in Pandoga section under Khad sub division HPPWD Khad.(SH: Hiring of excavator Cum Loader for removal debries/slips & C/O unlined drain etc.) -Phase-III						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock etc (where blasting is prohibte) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	90.00	Per Hour	1100.00	Rupees one thousand one hundred only	99000
				Total:		99000
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer
 Haroli Division
 HPPWD Haroli

Draft Schedule of quantity

Name of work: - Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP.

(SH: C/O Ms sliding gate no.2) Phase-I

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Estimated Cost: Rs
						Time:-
						₹ 99,172
						One month
						Earnest Money:-
						2000
						Amount
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in-charge, including carriage of material within all leads, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.88	Cum	5500	Rupees Five Thousand Five Hundred Only	4826
2	Renewing Wrought iron or M.S. Wheel or roller of steel door or gate and fitting and fixing the same with necessary clamps, nuts and bolts/welding and erection etc. complete. Wheel above 50 mm dia. including incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	12.00	Per/wheel	218.20	Rupees Two Hundred Eighteen Paise Twenty Only	2618
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	936.00	Kg	98.00	Rupees NinetyEight Only	91728
						Total
						99172
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

26

Draft Schedule of quantity


Name of work: - Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP.		Estimated Cost: Rs	₹ 99,446			
(SH: C/O Ms sliding gate no.2) Phase-ii		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Steel work welded in built up sections/ framed work, including cuttings, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	936.00	Kg	98.00	Rupees NinetyEight Only	91728
2	Finishing with Epoxy paint (two or more coats) on steel work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	62.24	Sqm	124.00	Rupees One Hundred TwentyFour Only	7718
					Total	99446
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H/P)

27

Schedule of quantity

Name of work : Restoration of rain damages on Link road from Una Jaizon road to Gulaban da Toba Km. 0/00 to 1/700		Estimated Cost: Rs		₹ 97,020		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	8.40	cum	3300.00	Rupees Three Thousand Three Hundred Only	27720
2	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of material within all leads . The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	12.60	cum	5500.00	Rupees Five Thousand Five Hundred Only	69300
				Total		97020
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018</p> <p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p> <p>Percentage quoted rate in figures</p> <p>Percentage quoted rate in words</p> <p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

28

Schedule of quantity

Name of work : Restoration of rain damages on Link road from Una Jaijon road to Gulaban da Toba Km. 0/00 to 1/700		Estimated Cost: Rs		₹ 93,535		
		Time:-		One month		
(SH: C/O U-Shape drain at RD. RD. 1/061 to 1/085 Rhs & 900 mm dia pipe at Rd. 1/085).		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive oetroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	30.60	CUM.	160.00	Rupees One Hundred Sixty Only	4896
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive oetroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	18.34	CUM.	3300.00	Rupees Three Thousand Three Hundred Only	60514

3	Providing and laying Non Pressure NP-2 class (Medium duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 900 mm dia RCC pipes. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are	7.50	R/mtr	3750.00	Rupees Three Thousand Seven Hundred Fifty Only	28125
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	93535
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

29

SCHEDULE OF QUANTITY									
Name of work :- Restoration of rain damages on Umralli Singan road km. 0/00 to 6/550(SH) :- P/L 60mm thick paver blocks in berm at RD 1/319.10 to 1/337.80 BHS)									
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	Estimated Cost	99642/-	2000/-
				Figures	Words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed. within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	19.44	cum	160.00	Rupess one hundred sixty only	3110			
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.48	cum	1100.00	Rupess one thousand one hundred only	8228			
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.48	cum	3300.00	Rupess three thousand three hundred only	24684			
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	74.80	sqm	800.00	Rupess eight hundred only	59840			
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.84	cum	4500.00	Rupess four thousand five hundred only	3780			
Total :-						99642			
1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)12/0212 dated 7.8.2018									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.R.)

30

SCHEDULE OF QUANTITY

Name of work: C/o Link rod from Nagnoli to SC Basti Via Chaprian (SH:- C/o B/wall in RD 0/958.50 to 0/977 RHS)Deposit work

Sl. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost Earnest Money Time limit	99918/- 2000/- One month AMOUNT
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.33	Per cubic metre	160.00	Rupees One hundred sixty only		1333
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	29.05	Per cubic metre	3300.00	Rupees three thousand three hundred only		95865
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) PVC pipe extending through the full width of the structures with slope of 1(V) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	17.00	Each	160.00	Rupees One hundred sixty only		2720
						Total:	99918
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018						
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3) 1/2020 dated 22.07.20						
	Percentage quoted rate in Figures						
	Percentage quoted rate in words						
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

(3)

Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jaifon Road 0/00 to 23/000		Estimated Cost: Rs	₹ 99,255			
(SH: C/O Retaining wall at Rd. 20/530 to 20/536.10 Rhs.)		Time:-	One month			
DESCRIPTION		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.96	Cum.	160.00	Rupees One Hundred Sixty Only	1274
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.67	Cum.	33000.00	Rupees Three Thousand Three Hundred Only	94611
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One Hundred Sixty Only	1760
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.93	Cum.	550.00	Rupees Five Hundred Fifty Only	1610
Total						99255

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

363

320

SCHEDULE OF QUANTITY					Estimated Cost	99550/-
					Earnest Money	2000/-
					Time limit	Two month
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government. NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018 2) The rates shall be including of all types of taxes including GST ectra)	90.50	Per Hour	1100.00	Rupees one thousand one hundred	99550
					Total:	99550

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

33

SCHEDULE OF QUANTITY							Estimated Cost	99121/-
Name of work: C/o Link rod from Nagnoli to SC Basti Via Chaprian (SH:- C/o B/wall in RD 0/977 to 0/990 & Edge wall at RD 0/916 to 0/934 RHS)Deposit work							Earnest Money	2000/-
							Time limit	One month
Sl. No.	Description of work	Quantity	Unit	Figures	Words	RATE In	AMOUNT	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi royalty maikhana toll tax,sale tax, GST, labour cess or other taxes imposed by the Government.	9.76	Per cubic metre	160.00	Rupees One hundred sixty only		1562	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1 : 4 : 8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802-803-1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty maikhana toll tax, GST, labour cess or other taxes imposed by the Government.	29.03	Per cubic metre	3300.00	Rupees three thousand three hundred only		95799	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimeter) PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 6:14-709-1204-3-7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, maikhana toll tax, GST, labour cess or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One hundred sixty only		1760	
							Total:	99121
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No:PBW(B)@{17}2/0212 dated 7.8.2018								
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20								
Percentage quoted rate in Figures								
Percentage quoted rate in words								
Note: - Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.								

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.R)

Draft Schedule of quantity

Name of work: -Restoration of rain damages on Link road Polian to Janani km. 0/00 to 6/00 .		Estimated Cost: Rs		₹ 99,200		
		Time:-		One month		
(SH: Deploymet of excavator Cum Loader & Tractor for Treming of Access soil in berm Removal of slips & C/O unilind drain etc. in rainy season etc.) - Phase II		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(wher blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	72.00	P/ Hour	1100.00	(Rupees one thousand one hundred only)	79200
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	(Rupees two thousand five hundred only)	20000
					Total	99200
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

35

SCHEDULE OF QUANTITY

Name of work: C/O link road to Harijan Basti Dulehar (SH : C/O B/wall RD 0/694 to 0/719)- Deposit work

Estimated Cost 99400
Earnest Money 2000/-

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	25.74	Per cubic metre	160.00	Rupees One hundred sixty only	4118
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1 : 4 : 8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, de-watering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.34	Per cubic metre	3300.00	Rupees three thousand three hundred only	93522
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 6.14.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One hundred sixty only	1760
				Total:		99400
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)[0/1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)[A/31/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jaijon Road 0/00 to 23/000		Estimated Cost: Rs	₹ 97,657			
(SH: C/O Retaining wall at Rd. 20/512 to 20/518 Rhs.)		Time:-	One month			
DESCRIPTION		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.83	Cum.	160.00	Rupees One Hundred Sixty Only	1253
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	93060
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One Hundred Sixty Only	1760
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.88	Cum.	550.00	Rupees Five Hundred Fifty Only	1584
Total						97657

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

37

SCHEDULE OF QUANTITY

Name of work: C/o Link rod from Nagnoli to SC Basti Via Chaprian (SH:- C/o B/wall in RD 0/940 to 0/958.50 RHS)Deposit work		Estimated Cost	99977/-
		Earnest Money	2000/-
Sl. No.	Description of work	Quantity	Unit
		Figures	Words
			Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	8.70	Per cubic metre
		160.00	Rupees One hundred sixty only
			1392
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	29.05	Per cubic metre
		3300.00	Rupees three thousand three hundred only
			95865
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment. wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614 709. 1204 3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	17.00	Each
		160.00	Rupees One hundred sixty only
			2720
			Total: 99977
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)@1712/0212 dated 7.8.2018		
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20		
	Percentage quoted rate in Figures		
	Percentage quoted rate in words		
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.		

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:CO R/wall at RD 1/128 to 1/146)- Deposit work

Estimated Cost 98535
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction of the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax sale tax, GST, labour cess or other taxes imposed by the Government.	7.64	160	160.00	Rupees One hundred Sixty only	1222
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand eight graded crushed /broken stone aggregate 40mm forty millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.90	Per cubic metre	3300.00	Rupees three thousand three hundred only	88770
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204 3 7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3 8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.46	Per cubic metre	550.00	Rupees five hundred fifty only	6303
					Total:	98535

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)@17/2/0212 dated 7.8.2018
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20

Percentage quoted rate in Figures
Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

39

SCHEDULE OF QUANTITY

Name of work : Restrotration of rain damages on Lалуwal Gondpur Jaichand to Singan, Jhungian upto Punjab Boundary road Km 0/00 to 13/570 (SH: Removal of debries & disilting of Hume Khad at RD 8/025)- Phase-II

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for removal of debries including sand , silt, boulders and other material from the bed of khad from down streams side as per direction of the Engineer-in-charge. The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	83.00	Per Hour	1100.00	Rupees One thousand one hundred only	91300
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for removal of debries including sand , silt, boulders and other material etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours. The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.00	Per Day	2000.00	Rupees Two thousand only	8000
Total:						99300
1) The bidder are requested to submit their bid as per notification issued by the Principal Secy,PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HPPWD Haroli

352

40

Schedule of quantity

Name of Work :- A/R & M/O PWD Non residential Building of HPPWD Division at Haroli.		Estimated Cost: Rs		₹ 99,893		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.41	Cum	550.00	Rupees Five Hundred Fifty Only	228
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Nos	156.25	Rupees One Hundred FiftySix Paise TwentyFive Only	625
3	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix), including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.32	Cum	800.00	Rupees Eight Hundred Only	256
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes Cement mortar 1:6 (1 cement : 6 coarse sand), including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.92	Cum	6750.00	Rupees Six Thousand Seven Hundred Fifty Only	26470
5	Half brick masonry in common burnt clay building bricks in superstructure : Cement Mortar 1:4 (1 cement:4 sand) First Class Bricks, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.75	Sqm	747.65	Rupees Seven Hundred FourtySeven Paise SixtyFive Only	561
6	15 mm Cement plaster in single coat on the fair side of brick/ concrete/stone walls 1:6 (1 cement: 6 fine sand) for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.10	Sqm	190.00	Rupees One Hundred Ninety Only	6479
7	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.10	Sqm	60.00	Rupees Sixty Only	2046

8	Applying priming coat on new concrete/masonry/asbestos cement/plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with :-Ready mixed primer. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	34.10	Sqm	50.55	Rupees Fifty Paise Fifty Five Only	1724
9	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two coat. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	83.31	Sqm	74.00	Rupees Seventy Four Only	6165
10	Providing and fixing fly proof galvanized MS wire gauge designation 140 G (one hundred forty G) with wire of dia 0.56mm to windows and clerestory windows including 60 x 20mm (beading upto any floor level/height as per the direction by the Engineer in charge. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.26	Sqm	550.00	Rupees Five Hundred Fifty Only	693
11	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (80 to 100 mm thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.30	Sqm	900.00	Rupees Nine Hundred Only	2970
12	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 6 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government.	11.85	Sqm	750.00	Rupees Seven Hundred Fifty Only	8888
13	Providing and fixing 15mm (fifteen millimetre) nominal bore size G.I. Pipes complete with G.I. fittings and clamps, including making good the walls etcetera concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall make of Jindal (Hissar)/Tata make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.00	Rmt	396.20	Rupees Three Hundred Ninety Six Paise Twenty Only	12678

14	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete.a) 110 mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	35.00	Mtr.	264.80	Rupees Two Hundred SixtyFour Paise Eighty Only	9268
15	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete.a) 75mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.00	Mtr.	203.20	Rupees Two Hundred Three Paise Twenty Only	2032
16	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete. 110 mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00	Each	139.05	Rupees One Hundred ThirtyNine Paise Five Only	834
17	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. complete. 75 mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	100.05	Rupees One Hundred Paise Five Only	200
18	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete 110 mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.00	Each	106.55	Rupees One Hundred Six Paise FiftyFive Only	320
19	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete 75 mm dia including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	87.05	Rupees EightySeven Paise Five Only	174
20	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete 110 mm X 75 mm. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	850.00	Rupees Eight Hundred Fifty Only	1700
21	Providing and fixing white vitreous china pedestal type water closet (European type) of size 385 x 675 x 780 mm with white solid plastic soft closing seat and lid of Jaquar (ECS-WHT-775ISS+ECS-WHT-201) /Hindware Snow White Shade ,10 (ten) litre low level white vitreous china flushing cistern and C.P. flush bend with fittings and C.I. brackets, 40 mm (forty millimetre) flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	7520.00	Rupees Seven Thousand Five Hundred Twenty Only	7520

22	Providing and fixing 8 mm (eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1.00 (one) metre long with S.S. triangular plate to European type W.C. of quality and make (Jaquar/Cera/Hindware) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	Each	297.60	Rupees Two Hundred NinetySeven Paise Sixty Only	298
23	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1.00	Each	3200.00	Rupees Three Thousand Two Hundred Only	3200
24	Providing and fixing uplasticised PVC connection pipe with brass unions 45cm (forty five centimetre) length 15mm (fifteen millimetre) nominal bore Cera/Jaquar/ Finolex / hindware Make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.00	Each	165.90	Rupees One Hundred SixtyFive Paise Ninety Only	664
25	Providing and fixing 15mm (fifteen millimetre) dia C.P. brass bib cock with wall flange of approved quality conforming to IS standards and weighing not less than 810 gms. (eight hundred ten gram) of Jaquar (CON-047KN) /Hindware Make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.00	Each	650.00	Rupees Six Hundred Fifty Only	3900
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99893
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)/A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)/A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (HP)

41

SCHEDULE OF QUANTITY							Estimated Cost	99200/-	
Name of work :- Restoriation of rain damages on (1) link road to village Tholian At RD 0/0 to 2/090 (2) link road to village Nayian Basti Baliwal at RD 0/0 to 1/500 (3)link rod to village Naiyan Rajputtan to Baliwal RD 0/0 to 1/600 Under section Ghaluwal (SH):- Hiring of excavator Cum Loader for Treming of Access soil in berm, removal of slips Debries & C/O Unlind drain in rainy season)							Earnest Money	2000/-	
							Time limit	one month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT			
				Figures	Words				
1	Hiring of hydraulic excavor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government.	72.00	Per Hour	1100.00	Rupess one thousand one hundred only	79200			
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	8.00	Per Day	2500.00	Rupess two thousand five hundred only	20000			
							Total:	99200	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018									
2) The rates shall be including of all types of taxes including GST ectra)									
Percentage quoted rate in Figures									
Percentage quoted rate in words									
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.									

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

42

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:C/O R/wall at RD 1/073 to 1/091)- Deposit work

Estimated Cost 98578
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification. Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.90	Per cubic metre	3300.00	Rupees three thousand three hundred only	88770
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax, octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax, octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
					Total:	98578

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jaijon Road 0/00 to 23/000

(SH: C/O Retaining wall at Rd. 20/506 to 20/512 Rhs.) - *work*

		Estimated Cost: Rs	₹ 97,977			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.83	Cum.	160.00	Rupees One Hundred Sixty Only	1253
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	93060
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.00	Each	160.00	Rupees One Hundred Sixty Only	2080
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.88	Cum.	550.00	Rupees Five Hundred Fifty Only	1584
Total						97977

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

Name of Work :- A/R & M/O Non residential Building of HPPWD Division at Haroli.

Name of Work :- A/R & M/O Non residential Building of HPPWD Division at Haroli.		Estimated Cost: Rs	₹ 99,806			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing and fixing anodized aluminium work for doors, windows, ventilators and partitions with Jindal aluminium extrusions built up standard tubular and other sections of approved make conforming to IS-733 and IS-1285 anodized transparent or dyed to required shade according to IS- 1868 fixed with rawl plugs and screws or with fixing clips or with expansion hold fasteners including necessary filling up of gaps at junctions and top and bottom, sides with required PVC/neoprene fill etc. Aluminium sections shall be smooth, rust free, straight mitered and jointed mechanically where ever required including cleat angle, aluminium snap leading for glazing/ paneling. C.P. brass stainless steel screw, all complete as per architectural drawing and the directions of Engineer-in-Charge for: including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	137.97	Kg	510.00	Rupees Five Hundred Ten Only	70365
2	Providing and fixing aluminium work for doors, windows, board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer- in-charge. Pre-laminated particle board with decorative lamination on both sides, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	21.45	Sqm	925.00	Rupees Nine Hundred TwentyFive Only	19841
3	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm thick glass panes, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.93	Sqm	850.00	Rupees Eight Hundred Fifty Only	2486
4	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	238.00	Rupees Two Hundred ThirtyEight Only	476
5	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :300x10 mm, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.00	Each	110.00	Rupees One Hundred Ten Only	220

44

6	Providing and fixing aluminum handles anodized transparent or dyed to required colour and shade with necessary screws etc . including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	4.00	Each	57.55	Rupees FiftySeven Paise FiftyFive Only	230
7	Providing and fixing white vitreous chinapedestal for wash basin completely recessed at the back for the reception of pipes and fittings. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1.00	Each	1420.00	Rupees One Thousand Four Hundred Twenty Only	1420
8	Providing and fixing 15mm (Fifteen millimetre) nominal bore C.P. brass stop cock for basin mixer and geyser points of approved quality conforming to IS:8931 of Jaquar (CON-CHR-059KN)/Hindware Make including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.00	Each	350.00	Rupees Three Hundred Fifty Only	1050
9	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete semi rigid pipe 32mm (thirty two millimetre) dia of Hindware or Cera make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals.The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.00	Each	160.00	Rupees One Hundred Sixty Only	320
10	Providing and fixing 100 mm dia C.P. Grating including fixing complete for gully floor or manni trap. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	4.00	Each	70.00	Rupees Seventy Only	280
11	providing and fixing 600x450mm bevelled edge mirror of superior glass mounted on 6mm thick A C sheet or plywood sheet and fixed to wooden plug with C P screws and washers. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1.00	Each	850.00	Rupees Eight Hundred Fifty Only	850
12	450 mm long towel rail with total length of 495 mm, 78 mm wide and effective height of 88 mm, weighing not less than 170 gms each 415.15 17.73.2 600. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	3.00	Each	550.00	Rupees Five Hundred Fifty Only	1650
13	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	1.50	Each	170.00	Rupees One Hundred Seventy Only	255

14	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundations of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer -in -charge, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	0.07	Cum	5500.00	Rupees Five Thousand Five Hundred Only	363
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99806
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

333

13

SCHEDULE OF QUANTITY						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
					Estimated Cost	99550/-
					Earnest Money	2000/-
					Time limit	one month
	Name of work: -Restoration of rain damages on Link Nagnoli to Harizan Basti Via Mohalla Brahmna, Gujran Chaperian KM 0/0 TO 3/345, Link road Nagnoli harizan basti to Rajputan Mohallan KM 0/0 to 1/500, Link Road Panjawan Bathri Road to Jhikla Panjawan KM 0/0 TO 2/550 Link road to the house of Mehtab singh KM 0/0 to 1/00 (SH:- Hiring of excavator Cum Loader for Treiming of Access soil in berm, removal of slips Debrries & C/O Unlind drain in rainy season).(Phase-III)					
1	Deployment of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor. The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST ,labour cess or other taxes imposed by the Government.	90.50	Per Hour	1100.00	Rupees One thousand one hundred only	99550
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99550
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity

46

Name of work: -C/O Levelling work in plyground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd . (Deposit work).						Estimated Cost: Rs	₹ 99,688
(SH: Providing & laying good earth material on top of play ground.) Phase-I						Time:-	One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge.The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	398.75	Cum	250.00	Rupees Two Hundred Fifty Only	99688	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99688	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W.D. Division Harol
Distt. Una (H.P.)

349

48

SCHEDULE OF QUANTITY

Estimated cost	92500
Earnest money	2000
Time limit	One month

Name of work: A/R & M/O PWD Non Residential building at Haroli (SH: P/F All in one HP-PC with i5 ,16 GB RAM ,1TB SSD with Microsoft office in Chief Office (HZ) Hamirpur HPPWD)

SCHEDULE OF WORK / ITEM(S)


S.No	Description of Work / Item(s)	Qty	Unit	RATE In		Amount
				Figures	Words	
1	Providing and installation commercial All in one HP make computer system with with i 5-27" (Twenty seven inch) size ,16 GB RAM ,1TB SSD, Intel UMA Graphics with Microsoft office & Window 11/12 Wi, fi, & Bluetooth 4.0 M.2/ wireless keyboard and mouse combo with 3 year warranty provided by the manufacturer from date of purchase) including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	1.00	Each	92500.00	Rupees Ninety Two thousand five hundred only	92500
					Total	92500
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HP.PWD.,Haroli

331

Schedule of quantity

Name of work: -C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd . (Deposit work).		Estimated Cost: Rs		₹ 99,516		
(SH: Providing & laying good earth material on top of play ground.) Phase-II		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	398.06	Cum	250.00	Rupees Two Hundred Fifty Only	99516
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99516
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haridwar
 Distt. Una (H.P.)

400

50

SCHEDULE OF QUANTITY

Name of work :- Gramin sampark R/wall from link road to the house of Sh Parveen kumar W No 2 GP Pandoga (SH:- C/O R/wall - phase -I)

Sl. No.	Description of work	Quantity	Unit	RATE IN		Estimated Cost Earned Money	99532/- 2000/- One month
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.13	Per cubic metre	160.00	Rupees One hundred sixty only	1781	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government	27.56	Per cubic metre	3300.00	Rupees three thousand three hundred only	90948	
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government	9.00	Each	160.00	Rupees One hundred sixty only	1440	
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government	9.75	Per cubic metre	550.00	Rupees One hundred sixty only	5363	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(17)2/02112 dated 7.8.2018						Total:	99532
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

51

SCHEDULE OF QUANTITY

Name of work : Restrotration of rain damages on Jaijon Mod Bhai ka Mod upto Tahlilwal Chowk Km 0/00 17/500 (SH: Removal of debries & disilting of Kangar Khad causeway at RD 3/795 to 3/830) - Phase-I		Estimated Cost				
		Earnest Money	99300			
		Time limit	2000/- One month			
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for removal of debries including sand , silt, boulders and other material from the bed of khad from both up stream and down streams as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	83.00	Per Hour	11000.00	Rupees One thousand one hundred only	91300
	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for removal of debries including sand , silt, boulders and other material etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Per Day	2000.00	Rupees Two thousand only	8000
				Total:		99300
1) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						


 Executive Engineer
 Haroli Division
 HPPWD Haroli

345

52

Schedule of quantity

Name of work: -C/O Levelling work in playground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd . (Deposit work).		Estimated Cost: Rs	₹ 99,344			
		Time:-	One month			
(SH: Providing & laying good earth material on top of play ground.) Phase-III		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge.The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	397.38	Cum	250.00	Rupees Two Hundred Fifty Only	99344
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99344
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Ha
Distt. Una (H.P.)

401

Draft Schedule of quantity

53

Name of work: -Restoration of rain damages on Link road Polian to Janani km. 0/00 to 6/00 .		Estimated Cost: Rs	₹ 98,100			
		Time:-	One month			
(SH: Deploymet of excavator Cum Loader & Trector for Treming of Access soil in berm Removal of slips & C/O unilind drain etc. in rainy season etc.) - Phos-I		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Deploymet of Hudraulic excavator 0.90 cum fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer in charge i/c all leads and lifts. The cost of Lubricant diesel etc. operator will be borne by the contractor.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	71.00	P/ Hour	1100.00	(Rupees one thousand one hundred only)	78100
2	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for disposing/carring of material like earth kankar moorum, shingles and boulder etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	8.00	P/day	2500.00	(Rupees two thousand five hundred only)	20000
					Total	98100
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

54

SCHEDULE OF QUANTITY

Estimates cost:- Rs. 98784/-
Earnest Money:- Rs. 2000/-
One Month.

Name of Work :- Repair & Restoration work on Umrali Singan road km0/00 ton 6/550 (Sh:- P/L Steel Built up Section /frame over U drain at RD 2/770 to 2/798-RHS) Deposit work

54

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1008.00	Per Kilogramme	98.00	Rupees ninety eight only	98784
	Total					98784
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)@17/02/12 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

378

55

Schedule of quantity

Name of work :- Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No 7.G.P. Badhera. (SH: C/O CC Pavement & Edge wall at Rd. 0/008.80 to 0/017.50) - P work		Estimated Cost: Rs	₹ 98,492			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	31.32	CUM.	850.00	Rupees Eight Hundred Fifty Only	26622
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge., including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.70	CUM.	170.00	Rupees One Hundred Seventy Only	799
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.61	CUM.	1150.00	Rupees One Thousand One Hundred Fifty Only	3002
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	13.57	CUM.	3400.00	Rupees Three Thousand Four Hundred Only	46145
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25 (i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	3.92	CUM.	5600.00	Rupees Five Thousand Six Hundred Only	21924
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total	98492
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

56

SCHEDULE OF QUANTITY

Name of work : Restroation of rain damages on Jaijon Mod Bhai ka Mod upto Tahliwal Chowk Km 0/00
 17/500 (SH: Removal of debries & disilting of Kangar Khad causeway at RD 3/795 to 3/830)- Phase-IV

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for removal of debries including sand , silt, boulders and other material from the bed of khad from both up stream and down streams as per direction of the Engineer-in-charge. The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	81.00	Per Hour	1100.00	Rupees One thousand one hundred only	89100
	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for removal of debries including sand , silt, boulders and other material etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours. The rate includes sale tax octori, royalty,maikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.00	Per Day	2000.00	Rupees Two thousand only	10000
					Total:	99100
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer
 Haroli Division
 HPPWD Haroli

348

57

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:C/O R/wall at RD 1/018 to 1/036)- Deposit work

Estimated Cost 98771
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.91	Per cubic metre	3300.00	Rupees three thousand three hundred only	88803
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 708, 1204.3.7 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.00	Each	160.00	Rupees One hundred Sixty only	2400
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
					Total:	98771
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/1712/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)/A(31)/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

365

58

Schedule of quantity

Name of work: - C/O Levelling work in plyground near GSSS Nangal Khurd Mohalla Thai Nangal Khurd . (Deposit work).		Estimated Cost: Rs		₹ 99,172		
(SH: Providing & laying good earth material on top of play ground.) Phase-IV		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana , toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	396.69	Cum	250.00	Rupees Two Hundred Fifty Only	99172
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99172
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli,
 Distt. Una (H.P.)

402

59

SCHEDULE OF QUANTITY						
Name of work : Restoration of rain damages on link road village Singan to HP Boundary Km 0/00 to 1/300 .(SH: Hiring of excavator cum Loader for the C/O unlined drain, clearance of existing drain, removal of minor slips etc.) -Phase-II		Quantity	Unit	Figures	Words	Estimated Cost
S. No.	Description of work					
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock etc (where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octroi, royalty,malkhana ,toil tax,GST,labour cess or other taxes imposed by the Government..	90 00	Per Hour	1100.00	Rupees one thousand one hundred only	99000
				Total:		99000
1) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HPPWD Haroli

17

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:C/O R/wall at RD 1/036 to 1/054)- Deposit work

Estimated Cost 98512
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.88	Per cubic metre	3300.00	Rupees three thousand three hundred only	88704
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)/one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709, 1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred only ^{Sixty}	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
					Total:	98512

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20

Percentage quoted rate in Figures
Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

62

SCHEDULE OF QUANTITY						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
	Name of work: -Restoration of rain damages on Link Road Lawana Basti Ispur to Dera Baba Bharthri Damamiyan KM 0/0 TO 5/580 in Pandoga section under Khad sub division HPPWDKhad (SH: Hiring of excavator Cum Loader for Treeming of Access soil in berm, removal of slips & C/OUNlined drain in rainy season).				Estimated Cost	99550/-
					Earnest Money	2000/-
					Time limit	one month
1	Hiring of hydraulic excavator 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock(where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within, all leads and lifts and other incidentals.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy ,PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021	90.50	Per Hour	1100.00	Rupees One thousand one hundred only	99550
					Total:	99550
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

63

SCHEDULE OF QUANTITY

Name of work : Restoriation of rain damages on Lалуwal Gondpur Jaichand to Singan, Jhungian upto Punjab Boundary road Km 0/00 to 13/570 (SH: Removal of debries & disifiting of Hume Khad at RD 8/025) - Phase-I

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for removal of debries including sand , silt, boulders and other material from the bed of khad from down streams side as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	82.00	Per Hour	1100.00	Rupees One thousand one hundred only	90200
2	Hiring of Tractor with Trolley 3 00cum. capacity to be deployed for removal of debries including sand , silt, boulders and other material etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakge during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4 00	Per Day	2000.00	Rupees Two thousand only	8000
					Total:	98200
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					

Executive Engineer
Haroli Division
HPPWD Haroli

(64)

SCHEDULE OF QUANTITY

Estimates cost:- Rs.99951
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at khad GP Khad (SH: C/O CC pavement & C/O R/wall - Phase-I)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.66	Per Cubic metre.	160.00	Rupees one hundred sixty only	1866
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203	27.05	Per Cubic metre.	3300.00	Rupees three thousand three hundred only	89265
	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.00	Each	160.00	Rupees one hundred sixty only	1120
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-25 (M-twenty five) nominal mix in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.40	Per Cubic metre.	5500.00	Rupees five thousand five hundred only	7700
	Total					99951
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)M(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

65

Schedule of quantity

Name of work :- Repair & Restoration work of road Baba Sidh Chano Temple to Mata Mandir Ward No 7.G.P. Badhara. (SH: C/O CC Pavement & Edge wall at Rd. 0/00 to 0/008.80)		Estimated Cost: Rs		₹ 99,623			
		Time:-		One month			
		Earnest Money:-		2000			
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (f/c equivalent design mix. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkama toll tax sale tax, GST, labour cess or other taxes imposed by the Government	31.68	CUM.	850.00	Rupees Eight Hundred Fifty Only	26928	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge.. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkama toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.75	CUM.	170.00	Rupees One Hundred Seventy Only	808	
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with roliavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkama toll tax sale tax, GST, labour cess or other taxes imposed by the Government	2.64	CUM.	1150.00	Rupees One Thousand One Hundred Fifty Only	3036	
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkama toll tax sale tax, GST, labour cess or other taxes imposed by the Government	13.73	CUM.	3400.00	Rupees Three Thousand Four Hundred Only	46675	
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 25(f)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkama toll tax sale tax, GST, labour cess or other taxes imposed by the Government	3.96	CUM.	5600.00	Rupees Five Thousand Six Hundred Only	22176	
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						Total	99623
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021							
Percentage quoted rate in figures							
Percentage quoted rate in words							
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected							

SCHEDULE OF QUANTITY

66

Estimates cost:- Rs.98741/-
 Earnest Money:- Rs. 20000/-
 Time Limit:- One Month.

Name of work:- Repair & Restoration work on Umrali Singan road km 0/00 to 6/550 (SH:- C/O U-shape drain at RD 2/770 to 2/796 RHS and V shape drain RD 2/760 to 2/720- RHS)Deposit work

	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	37.74	Per Cubic metre.	160.00	Rupees one hundred sixty only	6038
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement :three sand:six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-charge .including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	23.77	Per Cubic metre.	3900.00	Rupees three thousand nine hundred only	92703
Note:-	Total					98741
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt.of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B/A)(31/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

377

Rippon

67

Schedule of quantity

Name of work :- Balance work for the C/O link road from the H/O Sh. Pawan Kaundal to Lower Badhera ward no.5 G.P. Lower Badhera (Deposit work).		Estimated Cost: Rs		One month		
(SH: P/L 60 mm thick paver blocks length = 21.00 mtr.) (Phase-I)				₹ 98,154		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-	
					Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.90	Cum.	160.00	Rupees One Hundred Sixty Only	3024.00
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.30	Cum.	1100.00	Rupees One Thousand One Hundred Only	6930.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.30	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	20790.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	63.00	Cum	800.00	Rupees Eight Hundred Only	50400.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.78	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	17010.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)/A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)/A(31)/2020-1 Dated 07.10.2021				Total	98154
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note - Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

68

SCHEDULE OF QUANTITY

Estimates cost:- Rs.99654
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at khad GP Khad (SH: C/O CC pavement & C/O R/wall - Phase-II)- Deposit work


S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.66	Per Cubic metre	160.00	Rupees one hundred sixty only	1866
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:right graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work, as per drawings and technical specification Clause 802,803,1202 and 1203	26.86	Per Cubic metre	3300.00	Rupees three thousand three hundred only	88638
3	Providing weepholes in brick masonry/ stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204,3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	7.00	Each	160.00	Rupees one hundred SIXTY only	1120
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-25 (M-twenty five) nominal mix in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	1.46	Per Cubic metre	5500.00	Rupees five thousand five hundred only	8030
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter.No PBW(B)A(31)/2020 dated 22.07.20 Percentage quoted rate in Figures Percentage quoted rate in words					99654
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Tenderer with seal

Schedule of quantity
Name of Work:- Restoration of link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225

Name of Work:- Restoration of link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225		Estimated Cost: Rs		₹ 98,973		
(SH: C/O Retaining wall in Rd. 1/380 to 1/406 Rhns).		Time:-		One month		
DESCRIPTION		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	9.36	Cum.	160.00	Rupees One Hundred Sixty Only	1498
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.67	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94595
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 .including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government.	18.00	Each	160.00	Rupees One Hundred Sixty Only	2880
					Total:	98973
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						


Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

1103

Rispon

70

Schedule of quantity

Name of work :- Balance work for the C/O link road from the H/O Sh. Pawan Kaundal to Lower Badhera ward no.5 G.P. Lower Badhera (Deposit work).		Estimated Cost: Rs		₹ 99,089		
(SH: P/L 60 mm thick paver blocks length = 21.20 mtr.) (Phase-II)		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.08	Cum.	160.00	Rupees One Hundred Sixty Only	3053.00
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.36	Cum.	1100.00	Rupees One Thousand One Hundred Only	6996.00
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.36	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	20988.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	63.60	Cum	800.00	Rupees Eight Hundred Only	50880.00
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	3.82	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	17172.00
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99089
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note :-Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

572

SCHEDULE OF QUANTITY

Estimates cost:- Rs.99487/-
 Earnest Money:- Rs. 2000/-
 Time Limit:- One Month.

Name of work :- Restoration of Gramin Sampark alongwith R/wall to the campus of Mata Santoshi Temple at khad GP Khad (SH: C/O CC pavement & C/O R/wall - Phase-III)- Deposit work

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	11.62	Per Cubic metre.	160.00	Rupees one hundred sixty only	1859
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802,803,1202 and 1203	26.86	Per Cubic metre	3300.00	Rupees three thousand three hundred only	88638.
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204,3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	6.00	Each	160.00	Rupees one hundred sixty only	960
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-25 (M-twenty five) nominal mix in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.46	Per Cubic metre	5500.00	Rupees five thousand five hundred only	8030
	Total					99487

Note:- 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@1712/9212 dated 7.8.2018
 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20
 Percentage quoted rate in Figures
 Percentage quoted rate in words
 Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

394

73

Draft Schedule of quantity

Name of Work:- Restoration of link road to Co-Operative society Haroli via GSSS Haroli K.M. 0/00 to 2/225 (SH: Providing & laying 80 mm thick paver block at Rd. 1/445.50 to 1/460.90).		Estimated Cost: Rs		₹ 98,960		
		Time:-		One month		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.79	Cum.	160.00	Rupees One Hundred Sixty Only	3326
2	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.93	Cum.	1100.00	Rupees One Thousand One Hundred Only	7623
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.93	Cum	3300.00	Rupees Three Thousand Three Hundred Only	22869
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	69.30	Cum.	850.00	Rupees Eight Hundred Fifty Only	58905
5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.39	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	6237
					Total:	98960
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy.,PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

405

Executive Engineer,
H.P.P.W.D. Division Ha
N

74

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhalwala Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/I CC Pavement at Rd. 0/046 to 0/057). - D Work		Estimated Cost: Rs	₹ 98,613			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	17.33	CUM.	250.00	(Rupees two hundred fifty only)	4331
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	25.08	CUM.	160.00	(Rupees One hundred sixty only)	4013
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	12.76	CUM.	3900.00	(Rupees Three thousand nine hundred only)	49764
4	Steel work welded in built up sections/ framed work,including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.in gratings, frames, guard bar, ladder,railings, brackets, gates and similar works. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	144.00	Kg.	98.00	(Rupees ninety eight only)	14112

75

Schedule of quantity


Name of work:- Repair and restoration of Gramin Sampark from Chhahvala Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/033 to 0/046). <i>work</i>		Estimated Cost: Rs	₹ 98,824			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	20.48	CUM.	250.00	(Rupees two hundred fifty only)	5119
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508

76

Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jajion Road 0/00 to 23/000		Estimated Cost: Rs	₹ 97,497			
(SH: C/O Retaining wall at Rd. 20/518 to 20/524 Rhs.) - P. Nork		Time:-	One month			
DESCRIPTION		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.83	Cum.	160.00	Rupees One Hundred Sixty Only	1253
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	28.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	93060
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	10.00	Each	160.00	Rupees One Hundred Sixty Only	1600
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	2.88	Cum.	550.00	Rupees Five Hundred Fifty Only	1584
Total						97497

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018



 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhalwala Temple to Jongpur road GP Gondpur Bulla.		Estimated Cost: Rs		₹ 98,531		
(SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/020 to 0/033). → work		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	20.48	CUM.	250.00	(Rupees two hundred fifty only)	5119
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508

77

5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.55	CUM.	3300.00	(Rupees Three thousand three hundred only)	15015
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.45	CUM.	5500.00	(Rupees five thousand five hundred only)	2475
7	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	54.00	Kg.	90.00	(Rupees ninety only)	4860
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98531
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures				(+) 5% above	
	Percentage quoted rate in words				Five percent above	
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.W.D. Division Haroli
 Distt. Una (H.P.)

Rajat Kumar
 v.l. Sureshra
 Mr. S.D.H. Una Civil

Rajat

332

78

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhalva Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/070 to 0/083). <i>Dilwak</i>						Estimated Cost: Rs Time:-	₹ 99,687 One month
						Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.75	CUM.	250.00	(Rupees two hundred fifty only)	5688	
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812	
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508	

79

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: P/L CC Pavement at Rd. 0/353 to 0/367).		Estimated Cost: Rs		₹ 98,821		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.00	CUM.	3300	(Rupees Three thousand Three hundred only)	23100
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(f) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.60	CUM.	5500	(Rupees Five thousand five hundred only)	63814
3	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	132.30	Kg	90.00	(Rupees Ninety only)	11907
Total						98821
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

80

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: P/L CC Pavement at Rd. 0/339 to 0/353).		Estimated Cost: Rs		₹ 97,354		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.00	CUM.	3300	(Rupees Three thousand Three hundred only)	23100
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.51	CUM.	5500	(Rupees Five thousand five hundred only)	63319
3	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	121.50	Kg	90.00	(Rupees Ninety only)	10935
					Total	97354
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

81

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhawa Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/135 to 0/145).		Estimated Cost: Rs	₹ 77,923			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	17.50	CUM.	250.00	(Rupees two hundred fifty only)	4375
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.80	CUM.	160.00	(Rupees One hundred sixty only)	3648
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.60	CUM.	3900.00	(Rupees Three thousand nine hundred only)	45240
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	5.25	CUM.	1100.00	(Rupees One thousand one hundred only)	5775

82

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhawala Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/057 to 0/070). <i>→ D Wax</i>		Estimated Cost: Rs		₹ 99,118		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	20.48	CUM.	250.00	(Rupees two hundred fifty only)	5119
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508

5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.55	CUM.	3300.00	(Rupees Three thousand three hundred only)	15015
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.49	CUM.	5500.00	(Rupees five thousand five hundred only)	2673
7	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	58.32	Kg.	90.00	(Rupees ninety only)	5249
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	99118
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Sankar Arora
 J. P. O. GONDPUR Bala
 Mr. Board & Distt. Me
 SK

Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

83

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: P/L CC Pavement at Rd. 0/325 to 0/339).		Estimated Cost: Rs	Time:-	₹ 99,188		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.00	CUM.	3300	(Rupees Three thousand Three hundred only)	23100
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.63	CUM.	5500	(Rupees Five thousand five hundred only)	63938
3	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	135.00	Kg	90.00	(Rupees Ninety only)	12150
Total						99188
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP, vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
P.P.W.D. Division Ha
Distt. Una (H.P.)

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: Repair of old drain Rd. 0/297 to 0/350).		Estimated Cost: Rs	₹ 99,873			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix i/c equivalent design mix including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	44.75	CUM.	800.00	(Rupees eight hundred only)	35796
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	16.43	CUM.	3900.00	(Rupees Three Thousand Nine hundred only)	64077
					Total	99873
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
 H.P.P.W.D. Division Haridwar,
 Distt. Una (H.P.)

84

85


Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jajion Road 0/00 to 23/000

(SH: C/O Retaining wall at Rd. 20/500 to 20/506 Rhs.) - P. W. S. R.

Name of work:- Restoration of rain damage on Una Rampur Haroli Jajion Road 0/00 to 23/000		Estimated Cost: Rs		₹ 97,817		
(SH: C/O Retaining wall at Rd. 20/500 to 20/506 Rhs.) - P. W. S. R.		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.83	Cum.	160.00	Rupees One Hundred Sixty Only	1253
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	93060
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	Each	160.00	Rupees One Hundred Sixty Only	1920
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.88	Cum.	550.00	Rupees Five Hundred Fifty Only	1584
Total						97817

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018


 Executive Engineer,
 P.P.W.D. Division Haridwar
 Distt. Una (H.P.)

86

Schedule of quantity

Name of work: - Restoratin of rain damages on Panjwar Bathri Road to Ispur Pathak Mohalla Kayaria Road km. 0/0 to 1/900,L/R To Vill. Mohalla Tiperian KM 0/0 TO 6/650		Estimated Cost: Rs		₹ 98,832		
(SH: Repair of Rain cuts at Various RDs)		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	411.80	Cum	240.00	Rupees Two Hundred Fourty Only	98832
					Total:	98832
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

386

87

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: Repair of old drain Rd. 0/220 to 0/297).		Estimated Cost: Rs		₹ 98,637		
		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix i/c equivalent design mix including entire carriage of material within all leads and lifts and other incidentals and as per the direction of Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.93	CUM.	800.00	(Rupees eight hundred only)	5544
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	23.87	CUM.	3900.00	(Rupees Three Thousand Nine hundred only)	93093
					Total	98637
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haro
Distt. Una (H.P.)

88

Schedule of quantity

Name of work:- Restoration of rain damages on link road Butt to Butt Jagrian km 0/00 to 1/700 (SH: P/L CC Pavement at Rd. 0/367 to 0/381).		Estimated Cost: Rs	₹ 99,420			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including. including entire carriage of material within all leads and lifts and other incidentals and, as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	7.00	CUM.	3300	(Rupees Three thousand Three hundred only)	23100
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	11.64	CUM.	5500	(Rupees Five thousand five hundred only)	64016
3	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	136.71	Kg	90.00	(Rupees Ninety only)	12304
Total						99420
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 P.P.W.D. Division Ho
 Distt. Una (H.P.)

430

89

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhalivala Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/122 to 0/135).							Estimated Cost: Rs	₹ 98,513
							Time:-	One month
							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.75	CUM.	250.00	(Rupees two hundred fifty only)	5688		
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C.grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812		
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508		

5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.55	CUM.	3300.00	(Rupees Three thousand three hundred only)	15015
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.41	CUM.	5500.00	(Rupees five thousand five hundred only)	2277
7	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	49.68	Kg.	90.00	(Rupees ninety only)	4471
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018				Total	98513
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhāvāla Temple to Jongpur road GP Gondpur Bulla.							Estimated Cost: Rs	₹ 98,807
(SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/083 to 0/096). - D) work							Time:-	One month
							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.75	CUM.	250.00	(Rupees two hundred fifty only)	5688		
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812		
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508		

90

5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.55	CUM.	3300.00	(Rupees Three thousand three hundred only)	15015
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.43	CUM.	5500.00	(Rupees five thousand five hundred only)	2376
7	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	51.84	Kg.	90.00	(Rupees ninety only)	4666
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	98807
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021				(+) 5% above	
	Percentage quoted rate in figures				Five percent above	
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.F.)


Sikander Mohan
V.P.O. Gondpur Batta
T.G. Mohli, Distt. Una

ESG

912

Schedule of quantity

Name of work: - Restoratin of rain damages on Link Road Panjavar Bathri Road To Behli Khad KM 0/0 TO 3/040,Link Road To Village Khad KM 0/0 TO 2/240,Link Road to Vill daultapur KM 0/0 TO 1/660					Estimated Cost: Rs	₹ 99,225
(SH: Repair of Rain cuts at Various RDs)					Time:-	One month
					Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	413.44	Cum	240.00	Rupees Two Hundred Fourty Only	99225
					Total:	99225
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

SRT

93

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhalwala Temple to Jongpur road GP Gondpur Bulla. (SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/096 to 0/109).		Estimated Cost: Rs	₹ 99,100			
		Time:-	One month			
		Earnest Money:-	2000			
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.75	CUM.	250.00	(Rupees two hundred fifty only)	5688
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508

94

Schedule of quantity

Name of work:- Repair and restoration of Gramin Sampark from Chhawalwa Temple to Jongpur road GP Gondpur Bulla.							Estimated Cost: Rs	₹ 98,220
(SH: C/O U-Shape drain & P/L CC Pavement at Rd. 0/109 to 0/122).							Time:-	One month
							Earnest Money:-	2000
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount		
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	22.75	CUM.	250.00	(Rupees two hundred fifty only)	5688		
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	29.64	CUM.	160.00	(Rupees One hundred sixty only)	4742		
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	15.08	CUM.	3900.00	(Rupees Three thousand nine hundred only)	58812		
4	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	6.83	CUM.	1100.00	(Rupees One thousand one hundred only)	7508		

5	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	4.55	CUM.	3300.00	(Rupees Three thousand three hundred only)	15015
6	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	0.40	CUM.	5500.00	(Rupees five thousand five hundred only)	2178
7	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government	47.52	Kg.	90.00	(Rupees ninety only)	4277
					Total	98220
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures				(1) 55.00	
	Percentage quoted rate in words				Five hundred only	
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

~~Prateek Kumar~~
~~M.A. Suresh~~
~~Prateek Kumar~~
~~Prateek Kumar~~

96

SCHEDULE OF QUANTITY

		Estimated Cost		99819		
		Earnest Money		2000		
		Time limit		One month		
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
Name of work: Restoration of rain damages on Samnal Baliwal road by providing R/wall at RD 4/265 to 4/271.10 & P/L 900 mm dia RCC pipe)- Deposit work						
1	Earth work in excavation by mechanical means (hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	9.60	Per cubic metre	160.00	Rupees One hundred sixty only	1536
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in- charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government	28.11	Per cubic metre	3300.00	Rupees three thousand three hundred only	92763
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 6.14.709, 1204 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Each	160.00	Rupees One hundred sixty only	2880
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Per cubic metre	550.00	Rupees Five hundred fifty only	2640

Providing and laying 900mm (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in Single row including fixing collar with cement mortar but excluding excavation, protection work in head walls and parapets clause 1108 including carriage of material within all leads and lifts and other incidentals The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	5 00	Per Running metre	3650.00	Rupees three thousand six hundred fifty only	18250
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	99819
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
Percentage quoted rate in Figures					
Percentage quoted rate in words					
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer,
 H.P.P.W.D. Division Haridwar
 Distt. Una (H.P.)

97

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Samnal Baliwal road by providing R/wall at RD 4/257.50 to 4/265- Deposit work		Estimated Cost 99829				
		Earnest Money 2000				
		Time limit One month				
S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.60	Per cubic metre	160.00	Rupees One hundred sixty only	1536
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement : four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.11	Per cubic metre	3300.00	Rupees three thousand three hundred only	92763
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	18.00	Each	160.00	Rupees One hundred sixty only	2880
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Per cubic metre	550.00	Rupees Five hundred fifty only	2640
				Total:		99819
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/20212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

98

SCHEDULE OF QUANTITY

Estimated Cost 99603
Earnest Money 2000/-
Time limit One month

Name of work:- A/R & M/O Non Residential building PWD Rest House at Haroli (SH: Painting work to boundary wall etc.)

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	651.00	Per Square metre	10.00	Rupees ten only	6510
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	195.30	Per Square metre	60.00	Rupees sixty only	11718
3	Applying one coat of water thinnable cement primer of approved brand and manufacture surfac Water thinnable cement primer in any floor level/height including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	651.00	Per Square metre	45.00	Rupees forty only	29295
5	Finishing walls with Acrylic Smooth exterior paint of required shade Old work (Two or more coat applied @ 1.67 ltr/10 sqm) on existing cement paint surface including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	651.00	Per Square metre	80.00	Rupees eighty only	52080
	Total					99603
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.W.D. Division Haro
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Samnal Baliwal road by providing R/wall at RD 4/250 to 4/257.50- Deposit work

Estimated Cost 99979
Earnest Money 2000
Time limit One month

S. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, Malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	9.60	Per cubic metre	160.00	Rupees One hundred sixty only	1536
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 One cement: four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	28.11	Per cubic metre	3300.00	Rupees three thousand three hundred only	92763
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	19.00	Each	160.00	Rupees One hundred sixty only	3040
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Per cubic metre	550.00	Rupees Five hundred fifty only	2640
				Total:		99979

100

Percentage quoted rate in Figures
Percentage quoted rate in words
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

Executive Engineer,
H.P.W.D. Division Haridwar
Distt. Una (H.P.)

101

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on various roads under Haroli & T/wala Sub-Division HPPWD (SH:Supplying and fixing of sign boards & writing)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Supplying and fixing of direction and place identification sign boards as per IRC: 67 made of 1.5mm (One point five millimetre) thick MS sheeting vide clause 1701.23 with area exceeding 0.90sqm. supported on 40mm dia pipe , painted with red lead primer as approved drawing and technical specifications, clause 1701(1200mmx900mm) size boards including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	10.00	each	6200.00	Rupees Six thousand two hundred nly	62000
2	Writing letter of figures on any surface with black japan paint including stops, commas, hyphen extra including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkhana,GST toll tax sale tax other taxes imposed by the Govt.	20450.00	Per letter per centimetre height	1.75	Rupees one and paise seventy five only	35788
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government .	25.00	Per Square metre	80.00	Rupees eighty only	2000
				Total:		99788
<p>NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018</p> <p>3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7. 10.2021</p>						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						
						Executive Engineer, H.P.P.W.D. Division Haro Distt. Una (H.P.)

Draft Schedule of quantity

Name of work:- C/O Boundary wall at HWC ward no. 7 GP Pucca Prangan GP Pubowal.


		Estimated Cost: Rs		Time:-		
		Earnest Money:-		One month		
				1400		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in all leads of 20 mtrs:Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.20	Cum.	160.00	Rupees one hundred sixty only	192
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.24	Cum.	3300.00	Rupees three thousand three hundred only	792
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.20	Cum	3850.00	Rupees three thousand eight hundred fifty only	4620
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.60	Sqm.	350.00	Rupees three hundred fifty only	3360
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.80	Sqm.	284.20	Rupees two hundred eighty four and twenty paise only	227
6	Applying coat of hot bitumen (Mexpphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.80	Sqm.	95.85	Rupees Ninety five and eighty five paise only	77
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.32	Cum	6640.00	Rupees six thousand six hundred forty only	2108
8	Half brick masonry in common burnt clay building bricks in superstructure : Cement Mortar 1:4 (1 cement:4 sand) First Class Bricks. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	17.05	Sqm	850.00	Rupees Eight hundred fifty only	14493

103

D.P.R.

9	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	19.39	Sqm	210.00	Rupees two hundred ten only	4071
10	Providing & Laying Cement Concrete 1 : 2 : 4 (1Cement :2Sand :4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in :-String courses ,coping, bed plates . including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.11	Cum	5230.00	Rupees five thousand two hundred thirty only	595
11	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm). including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	19.66	Sqm	80.00	Rupees eighty only	1573
12	Steel work in single sections including cutting,hoisting,fixing in position and applying a priming coat of red lead paint in grating,Framed guards,bars,leadders,railings,brackets & similar works. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	265.00	kgs	95.00	Rupees ninety five only	25175
13	Painting two coats(excluding priming coat) on new steel and other metal surface with ready mixed paint,brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter:foreign matter. With ready mixed paint other than white. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	16.32	Sqm	80.00	Rupees eighty only	1306
	Total					58589

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018


 Executive Engineer,
 H.P.P.W.D. Division Haridwar
 Distt. Una (H.P.)

428

105

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:CO R/wall at RD 1/091 to 1/109)- Deposit work

Estimated Cost 98407
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana . toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/or ground complete including pumping or bailing out water; dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana . toll tax, GST, labour cess or other taxes imposed by the Government.	26.90	Per cubic metre	3300.00	Rupees three thousand three hundred only	88770
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614, 709, 1204, 3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana . toll tax, GST, labour cess or other taxes imposed by the Government.	13.00	Each	160.00	Rupees One hundred sixty only	2080
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204 3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana . toll tax, GST, labour cess or other taxes imposed by the Government.	11.50	Per cubic metre	550.00	Rupees five hundred fifty only	6325
					Total:	98407


Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

369

106

Schedule of quantity

Name of work : Restoration of rain damages on link road to Village Sainsowal road km. 0/00 to 2/205 (SH: C/O R/wall Rd. 1/740.80 to 1/744.90 Rh's & C/O approach slab)		Estimated Cost: Rs		₹ 99,526		
S.NO	DESCRIPTION	Time:-		One month		
		Qty	Unit	T.Rate	Amount	
		Earnest Money:-		Rate in words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.75	Cum.	160.00	Rupees One Hundred Sixty Only	1240
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	10.52	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	34704
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.00	nos	150.00	Rupees One Hundred Fifty Only	900
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1.97	Cum.	550.00	Rupees Five Hundred Fifty Only	1082
5	Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M 25 1:1.5:3 Design Mix. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Cum.	5500.00	Rupees Five Thousand Five Hundred Only	22000
6	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in superstructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	440.00	kg	90.00	Rupees Ninety Only	39600
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018					Total	99526
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						


 Executive Engineer,
 H.P.W.D. Division Haridwar
 Distt. Una (H.P.)

408

107

Schedule of quantity

Name of work : Restoration of rain damages on link road to Village Sainsowal road km. 0/00 to 2/205						Estimated Cost: Rs	₹ 99,294
(SH: C/O R/wall Rd. 1/730 to 1/740.80 RhS)						Time:-	One month
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-		
					Rate in words	Amount	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	20.41	Cum.	160.00	Rupees One Hundred Sixty Only	3266	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	27.70	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	91417	
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	11.00	nos	160.00	Rupees One Hundred Sixty Only	1760	
4	Back filling behind abutment , wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	5.18	Cum.	550.00	Rupees Five Hundred Fifty Only	2851	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018				Total	99294	
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						

Executive Engineer,
H.P.P.W-D. Division Haroli
Mett. Una (H.P.)

108

SCHEDULE OF QUANTITY

Name of work:-Restoration of rain damage on link road to Harijan Basti Beetan to village Beetan Km 0/00 to 1/300 (SH:CO R/wall at RD 1/146 to 1/164)- Deposit work

Estimated Cost 98611
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE IN		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.91	Per cubic metre	3300.00	Rupees three thousand three hundred only	88803
3	Providing weepholes in brick masonry/ stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred sixty only	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
				Total:		98611
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(1712/0212 dated 7.8.2018						
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No PBW(B)A(311/2020 dated 22.07.20						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.						

Executive Engineer,
H.P.P.W.D. Division, Haroli
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road Mohalla Kutta to Sant Danguwala Km 0/00 to 1300 (SH:C/O R/wall at RD 0/568 to 0/586)- Deposit work

Estimated Cost 98611/-
Earnest Money 2000/-
Time limit One month

109

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.91	Per cubic metre	3300.00	Rupees three thousand three hundred only	88803
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.708, 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	14.00	Each	160.00	Rupees One hundred fifty only	2240
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
					Total:	98611

NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)(17)2/0212 dated 7.8.2018
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)A(31)/2020 dated 22.07.20

Percentage quoted rate in Figures
Percentage quoted rate in words

Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.


 Executive Engineer,
 H.P.P.W.D. Division Harol
 Distt. Una (H.P.)

5 B1

110

SCHEDULE OF QUANTITY

Name of work: Restoration of rain damage on link road Mohalla Kutta to Sant Danguwala Km 0/00 to 1/300 (SH:C/O R/wall at RD 0/550 to 0/568)- Deposit work

Estimated Cost 98771/-
Earnest Money 2000/-
Time limit One month

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.70	160	160.00	Rupees One hundred Sixty only	1232
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundations/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight, graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	26.91	Per cubic metre	3300.00	Rupees three thousand three hundred only	88803
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)/dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	15.00	Each	160.00	Rupees One hundred fifty only	2400
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentials. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	11.52	Per cubic metre	550.00	Rupees five hundred fifty only	6336
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(BIA)(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures				Total:	98771
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

M

Executive Engineer,
H.P.P.W.D. Division Harol,
Distt. Una (H.P.)

382

SCHEDULE OF QUANTITY

112

Estimates cost:- Rs.98715/-
Earnest Money:- Rs. 2000/-
Time Limit:- One Month.

Name of work:- Repair & Restoration work on Umralli Singan road km 0/00 to 6/550 (SH:- C/O U-shape drain at RD 2/796 to 2/822 RHS) Deposit work

	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government	29.64	Per Cubic metre.	160.00	Rupees one hundred sixty only	4742
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:3:6 (One cement three sand six graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	16.12	Per Cubic metre.	3900.00	Rupees three thousand nine hundred only	62868
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	327.60	Per Kilogramme	98.00	Rupees ninety eight only	32105
Note:-	Total:					99715
	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018					
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

90%
20%

Executive Engineer,
H.P.P.W.D. Division Harol,
Distt. Una (HP)

376

SCHEDULE OF QUANTITY

113

Estimates cost:- Rs.99448/-
Earnest Money:- Rs. 2000/-
Time Limit:- One Month.

Name of work:- Repair & Restoration work on Umralli Singan road km 0/00 to 6/550 (SH:- P/L 300 mm dia RCC pipe at RD 2/822 to 2/872-RHS)Deposit work

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and rammings of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	17.50	Per Cubic metre	160.00	Rupees one hundred sixty only	2800
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or hauling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form,work as per drawings and technical specification Clause 802,803,1202 and 1203.	2.00	Per Cubic metre	3300.00	Rupees three thousand three hundred only	6600
3	Providing and laying 300mm dia reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material including fixing collar with cement mortar but excluding excavation, protection work in head walls and parapets clause 1108 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax,GST,labour cess or other taxes imposed by the Government.	50.00	per Running metre	850.00	Rupees eight hundred fifty only	42500
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M:20 (M-twenty) nominal mix 1:2:4 (One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or hauling out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana toll tax,GST,labour cess or other taxes imposed by the Government..	7.50	Per Cubic metre	4500.00	Rupees four thousand five hundred only	33750
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge . The rates are inclusive octroi, royalty,malkhana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	145.90	Per Kilogramme	98.00	Rupees ninety eight only	14298
Note:-	NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/12/02.12 dated 7.8.2018 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20 Percentage quoted rate in Figures Percentage quoted rate in words					99948
	Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

114

Schedule of quantity									
Name of work :- Restoration of rain damages on link road to village Naiyan Basti Baliwal road km. 0/00 to 1/500									
(SH: P/L 80 mm thick paver blocks at Rd. 0/429.10 TO 0/438.90)									
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Earnest Money:-		Estimated Cost: Rs		One month
					Rate in words	Amount	Time:-	2000	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.	24.03	Cum.	160.00	Rupees One Hundred Sixty Only	3846.00			
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 .including carriage of materials within all leads and lifts and other incidental. . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government.	5.66	Cum.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	21789.00			
3	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401.. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.	7.35	Cum.	1100.00	Rupees One Thousand One Hundred Only	8085.00			
4	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203.P.C.C. grade 10 Nominal Mix 1 : 4 : 8 .including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government.	4.90	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	16170.00			
5	PProviding and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government..	49.00	Cum	850.00	Rupees Eight Hundred Fifty Only	41650.00			
6	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana ,toll tax, GST,labour cess or other taxes imposed by the Government.	1.76	Cum.	4500.00	Rupees Four Thousand Five Hundred Only	7938.00			
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/20212 dated 07.08.2018									
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021									
Percentage quoted rate in figures									
Percentage quoted rate in words									
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected									
Total						99478			

Executive Engineer,
H.P.P.W.D. Division Haroli

116

Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una		Estimated Cost: Rs				
HP. (Deposit work)		Time:-				
(SH: Hill side cutting for extended portion of park Rd. 0/020 to 0/024)		One month				
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	2000 Amount
1	Earth work in excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification 2014 clause 302, 1603 in association with other clauses. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhanga, toll tax,GST,labour cess or other taxes imposed by the Government..	690.00	Cum.	140.00	Rupees One Hundred Fourty Only	96600
					Total	96600
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018					
	2) The bidder are requested to submit there bid as per notification issued by the Principal Sēcy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

116


Schedule of quantity

Name of work:- Balance work for the C/O Community Park, Outdoor open gym at ward no. 2 & 4 G.P. Dulehar Tehsil Haroli Distt Una
 HP. (Deposit work)
 (SH: C/O Breast wall for protection of hill side on extended portion of park front side Rd. 0/011 to 0/020)

Estimated Cost: Rs ₹ 99,295

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:-		Time:-
					Rate in words	2000 Amount	
1	Earth work in excavation for structures such as Retaining walls, breasts walls, culverts, drains and parapets etcetra in all type of classification of soil as per drawing and technical specifications Clause 305 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m (Fifty metre), dressing of sides and bottam and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00m (Three metre) depth. and as directed by the Engineer-in- Charge. . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	9.72	Cum.	140.00	Rupees One Hundred Fourty Only	1361	One month
2	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuutering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Foundation, footings basis of columns etc. and mass concrete.including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	54.00	Sqm	300.00	Rupees Three Hundred Only	16200	
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:4:8, {(one cement: four sand : eight graded crushed stone aggregate 40 mm (Forty millimetre nominal size)} on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	23.90	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	78854	

4	<p>Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.</p>	18.00	Each	160.00	Rupees One Hundred Sixty Only	2880
<p>Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018</p>						
<p>2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW no. PBW (B)A(3)1/2020-1 Dated 07.10.2021</p>						99295
<p>Percentage quoted rate in figures</p>						
<p>Percentage quoted rate in words</p>						
<p>Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected</p>						
<p>Total</p>						


 Executive Engineer,
 H.P.P.W.D. Division Haroli
 Distt. Una (H.P.)

321

118

Brief Schedule of quantity

Name of work: - Construction of Bus stand at Dulehar Tehsil Haroli Distt. Una HP.

		Estimated Cost: Rs		Time:-		₹ 97,746 One month	
		Earnest Money:-				2000	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount	
1	Providing & laying mechanically mixed and vibrated concrete for Plain/reinforced concrete in open foundation of cement concrete complete of Plain/reinforced concrete grade M-25 as per drawings and technical specification clause 802,803,1202 & 1203. M 25 Nominal Mix 1 : 1.5:3. and as per Direction of Engineer-in-charge, including carriage of material within all leads including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.48	Cum	5500.00	Rupees Five Thousand Five Hundred Only	2619	
2	Renewing Wrought iron or M.S. Wheel or roller of steel door or gate and fitting and fixing the same with necessary clamps, nuts and bolts/welding and erection etc. complete. Wheel above 50 mm dia. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	8.00	Per/wheel	218.20	Rupees Two Hundred Eighteen Paise Twenty Only	1746	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	914.40	Kg	98.00	Rupees NinetyEight Only	89611	
4	Finishing with Epoxy paint (two or more coats) on steel work at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	30.40	Sqm	124.00	Rupees One Hundred TwentyFour Only	3770	
						Total	97746

Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018

2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021

Percentage quoted rate in figures

Percentage quoted rate in words

Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected

119

SCHEDULE OF QUANTITY

		Estimated Cost	99000			
		Earnest Money	2000/-			
		Time limit	One month			
Name of work : Restrotaion of rain damages on link road Lawana Basti Ispur to Dera Baba Bharthri Damamiyan KM 0/0 TO 5/580 in Pandoga section under Khad sub division HPPWD Khad.(SH: Hiring of excavator Cum Loader for removal debries/slips & C/O unlined drain etc.) -Phase-II						
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for making drain and side cuttings in hard rock etc (where blasting is prohibited) as per direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST ,labour cess or other taxes imposed by the Government..	90.00	Per Hour	1100.00	Rupees one thousand one hundred only	99000
				Total:		99000
1) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
Percentage quoted rate in Figures						
Percentage quoted rate in words						
Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.						

Executive Engineer
Haroli Division
HPPWD Haroli

330

120

SCHEDULE OF QUANTITY

Name of work :- Gramin Sampark from main road to the house of Sh Krishan Dutt Sharma GP Pandoga (SH:- P/L paver block)

Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
						Estimated Cost 99475/- Earnest Money 2000/- Time limit One month
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	22.50	Per cubic metre	160.00	Rupees One hundred sixty only	3600
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana .toll tax, GST, labour cess or other taxes imposed by the Government.	11.25	Per cubic metre	3300.00	Rupees three thousand three hundred only	37125
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malikhana ,toll tax, GST, labour cess or other taxes imposed by the Government ..	65.00	Each	800.00	Rupees eight hundred only	52000
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement :two sand :four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana ,toll tax, GST, labour cess or other taxes imposed by the Government..	1.50	Per cubic metre	4500.00	Rupees four thousand five hundred only	6750
						NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018
						2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20
						Total: 99475
						Percentage quoted rate in Figures
						Percentage quoted rate in words
						Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.

(12)

SCHEDULE OF QUANTITY

Name of work : Restrotration of rain damages on Jaijon Mod Bhai ka Mod upto Tahliwal Chowk Km 0/00
17/500 (SH: Removal of debries & disilting of Kangar Khad causeway at RD 3/795 to 3/830) - Phase-II

S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of hydraulic excavtor 0.90 cum. fitted with rock breaker on through rate basis for removal of debries including sand , silt, boulders and other material from the bed of khad from both up stream and down streams as per direction of the Engineer-in-charge . The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octori, royalty,maikhana ,toll tax,GST ,labour cess or other taxes imposed by the Government.	83.00	Per Hour	1100.00	Rupees One thousand one hundred only	91300
	Hiring of Tractor with Trolley 3.00cum. capacity to be deployed for removal of debries including sand , silt, boulders and other material etc. including cost of fuel, oil lubricants and wages of operational staff any repair breakage during operation will be carried out by the owner at his risk and cost including shifting of Tractor with Trolley from one place to other and six hours per day will be required working hours .The rate includes sale tax octori, royalty,maikhana ,toll tax,GST ,labour cess or other taxes imposed by the Government.	4.00	Per Day	2000.00	Rupees Two thousand only	8000
					Total:	99300
	1) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					
	Percentage quoted rate in Figures					
	Percentage quoted rate in words					
	Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.					


 Executive Engineer
 Haroli Division
 HPPWD Haroli

347

122

SCHEDULE OF QUANTITY

Name of work :- Gramin sampark R/wall from link road to the house of Sh Parveen kumar W No 2 GP Pandoga (SH:- C/O R/wall - phase -II)

Sl. No.	Description of work	Quantity	Unit	RATE In		Estimated Cost	60475
				Figures	Words		
							One month
							AMOUNT
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	7.48	Per cubic metre	160.00	Rupees One hundred sixty only	1197	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water/dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	16.83	Per cubic metre	3300.00	Rupees three thousand three hundred only	55539	
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709. 1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	9.00	Each	160.00	Rupees One hundred sixty only	1440	
4	Providing Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	4.18	Per cubic metre	550.00	Rupees One hundred sixty only	2299	
Total:						60475	
NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)(17)2/0212 dated 7.8.2018							
2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 22.07.20							
Percentage quoted rate in Figures							
Percentage quoted rate in words							
Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.							

Executive Engineer,
H.P.P.W.D. Division Haridwar
Distt. Una (H.P.)

Draft Schedule of quantity

Name of work:- Restoration of rain damage on Una Rampur Haroli Jajjon Road 0/00 to 23/000

(SH: C/O Retaining wall at Rd. 20/524 to 20/530 Rhs.) → H.P.K

Name of work:- Restoration of rain damage on Una Rampur Haroli Jajjon Road 0/00 to 23/000		Estimated Cost: Rs		₹ 97,657		
(SH: C/O Retaining wall at Rd. 20/524 to 20/530 Rhs.) → H.P.K		Time:-		One month		
		Earnest Money:-		2000		
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.83	Cum.	160.00	Rupees One Hundred Sixty Only	1253
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.20	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	93060
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.00	Each	160.00	Rupees One Hundred Sixty Only	1760
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	2.88	Cum.	550.00	Rupees Five Hundred Fifty Only	1584
Total						97657

Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018

Executive Engineer,
H.P.P.W.D. Division Haro
Distt. Una (H.P.)

124

Schedule of quantity

Name of work:- C/O Boundary wall at HWC ward no. 7 GP Pucca Prangan GP Pubowal.		Estimated Cost: Rs		Time:-		Earnest Money:-	
		₹ 99,675		One month		2000	
S.NO	DESCRIPTION	Qty	Unit	T. Rate	Rate in words	Amount	
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking, the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in alleads of 20 mtrs: Length of boundary wall pick work, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.20	Cum	160.00	Rupees one hundred sixty only	1152	
2	Providing and laying in position concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	1.44	Cum	3300.00	Rupees three thousand three hundred only	4752	
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	7.20	Cum	3850.00	Rupees three thousand eight hundred fifty only	27720	
4	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuattering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	57.60	Sqm	350.00	Rupees three hundred fifty only	20160	
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement:2 sand:4 graded stone aggregates 12.5 mm nominal size) and curing complete, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Sqm	284.20	Rupees two hundred eighty four and twenty paise only	1364	
6	Applying coat of hot bitumen (Mexpahlt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	4.80	Sqm	95.85	Rupees Ninety five and eighty five paise only	460	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	0.80	Cum	6640.00	Rupees six thousand six hundred forty only	5312	
8	Half brick masonry in common burnt clay building bricks in superstructure : Cement Mortar 1:4 (1 cement:4 sand) First Class Bricks, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.	17.05	Sqm	850.00	Rupees Eight hundred fifty only	14493	

9	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	77.54	Sqm	210.00	Rupees two hundred ten only	16284
10	Providing & laying Cement Concrete 1:2:4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in String courses, coping, bed plates, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	0.34	Cum	5230.00	Rupees five thousand two hundred thirty only	1778
11	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	77.50	Sqm	80.00	Rupees eighty only	6200
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW/ (B) @ (17) 2/02012 dated 07.08.2018				Total	99675
	2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW/ (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW/ (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					

Executive Engineer,
H.P.W.D. Division Haridwar
Distt. Una (H/P)

Up 8

Schedule of quantity

Name of work:- C/O Boundary wall at HWC ward no. 7 GP Pucca Prangan GP Pubawal.

(SH: C/O Boundary wall Length = 23.00 Mtr). Phase - II

(D/work)

Estimated Cost: Rs

₹ 96,971

One month

2000

Time:-

Earnest Money:-

195

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Rate in words	Amount
1	Excavation in foundation trenches etc. in earth work, lift upto 1.50 mtrs. stacking the excavated soil not more than 3 mtrs clear from the edge of the excavation and then returning the stacked soil in 15 cm layers when required in to plinths sides of foundations etc consolidating each deposited layer by ramming as watering and then disposing of all surplus excavated earth as directed with in alleads of 20 mtrs.Length of boundary wall pick work. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.90	Cum	160.00	Rupees one hundred sixty only	1104
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	1.38	Cum.	3300.00	Rupees three thousand three hundred only	4554
3	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	6.90	Cum	3850.00	Rupees three thousand eight hundred fifty only	26565
4	Providing form work with steel plates 3.15mm.thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centering below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	55.20	Sqm.	350.00	Rupees three hundred fifty only	19320
5	Providing and laying damp proof course 38 mm thick cement concrete 1:2:4 (1 cement,2 sand,4 graded stone aggregates 12.5 mm nominal size) and curing complete. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.60	Sqm.	284.20	Rupees two hundred eighty four and twenty paise only	1307
6	Applying coat of hot bitumen (Mexpphalt) 80/100 or equivalent) using 1.70 kg per sqm. on damp proof course after cleaning the surface with a piece of cloth lightly soaked with kerosene oil. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.60	Sqm.	95.85	Rupees Ninety five and eighty five paise only	441
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand). including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	0.85	Cum	6640.00	Rupees six thousand six hundred forty only	5620
8	Half brick masonry in common burnt clay building bricks in superstructure : Cement Mortar 1:4 (1 cement:4 sand) First Class Bricks. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	17.05	Sqm	850.00	Rupees Eight hundred fifty only	14493

8	15mm thick cement plaster in single coat on rough side of concrete stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and rounded angles not exceeding 80mm in girth and finished even in and smooth in cement mortar 1:4 (1 cement : 4 sand) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	74.14	Sqm	210.00	Rupees two hundred ten only	15570
9	Providing & Laying Cement Concrete 1:2:4 (1 Cement : 2 Sand : 4 Graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced cement concrete work in :- String courses coping, bed plates including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	0.39	Cum	5230.00	Rupees five thousand two hundred thirty only	2065
10	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax, GST, labour cess or other taxes imposed by the Government.	74.14	Sqm	80.00	Rupees eighty only	5932
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018				Total	96971
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021					
	Percentage quoted rate in figures					
	Percentage quoted rate in words					
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected					



Executive Engineer,
H.P.W.D. Division Haroli
Distt. Una (H.P.)

Schedule of quantity
(SH: C/O Retaining wall at Rd. 1/177.20 to 1/182.90 RhS)

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)		Estimated Cost: Rs		Time:-		One month	
S.NO	DESCRIPTION	Qty	Unit	T.Rate	Earnest Money:- Rate in words	Amount	₹ 99,290
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.16	Cum.	160.00	Rupees One Hundred Sixty Only	985	
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.60	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94379	
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	12.00	nos	160.00	Rupees One Hundred Sixty Only	1920	
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.65	Cum.	550.00	Rupees Five Hundred Fifty Only	2006	
	Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
	2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
	Percentage quoted rate in figures						
	Percentage quoted rate in words						
	Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						
					Total	99290	

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)

327

Name of work:- C/O link road from House of Champa devi Rd. 0/00 to 1/200 (Deposit work)
(SH: C/O Retaining wall at Rd. 1/182.90 to 1/188.60 Rhs)

Schedule of quantity

S.NO	DESCRIPTION	Qty	Unit	T.Rate	Estimated Cost: Rs	
					Time:-	One month
					Earnest Money:-	
					Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	6.16	Cum.	160.00	Rupees One Hundred Sixty Only	985
2	Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	28.60	Cum.	3300.00	Rupees Three Thousand Three Hundred Only	94379
3	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.00	nos	160.00	Rupees One Hundred Sixty Only	1760
4	Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	3.65	Cum.	550.00	Rupees Five Hundred Fifty Only	2006
Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018						
2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021						
Percentage quoted rate in figures						
Percentage quoted rate in words						
Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected						
					Total	99130

Executive Engineer,
H.P.P.W.D. Division Haroli
Distt. Una (H.P.)