

HIMACHAL PRADESH  
PUBLIC WORK DEPARTMENT

No. PW/SD/CB/TA /2025-26- 8900

Dated:-18.10.2025

To,

The Executive Engineer  
IT Cell Nirman Bhawan Nigam Vihar,  
HP PWD Shimla.

Subject:-

Regarding Uploading /Publishing Notice  
Inviting tender on HPPWD website .


Enclosed please find herewith the Notice  
Inviting Tender (NIT) along with schedule of quantity for uploading on HP  
PWD website. This is for your kind information and necessary action at your  
end please.

Encls:- NIT copy & 61 Nos copy of Schedule of quantity.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai.

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-SD-CB-TA-2025-26- 8891-8899 dated: 18.10.2025 are urgent nature.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Short terms Sealed percentage rate tender on form PWD 6, 7 & 8 are invited by the Executive Engineer, Shillai, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible Contractors enlisted in HP PWD so as to reach in this office as per time schedule given below.

Job No.	Name of work	Estimated Cost	Earnest Money	Time of period	Cost of form	Eligible Class of Contractor
1	Date of receipt of application of tenders forms:-	27.10.2025 at 12:00 AM, up to 04:00 PM				
2	Date of issue/ sale of tender Forms:-	28.10.2025 at 10:00 AM, up to 12:30 PM				
3	Date of receipt of tender Forms :-	28.10.2025 at 02:00 PM, up to 03:30 PM				
4	Date of opening of tender:-	28.10.2025 at 04:00 PM.				
1	Restoration of Rain Damages on Jakhna to Sharli Manpur road km. 0/0 to 7/750 (SH:- C/O R/Wall in R/R masonry at RD. 3/356 to 3/360)	99756/-	2,000.00	One Month	350/-	" D Class
2	Restoration of Rain Damages on road Village Muinal Bag Km. 0/0 to 1/900(SH:- C/O B/wall in PCC 1:4:8 at RD 1/900 to 1/995)	99646/-	2,000.00	One Month	350 -	" D Class
3	Restoration of Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O R/Wall in R/R Masonry at RD 1/222 to 1/226)	98164/-	2,000.00	One Month	350/-	" D Class
4	Restoration of Damages on kotti Uttrou road km. 0/0 to 6/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/309 to 0/311)	98952/-	2,000.00	One Month	350 -	" D Class
5	Restoration of Rain Damages on L/R road village Pabhar Km. 0/00 to 4/00 (SH:-C/O R/wall in R/R Masonry at RD 0/068 to 0/075)	98478/-	2,000.00	One Month	350 -	" D Class
6	Restoration of Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O B/Wall in R/R Masonry at RD 5/047 to 5/056)	99080/-	2,000.00	One Month	350 -	" D Class
7	Restoration of Rain Damages on L/R Jamna Km. 0/0 to 2/00 (SH:- C/O R/wall in R/R masonry at RD. 1/112 to 1/118)	99991/-	2,000.00	One Month	350/-	" D Class
8	Restoration of Rain Damages on L/R Jamna Km. 0/0 to 2/00 (SH:- C/O B/wall in PCC 1:4:8 at RD. 1/324 to 1/330)	98175/-	2,000.00	One Month	350 -	" D Class
9	Restoration of Rain Damages on Bella Siyasu road Km. 0/0 to 9/00 (SH:- C/o R/wall in PCC 1:4:8 at RD 6/156 to 6/160)	99602/-	2,000.00	One Month	350 -	" D Class
10	Restoration of Rain Damages on Mashu Kando road Km. 0/0 to 3/600 (SH:- C/O R/wall in R/R Masonry at RD.0/150 to 0/154)	98727/-	2,000.00	One Month	350 -	" D Class
11	Restoration of Rain Damages on Balikoti Chamra Morar road Km. 0/00 to 7/300 (SH:- C/O r/wall in Pcc 1:4:8 at RD 0/080 to 1/087)	97065/-	2,000.00	One Month	350 -	" D Class
12	Restoration of Rain Damages on Link road Kando Dugana Shamah Pamta road Km. 0/0 to 5/870 (SH:- C/O B/Wall in PCC 1:4:8 at RD. 3/262 to 3/270)	97966/-	2,000.00	One Month	350 -	" D Class
13	Restoration of Rain Damages on Link road Kando Dugana Shamah Pamta road Km. 0/0 to 5/870 (SH:- C/O B/Wall in PCC 1:4:8 at RD. 3/250 to 3/258)	97966/-	2,000.00	One Month	350/-	" D Class
14	Restoration of Rain Damages on Millah Gundah road km. 0/00 to 12/075(SH:- C/O R/wall in R/R Masonry at RD 5/621 to 5/624)	98282/-	2,000.00	One Month	350 -	" D Class
15	Restoration of Rain Damages on Link road Village Bambrad Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 1/015 to 1/019)	99915/-	2,000.00	One Month	350/-	" D Class
16	Restoration of Rain Damages on Sharli Kumli road km. 0/0 to 7/00 (SH:- C/O R/Wall in wire crate with toe wall PCC 1:4:8 at RD 4/440 to 4/444)	99952/-	2,000.00	One Month	350 -	" D Class

P.T.O

17	Restoration of Rain Damages on Sharli Kumli road km. 0/0 to 7/00 (SH:- C/O R/Wall in wire crate with toe wall PCC 1:4:8 at RD 4/465 to 4/469)	99952/-	2,000.00	One Month	350/-	" D" Class
18	Restoration of Rain Damages on Link road to Village Juinal Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 0/722 to 0/726)	98698/-	2,000.00	One Month	350/-	" D" Class
19	Restoration of Rain Damages on Link road to Village Juinal Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 0/728 to 0/732)	98698/-	2,000.00	One Month	350/-	" D" Class
20	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500 (SH:- C/O R/Wall in wire crates at RD 1/036 to 1/039)	98820/-	2,000.00	One Month	350/-	" D" Class
21	Restoration of Rain Damages on Various road under Bali Koti Section Under Shillai Sub Division (SH:- Hiring of Excavator cum loader for removal of slips and dressing of road surface)Job-II	99900/-	2,000.00	One Month	350/-	" D" Class
22	Restoration of Rain Damages on Shilla Gundah Road Km. 0/0 to 33/500(SH:- C/O R/Wall in R/R Masonry at RD 17/765 to 17/771).	98255/-	2,000.00	One Month	350/-	" D" Class
23	Restoration of Rain Damages on Bella Siyasu road Km. 0/0 to 9/00 (SH:- Hiring of Excavator cum loader for removal of slips in KM 4/00 to 4/500)	99900/-	2,000.00	One Month	350/-	" D" Class
24	Restoration of Rain Damages on Millah Digwa Road Km. 0/0 to 6/900(SH:- C/O R/Wall in PCC 1:4:8 at RD 1/578 to 1/584)Under PDNA	94208/-	2,000.00	One Month	350/-	" D" Class
25	Restoration of Rain Damages to Gwali Pashmi Manal Matiyana road Km. 0/0 to 8/00 (SH:- C/o R/wall in R/R masonry at RD 2/274 to 2/279)	98672/-	2,000.00	One Month	350/-	" D" Class
26	Restoration of Rain Damages on Kando Dugana to Shamah Pamta road Km. 0/0 to 5/870(SH:- C/o B/Wall in PCC 1:4:8 at RD. 0/641 to 0/649)	98534/-	2,000.00	One Month	350/-	" D" Class
27	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/00 (SH:- C/O B/wall in R/R Masonry at RD 0/112 to 0/116)	97356/-	2,000.00	One Month	350/-	" D" Class
28	Restoration of Rain Damages on Shilla Gundah road Km. 0/0 to 33/265 (SH:- C/O Earthen Shoulder in Km 1/550 to 4/500 in Patches)	98055/-	2,000.00	One Month	350/-	" D" Class
29	Restoration of Rain Damages on Kotti Uttrou Road Km. 0/0 to 6/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 3/420 to 3/425)	98639/-	2,000.00	One Month	350/-	" D" Class
30	Restoration of Rain Damages on Kotti Uttrou Road Km. 0/0 to 6/00 (SH:- C/O B/Wall in R/R Masonry at RD 3/311 to 3/330)	98957/-	2,000.00	One Month	350/-	" D" Class
31	Restoration of Rain Damages on Naya Daya Kunhat road Km. 0/0 to 6/900(SH:- C/O R/wall in PCC 1:4:8 at RD 5/520 to 5/524)	98486/-	2,000.00	One Month	350/-	" D" Class
32	Restoration of Rain Damages on Kando Senga road Km. 0/0 to 3/500(SH:- C/O R/wall in PCC 1:4:8 at RD 1/910 to 1/916)	99840/-	2,000.00	One Month	350/-	" D" Class
33	Restoration of Rain Damages on Renuka Sataun road Km. 13/0 to 29/160(SH:- Hiring of Excavator cum loader for removal of slips rd 11/00 to 15/00)	99900/-	2,000.00	One Month	350/-	" D" Class
34	Restoration of Rain Damages on Rast Manal Chunoti Road Km. 0/00 to 15/135 (SH:- C/O R/wall in R/R Masonry at RD 0/370 to 0/374)	99104/-	2,000.00	One Month	350/-	" D" Class
35	Restoration of Rain Damages on Nainidhar Shakholi Rast km 0/00 to 8/00 (SH:- C/O B/Wall in RR Masonry at Rd 5/871 to 5/878)	98012/-	2,000.00	One Month	350/-	" D" Class
36	Restoration of Rain Damages on various Roads under Sataun Section in Sataun Sub Division (Sh:- Hiring fo Excavator Cum loader for removal of slips at various RDs).	99900/-	2,000.00	One Month	350/-	" D" Class

P.T.O

37	Restoration of Rain Damages on various Roads Under Timbi Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at various RDs).	99900/-	2,000.00	One Month	350/-	" D" Class
38	Restoration of Rain Damages on LPRR road km 97/00 to 112/167 (SH:- C/o R/wall in RR Masonry at RD 109/700 to 109/704).	98698/-	2,000.00	One Month	350/-	" D" Class
39	Restoration of Rain Damages to Gawali Pashmi Manal Matiyana road Km. 0/0 to 8/00 (SH:- C/o R/wall in R/R masonry at RD 4/015 to 4/019).	98698/-	2,000.00	One Month	350/-	" D" Class
40	Restoration of Rain Damages on Manal Kanti Mashwa Road Km. 0/0 to 13/350 (SH:- Hiring of Excavator Cum loader for removal of slips various Rds Between Km 6/500 to 13/00).	99900/-	2,000.00	One Month	350/-	" D" Class
41	Restoration of Rain Damages on Bharli Banour road from km 0/00 to 13/355 (SH:- Hiring of Excavator cul loader for removal of slips various Rds Between Km 5/00 to 9/500)	99900/-	2,000.00	One Month	350/-	" D" Class
42	Restoration of Rain Damages on Bharli Banour road from km 0/00 to 13/355 (SH:- Hiring of Excavator cum loader for removal of slips various Rds Between Km 10/00 to 13/355)	99900/-	2,000.00	One Month	350/-	" D" Class
43	Restoration of Rain Damages on Renuka Sataun road Km. 13/0 to 29/160 (SH:- Hiring of Excavator cum loader for removal of slips rd 21/00 to 24/00)	99900/-	2,000.00	One Month	350/-	" D" Class
44	Restoration of Rain Damages on Gangotli to Bambal road Km. 0/0 to 4/500(SH:- C/O B/wall in RR Masonry at RD 3/711 to 3/715)	98698/-	2,000.00	One Month	350/-	" D" Class
45	Restoration of rain damages on Mashu to Kando road Km 0/00 to 3/600 (SH:- C/o B/wall in R/R Masonry at RD 3/225 to 3/234)	98449/-	2,000.00	One Month	350/-	" D" Class
46	Restoration of rain damages on Mashu to Kando road Km 0/00 to 3/600 (SH:- C/o B/wall in PCC 1.4.8 at RD 3/240 to 3/246)	98913/-	2,000.00	One Month	350/-	" D" Class
47	Restoration of rain damages on Uttri More to Village Uttri road 0/00 to 2/500 (SH:- Hiring of Excavator cum loader for removal of slips from various RDs)	99900/-	2,000.00	One Month	350/-	" D" Class
48	Restoration of Rain Damages on Lojja to Hallan Km. 0/0 to 1/705 (SH:-C/o R/wall in PCC 1:4:8 at rd 1/660 to 1/665.	99856/-	2,000.00	One Month	350/-	" D" Class
49	Restoration of Rain Damages on Lojja to Hallan Km. 0/0 to 1/705 (SH:-C/o R/wall in PCC 1:4:8 at rd 1/667 to 1/672).	99919/-	2,000.00	One Month	350/-	" D" Class
50	Restoration of Rain Damages on Kafenu Kikrech to Bogra Thana Manalto Manal Road Km 0/00 to 5/5000 (SH:-Hiring of Excavator cum loader for removal of slips from various RDs).	99900/-	2,000.00	One Month	350/-	" D" Class
51	Restoration of Rain Damages on Naya Panjor Road Km 0/00 to 4/00 (SH:-Hiring of Excavator cum loader for removal of slips from various RDs)	99900/-	2,000.00	One Month	350/-	" D" Class
52	Restoration of rain damages on Gawali Pashmi Manal Matiyana road Km 0/00 to 8/00 (SH:- C/o R/wall in PCC 1:4:8 at Km 2/310 to 2/314)	98288/-	2,000.00	One Month	350/-	" D" Class
53	Restoration of rain damages on Gawali Pashmi Manal Matiyana road Km 0/00 to 8/00 (SH:- C/o R/wall in PCC 1:4:8 at Km 2/318 to 2/322)	98288/-	2,000.00	One Month	350/-	" D" Class
54	Restoration of Rain Damage on Parwa Lawagu Shakholi Road Km 0/0 to 4/500 (SH:- Hiring of Excavator cum loader for removal of slips from various RDs in Km 0/0 to 2/00)	99900/-	2,000.00	One Month	350/-	" D" Class
55	Restoration of Rain Damages on link road to Village Sathor Km 0/00 to 2/00 (SH:- Hiring of Excavator cum Loader for removal of slips from various RDs)	99900/-	2,000.00	One Month	350/-	" D" Class

56	Preparation of detailed estimate for A A & F S Technical Sanction Working Estimates & Draft schedule of quantity of the construction of Rajiv Gandhi Government Modal day Boarding	75,500	2,000.00	One Month	350/-	" D" Class
57	Restoration of Rain Damages on Various Roads under Shillai Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs).	99900	2,000.00	One Month	350/-	" D" Class
58	Restoration of Rain Damages on Various Roads under Meenus Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs).	99900	2,000.00	One Month	350/-	" D" Class
59	Restoration of Rain Damages on Various Roads under Kamrou Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs).	99900	2,000.00	One Month	350/-	" D" Class
60	Restoration of Rain Damages on Various Roads Chandani Section under Sataun Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs).	99900	2,000.00	One Month	350/-	" D" Class
61	Restoration of Rain Damages on Various Roads Rajpur Section under Sataun Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs).	99900	2,000.00	One Month	350/-	" D" Class

**Terms and conditions:-** The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application.

- 1 The Earnest Money for the above works should be submitted with applications for the purchase of the tender documents.
- 2 The Contractors should quote the % rate of overall item in the tender both in figures and words.
- 3 Income Tax and GST No. latest clearance certificate.
- 4 The contractors firms shall accompany his enlistment /renewal and EPF with his application.
- 5 The Executive Engineer reserves the right to accept / rejected any tender applications or all tenders without assigning any reason.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai

Dated:- 18.10.2025

PW-SD-CB-TA-NIT-2025-26- 8891-8899

**Copy forwarded for information and wide publicity to:-**

- 1 The Superintending Engineer 12<sup>th</sup> Circle HP PWD Nahan.
- 2 All the Assistant Engineer working under this Division.
- 3 A/B and D/B in this office.
- 4 Notice Board.


  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work - Restoration of Damages on Jakhana to Sharti Manpur road Km 0/00 to 7/750 (SH- Construction of R/wall R/R masonry at 3/356 to 3/358)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.28	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3909.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 801, 803, 1202 and 1203 1-4.8 (One cement Four Sand Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-charge.	24.40	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	82501.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer in-charge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
<b>Total:-</b>						<b>99756.00</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillal Division  
 HP PWD Shillal

Job - 1	Estimated Cost - 99756/- Only
3/356 to 3/358	Earnest Money - 2000/- Only
	Time Limit - One Month
<b>Select:-</b>	<b>Total:-</b>
Plus (+)	( .....%)
Minus (-)	( .....%)

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of Damages Link road village Mūnāl Bag Km 0/0 to 1/900 (SH:-Construction of R/wall in PCC 1:4:8 at RD 1/900 to 1/995)


Job - 2

Estimated Cost ~~99646.00~~ Only.

Earnest Money:- 2000/- Only  
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.85	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4077.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.06	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	91940.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.90	Per cubic metre	789.40	Rupees Seven Hundred Eighty Nine and Paise Forty Only	1500.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2129.00
				<b>Total:-</b>		<b>99646.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:- Restoration of rain damages on Shillai Achhoti Pandiyal road Km 0/0 to 7/500(SH:-Construction of R/wall in RR Masonry at RD 1/222 to 1/226)

Job - 3

Estimated Cost:- 98164/- Only  
 Earnest Money:- 2000/- Only Time Limit:- One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.04	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	2849.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	2.33	Per cubic metre	4415.20	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Only	10287.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).Including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts, and carriage of material as per the direction of the Engineer Incharge.	3.12	Per cubic metre	810.00	Rupees Eight Hundred Ten Only	2527.00
				<b>Total:-</b>		<b>98164.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:-Restoration of rain damages on Koli Utrru road Km 0/0 to 6/00(SH.-Construction of Rwall in PCC 1:4:8 at RD 0/309 to 0/311)

Job - **4**

Estimated Cost:-98952/- Only.  
Earnest Money:- 2000/- Only Time Limit - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.68	Per cubic metre	315.11	Rupees Three Hundred Fifteen and Paise Eleven Only	4311.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.80	Per cubic metre	4415.60	Rupees Four Thousand Four Hundred Fifteen and Paise Sixty Only	91844.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.92	Per cubic metre	810.40	Rupees Eight Hundred Ten and Paise Forty Only	1556.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	4.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	1241.00
				<b>Select:-</b>		
				<b>Total:-</b>		<b>98952.00</b>
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

## SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damages on LR road Village Pabhar Km 0/00 to 4/00(SH:- Construction of R/wall in R.R masonry at RD 0/068 to 0/075)		Job:- 5		Estimated Cost:- 98478/- Only.		
		Earnest Money:- 2000/- Only		Time Limit:- One Month		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.33	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4512.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203. 1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	3.17	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	13839.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6; including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	23.060	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	77970.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	2.73	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2157.00
				<b>Total:-</b>		<b>98478.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Shillai Achholi Pandiyat road Km 0/0 to 7/500(SH):-Construction of R/wall in RR Masonry at RD 5/047 to 5/056)

Job - 5 Estimated Cost:- 99080/- Only.  
 Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.26	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3609.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight Graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	2.70	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	11787.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).Including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.120	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	81555.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.Including carriage of materials in all leads and lifts as per direction of Engineer-In-Charge	8.00	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2129.00
				<b>Total:-</b>		<b>99080.00</b>
				<b>Select:-</b>		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:- Restoration of Damages on Link road Jamma Km 0/0 to 2/00(SH.-Construction of R/wall in RR Masonry at RD 1/112 to1/118)

Job :- 7

Estimated Cost:- 99991/- Only,  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.02	Per cubic metre	322.50	Rupees Three Hundred Twenty Two and Paise Fifty Only	4199.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4.8 (One cement: Four Sand:Eight graded stone aggregate)/25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge	2.70	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	11746.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6)including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.340	Per cubic metre	3310.50	Rupees Three Thousand Three Hundred Ten and	80578.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	4.08	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	3468.00
				<b>Total:-</b>		<b>99991.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:-Restoration of Damages on Link road Jamma Km 0/0 to 2/00 (SH:-Construction of BWall in PCC 1:4:8 at RD 1/324 to 1/330)

Job - 8

Estimated Cost:-98175/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.37	Per cubic metre	320.00	Rupees Three Hundred Twenty Only	3638.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.44	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	88924.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	2.22	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	1887.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3:7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	12.00 Nos.	Each	310.50	Rupees Three Hundred Ten and Paise Fifty Only	3726.00
				<b>Total:-</b>		<b>98175.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-


  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work - Restoration of rain damages on Mashu Kando road Km 0/0 to 3/600 (SH - Construction of Rwall in RR Masonry at RD 0/150 to 0/154) Job - 1/D Estimated Cost - 98727/- Only Earnest Money - 2000/- Only Time Limit - One Month

Sl. No	Sub-head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 505.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 502, 503, 1202 and 1203.1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge.	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6) including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Fifty Five and Hundred Fifty Five and Ninety Nine Only	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3, 7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.200	Each	799.00	Rupees Seven Hundred Ninety Nine Only	2557.00
				<b>Total:-</b>		<b>98727.00</b>
				Select:-	Plus(+)	(.....%)
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai



**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain damages on Baikoti Chamra Morar road KM 0/00 to 7/300(SH:-Construction of Rwall in PCC 1:4:8 at RD 1/080 to 1/087)

Job - 11  
 Estimated Cost:-97065/- Only.  
 Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.08	Per cubic metre	288.00	Rupees Two Hundred Eighty Eight Only	2903.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	21.35	Per cubic metre	4346.00	Rupees Four Thousand Three Hundred Forty Six Only	92787.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-In-Charge	5.00 Nos.	Each	275.00	Rupees Two Hundred Seventy Five Only	1375.00
				<b>Total:-</b>		<b>97065.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai  


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Kando Dugana to Shaman Pantla road Km 0/0 to 5/870(SH):-Construction of B/wall in PCC 1:4:8 at RD 3/262 to 3/270)

Job - 12

Estimated Cost-97966/- Only.  
Earnest Money- 2000/- Only Time Limit- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.52	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4260.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)/25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.54	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	89359.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	14.00 Nos.	Each	310.50	Rupees Three Hundred Ten and Paise Fifty Only	4347.00
				<b>Total:-</b>		<b>97966.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - **13**

Estimated Cost:-97966/- Only  
Earnest Money:-2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages on Kando Dugana to Shamah Pamia road Km 0/0 to 5/870(SH:-Construction of B/wall in PCC 1:4:8 at RD 3/250 to 3/258)

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.52	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4260.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	20.54	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	89359.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3:7.including carriage of materials in all leads and lifts as per direction of Engineer-In-Charge	14.00 Nos.	Each	310.50	Rupees Three Hundred Ten and Paise Fifty Only	4347.00
Total:-						97966.00
				Select:-	Plus(+)	(.....%)
					Minus(-)	(.....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Millah Gundah road Km 0/00 to 12/075(S.H:- Construction R/wall in R/R Masonry at RD 5/621 to 5/624)

Job - 14 Estimated Cost:- 98282/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	14.80	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4356.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.06	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	8993.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.40	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
				<b>Total:-</b>		<b>98282.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>	(.....%)	
				<b>Minus(-)</b>	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work - Restoration of rain damages Link road village Bambrad Km 0/0 to 2/500(SH):-Construction of R/wall in RR Masonry at RD 1/015 to 1/019)

Job - 15

Estimated Cost - 97972/- Only.

Earnest Money - 2000/- Only Time Limit: - One Month

Sl. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.40	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3944.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge	2.50	Per cubic metre	4415.20	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Only	11036.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6; including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One	82501.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
				<b>Total:-</b>		<b>99915.00</b>
				<b>Select:-</b>		
				Plus(+)		(.....%)
				Minus(-)		(.....%)

*(Signature)*

Executive Engineer

Shillai Division

HP PWD Shillai

*(Signature)*

Name and full address of the contractor:-


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Shari Kumi road Km 0/0 to 7/00(SH.-Construction of R/wall in wire crate with toe wall PCC 1:4:8 at RD 4/440 to 4/444) Job - 16

Estimated Cost - 98952/- Only.  
Earnest Money - 2000/- Only Time  
Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.24	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3308.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	4.80	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	20882.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	31.68	Per cubic metre	2355.95	Rupees Two Thousand Three Hundred Fifty Five and Paise Ninety Five Only	74636.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	1.44	Per cubic metre	781.85	Rupees Seven Hundred Eighty One and Paise Eighty Five Only	1126.00
<b>Total:-</b>						<b>99952.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	(.....%)
				<b>Minus(-)</b>	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai



**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Shari Kurnil road Km 0/0 to 7/00(SH:-Construction of R/wall in wire crate with toe wall PCC 1:4:8 at RD 4/465 to 4/469)

Job - 17

Estimated Cost:- 98952/- Only  
Earnest Money:- 2000/- Only  
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 Including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.24	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3308.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	4.80	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	20882.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	31.68	Per cubic metre	2355.95	Rupees Two Thousand Three Hundred Fifty Five and Paise Ninety Five Only	74636.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer incharge.	1.44	Per cubic metre	781.85	Rupees Seven Hundred Eighty One and Paise Eighty Five Only	1126.00
				<b>Total:-</b>		<b>99952.00</b>
				<b>Select:-</b>		
				Plus(+)	( .....%)	
				Minus(-)	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - 18

Estimated Cost:- 98698/- Only.


Earnest Money:- 2000/- Only Time

Limit - One Month

Name of work:- Restoration of rain damages on link road to Village Junnai Km 0/0 to 2/500 (SH:-Construction of Rwall in RR Masonry at RD 0/722 to 0/726)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Rupees Seven Hundred Ninety Only	83914.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00		2528.00
				<b>Select:-</b>		
				<b>Total:-</b>		<b>98698.00</b>
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - 19

Estimated Cost - 98698/- Only.

Name of work:- Restoration of rain damages on link road to Village Junal Km 0/0 to 2/500 (SH:-Construction of R/wall in RR Masonry at RD 0/728 to 0/732)

Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and Item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:5).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Ninety Only	83914.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
<b>Total:-</b>						<b>98698.00</b>
<b>Select:-</b>				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai



**SCHEDULE OF QUANTITY**


Name of work:-Restoration Of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500( SH:-Construction of R/wall in wire Crate at RD 1/036 to 1/039)

Job - 20

Estimated Cost -98820/- Only  
Earnest Money:- 2000/- Only Time Limit. - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.46 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	1607.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In- charge.	39.75 cubic metre	Per cubic metre	2445.60	Rupees Two Thousand Four Hundred Forty Five and Paise Sixty Only	97213.00
				<b>Total:-</b>		<b>98820.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job.- 2)

Estimated Cost:- 99900- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work: Restoration of Rain Damages on Various road under Bali koti Section Under Shillai Sub Division(SH:- Hiring of Excavator cum loader for removal of slips and drassing of road surface)Job-II

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
<b>Total:-</b>						<b>99900.00</b>
				<b>Select:-</b>	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-


  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of rain damages on Shilla Gundah road Km 0/0 to 33/500(SH:-Construction of R/wall in RR Masonry at RD 17/765 to 17/771) Job.- 22 Estimated Cost:- 98255/- Only.  
 Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.02 cubic metre	Per cubic metre	322.20	Rupees Three Hundred Twenty Two and Paise Twenty Only	4195.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.70 cubic metre	Per cubic metre	4250.00	Rupees Four Thousand Two Hundred Fifty Only	11475.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	24.340 cubic metre	Per cubic metre	3250.50	Rupees Three Thousand Two Hundred Fifty and Paise Fifty Only	79117.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) mimilimetre with smaller size toward:s the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	4.08 cubic metre	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	3468.00
				<b>Total:-</b>		<b>98255.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY						Job.- 23	Estimated Cost:-99900/- Only. Earnest Money:- 2000/- Only Time Limit: -Two Months
Name of work: Restoration of Rain Damages on Bella Siyasu road Km 0/0 to 9/00 (SH:- Hiring of Excavator cum loader for removal of slips in Km 4/00 to 4/500)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
				<b>Total:-</b>		<b>99900.00</b>	
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillaj 

**SCHEDULE OF QUANTITY**


Name of work:- Restoration of rain damages on Millah Digwa road Km 0/0 to 6/900(SH:-Construction of R/wall in PCC1:4:8 at RD 1/578 to 1/584) Under PDNA

Job.- 24 Estimated Cost:-94208/- Only  
Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.37 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	3583.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In- charge.	19.50 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	85129.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.22 cubic metre	Per cubic metre	800.00	Rupees Eight Hundred Only	1776.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	12.00 Nos.	Each	310.00	Rupees Three Hundred Ten Only	3720.00
<b>Total:-</b>						<b>94208.00</b>


Select:-	Plus(+)	( .....%)
	Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 25	Estimated Cost:- 98672/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of work:-Restoration of rain damages to Gwali Pashmi Manal Matiyana road Km 0/0 to 8/00(SH:-Construction of R/wall in RR Masonry at RD 2/274 to 2/279)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.10 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4758.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.PCC 1:6:12(One cement: Six Sand: Twelve graded stone aggregate)40mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	13.68 cubic metre	Per cubic metre	3950.00	Rupees Three Thousand Nine Hundred Fifty Only	54036.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	13.880 cubic metre	Per cubic metre	2450.00	Rupees Two Thousand Four Hundred Fifty Only	34006.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.90 cubic metre	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	3081.00
5	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2791.00
					<b>Total:-</b>	<b>98672.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 26	Estimated Cost:-98534/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work:-Restoration of Rain damages on Kando Dugana to Shamah Pamta road KM 0/00 to 5/870(SH:-Construction of B/wall in PCC 1:4:8 at RD 0/641 to 0/649)							
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.80 cubic metre	Per cubic metre	298.45	Rupees Two Hundred Ninety Eight and Paise Forty Five Only	4119.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In- charge.	20.54 cubic metre	Per cubic metre	4415.25	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Five Only	90689.00	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	14.00 Nos.	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	3726.00	
						<b>Total:-</b>	<b>98534.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)	
					<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai 

**SCHEDULE OF QUANTITY**


Job.- 27

Estimated Cost:- 98286/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of Damages on Shillai Achhoti Pandiyat road Km 0/00 to 7/00(SH:-Construction of B/wall in RR Masonry at RD 0/112 to 0/116)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.04 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	2849.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400 cubic metre	Per cubic metre	3385.20	Rupees Three Thousand Three Hundred Eighty Five	82599.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer incharge.	3.12 cubic metre	Per cubic metre	810.00	Rupees Eight Hundred Ten Only	2527.00
				<b>Total:-</b>		<b>97356.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY						Job.- 28	Estimated Cost:- 98055- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of rain damages on Shilla Gundah road Km 0/0 to 33/265 (SH:- construction of earthen shoulder in Km 1/550 to 4/500 in patches)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Construction of Sub grade and earthen Shoulders with approved materials obtained from borrow pits with all lift and leads, transporting to site spreading, grading to required slope and compacted to meet requirement of table 300.2 with lead upto 1000m as per technical specification clause 303.1 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	525.34	Per Square Metre	186.65	Rs. One hundred eighty Six & Sixty Five Paise only.	98055.00	
						<b>Total:-</b>	<b>98055.00</b>
Select:-							
Plus(+)						(.....%)	
Minus(-)						(.....%)	

Name and full address of the contractor:-

*[Handwritten signature]*

*[Handwritten signature]*  
Executive Engineer  
B & R Division  
HP PWD Shillai

SCHEDULE OF QUANTITY					Job.- 29	Estimated Cost:-98639/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work:-Restoration of Damages on Koti Uttru road Km 0/0 to 6/00( SH:-Construction of R/wall in PCC 1:4:8 at RD 3/420 to 3/425)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.95 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4081.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	20.85 cubic metre	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Five Only	90708.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.49 cubic metre	Per cubic metre	799.00	Rupees Seven Hundred Ninety Nine Only	1990.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	6.00 Nos.	Each	310.00	Rupees Three Hundred Ten Only	1860.00
					<b>Total:-</b>	<b>98639.00</b>
					<b>Select:-</b>	<b>Plus(+)</b> ( .....%)
						<b>Minus(-)</b> ( .....%)

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

## SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain damages on Koti Uttrou road KM 0/00 to 6/00(SH:- Construction of B/wall in R.R masonry at RD 3/1 1 to 3/330)		Job.- 30	Estimated Cost:- 98957/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month			
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.96 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4084.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.34 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10216.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	24.120 cubic metre	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	81555.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	10.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	3102.00
				Total:-		98957.00
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

*brunel*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 31	Estimated Cost-98486/- Only Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of work.-Restoration of rain damages on Naya Daya Kunhat road Km 0/0 to 6/900(SH:-Construction of R/wall in PCC 1:4:8 at RD 5/520 to 5/524)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.68 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4097.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	20.80 cubic metre	Per cubic metre	4415.60	Rupees Four Thousand Four Hundred Fifteen and Paise Sixty Only	91844.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.92 cubic metre	Per cubic metre	799.00	Rupees Seven Hundred Ninty Nine Only	1534.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	6.04 Nos.	Each	299.50	Rupees Two Hundred Ninty Nine and Paise Fifty Only.	1809.00
				<b>Total:-</b>		<b>99486.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-


  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of rain damages on Kando to Senga road Km 0/0 to 3/500(SH:-Construction of R/wall in PCC 1:4:8 at RD 1/910 to 1/916) Job.- 32 Estimated Cost:-98840/- Only.  
 Earnest Money:- 2000/- Only Time Limit: - One Month



Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	6.84 cubic metre	Per cubic metre	300.00	Rupees Three Hundred only	2052.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	21.36 cubic metre	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only	91848.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.30 cubic metre	Per cubic metre	800.00	Rupees Eight Hundred Only	2640.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	12.00 Nos.	Each	275.00	Rupees Two Hundred Seventy Five Only	3300.00
				Total:-		99840.00
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY						Job.- 33	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of Rain Damages on Renuka Sataun road Km 13/0 to 29/160 (SH:- Hiring of Excavator cum loader for removal of slips from Various RDs in Kn 13/00 to 15/00)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	


Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai 

SCHEDULE OF QUANTITY		Job: 34	Estimated Cost:-99104/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work:-Restoration of rain damages on Rast Manal Chunoti road Km 0/0 to 15/135 (SH:-Construction of R/wall in RR Masonry at RD 0/370 to 0/374) under PDNA			

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.58 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	3281.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) mimilimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20 cubic metre	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
				Total:-		99104.00
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job.- 35

Estimated Cost:-98012/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages Nanidhar Shakholi Rast road Km 0/0 to 8/00 (SH:-Construction of R/wall in RR Masonry at RD 5/871 to 5/878) under PDNA.


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	21.70 cubic metre	Per cubic metre	294.34	Rupees Two Hundred Ninety Four and Paise Thirty Four Only	6387.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	1.82 cubic metre	Per cubic metre	4415.30	Rupees Four Thousand Four Hundred Fifteen and Paise Thirty Only	8036.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	23.100 cubic metre	Per cubic metre	3450.14	Rupees Three Thousand Four Hundred Fifty and	79698.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	13.00 Nos.	Each	299.30	Rupees Two Hundred Ninety Nine and Paise Thirty Only	3891.00
				<b>Total:-</b>		<b>98012.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai


SCHEDULE OF QUANTITY				Job.- 36		Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of work: Restoration of Rain Damages on various roads under Sataun Section in Sataun Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY				Job - 37		Estimated Cost - 99900- Only Earnest Money - 2000/- Only Time Limit - One Month	
Name of work: Restoration of Rain Damages on various roads under Timbi Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	{ .....%}	
					Minus(-)	{ .....%}	


Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

Work at P DNA

SCHEDULE OF QUANTITY					Job.- 38	Estimated Cost:-98698/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work:-Restoration of rain damages on LPRR Road Km 97/0 to 112/167 (SH:-Construction of R/wall in RR Masonry at RD 109/700 to 109/704 )						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
				<b>Total:-</b>		<b>98698.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY				Job - 39	Estimated Cost:- 98698/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of Work :- Restoration of rain damages on Manal Matiyana road km. 0/0 to 8/00 (SH:- C/O R/Wall RR Masonary at RD 4/015 to 4/019 )						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.20 Nos.	Each	790.00	Rupees Seven Hundred Ninty Only	2528.00
				Total:-		98698.00
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

*Tommy*  
Executive Engineer  
Shillai Division  
HP PWD Shillai


SCHEDULE OF QUANTITY					Job.- 40	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of rain damages to Manal kanti mashwa road km 0/00 to 13/350 .(SH:- Hiring of excavator cum loader for removal of slips at various RD's between km. 6/500 to 13/00)						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai 

SCHEDULE OF QUANTITY					Job.- 41	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of rain damages to Bharli banour road km 0/0 to 13/355((SH:- Hiring of excavator cum loader for removal of slips at various RD'sbetween km. 5/00 to 9/500)						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
					<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillal



SCHEDULE OF QUANTITY					Job.- 42	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of rain damages to Bharli banour road km 0/0 to 13/355((SH:- Hiring of excavator cum loader for removal of slips at various RD'sbetween km. 10/00 to 13/355						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
						<b>Total:- 99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

*Signature*  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY						Job.- 43	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of rain damages Ranuka Sataun road km 13/450 to 29/400 .(SH:- Hiring of excavator cum loader for removal of slips at various RD's between km. 21/0 to 24/00)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai 

SCHEDULE OF QUANTITY			Job.- 44	Estimated Cost:- 98698/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work:-Restoration of rain damages to Gangtoli to Bambal road Km 0/0 to 4/500(SH:-Construction of B/wall in RR Masonry at RD 3/711 to 3/715)				

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.76 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	90630.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.20 Nos.	Each	790.00	Rupees Seven Hundred Ninty Only	2528.00
				Total:-		98698.00

Select:-	Plus(+)	( .....%)
	Minus(-)	( .....%)

Name and full address of the contractor:-

*[Signature]*  
Executive Engineer  
Shillai Division  
HP PWD Shillai *[Signature]*

**SCHEDULE OF QUANTITY**


Job.- 45

Estimated Cost:-98449/- Only.  
Earnest Money:- 2000/-- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages on Mashu Kando Raod Km 0/0 to 3/600 (SH:-Construction of R/wall in RR Masonry at RD 3/225 to 3/234 )


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	7.40 cubic metre	Per cubic metre	325.00	Rupees Three Hundred Twenty Five Only	2405.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In- charge.	1.48 cubic metre	Per cubic metre	4465.00	Rupees Four Thousand Four Hundred Sixty Five Only	6608.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	21.660 cubic metre	Per cubic metre	3900.00	Rupees Three Thousand Nine Hundred Only	84474.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	16.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	4962.00
					<b>Total:-</b>	<b>98449.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 46	Estimated Cost:-98913/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of work:-R/R Damages on Kashi Kando road km 0/00 to 3/600 (SH:-C/o R/wall in PCC 1:4:8 at km 3/240 to 3/ 246 )						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.06 cubic metre	Per cubic metre	315.00	Rupees Three Hundred Fifteen Only	3484.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In- charge.	19.58 cubic metre	Per cubic metre	4465.00	Rupees Four Thousand Four Hundred Sixty Five Only	87425.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.03 cubic metre	Per cubic metre	799.00	Rupees Seven Hundred Ninety Nine Only	2421.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	18.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	5583.00
					<b>Total:-</b>	<b>98913.00</b>
					<b>Select:-</b>	
					Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job-47

Estimated Cost:- 99900- Only.  
 Earnest Money:- 2000/- Only. Time  
 Limit:- One Month

Name of work: Restoration of Rain Damages on Uttri More to Village Uttri road Km 0/0 to 2/500 (SH:- Hiring of Excavator cum loader for removal of slips from Various RDs)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in-Charge. Crawling one side shall be paid to the contractor.	111.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
		Select:-		Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

*[Signature]*  
 Executive Engineer  
 B & R Division  
 HP PWD Shilla

Estimated Cost-99856/- Only.

Earnest Money:- 2000/- Only. Time

Limit: - One Month

SCHEDULE OF QUANTITY

Job - 48

Name of work:- Restoration of rain damages on Lijja Hallan road Km 0/0 to 1/705(SH):-Construction of R/wall in PCC 1:4:8 at RD 1/660 to 1/665)

Order PWD/

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.95	Per cubic metre	290.15	Rupees Two Hundred Ninety and Paise Fifteen Only	4628.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.58	Per cubic metre	4320.90	Rupees Four Thousand Three Hundred Twenty and Paise Ninety Only	88924.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads and lifts and carriage of material as per the direction of the Engineer incharge.	5.41	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	4274.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7, including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00	Each	253.70	Rupees Two Hundred Fifty Three and Paise Seventy Only	2030.00
Total:-						99856.00
Select:-		Plus(+)		Minus(-)		
		(.....%)		(.....%)		

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Lijja Hallan road Km 0/0 to 1/705(SH):-Construction of R/wall in PCC 1:4:8 at RD 1/672 to 1/672)  
 Job:- 49  
 Estimated Cost:-99919/- Only  
 Earnest Money:-2000/- Only  
 Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.95	Per cubic metre	290.15	Rupees Two Hundred Ninety and Paise Fifteen Only	4628.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.58	Per cubic metre	4320.90	Rupees Four Thousand Three Hundred Twenty and Paise Ninety Only	88924.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	5.17	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	4084.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7, including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00	Each	253.70	Rupees Two Hundred Fifty Three and Paise Seventy Only	2283.00
				<b>Total:-</b>		<b>99919.00</b>
		<b>Select:-</b>		<b>Plus(+)</b>	(.....%)	
				<b>Minus(-)</b>	(.....%)	

Name and full address of the contractor:-

*Praveen*  
 Executive Engineer  
 Shilal Division  
 HP PWD Shillal

**SCHEDULE OF QUANTITY**

Name of work: Restoration of Rain Damages on Kaafenu Kukrech to Bogra Thana Manal road Km 0/0 to 5/500(SH.- Hiring of Excavator cum loader for removal of slips from Various RDs)

Job - 50

Estimated Cost:- 99900.- Only.

Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. Including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
Select:-				Plus(+)	( .....%)	( .....%)
				Minus(-)	( .....%)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work: Restoration of Rain Damages on Naya Panjor road Km 0/0 to 4/00(SH.- Hiring of Excavator cum loader for removal of slips from Various RDS)

Job - 5 /

Estimated Cost - 99900.- Only. Time  
 Earnest Money:- 2000/- Only  
 Limit: - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+) Minus(-)	( .....%) ( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shilla

**SCHEDULE OF QUANTITY**


Name of work:-R/R Damages on Gwali Pashmi Manal Matiyana road km 0/00 to 8/00 (SH:-C/o R/wall in PCC 1:4:8 at km 2/310 to 2/ 314 )

Job - 52

Estimated Cost:-98288/- Only.  
Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.60	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4285.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.80	Per cubic metre	4328.60	Rupees Four Thousand Three Hundred Twenty Eight and Paise Sixty Only	90035.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.92	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	1517.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	306.42	Rupees Three Hundred Six and Paise Forty Two Only	2451.00
				Total:-		98288.00
				Select:-		
				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work: -R/R Damages on Gwalli Pashmi Manal Matiyana road km 0/00 to 8/00 (SH:-C/O R/wall in PCC 1:4:8 at km 2/318 to 2/ 322 )

Job - 53

Estimated Cost:-98288/- Only.  
Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.60	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4285.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.80	Per cubic metre	4328.60	Rupees Four Thousand Three Hundred Twenty Eight and Paise Sixty Only	90035.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	1.92	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	1517.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3:7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	306.42	Rupees Three Hundred Six and Paise Forty Two Only	2451.00
<b>Total:-</b>						<b>98288.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work: Restoration of Rain Damages on Parwa Lawagu Shakholi road Km 0/0 to 4/500 (SH:- Hiring of Excavator cum loader for removal of slips from Various RDS in Km 0/0 to2 /00)

Job - 24 Estimated Cost:- 99900.- Only. Earnest Money:- 2000.- Only Time Limit:- One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
<b>Total:-</b>						<b>99900.00</b>
Select:-				Plus(+)	(.....%)	(.....%)
				Minus(-)	(.....%)	(.....%)

Name and full address of the contractor:-

*forward*  
**Executive Engineer**  
 B & R Division  
 HP PWD Shillal

**SCHEDULE OF QUANTITY**

Job - 55


Estimated Cost:- 99900/- Only.

Earnest Money:- 2000/- Only Time Limit: - One Month

Name of work: Restoration of Rain Damages on link road to Village Sathor Km 0/0 to 2/00 (SH:- Hiring of Excavator cum loader for removal of slips from Various RDs)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum (Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
<b>Total:-</b>						<b>99900.00</b>
				Select:-	Plus(+)	(.....%)
					Minus(-)	(.....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillal

**SCHEDULE OF QUANTITY**


56

Name of work :- Preparation of detailed estimate for A/A & E/S, Technical sanction/working estimates & draft schedule of quantity of the construction of Rajiv Gandhi Government Model day Boarding School at Sataun,).

Estimated cost :- Rs. 75,500 /-  
 Earnest Money :- Rs. 2,000 /-  
 Time allowed :- One months

S.No.	Sub-head & item of works	Quantity	Rate in		Unit	Amount	
			Figure	Words			
1	Preparation of detailed estimate for A/A & E/S, Technical sanction/working estimates & draft schedule of quantity of building works on detailed analysis of rates of subject cited work under Sataun Sub-Division in all respect & submission to the same to higher office for approval If any correction/ amendment will be desired by the head office the same may be corrected as desired & directed by the Engineer-in-Charge and complete in all respect. After approval the same from the head office should be submitted with soft copy.	1.00	75500.00	Rs. Seveny five thousand five hundred & paise nil only.	Each	75500	
<b>Total :-</b>						<b>75500</b>	
Select:-						Plus(+)	(.....%)
						Minus(-)	(.....%)

Signature of the Contractor with full address.

  
 Executive Engineer,  
 Shillai Division, HP.PWD.,  
 Shillai

**SCHEDULE OF QUANTITY**

Name of work: Restoration of Rain Damages on various roads under Shillai Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDS)

Job - **57**

Estimated Cost:- 99900- Only  
Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
<b>Total:-</b>						<b>99900.00</b>
Select:-				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai


SCHEDULE OF QUANTITY				Job.-58		Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month	
Name of work: Restoration of Rain Damages on various roads under Meenus Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Name and full address of the contractor:-

  
Executive Engineer  
B & R Division  
HP PWD Shillai 

SCHEDULE OF QUANTITY						Job.- 59	Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month
Name of work: Restoration of Rain Damages on various roads under Kamrau Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs)							
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shell be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00	
						<b>Total:-</b>	<b>99900.00</b>
				Select:-	Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Name and full address of the contractor:-

  
Executive Engineer  
B & R Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work: Restoration of Rain Damages on various roads Chandani Section under Sataun Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDS)

Job.- **50**

Estimated Cost:- 99900.- Only.  
Earnest Money:- 2000.- Only Time Limit: - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
Select:-				Plus(+)	(.....%)	
				Minus(-)	(.....%)	

Name and full address of the contractor:-

*Harmand*  
Executive Engineer  
B & R Division  
HP PWD Shillai

*[Signature]*

**SCHEDULE OF QUANTITY**

Name of work: Restoration of Rain Damages on various roads Rajpur Section under Sataun Sub Division (SH:- Hiring of Excavator cum loader for removal of slips at Various RDs)

Job.- 61

Estimated Cost - 99900.- Only  
 Earnest Money - 2000/- Only Time  
 Limit - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shell be paid to the contractor.	111.00	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
<b>Total:-</b>						<b>99900.00</b>
				Select:-	Plus(+) <input type="text"/>	<input type="text"/>
					Minus(-) <input type="text"/>	<input type="text"/>

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai