

**HIMACHAL PRADESH  
PUBLIC WORK DEPARTMENT**

No. PW/SD/CB/TA /2025-26- 8789

Dated:- 17.10.2025

To,


The Executive Engineer  
IT Cell Nirman Bhawan Nigam Vihar,  
HP PWD Shimla.

Subject:-

Regarding Uploading /Publishing Notice  
Inviting Tender on HPPWD Website .


Enclosed please find herewith the Notice  
Inviting Tender (NIT) along with Schedule of Quantity for uploading on HP  
PWD website. This is for your kind information and necessary action please.

Encls:- NIT copy & 63 Nos copy of Schedule of Quantity.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai.

## CERTIFICATE

Certified that the tenders of works, called vide this office letter No.PW-SD-CB-TA-2025-26- 8780-88 dated:-17.10.2025 are urgent and post disaster nature.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Short terms Sealed percentage rate tender on form PWD 6, 7 & 8 are invited by the Executive Engineer Shillai, Division HP, PWD on behalf of Governor of Himachal Pradesh for the following works from the approved and eligible Contractors enlisted in HP PWD so as to reach in this office as per time schedule given below.

Job No.	Name of work	Estimated Cost	Earnest Money	Time of period	Cost of form	Eligible Class of Contractor
1	Date of receipt of application of tenders forms:-	28.10.2025 at 12:00 AM, up to 04:00 PM				
2	Date of issue/ sale of tender Forms:-	29.10.2025 at 10:00 AM, up to 12:30 PM				
3	Date of receipt of tender Forms :-	29.10.2025 at 02:00 PM, up to 03:30 PM				
4	Date of opening of tender:-	29.10.2025 at 04.00 PM.				
1	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O R/Wall in R/R Masonry at RD 3/307 to 3/711).	99674/-	2,000.00	One Month	350/-	" D" Class
2	Restoration of Rain Damages on Kando Bhatnol road Km 0/0 to 2/500 (SH:-C/O B/wall in PCC 1:4:8 at RD 0/173 to 0/180)	99453/-	2,000.00	One Month	350/-	" D" Class
3	Restoration of Rain Damages on Jakhna to Sharli Manpur road km. 0/0 to 7/750 (SH:- C/O R/Wall in R/R masonry at RD. 3/350 to 3/354)	99849/-	2,000.00	One Month	350/-	" D" Class
4	Restoration of Rain Damages on Kando Bhatnol road Km 0/0 to 2/500 (SH:-C/O B/wall in PCC 1:4:8 at RD 0/165 to 0/172)	99543/-	2,000.00	One Month	350/-	" D" Class
5	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O R/Wall in R/R Masonry at RD 3/701 too 3/705).	99674/-	2,000.00	One Month	350/-	" D" Class
6	Restoration of Rain Damages on road Village Muinal Bag Km. 0/0 to 1/900(SH:- C/O B/wall in PCC 1:4:8 at RD 1/891 to 1/899)	99607/-	2,000.00	One Month	350/-	" D" Class
7	A/R & M/O LPRR road km. 97/00 to 112/167 (SH:- Providing and erecting street light mounted on a steel circular hollow pole between km. 107/520 to 108/00)	99100/-	2,000.00	One Month	350/-	" D" Class
8	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O R/Wall in R/R Masonry at RD 1/216 to 1/220)	98164/-	2,000.00	One Month	350/-	" D" Class
9	Restoration of Damages on Kotti Uttrou road km. 0/0 to 6/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 0/305 to 0/309)	99572/-	2,000.00	One Month	350/-	" D" Class
10	Restoration of Rain Damages on L/R road village Pabhar Km. 0/00 to 4/00 (SH:-C/O R/wall in R/R Masonry at RD 0/060 to 0/067)	98478/-	2,000.00	One Month	350/-	" D" Class
11	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/500 (SH:- C/O B/Wall in R/R Masonry at RD 5/037 to 5/046)	99473/-	2,000.00	One Month	350/-	" D" Class
12	Restoration of Rain Damages on L/R Jamna Km. 0/0 to 2/00 (SH:- C/O R/wall in R/R masonry at RD. 1/105 to 1/111)	99991/-	2,000.00	One Month	350/-	" D" Class
13	Restoration of Rain Damages on L/R Jamna Km. 0/0 to 2/00 (SH:- C/O B/wall in PCC 1:4:8 at RD. 1/315 to 1/321)	98175/-	2,000.00	One Month	350/-	" D" Class
14	Restoration of rain damages on Gangtoli to Kuhant road 0/0 to 5/00 (SH:- Hiring of Excavator cum loader for removal of slips from various RDs)	99900/-	2,000.00	One Month	350/-	" D" Class


15	Balance Work of Govt. High School Sunog in Tehsil Paonta Sahib Distt. Sirmaur H.P. (S.H. Providing and laying Painting)	98494/-	2,000.00	One Month	350/-	" D" Class
16	Restoration of Rain Damages on Bella Siyasu road Km. 0/0 to 9/00 (SH:- C/o R/wall in PCC 1:4:8 at RD 6/150 to 6/154)	99868/-	2,000.00	One Month	350/-	" D" Class
17	Restoration of Rain Damages on Mashu Kando road Km. 0/0 to 3/600 (SH:- C/O R/wall in R/R Masonry at RD.0/156 to 0/160)	98727/-	2,000.00	One Month	350/-	" D" Class
18	Restoration of Rain Damages on Jakhana Sharli Manpur Road Km 0/0 to 7/750 (Construction of Earthen Shoulder in Km 3/500 to 7/500 in patches)	99731/-	2,000.00	One Month	350/-	" D" Class
19	Restoration of Rain Damages on Mashu Kando Road Km 0/00 to 3/600 & Jakhana Sharli Manpur Road Km 0/0 to 7/500 (SH:- Clearing Jungle including uprooting of rank vegetation , grass, Brush wood, tree and saplings of grith up to 30cm measured on various Road.)	99831/-	2,000.00	One Month	350/-	" D" Class
20	Restoration of Rain Damages on Millah Gundah road km. 0/00 to 12/075(SH:- C/O R/wall in R/R Masonry at RD 5/600 to 5/604)	97635/-	2,000.00	One Month	350/-	" D" Class
21	Restoration of Rain Damages on Link road Village Bambrad Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 1/010 to 1/014)	99915/-	2,000.00	One Month	350/-	" D" Class
22	Restoration of Rain Damages on Sharli Kumli road km. 0/0 to 7/00 (SH:- C/O R/Wall in wire crate with toe wall PCC 1:4:8 at RD 4/452 to 4/456)	98952/-	2,000.00	One Month	350/-	" D" Class
23	Restoration of Rain Damages on Sharli Kumli road km. 0/0 to 7/00 (SH:- C/O R/Wall in wire crate with toe wall PCC 1:4:8 at RD 4/446 to 4/450)	98952/-	2,000.00	One Month	350/-	" D" Class
24	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500 (SH:- C/O R/Wall in wire crates at RD 1/028 to 1/031)	98820/-	2,000.00	One Month	350/-	" D" Class
25	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500 (SH:- C/O R/Wall in wire crates at RD 1/032 to 1/035)	98820/-	2,000.00	One Month	350/-	" D" Class
26	Restoration of Rain Damages on Various road under Bali Koti Section Under Shillai Sub Division (SH:- Hiring of Excavator cum loader for removal of slips and dressing of road surface)Job	99900/-	2,000.00	One Month	350/-	" D" Class
27	Restoration of Rain Damages on Link road to Village Juinal Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 0/710 to 0/714)	98698/-	2,000.00	One Month	350/-	" D" Class
28	Restoration of Rain Damages on Link road to Village Juinal Km. 0/0 to 2/500 (SH:- C/O R/Wall in R/R Masonry at RD 0/716 to 0/720)	98698/-	2,000.00	One Month	350/-	" D" Class
29	Restoration of Rain Damages on Shilla Gundah Road Km. 0/0 to 33/500(SH:- C/O R/Wall in R/R Masonry at RD 17/774 to 17/771)	98255/-	2,000.00	One Month	350/-	" D" Class
30	Restoration of Rain Damages on Millah Digwa Road Km. 0/0 to 6/900(SH:- C/O R/Wall in PCC 1:4:8 at RD 1/578 to 1/584) Under PDNA	94828/-	2,000.00	One Month	350/-	" D" Class
31	Restoration of Rain Damages on Shillai Achhoti Pandiyat road Km. 0/0 to 7/00 (SH:- C/O B/wall in R/R Masonry at RD 0/105 to 0/109)	99038/-	2,000.00	One Month	350/-	" D" Class
32	Restoration of Rain Damages to Gawali Pashmi Manal Matiyana road Km. 0/0 to 8/00 (SH:- C/o R/wall in R/R Masonry at RD 2/280 to 2/284)	98672/-	2,000.00	One Month	350/-	" D" Class

33	Restoration of Rain Damages on Bella Siyasu road km. 0/0 to 9/00 (SH:- C/O R/wall in Wire Crate RD 4/105 to 4/113)	99701/-	2,000.00	One Month	350/-	" D" Class
34	Restoration of Rain Damages on Bella Siyasu road km. 0/0 to 9/00 (SH:- C/O R/wall in wire crate RD. 4/115 to 4/123)	99701/-	2,000.00	One Month	350/-	" D" Class
35	Restoration of Rain Damages on Kando Dugana to Shamah Pantta road Km. 0/0 to 5/870(SH:- C/o B/Wall in PCC 1:4:8 at RD. 0/630 to 0/638)	98534/-	2,000.00	One Month	350/-	" D" Class
36	Restoration of Rain Damages on Jakhna Sharli Manpur road Km. 0/0 to 7/500 (SH:- C/O Earthen Shoulder in Km. 2/550 to 3/500 in patches)	98055/-	2,000.00	One Month	350/-	" D" Class
37	Restoration of Rain Damages on Kotti Uttrou Road Km. 0/0 to 6/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 3/427 to 3/432)	98019/-	2,000.00	One Month	350/-	" D" Class
38	Restoration of Rain Damages on Kotti Uttrou Road Km. 0/0 to 6/00 (SH:- C/O B/Wall in R/R Masonry at RD 3/300 to 3/309)	98646/-	2,000.00	One Month	350/-	" D" Class
39	Restoration of Rain Damages on Link road Harijan Basti Kharech Km. 0/0 to 2/00 (SH:- C/O R/wall in PCC 1:4:8 at RD 0/762 to 0/766)	99980/-	2,000.00	One Month	350/-	" D" Class
40	Balance Work of Govt High School Sunog in Tehsil Paonta Sahib Distt. Sirmour HP(SH:- Providing Brick work in Plinth)	96192/-	2,000.00	One Month	350/-	" D" Class
41	Restoration of Rain Damages on Naya Daya Kunhat road Km. 0/0 to 6/900(SH:- C/O R/wall in PCC 1:4;8 at RD 5/532 to 5/536)	98486/-	2,000.00	One Month	350/-	" D" Class
42	Restoration of Rain Damages on Link road Harijan Basti Kharech Km. 0/0 to 2/00 (SH:- C/O R/wall in PCC 1:4:8 at RD 0/767 to 0/781)	99714/-	2,000.00	One Month	350/-	" D" Class
43	Restoration of Rain Damages on Kando Senga road Km. 0/0 to 3/500(SH:- C/O R/wall in PCC 1:4;8 at RD 1/900 to 1/906)	99847/-	2,000.00	One Month	350/-	" D" Class
44	Restoration of Rain Damages on Renuka Sataun road Km. 13/0 to 29/160(SH:- Hiring of Excavator cum loader for removal of slips rd 16/500 to 20/00)	99900/-	2,000.00	One Month	350/-	" D" Class
45	Restoration of Rain Damages on Rast Manal Chunnoti Road Km. 0/0 to 15/135 (SH:- C/O R/wall in PCC 1:4:8 at RD 0/756 to 0/760)	99082/-	2,000.00	One Month	350/-	" D" Class
46	Restoration of Rain Damages on Rast Manal Chunnoti Road Km. 0/0 to 15/135 (SH:- C/O R/wall in PCC 1:4:8 at RD 0/750 to 0/754)	99082/-	2,000.00	One Month	350/-	" D" Class
47	R/R damages on Nainidhar Shakholi Rast km 0/00 -8/00 (Sh:- C/O B/Wall in RR Masonry at Rd 5/862 to 5/869)	97930/-	2,000.00	One Month	350/-	" D" Class
48	R/R damages on Nainidhar Shakholi Rast km 0/00 -8/00 (Sh:- C/O B/Wall in RR Masonry at Rd 3/150 to 3/157)	98115/-	2,000.00	One Month	350/-	" D" Class
49	A/R & M/O LPRR road km. 97/00 to 112/167 (SH:- Providing and erecting street light mounted on a steel circular hollow pole between km. 107/020 to 107/500)	99100/-	2,000.00	One Month	350/-	" D" Class
50	R/R damages on LPRR road km 97/00 to 112/167 (SH:- C/o R/wall in RR Masonry at rd 107/850 to 107/854).	99104/-	2,000.00	One Month	350/-	" D" Class
51	R/R damages on LPRR road km 97/00 to 112/167 (SH:- C/o R/wall in RR Masonry at rd 109/706 to 109/710).	98698/-	2,000.00	One Month	350/-	" D" Class
52	Restoration of Rain Damages to Gawali Pashmi Manal Matiyana road Km. 0/0 to 8/00 (SH:- C/o R/wall in R/R masonry at RD 4/010 to 4/014)	98698/-	2,000.00	One Month	350/-	" D" Class

53	R/R damages on Manal Kanti Mashwa road km. 0/0 to 13/350(SH:- Hiring of Excavator cum loader for removal of slips various Rds Between Km 0/00 to 6/00)	99900/-	2,000.00	One Month	350/-	" D" Class
54	R/R damages on Bharli Hanour road from km 0/00 to 13/355 (SH:- Hiring of Excavator cul loader for removal of slips various Rds Between Km 0/00 to 4/500)	99900/-	2,000.00	One Month	350/-	" D" Class
55	Restoration of Rain Damages on Rentuka Sataun road Km. 13/0 to 29/160(SH:- Hiring of Excavator cum loader for removal of slips rd 25/500 to 29/00)	99900/-	2,000.00	One Month	350/-	" D" Class
56	R/R damages on various road Chandni Kaihwar (Sh:- Hiring of excavator cum loader for removal of slips various RD between 0/00 to 10/500.)	99900/-	2,000.00	One Month	350/-	" D" Class
57	R/R Damages to Gangotli to Bumbal road Km. 0/0 to 4/500(SH:- C/O B/wall in RR Masonry at RD 3/705 to 3/709)	98698/-	2,000.00	One Month	350/-	" D" Class
58	Restoration of Rain Damages on Jakahna Sharli Manpur Road Km 0/0 to 7/500 (SH:- Construction of R/wall in R/R Masonry at RD 3/338 to 3/342).	99849/-	2,000.00	One Month	350/-	" D" Class
59	Restoration of Rain Damages on Jakahna Sharli Manpur Road Km 0/0 to 7/300 (SH:- Construction of R/wall in PCC 1:4:8 at RD 3/344 to 3/348).	99880/-	2,000.00	One Month	350/-	" D" Class
60	Restoration of Rain Damages on Jakahna Kumli Road Km 0/0 to 7/500 (SH:- Construction of R/wall in R/R Masonry at RD 5/300 to 5/308).	98427/-	2,000.00	One Month	350/-	" D" Class
61	Restoration of Rain Damages on Jakahna Kumli Road Km 0/0 to 7/500 (SH:- Construction of R/wall in R/R Masonry at RD 5/308 to 5/312).	98999/-	2,000.00	One Month	350/-	" D" Class
62	Restoration of Rain Damages on Link road Kando Dugana Shamah Pamta road Km. 0/0 to 5/870 (SH:- C/O B/Wall in PCC 1:4:8 at RD. 3/295 to 3/300)	97311/-	2,000.00	One Month	350/-	" D" Class
63	Restoration of Rain Damages on Link road Kando Dugana Shamah Pamta road Km. 0/0 to 5/870 (SH:- C/O B/Wall in PCC 1:4:8 at RD. 3/288 to 3/293)	97311/-	2,000.00	One Month	350/-	" D" Class

**Terms and conditions:-** The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application.

- 1 The Earnest Money for the above works should be submitted with applications for the purchase of the tender documents.
- 2 The Contractors should quote the % rate of overall item in the tender both in figures and words.
- 3 Income Tax and GST No. latest clearance certificate.
- 4 The contractors/firms shall accompany his enlistment (renewal and EPF with his application.
- 5 The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reason.


  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai

Dated:- 17.10.2025

PW-SD-CB-TA-NIT-2025-26- 8780-88

Copy forwarded for information and wide publicity to:-

- 1 The Superintending Engineer 12<sup>th</sup> Circle HP PWD Nahar.
- 2 All the Assistant Engineer working under this Division.
- 3 A/B and D/B in this office.
- 4 Notice Board.

  
Executive Engineer  
Shillai (B&R) Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of Damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500(SH)-Construction of R/wall in R/R Masonry at RD 3/707 to 3/711). **Job - 01**

Estimated Cost- 99674/- Only.  
Earnest Money:- 2000/- Only  
Time Limit. - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 205.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal of leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.00	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3827.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203,1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	2.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 including rubble masonry (2nd Sort) in cement mortar 1:6, including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.40	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise	82501.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 (Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer In-charge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2452.00
<b>Total:-</b>						<b>99674.00</b>
<b>Select:-</b>						<b>Plus(+)</b> ( .....%)
						<b>Minus(-)</b> ( .....%)


Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

88

Name of work:-Restoration of Rain damages Kando Bhatnol road Km 0/0 to 2/500( SH:-Construction of B/wall in PCC 1:4:8 at RD0/173 to 0/0/180)		Job.- D2		Estimated Cost:-99543/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.51 cubic metre	Per cubic metre	322.10	Rupees Three Hundred Twenty Two and Paise Ten Only	4029.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	20.72 cubic metre	Per cubic metre	4350.15	Rupees Four Thousand Three Hundred Fifty and Paise Fifteen Only	90135.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.51 cubic metre	Per cubic metre	850.30	Rupees Eight Hundred Fifty and Paise Thirty Only	2985.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	299.23	Rupees Two Hundred Ninety Nine and Paise Twenty Three Only	2394.00
				<b>Total:-</b>		<b>99543.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....%)
				<b>Minus(-)</b>		( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY				Job.- 03	Estimated Cost:- 99849/- Only.	
Name of work:- Restoration of Damages on Jakhana to Sharii Manpur road Km 0/00 to 7/750 (SH):- Construction of R/wall R/R masonry at 3/350 to 3/354)				Earnest Money:- 2000/- Only	Time Limit:- One Month	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.28	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3909.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802, 803, 1202 and 1203.1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	2.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702, 704, 1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6, including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.40	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	82501.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.24	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2525.00
				<b>Total:-</b>		<b>99849.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY		Job.- 04		Estimated Cost:-99543/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work:-Restoration of Rain damages Kando Bhatnol road Km 0/0 to 2/500( SH:-Construction of B/wall in PCC 1:4:8 at RDO/165 to 0/0/172)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.51 cubic metre	Per cubic metre	322.10	Rupees Three Hundred Twenty Two and Paise Ten Only	4029.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	20.72 cubic metre	Per cubic metre	4350.15	Rupees Four Thousand Three Hundred Fifty and Paise Fifteen Only	90135.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.51 cubic metre	Per cubic metre	850.30	Rupees Eight Hundred Fifty and Paise Thirty Only	2985.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	299.23	Rupees Two Hundred Ninety Nine and Paise Twenty Three Only	2394.00
				<b>Total:-</b>		<b>99543.00</b>
				<b>Select:-</b>		<b>Plus(+)</b> ( .....% )
						<b>Minus(-)</b> ( .....% )

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

**Job - 05**

**Estimated Cost:- 99674/- Only.  
Earnest Money:- 2000/- Only  
Time Limit:- One Month**

**Name of work:- Restoration of Damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500(SH:- Construction of R/wall in R/R Masonry at RD 3/701 to 3/705).**

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.00	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3827.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203. 1:4:8 (One cement: Four Sand: Eight graded stone aggregate) 25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- in-charge.	2.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.40	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind a butment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer incharge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
				<b>Total:-</b>		<b>99674.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )

**Name and full address of the contractor:-**

*(Signature)*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
<p><b>Job - 06</b> Estimated Cost:-99607/- Only.                      Earnest Money:- 2000/- Only                      Time Limit: - One Month</p>							
<p><b>Name of work:-</b>Restoration of Damages Link road village Muinal Bag Km 0/0 to 1/900(SH):-Construction of B/wall in PCC1:4:8 at RD 1/891 to 1/899 ).</p>							
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	14.11 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4153.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	21.56 cubic metre	Per cubic metre	4328.60	Rupees Four Thousand Three Hundred Twenty Eight and Paise Sixty Only	93325.00
4		Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2129.00
					<b>Total:-</b>		<b>99607.00</b>
					<b>Select:-</b>		( .....%)
							( .....%)

Name and full address of the contractor:-

*Shillai*  
 Executive Engineer

Shillai Division

HP PWD Shillai

Job:- 07


Estimated Cost:- 99100/- Only.  
Earnest Money:- 2000/- Only  
Limit:- One Month


SCHEDULE OF QUANTITY

Name of work:- A/R & M/O LPRR road Km 97/00 to 112/167 (Sh:- Providing and erecting street light mounted on a steel circular hollow pole Between Km 107/520 to 108/00)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 3:35.1 including sitting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.38 cubic metre	Per cubic metre	290.06	Rupees Two Hundred Ninety and Paise Six Only	980.00
2	Providing and laying plain cement concrete 1-24 and curing completed including the cow of form work for plain/reinforced concrete complete as per the technical specifications etc including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	3.38 cubic metre	Per cubic metre	6200.00	Rupees Six Thousand Two Hundred Only	20956.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	4.000 cubic metre	Per cubic metre	19290.90	Rupees Nineteen Thousand Two Hundred Ninety and Paise Ninety Only	77164.00
<b>Total:-</b>						<b>99100.00</b>
<b>Select:-</b>				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-



  
Executive Engineer  
Shillai Division  
HP PWD Shillai

Job - 08 Estimated Cost:- 98164/- Only.  
 Earnest Money:- 2000/- Only Time Limit - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.04	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	2849.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.33	Per cubic metre	4415.20	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Only	10287.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.12	Per cubic metre	810.00	Rupees Eight Hundred Ten Only	2527.00
				<b>Total:-</b>		<b>98164.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....% )
				<b>Minus(-)</b>		( .....% )

Name and full address of the contractor:-

*forward*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


**Job.- 09**

Estimated Cost:-99572/- Only.  
Earnest Money:- 2000/- Only Time Limit:- One Month

Name of work:-Restoration of rain damages on Koti Ultru road Km 0/0 to 6/00(SH):-Construction of R/wall in PCC 1:4:8 at RD 0/305 to 0/309)

Sl. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.68 cubic metre	Per cubic metre	315.11	Rupees Three Hundred Fifteen and Paise Eleven Only	4311.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)/25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	20.80 cubic metre	Per cubic metre	4415.60	Rupees Four Thousand Four Hundred Fifteen and Paise Sixty Only	91844.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.92 cubic metre	Per cubic metre	810.40	Rupees Eight Hundred Ten and Paise Forty Only	1556.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-In-Charge	6.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	1861.00
				<b>Select:-</b>	<b>Total:-</b>	<b>99572.00</b>
					<b>Plus(+)</b> ( .....% )	
					<b>Minus(-)</b> ( .....% )	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain damages on L/R road Village Pabhar Km 0/00 to 4/00(SH):- Construction of R/wall in R.R masonry at RD 0/060 to 0/067

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.33	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4512.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	3.17	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	13839.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	23.060	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	77970.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.73	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2157.00
				Total:-		98478.00
				Select:-		( .....%)
						( .....%)

Name and full address of the contractor:-

*forward*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job.- / /  
 Estimated Cost:- 99473/- Only.  
 Earnest Money:- 2000/- Only  
 Limit:- One Month

Name of work:- Restoration of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500(SH):-Construction of R/wall in RR Masonry at RD 5/037 to 5/046)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.26 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3609.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.70 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	11787.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.120 cubic metre	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	81555.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00 Nos.	Each	315.20	Rupees Three Hundred Fifteen and Paise Twenty Only	2522.00
				<b>Total:-</b>		<b>99473.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - 12

Estimated Cost:- 99991/- Only.  
Earnest Money:- 2000/- Only Time  
Limit:- One Month

Name of work:- Restoration of Damages on Link road Jamna Km 0/0 to 2/00(SH):-Construction of R/wall in RR Masonry at RD 1/105 to 1/111)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.02	Per cubic metre	322.50	Rupees Three Hundred Twenty Two and Paise Fifty Only	4199.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.70	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	11746.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.340	Per cubic metre	3310.50	Rupees Three Thousand Three Hundred Ten and	80578.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads and carriage of material as per the direction of the Engineer Incharge.	4.08	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	3468.00
<b>Total:-</b>						<b>99991.00</b>
<b>Select:-</b>						<b>( .....% )</b>
						<b>( .....% )</b>


Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai.

**SCHEDULE OF QUANTITY**

Job.- 13		Estimated Cost:-98175/- Only. Earnest Money:- 2000/- Only Limit: - One Month				
Name of work:-Restoration of Damages on Link road Jamna Km 0/0 to 2/00( SH:-Construction of Bl/wall in PCC 1:4:8 at RD 1/315 to 1/321)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.37	Per cubic metre	320.00	Rupees Three Hundred Twenty Only	3638.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.44	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	88924.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.22	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	1887.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3:7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	12.00	Each	310.50	Rupees Three Hundred Ten and Paise Fifty Only	3726.00
				<b>Total:-</b>		<b>98175.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

**Job.- 14**

Estimated Cost:- 99900- Only. Time  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work: Restoration of Rain Damages on Gangtoli to Kunhat road Km 0/0 to 4/500 (SH:- Hiring of Excavator cum loader for removal of slips from Various RDs)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai


**SCHEDULE OF QUANTITY**

Sr. No		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
1		Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts including all incidental charges. as per drawings and technical specifications clause	765.00 Square Metre	Per Square Metre	128.25	Rs. One hundred twenty eight & twenty Five Paise only.	98111.00
					<b>Total:-</b>		<b>98111.00</b>
					Select:-	Plus(+)	( .....%)
						Minus(-)	( .....%)

Name of work:- Balance work on Govt.High School Sunog in Tehsil Paonta Sahib Distt. Sirmour H.P.(S.H: Providing and laying Painting work)

Job.- 15  
Estimated Cost:-98111/- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month Time

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - **16**

Estimated Cost:-99868/- Only  
 Earnest Money:- 2000/- Only  
 Time Limit: - One Month

Name of work:- Restoration of Damages on Bella Sivasu road Km 0/0 to 9/00 (SH: Construction of R/wall in PCC 1:4:8 at RD 6/150 to 6/154).

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.70	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4033.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate):25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	21.06	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	91940.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer-In-charge.	1.90	Per cubic metre	789.40	Rupees Seven Hundred Eighty Nine and Paise Forty Only	1500.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2395.00
				<b>Total:-</b>		<b>99868.00</b>
				<b>Select:-</b>		
						( .....% )
						( .....% )

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Mashu Kando road Km 0/0 to 3/600(SH:-Construction of R/wall in RR Masonry at RD 0/156 to 0/160)

Job.- 17

Estimated Cost- 98727/- Only.  
Earnest Money:- 2000/- Only Time  
Limit - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6,including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7,including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.200 cubic metre	Each	799.00	Rupees Seven Hundred Ninety Nine Only	2557.00
				<b>Total:-</b>		<b>98727.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )

Name and full address of the contractor:-

*Shillai*  
Executive Engineer

Shillai Division

HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work: Restoration of rain damages on Jakhana Shari Manpur road Km 0/0 to 7/750(SH):- construction of earthen shoulder in Km 2/500 to 7/500 in patches)

Job: - 18  
 Estimated Cost - 99731.00  
 Earnest Money - 20000.00  
 Limit - One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Construction of Sub grade and earthen Shoulders with approved materials obtained from borrow pits with all liftand leads, transporting to site speariding, grading to required slope and compacted to meet requirement of table 300.2 with lead upto 1000m as per technical specification clause 303.1 . . Including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	534.32	Per cubic metre	186.65	Rupees One hundred Eighty Six and Paise Sixty Five Only	99731.00
				<b>Total:-</b>		<b>99731.00</b>
				Select:-	( )	( )
					( )	( )

Name and full address of the contractor:-

  
 Executive Engineer  
 S & R Division  
 HP PWD Shillong

**SCHEDULE OF QUANTITY**


Job.-19

Estimated Cost- 99831- Only  
Earnest Money- 20000- Only  
Limit - One Month

Name of work: Restoration of rain damages on Mashu Kando road Km 0/0 to 3/600 & Jakhana Sharli Manour road Km 0/0 to 7/500 (SH:- Clearing Jungle including uprooting of rank vavitation,grass, Brush wood,trees, and saplings of grith upto 30cm measured from Various road )

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Clearing Jungle including uprooting of rank vavitation,grass, Brush wood,trees, and saplings of grith upto 30cm measured at hightof 1 mtr ( One metre) above ground level and removal of rubbish up to a distance of 50m out side the periphery of the area cleared. including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	16050.00	Per Square metre	6.22	Supplier Six and Paise Twenty Two Only	99831.00
				<b>Total:-</b>		<b>99831.00</b>
				Selected-	( )	( )
					Minus:-	( )

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

Job - 20

Estimated Cost:- 97635/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - One Month

## SCHEDULE OF QUANTITY

Name of work:-Restoratiinn of rain damages on Millah Gundah road Km 0/00 to 12/075(S.H):- Construction R/wall in R/R Masonry at RD 5/600 to 5/604)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.60 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3709.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.06 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	8993.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.40 cubic metre	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer incharge.	3.12 cubic metre	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
				<b>Total:-</b>		<b>97635.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

**Job.- 2/**

Estimated Cost:- 99915/- Only.  
Earnest Money:- 2000/- Only  
Limit - One Month

Name of work:- Restoration of rain damages Link road village Bambrad Km 0/0 to 2/500(SH):-Construction of R/wall in RR Masonry at RD 1/010 to 1/014)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.40	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3944.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.50	Per cubic metre	4415.20	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Only	11038.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One	82501.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 500 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.12	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2432.00
				<b>Total:-</b>		<b>99915.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - 22

Estimated Cost:-98952/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages on Sharii Kumli road Km 0/0 to 7/00(SH.-Construction of R/wall in wire crate with toe wall PCC 1:4:8 at RD 4/452 to 4/456)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.24	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3308.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	4.80	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	20882.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	31.68	Per cubic metre	2355.95	Rupees Two Thousand Three Hundred Fifty Five and Paise Ninety Five Only	74636.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.44	Per cubic metre	781.85	Rupees Seven Hundred Eighty One and Paise Eighty Five Only	1126.00
				<b>Total:-</b>		<b>99952.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

  
Executive Engineer

Shillai Division

HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job:- 23

Estimated Cost:- 98952/- Only.  
Earnest Money:- 2000/- Only Time Limit:- One Month

Name of work:- Restoration of rain damages on Shari Kumli road Km 0/0 to 7/00(SH):-Construction of R/wall in wire crate with toe wall PCC 1:4:8 at RD 4/446 to 4/450)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.24	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3308.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	4.80	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	20882.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	31.68	Per cubic metre	2355.95	Rupees Two Thousand Three Hundred Fifty Five and Paise Ninety Five Only	74636.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 500 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.44	Per cubic metre	781.85	Rupees Seven Hundred Eighty One and Paise Eighty Five Only	1126.00
				<b>Total:-</b>		<b>99952.00</b>
				<b>Select:-</b>		( .....%)
						( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:- Restoration Of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500( SH:-Construction of R/wall in wire Crate at RD 1/028 to 1/031)

Job - 24

Estimated Cost:- 98820/- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.46	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	1607.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4-8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	39.75	Per cubic metre	2445.60	Rupees Two Thousand Four Hundred Forty Five and Paise Sixty Only	97213.00
				<b>Total:-</b>		<b>98820.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )


Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Job.- 25 Name of work:- Restoration Of rain damages on Shillai Achhoti Pandiyat road Km 0/0 to 7/500( SH:-Construction of R/wall in wire Crate at RD 1/032 to 1/035)							
Estimated Cost-98820/- Only. Earnest Money- 2000/- Only Time Limit: - One Month							
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.46 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	1607.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	39.75 cubic metre	Per cubic metre	2445.60	Rupees Two Thousand Four Hundred Forty Five and Paise Sixty Only	97213.00
					<b>Total:-</b>		<b>98820.00</b>
					<b>Select:-</b>		
					<b>Plus(+)</b>		( .....%)
					<b>Minus(-)</b>		( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

**Job.-26**

Estimated Cost:- 99900- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work: Restoration of Rain Damages on Various road under Baij koti Section Under Shillai Sub Division (SH:- Hiring of Excavator cum loader for removal of slips and drassing of road surface)Job-1

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - 27

Estimated Cost - 98698/- Only.  
Earned Money - 2000/- Only  
Limit - One Month

Name of work: Restoration of rain damages on link road to Village Juinal Km 0/0 to 2/500 (SH)-Construction of R/wall in RR Masonry at RD 0/710 to 0/714)


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Ninety Only	83914.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
				<b>Total:-</b>		<b>98698.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )

Name and full address of the contractor:-

Executive Engineer

Shillai Division

HP PWD Shillai



**SCHEDULE OF QUANTITY**

Job - 28

Estimated Cost:- 98698/- Only.  
Earnest Money:- 2000/- Only Time Limit: - One Month

Name of work:- Restoration of rain damages on link road to Village Junal Km 0/0 to 2/500 (SH:-Construction of R/wall in RR Masonry at RD 0/716 to 0/720)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Ninety Only	83914.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00		2528.00
				<b>Total:-</b>		<b>98698.00</b>
				<b>Select:-</b>		
						( .....%)
						( .....%)


Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job-29		Estimated Cost- 98255/- Only.				
Name of work:- Restoration of rain damages on Shilla Gundah road Km 0/0 to 33/500(SH)-Construction of Rwall in RR Masonry at RD 17/774 to 17/781)		Earnest Money:- 2000/- Only Time Limit - One Month				
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.02	Per cubic metre	322.20	Rupees Three Hundred Twenty Two and Paise Twenty Only	4195.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.70	Per cubic metre	4250.00	Rupees Four Thousand Two Hundred Fifty Only	11475.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	24,340	Per cubic metre	3250.50	Rupees Three Thousand Two Hundred Fifty and Paise Fifty Only	79117.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads and carriage of material as per the direction of the Engineer Incharge.	4.08	Per cubic metre	850.00	Rupees Eight Hundred Fifty Only	3468.00
				Total:-		98255.00
				Select:-		( .....% )
				Minus(-)		( .....% )

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - **30**

Estimated Cost:-94828/- Only.  
Earnest Money:- 2000/- Only Time  
Limit - One Month

Name of work:- Restoration of rain damages on Millah Digwa road Km 0/0 to 6/900(SH):-Construction of R/wall in PCC1:4:8 at RD 1/578 to 1/584)Under PDNA

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	11.37	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	3583.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	19.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	85129.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.22	Per cubic metre	800.00	Rupees Eight Hundred Only	1776.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	14.00	Each	310.00	Rupees Three Hundred Ten Only	4340.00
<b>Total:-</b>						<b>94828.00</b>
<b>Select:-</b>						<b>( .....%)</b>
<b>Minus(-)</b>						<b>( .....%)</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Name of work:- Restoration of Damages on Shillai Achhoti Pandiyat road Km 0/00 to 7/00(SH):-Construction of B/wall in RR Masonry at RD 0/105 to 0/109

Job.- 3/

Estimated Cost:- 99038/- Only.  
Earnest Money:- 2000/- Only  
Limit - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.04	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	2849.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge	2.50	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	11063.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3385.20	Rupees Three Thousand Three Hundred Eighty Five	82599.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.12	Per cubic metre	810.00	Rupees Eight Hundred Ten Only	2527.00
				<b>Select:-</b>	<b>Total:-</b>	<b>99038.00</b>
					Plus(+)	( .....% )
					Minus(-)	( .....% )

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages to Gwall Pashmi Manal Matiyana road Km 0/0 to 8/00(SH:-Construction of R/wall in RR Masonry at RD 2/280 to 2/284)

Job - 32  
Estimated Cost:- 98672/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.10 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4758.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.PCC 1:6:12(One cement: Six Sand: Twelve graded stone aggregate)40mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	13.68 cubic metre	Per cubic metre	3950.00	Rupees Three Thousand Nine Hundred Fifty Only	54036.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6)including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	13.880 cubic metre	Per cubic metre	2450.00	Rupees Two Thousand Four Hundred Fifty Only	34006.00
4	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.90 cubic metre	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	3081.00
5	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2791.00
				<b>Total:-</b>		<b>98672.00</b>
				<b>Select:-</b>		( .....%)
						( .....%)


Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Name of work:- Restoration of Damages on Bella Siyasu road Km 0/0 to 9/00 ( SH:-Construction of R/wall in wire Crate at RD 4/105 to 4/113		Job:- 33		Estimated Cost-99701/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	22.95	cubic metre	322.10	Rupees Three Hundred Twenty Two and Paise Ten Only	7392.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	35.10	cubic metre	2517.60	Rupees Two Thousand Five Hundred Seventeen and Paise Sixty Only	88368.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 500 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	4.95	cubic metre	796.15	Rupees Seven Hundred Ninety Six and Paise Fifteen Only	3941.00
				<b>Total:-</b>		<b>99701.00</b>
				<b>Select:-</b>		<b>( .....%)</b>
						<b>( .....%)</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

**Job - 34**

Estimated Cost:-99701/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of Damages on Bella Siyasu road Km 0/0 to 9/00 ( SH:-Construction of R/wall in wire Grate at RD 4/115 to 4/123

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	22.95	cubic metre	322.10	Rupees Three Hundred Twenty Two and Paise Ten Only	7392.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1.4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	35.10	Per cubic metre	2517.60	Rupees Two Thousand Five Hundred Seventeen and Paise Sixty Only	88368.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	4.95	Per cubic metre	796.15	Rupees Seven Hundred Ninety Six and Paise Fifteen Only	3941.00
				<b>Total:-</b>		<b>99701.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....%)
				<b>Minus(-)</b>		( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY		Job-35		Estimated Cost:-88534/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work:-Restoration of Rain damages on Kando Dugana to Shamah Pantia road KM 0/00 to 5/870(SH):-Construction of B/wall in PCC 1:4:8 at RD 0/630 to 0/638)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.80	Per cubic metre	298.45	Rupees Two Hundred Ninety Eight and Paise Forty Five Only	4119.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.54	Per cubic metre	4415.25	Rupees Four Thousand Four Hundred Fifteen and Paise Twenty Five Only	90689.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	14.00	Each Nos.	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	3726.00
				<b>Total:-</b>		<b>98534.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**


**Job.- 36**


Estimated Cost:- 98055- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work: Restoration of rain damages on Jakhana Shari Manpur road Km 0/0 to 7/500 (SH:- construction of earthen shoulder in Km 2/550 to 3/500 in patches)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Construction of Sub grade and earthen Shoulders with approved materials obtained from borrow pits with all liftand leads, transporting to site spearing , grading to required slope and compacted to meet requirement of table 300.2 with lead upto 1000m as per technical specification clause 303.1 including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	525.34 Square Metre	Per Square Metre	186.65	Rs. One hundred eighty Six & Sixty Five Paise only.	98055.00
				<b>Total:-</b>		<b>98055.00</b>
				Select:-	Plus(+) ( .....%)	( .....%)
					Minus(-) ( .....%)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillaj



SCHEDULE OF QUANTITY		Job - 37		Estimated Cost:-98019/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work:- Restoration of Damages on Koti Ultru road Km 0/0 to 6/00( SH:-Construction of R/wall in PCC 1:4:8 at RD 3/427 to 3/432)						
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.95	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4081.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	20.85	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Five Only	90708.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.49	Per cubic metre	799.00	Rupees Seven Hundred Ninety Nine Only	1990.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	4.00	Each	310.00	Rupees Three Hundred Ten Only	1240.00
				Total:-		98019.00
				Select:-		Plus(+) ( .....%)
						Minus(-) ( .....%)

Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

## SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.96 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4084.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.34 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10216.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.120 cubic metre	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty	81555.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00 Nos.	Each	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2791.00
				<b>Total:-</b>		<b>98646.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

*Forward*  
Executive Engineer  
Shillai Division  
HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of Damages on Link road Harijan Basti Kharech Km 0/0 to 2/00 (SH:-Construction of R/wall in PCC1:4:8 at RD 0762 to 0.766)

Job-39  
Estimated Cost:-99980/- Only.  
Earnest Money:- 2000/- Only  
Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.70 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4033.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	21.09 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	92071.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer incharge.	1.90 cubic metre	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	1481.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	9.00 Nos.	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2395.00
				<b>Total:-</b>		<b>99980.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....%)
				<b>Minus(-)</b>		( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai


**SCHEDULE OF QUANTITY**

Sr. No		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
1		Brick work with common burnt clay F.P.S. (nonmodular) brick of class designation 7.5 in foundation and plinth Cement mortar 1:4 (1 cement : 4 coarse sand including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts including all incidental charges. as per drawings and technical specifications clause	17.40	Per hour	5528.25	Rupees Five Thousand Five Hundred Twenty Eight and Paise Twenty Five Only	96192.00
					<b>Total:-</b>		<b>96192.00</b>
Select:-					Plus(+)	( .....%)	
					Minus(-)	( .....%)	

Job.- 40  
 Estimated Cost- 96192/- Only.  
 Earnest Money- 2000/- Only  
 Limit: - One Month

Name of work: Balance work on Govt.High School Sunog in Tehsil Paonta Sahib Distt. Sirmour H.P.(S.H):- Providing Brick work in Plinth

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai


**SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages on Naya Daya Kunhat road Km 0/0 to 6/900(SH:- Construction of R/wall in PCC 1:4:8 at RD 5/532 to 5/536)

Job - 4/1  
Estimated Cost:-98486/- Only.  
Earnest Money:- 2000/- Only Time Limit: - One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.68	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	4097.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.80	Per cubic metre	4415.60	Rupees Four Thousand Four Hundred Fifteen and Paise Sixty Only	91844.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.92	Per cubic metre	799.00	Rupees Seven Hundred Ninty Nine Only	1534.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	6.00	Each Nos.	299.50	Rupees Two Hundred Ninty Nine and Paise Fifty Only.	1797.00
<b>Total:-</b>						<b>99486.00</b>
<b>Select:-</b>				<b>Plus(+)</b>		<b>( .....% )</b>
				<b>Minus(-)</b>		<b>( .....% )</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Name of work:- Restoration of Damages on Link road Harijan Basti Kharech Km 0/0 to 2/00 (SH:-Construction of R/wall in PCC1:4:8 at RD 0767 to 0781)							
Job - 42 Estimated Cost:-99714/- Only. Earnest Money:- 2000/- Only Time Limit: - One Month							
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.70	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	4033.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- in- charge.	21.09	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	92071.00
3		Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	1.90	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	1481.00
4		Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	8.00	Each	266.15	Rupees Two Hundred Sixty Six and Paise Fifteen Only	2129.00
					<b>Total:-</b>		<b>99714.00</b>
					<b>Select:-</b>		<b>( .....%)</b>
							<b>( .....%)</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

Job - 43

Estimated Cost:-98840/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

## SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kando to Senga road Km 0/0 to 3/500(SH):-Construction of R/wall in PCC 1:4:8 at RD 1/900 to 1/906)

## Sub-Head and item of work

Sr. No.	Quantity	Unit	Figures	Rate in		Amount
				Words	Amount	
1	6.84 cubic metre	Per cubic metre	300.00	Rupees Three Hundred only		2052.00
2	21.36 cubic metre	Per cubic metre	4300.00	Rupees Four Thousand Three Hundred Only		91848.00
3	3.30 cubic metre	Per cubic metre	800.00	Rupees Eight Hundred Only		2640.00
4	12.00 Nos.	Each	275.00	Rupees Two Hundred Seventy Five Only		3300.00
Total:-						99840.00
Select:-						( .....% )
						( .....% )

Name and full address of the contractor:-

*Shillai*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

SCHEDULE OF QUANTITY		Job.-44		Estimated Cost:- 99900.- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work: Restoration of Rain Damages on Renuka Sataun road Km 13/0 to 29/160 (SH):- Hiring of Excavator cum loader for removal of slips from Various RDs in Kn 16/500 to 20/00)						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....% )
					Minus(-)	( .....% )

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - 45

Estimated Cost:-99082/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages on Rast Manal Chunoti road Km 0/0 to 15/135(SH)-Construction of R/wall in PCC 1:4:8 at RD 0/756 to 0/760) Under PDNA

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1.	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	18.90 cubic metre	Per cubic metre	290.15	Rupees Two Hundred Ninety and Paise Fifteen Only	5484.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.51 cubic metre	Per cubic metre	4320.90	Rupees Four Thousand Three Hundred Twenty and Paise Ninety Only	88622.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer incharge.	4.05 cubic metre	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	3200.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	7.00 Nos.	Each	253.70	Rupees Two Hundred Fifty Three and Paise Seventy Only	1776.00
				<b>Total:-</b>		<b>99082.00</b>
				<b>Select:-</b>		<b>( .....%)</b>
						<b>( .....%)</b>

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**


Job - 46

Estimated Cost:-99082/- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work:- Restoration of rain damages on Rast Manal Chunoti road Km 0/0 to 15/135(SH):-Construction of R/wall in PCC 1:4:8 at RD 0/750 to 0/754) under PDNA.

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	18.90	Per cubic metre	290.15	Rupees Two Hundred Ninety and Paise Fifteen Only	5484.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.51	Per cubic metre	4320.90	Rupees Four Thousand Three Hundred Twenty and Paise Ninety Only	88622.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts and carriage of material as per the direction of the Engineer Incharge.	4.05	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	3200.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	7.00	Each Nos.	253.70	Rupees Two Hundred Fifty Three and Paise Seventy Only	1776.00
				<b>Total:-</b>		<b>99082.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job.- 47

Estimated Cost:-99104/- Only.  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work:-Restoration of rain damages Nanidhar Shakholi Rast road Km 0/0 to 8/00 (SH:-Construction of R/wall in RR Masonry at RD 5/862 to 5/869) under PDNA.

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	21.42 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	6643.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-In-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	23.100 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	77505.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	13.00 Nos.	Each	299.30	Rupees Two Hundred Ninety Nine and Paise Thirty Only	3891.00
				<b>Total:-</b>		<b>97420.00</b>
				<b>Select:-</b>		<b>( .....%)</b>
						<b>( .....%)</b>

Name and full address of the contractor:-

*(Signature)*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - **48**

Estimated Cost:-98115/- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work:-Restoration of rain damages Nanidhar Shakholi Rast road Km 0/0 to 8/00 (SH:-Construction of R/wall in RR Masonry at RD 3/150 to 3/157) Under PDNA.

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	22.05 cubic metre	Per cubic metre	294.34	Rupees Two Hundred Ninety Four and Paise Thirty Four Only	6490.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge.	1.82 cubic metre	Per cubic metre	4415.30	Rupees Four Thousand Four Hundred Fifteen and Paise Thirty Only	8035.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	23.100 cubic metre	Per cubic metre	3450.14	Rupees Three Thousand Four Hundred Fifty and	79698.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	13.00 Nos.	Each	299.30	Rupees Two Hundred Ninety Nine and Paise Thirty Only	3891.00
				<b>Total:-</b>		<b>98115.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )

Name and full address of the contractor:-

Executive Engineer  
Shillai Division  
HP PWD Shillai


**SCHEDULE OF QUANTITY**


Name of work:-AVR & M/O LPRR road Km 97/00 to 112/167 (Sh:- Providing and erecting street light mounted on a steel circular hollow pole Between Km 107/020 to 107/500)

Job.- 419  
Estimated Cost:- 99100/- Only.  
Earnest Money:- 2000/- Only  
Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation for structure as per drawing and technical specification clause 3:35.1 including cutting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metres dressing of sides and bottom and back filling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.38 cubic metre	Per cubic metre	290.06	Rupees Two Hundred Ninety and Paise Six Only	980.00
2	Providing and laying plain cement concrete 1-24 and curing completed including the cow of form work for plain/remforced concrete complete as per the technical specifications etc including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	3.38 cubic metre	Per cubic metre	6200.00	Rupees Six Thousand Two Hundred Only	20956.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	4.000 cubic metre	Per cubic metre	19290.90	Rupees Nineteen Thousand Two Hundred Ninety and Paise Ninety Only	77164.00
<b>Total:-</b>						<b>99100.00</b>
<b>Select:-</b>				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

  
AE

  
Executive Engineer  
Shillai Division  
HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - **50**  
 Estimated Cost:-99104/- Only.  
 Earnest Money:- 2000/- Only Time  
 Limit: - One Month

Name of work:-Restoration of rain damages on LPRR Road Km 97/0 to 11167 (SH)-Construction of R/wall in RR Masonry at RD 107/850 to 107/854 )  
 Under PANNA

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	10.58	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	3281.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.12	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
				<b>Total:-</b>		<b>99104.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....%)
					<b>Minus(-)</b>	( .....%)

Name and full address of the contractor:-

*Shillai*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job- 51

Estimated Cost:-98698/- Only.  
Earnest Money:- 2000/- Only Time  
Limit - One Month

Name of work:-Restoration of rain damages on LPRR Road Km 97/0 to 112/167 (SH:-Construction of R/wall in RR Masonry at RD 109/706 to 109/710 )  
Under P D N A -

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Paise Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6),including carriage of materials in all leads and lifts as per the dirction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Ninety Only	83914.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3:8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.20 cubic metre	Per cubic metre	790.00	Rupees Seven Hundred Ninety Only	2528.00
				<b>Total:-</b>		<b>98698.00</b>
<b>Select:-</b>				<b>Plus(+)</b>	( .....%)	
				<b>Minus(-)</b>	( .....%)	

Name and full address of the contractor:-

*(Signature)*  
Executive Engineer  
Shillai Division  
HP PWD Shillai

Job - 52  
 Estimated Cost:- 98698/- Only.  
 Earnest Money:- 2000/- Only Time Limit:- One Month

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27 cubic metre	Per cubic metre	310.15	Rupees Three Hundred Ten and Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge	2.12 cubic metre	Per cubic metre	4425.20	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	9381.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010 cubic metre	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and Ninty Only	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.20 Nos.	Each	790.00	Rupees Seven Hundred Ninty Only	2528.00
Total:-						98698.00
Select:-				Plus(+)	( .....%)	
				Minus(-)	( .....%)	

Name and full address of the contractor:-

*Shillai*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job.-53

Estimated Cost:- 99900- Only,  
Earnest Money:- 2000/- Only Time  
Limit: - One Month

Name of work: Restoration of rain damages to Manal kanti mashwa road km 0/00 to 13/350 (SH:- Hiring of excavator cum loader for removal of slips at various RD's between km. 0/00 to 6/0)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, disel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				Select:-	Total:-	99900.00
					Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

SCHEDULE OF QUANTITY		Job.-54		Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Time Limit: - One Month		
Name of work: Restoration of rain damages to Bharli banour road km 0/0 to 13/355(SH):- Hiring of excavator cum loader for removal of slips at various RD's between km. 0/0 to 4/500						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+) Minus(-)	( .....% ) ( .....% )

Name and full address of the contractor:-

  
Executive Engineer  
B & R Division  
HP PWD Shillai


### SCHEDULE OF QUANTITY

Job. - 55  
 Estimated Cost:- 99900- Only.  
 Earnest Money:- 2000/- Only Time  
 Limit: - One Month

Name of work: Restoration of rain damages Ranuka Sataun road km 13/450 to 29/400 (SH:- Hiring of excavator cum loader for removal of slips at various RD's between km. 25/0 to 29/00)

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge. Crawling one side shall be paid to the contractor.	111.00 Hours	Per hour	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)


Name and full address of the contractor:-

  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

		Job.- 56		Estimated Cost:- 99900- Only. Earnest Money:- 2000/- Only Limit: - One Month Time		
Name of work: Restoration of rain damages to Chandani to Kathwar road km 0/00 to 13/500 (SH:- Hiring of excavator cum loader for removal of slips at various RD's between km. 0/00 to 10/500)						
Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris and dressing of berms with a minimum capacity of 28.00 cum ( Sixty Cubic metre) per hours including cost of Services of operating staff, cost of lubrication oil, diesel/petrol Kerosene oil, other consumables for running the machinery and all the taxes. including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORT specification and the direction of Engineer-in Charge.Crawling one side shall be paid to the contractor.	111.00	Per hour Hours	900.00	Rs. Nine hundred & Nil Paise only.	99900.00
				<b>Total:-</b>		<b>99900.00</b>
				Select:-	Plus(+)	( .....%)
					Minus(-)	( .....%)

Name and full address of the contractor:-


  
 Executive Engineer  
 B & R Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - **57**  
 Estimated Cost:- 98698/- Only.  
 Earnest Money:- 2000/- Only  
 Limit: - One Month

Name of work:- Restoration of rain damages to Gangtoil to Bambal road Km 0/0 to 4/500(SH):-Construction of B/wall in RR Masonry at RD 3/705 to 3/709)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	9.27	Per cubic metre	310.15	Rupees Three Hundred Ten and Fifteen Only	2875.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-Charge.	20.76	Per cubic metre	4365.60	Rupees Four Thousand Four Hundred Twenty Five and Paise Twenty Only	90630.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	25.010	Per cubic metre	3355.20	Rupees Three Thousand Three Hundred Fifty Five and	83914.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	3.20	Each Nos.	790.00	Rupees Seven Hundred Ninty Only	2528.00
				<b>Total:-</b>		<b>98698.00</b>
				<b>Select:-</b>	<b>Plus(+)</b>	( .....% )
					<b>Minus(-)</b>	( .....% )

Name and full address of the contractor:-  
  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job - **58**  
 Estimated Cost:- 99849/- Only.  
 Earnest Money:- 2000/- Only  
 Limit: - One Month

Name of work:- Restoration of rain damages on Jakhana Shari Manpur road Km 0/0 to 7/750(SH):-Construction of R/wall in R/R Masonry at RD 3/338to 3/342)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.28	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3909.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In-charge.	2.50	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24.400	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	82501.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.24	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2525.00
				<b>Total:-</b>		<b>99849.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....%)
				<b>Minus(-)</b>		( .....%)

Name and full address of the contractor:-

Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Name of work:- Restoration of rain damages on Jakhana Sharli Manpur road Km 0/0 to 7/750(SH):-Construction of R/wall in R/R Masonry at RD 3/344 to 3/348)							
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	13.28 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3909.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1-4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer- In- charge.	2.50 cubic metre	Per cubic metre	4365.60	Rupees Four Thousand Three Hundred Sixty Five and Paise Sixty Only	10914.00
3		Stone masonry in cement mortar for substructure complete as per drawing & technical specification clauses 702,704,1202 and 1204 random rubble masonry (2nd Sort) in cement mortar 1:6).including carriage of materials in all leads and lifts as per the direction of the Engineer-in-Charge.	24,400 cubic metre	Per cubic metre	3381.20	Rupees Three Thousand Three Hundred Eighty One and Paise Twenty Only	82501.00
3		Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	3.28 cubic metre	Per cubic metre	779.40	Rupees Seven Hundred Seventy Nine and Paise Forty Only	2556.00
<b>Total:-</b>							<b>99880.00</b>
<b>Select:-</b>							( .....% )
							( .....% )

Name and full address of the contractor:-

Executive Engineer  
Shillai Division  
HP PWD Shillai



**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Name of work:- Restoration of rain damages on Sharli Manpur to Kumli Raod Km 0/0 to 7/700(SH:-Construction of R/wall in PCC 1:4:8 at RD 5/300 to 5/308)							
Job:- 60							
Estimated Cost:-98427/- Only. Earnest Money:- 2000/- Only Time Limit - One Month							
1		Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.95 cubic metre	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3812.00
2		Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.85 cubic metre	Per cubic metre	4385.60	Rupees Four Thousand Three Hundred Eighty Five and Paise Sixty Only	91440.00
3		Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 600 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.49 cubic metre	Per cubic metre	815.40	Rupees Eight Hundred Fifteen and Paise Forty Only	2030.00
4		Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	4.00 Nos.	Each	286.15	Rupees Two Hundred Eighty Six and Paise Fifteen Only	1145.00
					<b>Total:-</b>		<b>98427.00</b>
					<b>Select:-</b>		<b>( .....%)</b>
					<b>Minus(-)</b>		<b>( .....%)</b>

Name and full address of the contractor:-

Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Job.- 61

Estimated Cost:-98999/- Only.  
Earnest Money:- 2000/- Only  
Limit: - One Month

Name of work:-Restoration of rain damages on Sharli Manpur to Kumli Raod Km 0/0 to 7/700(SH:-Construction of R/wall in PCC 1:4:8 at RD 5/308 to 5/312)

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	12.95	Per cubic metre	294.35	Rupees Two Hundred Ninety Four and Paise Thirty Five Only	3812.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.85	Per cubic metre	4385.60	Rupees Four Thousand Three Hundred Eighty Five and Paise Sixty Only	91440.00
3	Providing and laying filter media with granular crushed aggregates as per specifications to a thickness of not less than 500 ( Six hundred) millimetre with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 (One thousand two hundred four point three point eight) within all leads lifts.and carriage of material as per the direction of the Engineer Incharge.	2.49	Per cubic metre	815.40	Rupees Eight Hundred Fifteen and Paise Forty Only	2030.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	6.00	Each Nos.	286.15	Rupees Two Hundred Eighty Six and Paise Fifteen Only	1717.00
				<b>Total:-</b>		<b>98999.00</b>
				<b>Select:-</b>		( .....% )
						( .....% )

Name and full address of the contractor:-

Executive Engineer  
Shillai Division  
HP PWD Shillai



**SCHEDULE OF QUANTITY**

Job.- 62		Estimated Cost:-97311/- Only.				
Name of work:-Restoration of rain damages on Kando Dugana to Shamah Pamta road Km 0/0 to 5/870(SH):-Construction of B/wall in PCC 1:4:8 at RD 3/295 to 3/300)		Earnest Money:- 2000/- Only Time Limit: - One Month				
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	16.51	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	5202.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.03	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	87141.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	16.00	Each Nos.	310.50	Rupees Three Hundred Ten and Paise Fifty Only	4968.00
				<b>Total:-</b>		<b>97311.00</b>
				<b>Select:-</b>		
				<b>Plus(+)</b>		( .....%)
				<b>Minus(-)</b>		( .....%)


Name and full address of the contractor:-

*Shillai*  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai

**SCHEDULE OF QUANTITY**

Sr. No.		Sub-Head and item of work	Quantity	Unit	Rate in		Amount
					Figures	Words	
Job - <b>63</b>		Estimated Cost-97311/- Only.					
Name of work:- Restoration of rain damages on Kando Dugana to Shamah Pamia road Km 0/0 to 5/870(SH)-Construction of B/wall in PCC 1:4:8 at RD 3/288 to 3/293)		Earnest Money:- 2000/- Only Time Limit: - One Month					
1	Earthwork in excavation in all heights and depths in all kinds of soils for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal all leads dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	16.51 cubic metre	Per cubic metre	315.10	Rupees Three Hundred Fifteen and Paise Ten Only	5202.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clauses 802,803,1202 and 1203.1:4:8 (One cement: Four Sand:Eight graded stone aggregate)25mm nominal size including carriage of material in all leads and lifts as per the direction of the Engineer-in-charge.	20.03 cubic metre	Per cubic metre	4350.50	Rupees Four Thousand Three Hundred Fifty and Paise Fifty Only	87141.00	
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7.including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge	16.00 Nos.	Each	310.50	Rupees Three Hundred Ten and Paise Fifty Only	4968.00	
				<b>Total:-</b>		<b>97311.00</b>	
				<b>Select:-</b>		( .....%)	
						( .....%)	

Name and full address of the contractor:-

  
 Executive Engineer  
 Shillai Division  
 HP PWD Shillai