

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2025/ 10720-50

Dated/ 17-10-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter NO. PBW (B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2025/-10720- 50 Dated 17-10-2025
are urgent in nature and in public interest.

Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **27.10.2025** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 25.10.2025 up to 4.00 P.M and the application for issue of tender form shall be received 24.10.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	A/R & M/O Dharer Rajnali Bhagotla road KM 0/00 to 5/00 (SH:- Removing of slips & Clearance of drain from RD 0/00 to 5/00)	Rs. 98,900.00	Rs. 2,000.00	Two Month
2	A/R & M/O Parour Lahla Gopalpur Rakh Sukeri Kandi Bandla Palampur road KM 0/00 to 31/00 (SW:- Removing of slips & clearance of drain from RD 17/00 to 31/00)	Rs. 98,900.00	Rs. 2,000.00	Two Month
3	C/o office of Assistant Director Animal Husbandary Sperm Station Palampur (SW:- C/o Chamber and Sewer line etc (Deposit)	Rs. 99,750.00	Rs.2,000.00	Two Month
4	Restoration of damages to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna (SW:- C/o U-shape drain along with grating work from RD 1/320 to 1/339.00) (JSV Deposit)	Rs. 99,815.00	Rs. 2,000.00	Three Month
5	Restoration of damages to digging of road trenches for laying of water Supply pipe line from Palampur Neugal Park to Lohna (SW:- C/o U-shape drain alongwith grating work from RD 1/339 to 1/358) (JSV Deposit)	Rs. 99,815.00	Rs. 2000.00	Three Month
6	Restoration of damages to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna (SW:- C/o U-shape drain cum Edge wall from RD 1/410 to 1/512 (JSV Deposit)	Rs. 99,909.00	Rs. 2000.00	Three Month
7	C/o link road Gehar Spedu Kandwari Rajehar KM 0/00 to 4/650 i/c 19.25 mtrs Span bridge over Pun Khad (SW:- C/o unlined drain and earthen shoulders at RD 0/500 to 1/00 (Under Nabard)	Rs. 99,441.00	Rs. 2,000.00	Three Months
8	C/o link road Gehar Spedu Kandwari Rajehar KM 0/00 to 4/650 i/c 19.25 mtrs Span bridge over Pun Khad (SW:- C/o unlined drain and earthen shoulders at RD 0/00 to 0/500(Under Nabard)	Rs. 99,395.00	Rs. 2000.00	Three Month
9	Up-gradation of Kulani Chandpur Bharmat Colony Kamakhya Mandir via Holta Patti Simblu road Km 0/00 to 9/300 (SW:- C/o Unlined drain and Earthen shoulders at RD 3/500 to 4/00 (Under Nabard)	Rs. 99,472.00	Rs. 2,000.00	Three Months
10	Up-gradation of Kulani Chandpur Bharmat Colony Kamakhya Mandir via Holta Patti Simblu road Km 0/00 to 9/300 (SW:- C/o Unlined drain and Earthen shoulders at RD 4/100 to 4/550 (Under Nabard)	Rs. 99,658.00	Rs. 2,000.00	Three Months

11	C/o link road Chowan to Goart Km 0/00 to 0/700 (SW:- Hiring of JCVB for preparing of Earthen shoulders)	Rs. 98,900.00	Rs. 2,000.00	Three Months
12	R/D on link road from GMS Dharot to Harizan Basti via Hari Ram House in GP Lahla KM 0/00 to 1/00 (SW:- P/L CC Pavement at RD 0/00 to 0/020 and 0/054 to 0/069)	Rs. 99,225.00	Rs. 2,000.00	Three Months
13	Augmentation of Imp of water Supply scheme Chandpur Langha Kullani Km 0/00 to 5/00 (SW:- Removal of slips, maintenance of Earthen shoulders at RD 3/00 to 3/400)	Rs. 95,041.00	Rs. 2,000.00	Three Months
14	A/R & M/O various roads under Kandwari section Sub-Division Palampur (SW:- Hiring of JCB & unlined surface drain at various RDs)	Rs. 99,422.00	Rs. 2,000.00	Three Months
15	Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road KM 33/00 to 40/500 (SW:- 1.00 mtrs span culvert at RD 37/765)	Rs. 99,578.00	Rs. 2,000.00	Three Months
16	Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road KM 33/00 to 40/500 (SW:- 1.00 mtrs span culvert at RD 37/765) (Rajpur side)	Rs. 99,971.00	Rs. 2,000.00	Three Months
17	Restoration of rain damages on Bandla Ghuggar Thakurdwara road Km 0/000 to 6/000 (SW:- C/o R/Wall from RD 2/105 to 2/111)	Rs. 71,638.00	Rs. 1,500.00	Three Months
18	Balance work of main road on Tanda to SCVB Degree College (SW:- P/L Interlocking concrete blocks at RD 4/200 to 4/225)	Rs. 99,714.00	Rs. 2,000.00	Three Months
19	R/Wall to protect the land of Sh. Mool Chand Rana Deot Basti Chandropa (SW:- C/o R/Wall)	Rs. 99,174.00	Rs. 2,000.00	Three Months
20	C/o Cow Shed at Kudan Dehal PO Jia Tehsil Palampur Distt. Kangra (SW:- C/o U-shape drain and Edge wall behind Tudi Store along with Grating (Deposit)	Rs. 99,117.00	Rs. 2,000.00	Three Months
21	C/o Additional Accommodation GSSS at Kandwari Tehsil Palampur Distt Kangra (HP) (SW:- Railing work etc) (Deposit)	Rs. 53,489.00	Rs. 1,100.00	Three Months
22	R/D on Parour Lahla Gopalpur Rakh Sukeri Kandi Bandla Palampur road KM 0/00 to 33/00 (SH:- C/o R/Wall at RD 11/550 to 11/557)	Rs. 99,379.00	Rs. 2,000.00	Two Months
23	R/D on Chachian Khas to Rakh road Km 0/00 to 3/00 (SW:- C/o R/Wall at RD 2/190 to 2/195)	Rs. 97,827.00	Rs. 2,000.00	Two Months
24	R/D on Chachian Khas to Rakh road Km 0/00 to 3/00 (SW:- C/o R/Wall at RD 2/197 to 2/202)	Rs. 97,827.00	Rs. 2,000.00	Two Months
25	A/R & M/O various road under Ghar Section Sub-Division Palampur (SW:- Drain, maintenance of Earthen shoulders etc)	Rs. 98,860.00	Rs. 2,000.00	Three Months
26	A/R and M/o various roads under Ghar section Sub-division Palampur (SW:- Drain, Edge wall etc)	Rs. 98,628.00	Rs. 2,000.00	Three Months
27	C/o R/Wall to protect the land of Sanjay Kumar S/o Kalu Ram Khayan Patt (SW:- C/o R/Wall etc)	Rs. 98,802.00	Rs. 2,000.00	Three Months
28	C/o Jeepable road main road towards the house of Sh. Thakur Dass via Smt. Rampyari House 4 Mohal Kaloond (SH:- P/L Interlocking Tiles at RD 0/00 to 0/031 (Deposit 1.00 lacs)	Rs. 99,905.00	Rs. 2,000.00	Two Months
29	Fencing of Indunag Rakh Mahila Mandal Bhawan Kaloond (SW:- C/o R/Wall for protection of grounds) (VKVNY deposit)	Rs. 99,536.00	Rs. 2,000.00	Two Months
30	Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/000 to 40/500 (SW:- C/o V-Shape drain & Edge wall at RD 37/820 to 37/832) (Under SDRF)	Rs. 97,417.00	Rs. 2,000.00	Three Months

31	Restoration of Rain damages on link road to village Fotta Km 0/00 to 1/500 (SW:- Providing and laying G-II and CC Pavement in Km 0/200 to 0/233)	Rs. 99,630.00	Rs. 2,000.00	Two Months
32	Crossing of Water Pipe line under Palampur Sub-Division (SW:- Balance work of C/o 6.00 mtrs Span RCC slab and Pulli over drain) (IPH Deposit)	Rs. 99,836.00	Rs. 2,000.00	Three Months
33	Crossing of Water Pipe line under Palampur Sub-Division (SW:- Balance work of C/o 6.00 mtrs Span RCC slab and Pulli over drain) (IPH Deposit)	Rs. 81,028.00	Rs. 1,700.00	Three Months
34	R/D on Neugal Bridge to Latwala road KM 0/00 to 5/00 (SW:- C/o R/Wall at RD 1/980 to 1/989 (Deposit)	Rs. 99,858.00	Rs. 2,000.00	Two Months
35	R/D on Neugal Bridge to Latwala road KM 0/00 to 5/00 (SW:- C/o R/Wall at RD 1/968 to 1/975 (Deposit)	Rs. 99,701.00	Rs. 2,000.00	Two Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Dharer Rajnali Bhagotla road Km 0/00 to 5/00. (SH:- Removing of slips & clearance of drain from Rd 0/00 to 5/00).					Estimated cost Rs.	
					Earnest Money Rs.	
					Time Limits	
Sr. No.	Description of Item	Quantity	In Figures	Rate	Unit	Amount
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
					Total	


 Executive Engineer
 Palampur Division
 HP PWD Palampur

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:- A/R & M/O Parour Lahia Gopalpur Rakh Sukeri Kandi Bandla Palampur road Km 0/00 to 31/00. (SH:- Removing of slips & clearance of drain from Rd 17/00 to 31/00).						
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Hiring of JCB (Excavator-Cum-Loader) including P.O.L. charges shifting charges and other ancillary equipments as per required at site of work for removal of slips. The disposal of this un-serviceable material has to be done in the required width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per ministry of Transport as per instructions of the Engineer-In-Charge including all leads and lifts.	86.00			Per Hour	
						Total
						Two Months
						98900.00
						2000.00


 Executive Engineer
 Palampur Division
 H.P. PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- C/o office of Assistant Director Animal Husbandary sperm station Palampur, (SH:- C/o Chamber and sewer line etc.). Deposit				Estimated cost Rs.		99750.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr No.	Description of item	Quantity	In Figures	Rate		Amount
				In Word	Unit	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification of clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	80.00			Per cubic metre	
2	Constructing masonry Chamber With common burnt clay F.P.S (non modular) bricks of class designation 7.5 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 12.4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	6.00			Each	
3	Providing and fixing 110 mm Coupler on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	100.00			Each	
4	Providing and fixing 15 mm nominal outer dia Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plan & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	70.00			Per Running Metre	
	Total					


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Work :- Restoration of damages to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna
(S. W. :- C/O U-shape drain along with grating work from RD 1/320 to 1/330.00 (J.S.V. Deposit))

Work No. 4

Estimated Cost :- Rs. 99,815/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	7.41	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	4.32	Cubic metre			Per Cubic metre	
3	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	841.70	Kilogram me			Per Kilogram me	
					Total:-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work :- Restoration of damages to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna
W :- C/O U-shape drain along with grating work from RD 1/339 to 1/358 (JSV Deposit)

Work No. 15

Estimated Cost :- Rs. 99,815/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words				
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	7.41	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	4.32	Cubic metre			Per Cubic metre	
3	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	841.70	Kilogram me			Per Kilogram me	
						Total:-	

Executive Engineer,
Palampur Division,
HPWD Palampur

Schedule of Quantity

Work :- Restoration of damages to digging of road trenches for laying of water supply pipe line from Palampur Neugal Park to Lohna
(S.W. :- C/O U-shape drain cum Edge wall from RD 1/410 to 1/512 (JSV Deposit)

Work No. **6**

Estimated Cost :- Rs. 99,909/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	22.95			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	19.89			Per Cubic metre	
				Total:-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Name of Work :- C/O link road Gehar Spedu Kandwari Rajehar Km. 0/00 to 4/650 i/c 19.25 mtr. Span bridge over Pun Khad
(S. W. :- C/O unlined drain and earthen shoulders at Rd 0/500 to 1/00 ~~Under Nabad~~)

Work No. 57

Estimated Cost :- Rs.99,441/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m. (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	394.50			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	1292.80			Per Square metre	
				Total:-		

 Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work :- C/O link road Gehar Spedu Kandwari Rajehar Km. 0/00 to 4/650 i/c 19.25 mtr. Span bridge over Pun Khad
 :- C/O unlined drain and earthen shoulders at Rd 0/00 to 0/500 Under Retention

Work No. 8

Estimated Cost :- Rs.99,395/-

Earnest Money :- Rs.2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m. (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	394.50	Running metre			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	1292.00	Square metre			Per Square metre	
						Total:-	

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

Schedule of Quantity

Work :- Upgradation of Kulani Chandpur Bharmat Colony Kamakhya Mandir via Holta Patti Simblu road Km. 0/00 to 9/300

W. :- C/O unlined drain and earthen shoulders at Rd 3/500 to 4/00 Under Nabad

Work No. 9

Estimated Cost :- Rs.99,472/-

Earnest Money :- Rs.2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m. (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	395.00			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	1292.80			Per Square metre	
				Total:-		

Executive Engineer,
Palampur Division,
HPPWD Palampur

Work No. 10

Estimated Cost :- Rs.99,658/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

Schedule of Quantity
Work :- Upgradation of Kulani Chandpur Bhamat Colony Kamakhya Mandir via Holta Patti Simblu road Km. 0/00 to 9/300
W. :- C/O unlined drain and earthen shoulders at Rd 4/100 to 4/550 (Nabore)

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m. (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	395.00	Running metre			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	1296.00	Square metre			Per Square metre	
					Total:-		

Executive Engineer,
Palampur Division,
HPPWD Palampur


Schedule of Quantity

Particulars of Work :- C/o link road Chowan to Goart Km. 0/00 to 0/700

Estimate Cost :- Rs. 98,900/-
Earnest Money :- Rs. 2000/-
Time Limit :- Two months

Sub Work : -(Hiring of JCB for preparing of earthen shoulder)


S. No	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In Words		Rupees
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of work for removal of slips.The disposal of this un-serviceable material has to be done in the aquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transporty as per instructions of the Engineer-in -Charge including all leads and lifts of material.	86.00				Per /Hour	
Total :-							


Executive Engineer,
Palampur Division,
HPPWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on link road from GMS Dharot to Harizan Basti via Hari Ram House in G.P. Lahla Km 0/00 to 1/00.
(SH:- P/L C.C. Pavement at Rd 0/00 to 0/020 & 0/054 to 0/069).

SCHEDULE OF QUANTITIES							Estimated cost Rs.	99225.00			
Name of work:- R/D on link road from GMS Dharot to Harizan Basti via Hari Ram House in G.P. Lahla Km 0/00 to 1/00. (SH :- P/L C.C. Pavement at Rd 0/00 to 0/020 & 0/054 to 0/069).							Earnest Money Rs.		2000.00		
							Time Limits		Unit		Amount
							Rate		In Word		
Sr No.	Description of Item	Quantity	In Figures			Per cubic metre.					
1	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.75									


 Executive Engineer
 Palampur Division
 H.P. PWD Palampur

Schedule of Quantity

Work :- Augumentation of Imp. of water Supply Scheme Chandpur langha kulani Km 0/0 to 5/0
 :- Removal of slips, maintenance of earthen shoulders etc. at RD 3/0 to 3/400

Work No. 13

Estimated Cost :- Rs.95,041/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	357.00	Running metre			Per Running metre	
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	768.90	Square metre			Per Square metre	
3	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift up to 1.5m and lead up to 1000m as per technical specification 302.3.5 and 1611 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	232.81	Cubic metre			Per Cubic metre	
						Total:-	

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

Schedule of Quantity

name of Work :- A/R & M/O various roads under Kandwari section Sub- Division Palampur

Sub Work : - Hiring of JCB & Unlined,drain^{Surface} at various Rds

Estimate Cost :- Rs 99,422/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Hiring of J.C.B.(Excavator -Cum -Loader) including P.O.L. charges,shifting charges and other ancillary equipments as required at site of work for removal of slips.The disposal of this un-serviceable material has to be done in the aquired width of the road to avoid damages to the properties of the people or in case any damage took place, the contractor is liable for it. The work shall have to be carried out as per Ministry of Transporay as per instructions of the Engineer-in -Charge including all leads and lifts of material.	43.00			Per /Hour	
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines,grades,levels and dimensions.Excavated material to be used in embankment with a lift upto 3m and lead of 50m.(average lead 25 m)as per Technical Specification Clause 307. Manual means,as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	806.00			Per Running metre	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work No. **15**

Work :- Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road km. 33/000 to 40/500
W. :- 1.00 mtr. Span culvert at RD.37765

Estimated Cost :- Rs. 99,578/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	22.86	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	1.44	Cubic metre			Per Cubic metre	
3	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	10.76	Cubic metre			Per cubic metre	
4	Providing and laying Reinforced cement concrete in 1:1.5:3 (one cement : one point five coarse sand : three graded crushed stone aggregate) 20 mm nominal size so as to obtain minimum crushing strength of R.C.C. grade M-25 (M-Twenty Five) and curing complete excluding cost of reinforcement for reinforced concrete work in foundations and plinth as per drawings and technical specifications Clauses 802,803,1202 and 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	1.36	Cubic metres			Per Cubic metre	
5	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix up to all height R.C.C grade M 20 (M-Twenty) in sub structure as per drawing and Technical Specifications Clause 802,804, 805,806,807,1202 &1204 including carriage of materials within all leads and lift and other incidentals.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.43	Cubic metre			Per Cubic metre	
6	Supplying,fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202.as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	157.73	Kilogram			Per Kilogram	
					Total:-		


Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Work :- Restoration of OFC damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road km. 33/000 to 40/500
 V :- 1.00 mtr. Span culvert at RD.37/765 (Rajpur side)

Work No.

Estimated Cost :- Rs. 99,971/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	22.86	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	1.44	Cubic metre			Per Cubic metre	
3	Providing plain/ reinforced Cement concrete in Sub Structure 1:2.5:5 (1 Cement : 2.5 sand : 5 crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-fifteen) complete as per drawings and technical specifications Claus 802,804,805,806,807,1202 and 1204 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	10.76	Cubic metre			Per cubic metre	
4	Providing and laying Reinforced cement concrete in 1:1.5:3 (one cement : one point five coarse sand : three graded crushed stone aggregate) 20 mm nominal size so as to obtain minimum crushing strength of R.C.C. grade M-25 (M-Twenty Five) and curing complete excluding cost of reinforcement for reinforced concrete work in foundations and plinth as per drawings and technical specifications Clauses 802,803,1202 and 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	1.36	Cubic metres			Per Cubic metre	
5	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix up to all height R.C.C grade M 20 (M-Twenty) in sub structure as per drawing and Technical Specifications Clause 802,804, 805,806,807,1202 & 1204 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	0.43	Cubic metre			Per Cubic metre	
6	Supplying, fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002,1010 and 1202 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	158.58	Kilogram			Per Kilogram	
	Total:-						

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

Schedule of Quantity

Restoration of rain damages on Bandla Ghuggar Thakurdwara road km. 0/000 to 6/000
R/Wall from RD. 2/105 to 2/111

Work No.

Estimated Cost :- Rs. 71,638/-

Earnest Money :- Rs. 1500/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	6.12	Cubic metre			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specifications section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	15.15	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	4.00	Nos.			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	5.44	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer-in-charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	64.70			Per square metre	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix P.C.C. grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	2.25			Per Cubic metre	
3	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per Direction of Engineer-in-charge i/c carriage of materials within all leads, lifts and other incidentals by Manual Means. The rates are inclusive octroi, royalty, Malkana, toll tax, toll tax or any other taxes imposed by the Government.	1.21			Per Cubic metre.	
					Total:-	

Executive Engineer,
 Palampur Division,
 HPPWD Palampur

Schedule of Quantity

Name of Work :- R/Wall to protect the land of Sh. Mool Chand Rana Deotbasti Chandropa

(S. W. :- C/O R/Wall

Work No. 19

Estimated Cost :- Rs. 99,174/-

Earnest Money : 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	8.62			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	22.00			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	8.00			Each	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

20

SCHEDULE OF QUANTITY

Name of work:- C/o Cow Shed at Kudan Dehal P.O. Jia Tehsil Palampur Distt. Kangra H.P. (SH:- C/o U-Shape Drain and Edge wall behind Tudi store along with Grating). Deposit				Estimated cost Rs.	
				Earnest Money Rs.	
				Time Limits	Two Months
Sr No.	Description of Item	Quantity	Rate		Unit
			In Figures	In Word	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and baling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	19.20			Per cubic metre
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement five sand ten graded crushed stone aggregate 40mm forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and baling / carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	4.50			Per cubic metre
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement Three sand Six graded crushed / broken stone aggregate 20 mm (twenty millimeters) nominal and below size in or under water including curing complete, pumping or baling out water, dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the government.	8.89			Per cubic metre
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	286.40			Per Kilogram
5	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110 mm diameter. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	14.00			Per Running Metre
6	Providing and fixing 10 litre capacity - White P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	1.00			Each
Total					


H.P.W.D., Palampur

Schedule of Quantity

Work No.

Name of Work :- C/O Additional accomodation GSSS at Kandwari Tehsil Palampur Distt. Kangra (H.P.)

Estimate Cost :- Rs. 53,489/-

Earnest Money :- Rs. 1100/-

Time Limit :- Three Months

Sub Work :- Railing work etc. (Deposit)

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
				In figure	In Words		
1	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	309.12	Kilogram me			Per Kilogram me	
2	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete with in all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	18.70	Square metres.			Per Square metere	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

22

SCHEDULE OF QUANTITY

Name of work:- R/D on Parour Lahla Gopalpur Rakh Sukeri Kandi Bandla Palampur road Km 0/00 to 33/00. (SH:- C/o R/wall at Rd 11/550 to 11/557).				Estimated cost Rs.		99379.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	In Figures	Rate		Amount
				In Word	Unit	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	6.30			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and bailing /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	22.05			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plan or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	10.00			Each	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

SCHEDULE OF QUANTITY

Name of work:- R/D on Chachian Khas to Rakh road Km 0/00 to 3/00. (SH:- C/o R/wall at Rd 2/190 to 2/195).				Estimated cost Rs.		97827.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and baling out water (surface and sub soil water) upto any depth and any quantum of water including clearing of slash which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	7.92			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement: five sand: ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.83			Per cubic metre	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	6.00			Each	
Total						

Executive Engineer,
Palampur Division
HP PWD Palampur

24

SCHEDULE OF QUANTITY

Name of work:- R/D on Chachian Khas to Rakh road Km 0/00 to 3/00. (SH :- C/o R/wall at Rd 2/197 to 2/202).				Estimated cost Rs.		97827.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of Item	Quantity	In Figures	Rate		Amount
				In Word	Unit	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any 100 including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	7.92			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1 : 5 : 10 (one cement, five sand, ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government	21.83			Per cubic metre	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	6.00			Each	
Total						


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

of Work :- A/R & M/O Various roads Under Ghar Section Sub-division Palampur
 W :- Drain, Maintenance of earthen shoulder etc.

Work No. 25

Estimated Cost :- Rs. 98,860/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	4.96	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	3.13	Cubic metre			Per Cubic metre	
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25 m) as per Technical Specification Clause 307. Manual means, as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	840.00	Running metre			Per Running metre	
4	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	528.00	Square metre			Per Square metre	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

of Work :- A/R & M/O Various roads Under Ghar Section Sub-division Palampur
 S. W. :- Drain, Edge wall etc.

Work No.

Estimated Cost :- Rs. 98,628/-
 Earnest Money :- Rs. 2000/-
 Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	4.59	Cubic metre			Per Cubic metre	
2	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	2.89	Cubic metre			Per Cubic metre	
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines,grades,levels and dimensions.Excavated material to be used in embankment with a lift upto 3m and lead of 50m.(average lead 25 m)as per Technical Specification Clause 307. Manual means,as per the Directions of Engineer-in-Charge including carriage of materials, with in all leads, lifts and other incidental.	840.00	Running metre			Per Running metre	
4	Maintenance of Earthen shoulder (Filling with fresh selected soil) making up loss of material / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903, as per the Directions of Engineer-in-charge including carriage of materials, with in all leads, lifts and other incidental.	528.00	Square metre			Per Square metre	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

Name of Work :- C/O R/wall to protect the land of Sanjay kumar s/o kalu Ram Khayan patt
(S.W. :- C/O R/Wall etc.

Work No.

Estimated Cost :- Rs. 98,802/-
Earnest Money :- Rs. 2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	9.12	Cubic metre		Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work-in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.24	Cubic metre		Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	16.00	Nos.		Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	7.20	Cubic metre		Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

28

SCHEDULE OF QUANTITY						
Name of work:- C/o Jeepable road main road towards the house of Sh. Thakur Dass via Smt. Rampyari House 4 Mohal Kaloond. (SH:- P/L Interlocking tiles at Rd 0/00 to 0/031). Deposit 1.00 Lacs						
Sr No	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
						99905.00
						2000.00
						Two Months
1	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	68.20			Per square metre	
2	Providing and laying Cement concrete 1:4:8 (One Cement : Four Sand : Light crushed stone aggregate) Nominal Mix P.C.C. grade for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.50			Per cubic metre	
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : two Sand : four crushed stone aggregate) Nominal Mix P.C.C. grade M-20 (M-twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time	0.93			Per cubic metre	
	Total					

Executive Engineer
Palampur Division
HP PWD Palampur

29

SCHEDULE OF QUANTITY						
Name of work:- Fencing of Indrunag Rakh Mahila Mandal Bhawan Kaloond. (SH:- C/o R/wall for protection of ground).						
VKVNY Deposit 1.00 Lacs						
Sr No.	Description of item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials, upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	7.20			Per cubic metre	99536.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1:5:10 (one cement five sand ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera complete as per the direction of Engineer-in-Charge, as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	21.60			Per cubic metre	2000.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	16.00			Each	
Total						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Dharamshala Yol Dadh Holta Chadhar Sandhole road Km. 33/000 to 40/500
(S. W. :- C/o V-shape drain & Edge wall at RD 37/820 to 37/832)

Work No. 30

Estimated Cost :- Rs. 97,417/-

Earnest Money :- Rs. 2000/-

Time limit : Three Months.

S. No.	Description of Item	Quantity		Rate		Unit	Amount
				In figure	In words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	6.95	Cubic metre			Per Cubic metre	
2	Providing and Laying concrete for plain/reinforced concrete in open foundations 1:3:10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including the cost of form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; within all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	20.09	Cubic metre			Per Cubic metre	
3	Providing weep holes in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v) : 20 (H) towards drain face complete as per drawing and technical specification clause 614, 709, 1204.307 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	8.00	Numbers			Each	
4	Back filling granular material behind R/Wall, abutment wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government.	4.86	Cubic metre			Per Cubic metre	
5	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	0.77	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

31

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on link road to village Fotta Km 0/00 to 1/500. (SH:- Providing and laying G-II & C.C. Pavement in Km 0/200 to 0/233)					Estimated cost Rs.		99630.00
					Earnest Money Rs.		2000.00
					Time Limits		Two Months
Sr. No.	Description of Item	Quantity	Rate		Unit	Amount	
			In Figures	In Word			
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Per cubic metre		
2	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	15.10			Per cubic metre.		
Total							

Executive Engineer,
Palampur Division
HP.PWD Palampur.

Name of Work :- Crossing of water pipe line under Palampur sub-division (CIPH DEPOSIT) Schedule of Quantity

Sub Work :- balance work of C/o 0.60 mtr. Span RCC slab & Pulli over drain

Estimate Cost :- Rs. 99,836/-
Earnest Money :- Rs. 2000/-

Time Limit :- Three months

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees
		In figure	In Words	In figure	In Words		
1	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government.	11.61	Cubic metres			Per Cubic metre.	
2	Supplying, fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002, 1010 and 1202. as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	290.14	kilogram me			Per kilogram me	
Total :-							

Executive Engineer,
Palampur Division,
HPPWD Palampur

Schedule of Quantity

Bill of Work :- Crossing of water pipe line under Palampur sub- division (IPH Deposit)

Sub Work :- - balance work of C/o 0.50 mtr. Span RCC slab & Pulli over drain

Estimate Cost :- Rs. 81,028/-
Earnest Money :- Rs.1700/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rupees
			In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	18.88			Per Cubic metre	
	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in-Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the Government..	10.82			Per Cubic metre	
2	Providing concrete for plain/reinforced concrete in open foundations 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate (20 mm nominal size) R.C.C. grade M- 25 (M-Twenty Five) complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts of materials and other incidentals .The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	3.71			Per Cubic metre	
Total :-						

Executive Engineer,
Palampur Division,
HPPWD Palampur

34

SCHEDULE OF QUANTITY


Name of work:- R/D on Neugal Bridge to Latwala Road Km 0/00 to 5/00. (SH:- C/o R/wall at Rd 1/980 to 1/989). Deposit				Estimated cost Rs.	
3.00 Lacs				2000.00	
				Two Months	
Sr. No.	Description of item	Quantity	In Figures	Rate	
				In Word	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Matkana, toll tax, GST or other taxes imposed by the Government time to time.	6.48		Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	22.28		Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00		Each	
Total					

Executive Engineer,
Palampur Division
HP.PWD Palampur

(35)

SCHEDULE OF QUANTITY

Name of work:- R/D on Neugal Bridge to Latwala Road Km 0/00 to 5/00, (SH:- C/o R/wall at Rd 1/968 to 1/975), Deposit 3.00 Lacs				Estimated cost Rs.		99701.00
				Earnest Money Rs.		2000.00
				Time Limits		Two Months
Sr. No.	Description of item	Quantity	In Figures	Rate		Amount
				In Word	Unit	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government time to time.	9.45			Per cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation as per drawing and technical specification section 800, 1200 & 1600 for nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete, including the cost of form work in Retaining Wall, Breast Wall etcetera, complete as per the direction of Engineer-in-Charge; as per the drawing and hauling /carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the government.	22.05			Per cubic metre.	
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimetre) dia P.V.C. pipe extending through the full width of the structures with slope of 1(V): 20(H) towards draining face complete as per drawing and M.O.R.D.technical specification section 700 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax or other taxes imposed by the government.	8.00			Each	
Total						


 Executive Engineer,
 Palampur Division
 HP.PWD Palampur