

**OFFICE OF  
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI**

**Phone No. 01899-233287 Email: ee-slo-hp@nic.in**

**\*NOTING INVITING TENDER\***

Sealed item rate tender on form 6&8 are hereby invited by the Executive Engineer, Salooni Division HPPWD Salooni on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before **21.10.2025 to 11:00 AM** and the same shall be opened on the same day at **11:30 AM**, in the presence of the intending Contractor or their authorized representatives if any. The tender form can be obtained from his office on cash payment (Non refundable) on **18.10.2025 upto 03.30 PM** and the application for issue of tender form shall be received on **18.10.2025 upto 04.30 P.M.** The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Salooni Division HPPWD Salooni must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class
1.	Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining wall at R.D. 1/760.20 to 1/462.75)	98,507/-	2000/-	350/-	90 Days	D & C
2.	Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	97,850/-	2000/-	350/-	90 Days	D & C
3.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: Hiring of JCB for removal of slips at R.D. 0/030 to 0/060, 0/110 to 0/150, 0/340 to 0/360 and 0/630 to 0/655)	99,950/-	2000/-	350/-	90 Days	D & C
4.	Restoration of rain damages on Bhalei to Dhar road K.M. 0/0 to 3/500 (SH: Hiring of JCB for removal of slips at R.D. 0/0 to 0/050, 0/840 to 0/880, 2/135 to 2/150 and 2/510 to 2/540)	99,990/-	2000/-	350/-	90 Days	D & C
5.	Restoration of rain damages on Jawnas to Bhasua road K.M. 0/0 to 9/400 (SH: Hiring of JCB for removal of slips at various RD's)	97,002/-	2000/-	350/-	C & D	90 Days
6.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/483.60 to 23/485.40)	98,250/-	2000/-	350/-	90 Days	D & C
7.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Hiring of JCB for removal of slips at R.D. 1/930 to 1/990 and 2/0 to 2/030)	99,326/-	2000/-	350/-	C & D	90 Days
8.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 26/050 to 26/110 and 26/160 to 26/210)	99,000/-	2000/-	350/-	90 Days	D & C
9.	Restoration of rain damages on Kandi to Athed road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 10/520 to 10/610)	97,709/-	2000/-	350/-	90 Days	D & C
10.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Hiring of JCB for removal of slips at R.D. 0/130 to 0/150, 0/405 to 0/455, 2/510 to 2/550 and 3/300 to 3/320)	99,743/-	2000/-	350/-	90 Days	D & C
11.	Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 18/0 to 27/0)	98,880/-	2000/-	350/-	C & D	90 Days

12.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)	99,910/-	2000/-	350/-	90 Days	D & C
13.	Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 11/900 (SH: Hiring of JCB for removal of slips at various RD's)	99,635/-	2000/-	350/-	C & D	90 Days
14.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: Hiring of JCB for removal of slips at R.D. 0/780 to 0/810, 1/030 to 1/050 and 1/650 to 1/700)	99,338/-	2000/-	350/-	90 Days	D & C
15.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)	99,910/-	2000/-	350/-	C & D	90 Days
16.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 8/360 to 8/450)	99,900/-	2000/-	350/-	C & D	90 Days
17.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/364.50 to 23/366.40)	99,826/-	2000/-	350/-	C & D	90 Days
18.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)	97,850/-	2000/-	350/-	90 Days	D & C
19.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at various RD's)	99,910/-	2000/-	350/-	C & D	90 Days
20.	Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Hiring of JCB for removal of slips at various RD's)	99,842/-	2000/-	350/-	C & D	90 Days
21.	Restoration of rain damages on Surella Pukhri Part-II road K.M. 0/0 to 0/480 (SH: Hiring of JCB for removal of slips at R.D. 0/170 to 0/190, 0/200 to 0/235 and 0/320 to 0/375)	99,900/-	2000/-	350/-	C & D	90 Days
22.	Restoration of rain damages on Kainthly to Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	99,626/-	2000/-	350/-	C & D	90 Days
23.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at R.D. 3/620 to 3/650 and 4/880 to 4/930)	99,900/-	2000/-	350/-	C & D	90 Days
24.	Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining wall at R.D. 1/768 to 1/770)	77,738/-	2000/-	350/-	90 Days	D & C
25.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)	98,880/-	2000/-	350/-	90 Days	D & C
26.	Restoration of rain damages on Sundla Danoon Kund Patruma road K.M. K.M. 0/0 to 2/075 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 2/075)	99,910/-	2000/-	350/-	C & D	90 Days
27.	Restoration of rain damages on link road Rolka to Halela K.M. 0/0 to 3/400 (SH: Construction of Retaining wall in wire crate at R.D. 0/277.50 to 0/285)	95,615/-	2000/-	350/-	90 Days	D & C
28.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 0/030 to 0/060, 1/210 to 1/270 and 1/940 to 1/960)	99,563/-	2000/-	350/-	C & D	90 Days
29.	Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/695 to 0/712.50 and edging both side of road at R.D. 0/700 to 0/708)	99,425/-	2000/-	350/-	C & D	90 Days

30.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 15/390 to 15/420, 16/0 to 16/020 and 16/330 to 16/375)	99,900/-	2000/-	350/-	C & D	90 Days
31.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 7/040)	99,910/-	2000/-	350/-	C & D	90 Days
32.	Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	99,910/-	2000/-	350/-	90 Days	D & C
33.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 16/800 to 16/820, 16/950 to 17/0 and 17/965 to 17/995)	99,349/-	2000/-	350/-	C & D	90 Days
34.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)	95,790/-	2000/-	350/-	C & D	90 Days
35.	Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of edging both side of road at R.D. 0/708 to 0/744.50)	99,719/-	2000/-	350/-	C & D	90 Days
36.	Restoration of rain damages on Bhalei Matta temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Breast wall at R.D. 2/870 to 2/876)	96,298/-	2000/-	350/-	C & D	90 Days
37.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 13/490 to 13/530, 14/480 to 14/510 and 15/0 to 15/020)	99,675/-	2000/-	350/-	C & D	90 Days
38.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at R.D. 0/140 to 0/180 and 0/750 to 0/780)	99,945/-	2000/-	350/-	C & D	90 Days
39.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)	98,880/-	2000/-	350/-	C & D	90 Days
40.	Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 11/900 (SH: Hiring of JCB for removal of slips at various RD's)	98,503/-	2000/-	350/-	C & D	90 Days
41.	Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/480 to 23/481.80)	98,250/-	2000/-	350/-	90 Days	D & C
42.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Hiring of JCB for removal of slips between K.M. t 0/0 to 7/040)	99,910/-	2000/-	350/-	C & D	90 Days
43.	Restoration of rain damages on near Telka to Thaloga road K.M. 0/0 to 4/700 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 4/700)	99,910/-	2000/-	350/-	C & D	90 Days
44.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 4/735 to 4/795, 5/720 to 5/750 and 6/680 to 6/700)	99,945/-	2000/-	350/-	C & D	90 Days
45.	Restoration of rain damages on near Ani to Salooni (Drekri road K.M. K.M. 0/0 to 4/900 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 4/900)	99,910/-	2000/-	350/-	C & D	90 Days
46.	Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/650 to 0/672.50)	99,137/-	2000/-	350/-	C & D	90 Days
47.	Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 10/700 to 11/100)	99,910/-	2000/-	350/-	C & D	90 Days

48.	Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	96,820/-	2000/-	350/-	90 Days	D & C
49.	Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 27/0 to 36/500)	99,910/-	2000/-	350/-	C & D	90 Days
50.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-I) (SH: Hiring of JCB for removal of slips at various RD's)	99,910/-	2000/-	350/-	90 Days	D & C
51.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)	96,820/-	2000/-	350/-	C & D	90 Days
52.	Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	98,880/-	2000/-	350/-	90 Days	D & C
53.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 7/195 to 7/225 and 9/120 to 9/175)	99,900/-	2000/-	350/-	C & D	90 Days
54.	Restoration of rain damages on link road to village Drekri K.M. 0/0 to 1/150 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 1/150)	99,910/-	2000/-	350/-	C & D	90 Days
55.	Restoration of rain damages on Kund to Siula road K.M. 0/0 to 6/255 (SH: Construction of crate work Retaining wall at R.D. 4/350 to 4/360)	96,262/-	2000/-	350/-	90 Days	D & C
56.	Restoration of rain damages on link road to village Jatota K.M. 0/0 to 2/600 (SH: Hiring of JCB for removal of slips at various RD's)	97,189/-	2000/-	350/-	90 Days	D & C
57.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)	97,850/-	2000/-	350/-	C & D	90 Days
58.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)	96,820/-	2000/-	350/-	90 Days	D & C
59.	Restoration of rain damages on various roads under Salooni Sub Division (Salooni Diur) (SH: Hiring of JCB for removal of slips at various RD's)	98,880/-	2000/-	350/-	90 Days	D & C
60.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 0/840 to 0/880, 1/120 to 1/150 and 3/430 to 3/455)	99,968/-	2000/-	350/-	C & D	90 Days
61.	Restoration of rain damages on Chakoli to Dhalla road K.M. 0/0 to 5/100 (SH: Hiring of JCB for removal of slips at various RD's)	99,369/-	2000/-	350/-	C & D	90 Days
62.	Restoration of rain damages on Jawnas to Bhasua road K.M. 0/0 to 9/400 (SH: Hiring of JCB for removal of slips at various RD's)	98,532/-	2000/-	350/-	C & D	90 Days
63.	Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at R.D. 12/570 to 12/620 and 13/100 to 13/150)	99,716/-	2000/-	350/-	C & D	90 Days
64.	Restoration of rain damages on Kainthly to Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)	97,650/-	2000/-	350/-	C & D	90 Days
65.	Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/672.50 to 0/695)	99,493/-	2000/-	350/-	C & D	90 Days
66.	Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 18/0 to 27/0)	99,910/-	2000/-	350/-	C & D	90 Days

**TERMS AND CONDITIONS:-**

1. The contractor should produce a copy of enlistment /renewal at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No., the copy of Pan number same be attached with the application.
4. The earnest Money shall be deposited duly pledged in favour of Executive Engineer, Salooni Division HPPWD Salooni and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.

  
Executive Engineer,  
Salooni Division  
HPPWD Salooni.

No. PW/SD/GA/Contract/Tender/2025-2026- 7051-7100

Dated: - 13 /10/2025

**Copy forwarded to:-**

1. The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (Kangra Zone) HPPWD Dharamshala.
4. The Superintending Engineer, 7<sup>th</sup> Circle HPPWD Dalhousie.
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
6. All the Assistant Engineers under Salooni Division.
7. All the Contractor working under this division.
8. H.D.M./Supdt./Acctt. of this office.
9. Notice Board.

  
Executive Engineer,  
Salooni Division  
HPPWD Salooni.

OFFICE OF  
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI  
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI  
Phone No. 01899-233287 Email: ee-slo-hp@nic.in

\*CERTIFICATE\*

Certified that tender of works, as called vide this office letter No.  
PW/SD/GA/Contract/tender/2025-2026- 7051-7100 Dated: 13/10/2025 are emergent  
nature in exigency of public interest.


  
Executive Engineer,  
Salooni Division  
HPPWD Salooni.  


## DNIT

Name of work:- Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining wall at R.D. 1/760.20 to 1/462.75)				Estimated cost		98507.00
				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	8.30	491.85	Per Cubic Metre	Rupees Four Hundred Ninety One And Paise Eighty Five Only	4082.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	14.99	5992.40	Per Cubic Metre	Rupees Five Thousand Nine Hundred Ninety Two And Paise Forty Only	89826.00
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.22	1210.20	Per Cubic Metre	Rupees One Thousand Two Hundred Ten And Paise Twenty Only	2687.00
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	6.00	318.60	Each	Rupees Three Hundred Eighteen And Paise Sixty Only	1912.00
<b>Total</b>						<b>98507.00</b>
<b>Rupees Ninety Eight Thousand Five Hundred Seven Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		97850.00
Name of work:- Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only One Thirty	97850.00
Total						97850.00
Rupees Ninety Seven Thousand Eight Hundred Fifty Only						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni



DNIT				Estimated cost		99950.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: 0/030 to 0/060, 0/110 to 0/150, 0/340 to 0/360 and 0/630 to 0/655)				Earnest money		2000.00
Hiring of JCB for removal of slips at R.D. 0/030 to 0/060, 0/110 to 0/150, 0/340 to 0/360 and 0/630 to 0/655)				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1110.55	90.00	Per Cum	Rupees Ninety Only	99950.00
<b>Total</b>						<b>99950.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Fifty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni   


<u>DNIT</u>						
Name of work:- Restoration of rain damages on Bhalei to Dhar road K.M. 0/0 to 3/500 (SH: Hiring of JCB for removal of slips at R.D. 0/0 to 0/050, 0/840 to 0/880, 2/135 to 2/150 and 2/510 to 2/540)					Estimated cost	99990.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1111.00	90.00	Per Cum	Rupees Ninety Only	99990.00
					<b>Total</b>	<b>99990.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ninety Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost	97002.00	
Name of work:- Restoration of rain damages on Jawnas to Bhasua road K.M. 0/0 to 9/400 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money	2000.00	
				Time limit	90 days	
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1077.80	90.00	Per Cum	Rupees Ninety Only	97002.00
<b>Total</b>						<b>97002.00</b>
<b>Rupees Ninety Seven Thousand Two Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		98250.00
Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/480 to 23/481.80)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	9.25	487.80	Per Cubic Metre	Rupees Four Hundred Eighty Seven And Paise Eighty Only	4512.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	15.73	5684.30	Per Cubic Metre	Rupees Five Thousand Six Hundred Eighty Four And Paise Thirty Only	89414.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	6.00	303.10	Each	Rupees Three Hundred Three And Paise Ten Only	1819.00
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1.94	1291.40	Per Cubic Metre	Rupees One Thousand Two Hundred Ninety One And Paise Forty Only	2505.00
<b>Total</b>						<b>98250.00</b>
<b>Rupees Ninety Eight Thousand Two Hundred Fifty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99326.00
Name of work:- Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Hiring of JCB for removal of slips at R.D. 1/930 to 1/990 and 2/0 to 2/030)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1103.62	90.00	Per Cum	Rupees Ninety Only	99326.00
<b>Total</b>						<b>99326.00</b>
<b>Rupees Ninety Nine Thousand Three Hundred Twenty Six Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99000.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 26/050 to 26/110 and 26/160 to 26/210)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1100.00	90.00	Per Cum	Rupees Ninety Only	99000.00
<b>Total</b>						<b>99000.00</b>
<b>Rupees Ninety Nine Thousand Only</b>						


  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

(B)

DNIT						Estimated cost	97709.00
Name of work:-Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 10/520 to 10/610)						Earnest money	2000.00
						Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1085.66	90.00	Per Cum	Rupees Ninety Only	97709.00	
<b>Total</b>						<b>97709.00</b>	
<b>Rupees Ninety Seven Thousand Seven Hundred Nine Only</b>							

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99743.00
Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Hiring of JCB for removal of slips at R.D. 0/130 to 0/150, 0/405 to 0/455, 2/510 to 2/550 and 3/300 to 3/320)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1108.25	90.00	Per Cum	Rupees Ninety Only	99743.00
<b>Total</b>						<b>99743.00</b>
<b>Rupees Ninety Nine Thousand Seven Hundred Forty Three Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

<b>DNIT</b>						Estimated cost	98880.00
Name of work:- Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 18/0 to 27/0)						Earnest money	2000.00
						Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verfied by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00	
<b>Total</b>						<b>98880.00</b>	
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>							

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT						
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)					Estimated cost	99910.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99635.00
Name of work:- Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 11/900 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1107.05	90.00	Per Cum	Rupees Ninety Only	99635.00
<b>Total</b>						<b>99635.00</b>
<b>Rupees Ninety Nine Thousand Six Hundred Thirty Five Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni





DNIT				Estimated cost		99338.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road to village Lamni K.M. 0/0 to 2/500 (SH: Hiring of JCB for removal of slips at R.D. 0/780 to 0/810, 1/030 to 1/050 and 1/650 to 1/700)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1103.75	90.00	Per Cum	Rupees Ninety Only	99338.00
<b>Total</b>						<b>99338.00</b>
<b>Rupees Ninety Nine Thousand Three Hundred Thirty Eight Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 



<u>DNIT</u>						
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 8/360 to 8/450)					Estimated cost	99900.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cum	Rupees Ninety Only	99900.00
<b>Total</b>						<b>99900.00</b>
Rupees Ninety Nine Thousand Nine Hundred Only						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 


DNIT				Estimated cost		99826.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/364.50 to 23/366.40)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	7.64	524.10	Per Cubic Metre	Rupees Five Hundred Twenty Four And Paise Ten Only	4004.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	15.71	5836.90	Per Cubic Metre	Rupees Five Thousand Eight Hundred Thirty Six And Paise Ninety Only	91698.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	5.00	317.40	Each	Rupees Three Hundred Seventeen And Paise Forty Only	1587.00
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	2.11	1202.37	Per Cubic Metre	Rupees One Thousand Two Hundred Two And Paise Thirty Seven Only	2537.00
<b>Total</b>						<b>99826.00</b>
<b>Rupees Ninety Nine Thousand Eight Hundred Twenty Six Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		97850.00
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	97850.00
<b>Total</b>						<b>97850.00</b>
<b>Rupees Ninety Seven Thousand Eight Hundred Fifty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 


DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99842.00
Name of work:- Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1109.35	90.00	Per Cum	Rupees Ninety Only	99842.00
<b>Total</b>						<b>99842.00</b>
<b>Rupees Ninety Nine Thousand Eight Hundred Forty Two Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT					Estimated cost	99900.00
Name of work:- Restoration of rain damages on Surella Pukhri Part-II road K.M. 0/0 to 0/480 (SH: Hiring of JCB for removal of slips at R.D. 0/170 to 0/190, 0/200 to 0/235 and 0/320 to 0/375)					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cum	Rupees Ninety Only	99900.00
					<b>Total</b>	<b>99900.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni (B)

DNIT				Estimated cost		99626.00
Name of work:- Restoration of rain damages on Kainthly to Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.95	90.00	Per Cum	Rupees Ninety Only	99626.00
<b>Total</b>						<b>99626.00</b>
<b>Rupees Ninety Nine Thousand Six Hundred Twenty Six Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 



DNIT				Estimated cost		99900.00
Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at R.D. 3/620 to 3/650 and 4/880 to 4/930)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cum	Rupees Ninety Only	99900.00
<b>Total</b>						<b>99900.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni (B)

DNIT						Estimated cost	98507.00
Name of work:- Restoration of rain damages on Chhudra to Tuhien road K.M. 0/0 to 2/225 (SH: Construction of PCC Retaining wall at R.D. 1/768 to 1/770)						Earnest money	2000.00
						Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.30	491.85	Per Cubic Metre	Rupees Four Hundred Ninety One And Paise Eighty Five Only	3099.00	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	11.76	5997.80	Per Cubic Metre	Rupees Five Thousand Nine Hundred Ninety Seven And Paise Eighty Only	70534.00	
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1.80	1244.70	Per Cubic Metre	Rupees One Thousand Two Hundred Forty Four And Paise Seventy Only	2240.00	
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	6.00	310.90	Each	Rupees Three Hundred Ten And Paise Ninety Only	1865.00	
<b>Total</b>						<b>77738.00</b>	
<b>Rupees Seventy Seven Thousand Seven Hundred Thirty Eight Only</b>							

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		98880.00
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00
<b>Total</b>						<b>98880.00</b>
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni


DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Sundla Danoon Kund Patruma road K.M. K.M. 0/0 to 2/075 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 2/075)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00
<b>Total</b>						<b>98880.00</b>
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		95615.00
Name of work:- Restoration of rain damages on link road Rolka to Halela K.M. 0/0 to 3/400 (SH: Construction of Retaining wall in wire crate at R.D. 0/277.50 to 0/285)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals.	16.43	487.80	Per cubic metre	Rupees Four Hundred Eighty Seven And Paise Eighty Only	8015.00
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred milimeters into hundred milimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	31.20	2807.70	Per cubic metre	Rupees Two Thousand Eight Hundred Seven And Paise Seventy Only	87600.00
<b>Total</b>						<b>95615.00</b>
<b>Rupees Ninety Five Thousand Six Hundred Fifteen Only</b>						



  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99563.00
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 0/030 to 0/060, 1/210 to 1/270 and 1/940 to 1/960)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1106.25	90.00	Per Cum	Rupees Ninety Only	99563.00
<b>Total</b>						<b>99563.00</b>
<b>Rupees Ninety Nine Thousand Five Hundred Sixty Three Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 



## DNIT

Name of work:- Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/695 to 0/712.50 and edging both side of road at R.D. 0/700 to 0/708)				Estimated cost		99425.00
				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	15.05	531.30	Per cubic metre	Rupees Five Hundred Thirty One And Paise Thirty Only	7996.00
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	26.25	2650.40	Per cubic metre	Rupees Two Thousand Six Hundred Fifty And Paise Forty Only	69573.00
3	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	3.84	5691.70	Per Cubic Metre	Rupees Five Thousand Six Hundred Ninety One And Paise Seventy Only	21856.00
<b>Total</b>						<b>99425.00</b>
<b>Rupees Ninety Nine Thousand Four Hundred Twenty Five Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT


Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 15/390 to 15/420, 16/0 to 16/020 and 16/330 to 16/375)					Estimated cost	99900.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cum	Rupees Ninety Only	99900.00
<b>Total</b>						<b>99900.00</b>
Rupees Ninety Nine Thousand Nine Hundred Only						

  
Executive Engineer  
Salooni Division  
HPPWD Salooni 

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 7/040)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99349.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 16/800 to 16/820, 16/950 to 17/0 and 17/965 to 17/995)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1103.88	90.00	Per Cum	Rupees Ninety Only	99349.00
<b>Total</b>						<b>99349.00</b>
<b>Rupees Ninety Nine Thousand Three Hundred Forty Nine Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		95790.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	93.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	95790.00
<b>Total</b>						<b>95790.00</b>
<b>Rupees Ninety Five Thousand Seven Hundred Ninety Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 



DNIT				Estimated cost		99719.00
Name of work:- Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of edging both side of road at R.D. 0/708 to 0/744.50)				Earnest money		2000.00
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 ( one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	17.52	5691.70	Per Cubic Metre	Rupees Five Thousand Six Hundred Ninety One And Paise Seventy Only	99719.00
<b>Total</b>						<b>99719.00</b>
<b>Rupees Ninety Nine Thousand Seven Hundred Nineteen Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		96298.00
Name of work:- Restoration of rain damages on Bhalei Matta temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Breast wall at R.D. 2/870 to 2/876)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	12.30	531.30	Per Cubic Metre	Rupees Five Hundred Thirty One And Paise Thirty Only	6535.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	18.12	4889.70	Per Cubic Metre	Rupees Four Thousand Eight Hundred Eighty Nine And Paise Seventy Only	88601.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	4.00	290.40	Each	Rupees Two Hundred Ninety And Paise Forty Only	1162.00
<b>Total</b>						<b>96298.00</b>
<b>Rupees Ninety Six Thousand Two Hundred Ninety Eight Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT						
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at R.D. 13/490 to 13/530, 14/480 to 14/510 and 15/0 to 15/020)					Estimated cost	99675.00
					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1107.50	90.00	Per Cum	Rupees Ninety Only	99675.00
					Total	99675.00
Rupees Ninety Nine Thousand Six Hundred Seventy Five Only						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT					Estimated cost		99945.00
Name of work:- Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at R.D. 0/140 to 0/180 and 0/750 to 0/780)					Earnest money		2000.00
					Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.50	90.00	Per Cum	Rupees Ninety Only	99945.00	
						<b>Total</b>	<b>99945.00</b>

Rupees Ninety Nine Thousand Nine Hundred Forty Five Only

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		96880.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880 00
<b>Total</b>						<b>98880.00</b>
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni   


DNIT				Estimated cost		98503.00
Name of work:- Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 11/900 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1094.48	90.00	Per Cum	Rupees Ninety Only	98503.00
<b>Total</b>						<b>98503.00</b>
<b>Rupees Ninety Eight Thousand Five Hundred Three Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni   


DNIT				Estimated cost		98250.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 13/130 to 28/0 (SH: Construction of PCC Retaining wall at R.D. 23/483.60 to 23/485.40)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	9.25	487.80	Per Cubic Metre	Rupees Four Hundred Eighty Seven And Paise Eighty Only	4512.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 ( one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	15.73	5684.30	Per Cubic Metre	Rupees Five Thousand Six Hundred Eighty Four And Paise Thirty Only	89414.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (v): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	6.00	303.10	Each	Rupees Three Hundred Three And Paise Ten Only	1819.00
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1.94	1291.40	Per Cubic Metre	Rupees One Thousand Two Hundred Ninety One And Paise Forty Only	2505.00
<b>Total</b>						<b>98250.00</b>
<b>Rupees Ninety Eight Thousand Two Hundred Fifty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni


DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 7/040)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 


DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on near Telka to Thaloga road K.M. 0/0 to 4/700 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 4/700)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99945.00
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 4/735 to 4/795, 5/720 to 5/750 and 6/680 to 6/700)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1110.50	90.00	Per Cum	Rupees Ninety Only	99945.00
<b>Total</b>						<b>99945.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Forty Five Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on near Ani to Salooni (Drekri road K.M. K.M. 0/0 to 4/900 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 4/900)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
**Executive Engineer**  
**Salooni Division**  
**HPPWD Salooni**

DNIT				Estimated cost		99137.00
Name of work:- Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/650 to 0/672.50)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305 1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals.	18.23	531.30	Per cubic metre	Rupees Five Hundred Thirty One And Paise Thirty Only	9686.00
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred milimeters into hundred milimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	33.75	2650.40	Per cubic metre	Rupees Two Thousand Six Hundred Fifty And Paise Forty Only	89451.00
<b>Total</b>						<b>99137.00</b>
<b>Rupees Ninety Nine Thousand One Hundred Thirty Seven Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni


DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 10/700 to 11/100)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		96820.00
Name of work:- Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	96820.00
<b>Total</b>						<b>96820.00</b>
<b>Rupees Ninety Six Thousand Eight Hundred Twenty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on Sundla Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 27/0 to 36/500)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00
<b>Total</b>						<b>98880.00</b>
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-I) (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
<b>Total</b>						<b>99910.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Ten Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		96820.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	96820.00
<b>Total</b>						<b>96820.00</b>
<b>Rupees Ninety Six Thousand Eight Hundred Twenty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		98880.00
Name of work:- Restoration of rain damages on Kainthly Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00
<b>Total</b>						<b>98880.00</b>

Rupees Ninety Eight Thousand Eight Hundred Eighty Only

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

<u>DNIT</u>					Estimated cost	99900.00
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 7/195 to 7/225 and 9/120 to 9/175)					Earnest money	2000.00
					Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1110.00	90.00	Per Cum	Rupees Ninety Only	99900.00
					<b>Total</b>	<b>99900.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni (B)

DNIT				Estimated cost		99910.00
Name of work:- Restoration of rain damages on link road to village Drekri K.M. K.M. 0/0 to 1/150 (SH: Hiring of JCB for removal of slips between K.M. 0/0 to 1/150)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	99910.00
Total						99910.00
Rupees Ninety Nine Thousand Nine Hundred Ten Only						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		96257.00
Name of work:- Restoration of rain damages on Kund to Siula road K.M. 0/0 to 6/255 (SH: Construction of crate work Retaining wall at R.D. 4/350 to 4/360)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	9.60	531.30	Per Cubic Metre	Rupees Five Hundred Thirty One And Paise Thirty Only	5100.00
2	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	7.20	1200.08	Per Cubic Metre	Rupees One Thousand Two Hundred And Paise Eight Only	8641.00
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred milimeters into hundred milimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	31.25	2640.50	Per Cubic Metre	Rupees Two Thousand Six Hundred Forty And Paise Fifty Only	82516.00
<b>Total</b>						<b>96257.00</b>
<b>Rupees Ninety Six Thousand Two Hundred Fifty Seven Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

97,189.00

DNIT				Estimated cost		97,189.00
Name of work:- Restoration of rain damages on link road to village Jatota K.M. 0/0 to 2/600 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1079.88	90.00	Per Cum	Rupees Ninety Only	97189.00
Total						97189.00
Rupees Ninety Seven Thousand One Hundred Eighty Nine Only						

  
Executive Engineer  
Salooni Division  
HPPWD Salooni 

DNIT				Estimated cost		97850.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	97850.00
Total						97850.00
Rupees Ninety Seven Thousand Eight Hundred Fifty Only						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 



DNIT				Estimated cost		96890.00
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni section-II) (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	96820.00
<b>Total</b>						<b>96820.00</b>
<b>Rupees Ninety Six Thousand Eight Hundred Twenty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni

DNIT				Estimated cost		98880.00
Name of work:- Restoration of rain damages on various roads under Salooni Sub Division (Salooni Diur) (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees One Thousand Thirty Only	98880.00
<b>Total</b>						<b>98880.00</b>
<b>Rupees Ninety Eight Thousand Eight Hundred Eighty Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99968.00
Name of work:- Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at R.D. 0/840 to 0/880, 1/120 to 1/150 and 3/430 to 3/455)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1110.75	90.00	Per Cum	Rupees Ninety Only	99968.00
<b>Total</b>						<b>99968.00</b>
<b>Rupees Ninety Nine Thousand Nine Hundred Sixty Eight Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99369.00
Name of work:- Restoration of rain damages on Chakoli to Dhalla road K.M. 0/0 to 5/100 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1104.10	90.00	Per Cum	Rupees Ninety Only	99369.00
<b>Total</b>						<b>99369.00</b>
<b>Rupees Ninety Nine Thousand Three Hundred Sixty Nine Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		98532.00
Name of work:- Restoration of rain damages on Jawnas to Bhasua road K.M. 0/0 to 9/400 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1094.80	90.00	Per Cum	Rupees Ninety Only	98532.00
<b>Total</b>						<b>98532.00</b>
<b>Rupees Ninety Eight Thousand Five Hundred Thirty Two Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		99716.00
Name of work:- Restoration of rain damages on Chouga Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at R.D. 12/570 to 12/620 and 13/100 to 13/150)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana,Toll tax, GST or other taxes imposed by the Government.	1107.95	90.00	Per Cum	Rupees Ninety Only	99716.00
<b>Total</b>						<b>99716.00</b>
<b>Rupees Ninety Nine Thousand Seven Hundred Sixteen Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT				Estimated cost		97650.00
Name of work:- Restoration of rain damages on Kainthly to Bhidroh road K.M. 0/0 to 6/700 (SH: Hiring of JCB for removal of slips at various RD's)				Earnest money		2000.00
				Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Removal of landslide in all classification of soil and ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts or as directed by Engineer- in Charge as per technical specification 302.3.5 and 1611 any damages to the private property is the responsibility of the contractor. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	1085.00	90.00	Per Cum	Rupees Ninety Only	97650.00
<b>Total</b>						<b>97650.00</b>
<b>Rupees Ninety Seven Thousand Six Hundred Fifty Only</b>						


  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT

Name of work:- Imp. & M/T of approach road to Helipad Kundi in Tehsil Salooni District Chamba HP (SH: Construction of Crate work for toe protection at R.D. 0/672.50 to 0/695)				Estimated cost	99493.00	
				Earnest money	2000.00	
				Time limit	90 days	
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals.	18.90	531.30	Per cubic metre	Rupees Five Hundred Thirty One And Paise Thirty Only	10042.00
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred milimeters into hundred milimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi,royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	33.75	2650.40	Per cubic metre	Rupees Two Thousand Six Hundred Fifty And Paise Forty Only	89451.00
					<b>Total</b>	<b>99493.00</b>
<b>Rupees Ninety Nine Thousand Four Hundred Ninety Three Only</b>						

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni 

DNIT							Estimated cost	99910.00
Name of work:- Restoration of rain damages on Sundia Girjindoo road K.M. K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips between K.M. 18/0 to 27/0)							Earnest money	2000.00
							Time limit	90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words		Amount	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	99910.00	
<b>Total</b>							<b>99910.00</b>	
Rupees Ninety Nine Thousand Nine Hundred Ten Only								

  
 Executive Engineer  
 Salooni Division  
 HPPWD Salooni