

**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Shahpur Distt. Kangra (H.P.)-176206**  
**e-mail id: ee-shahpur-pwd@hp.gov.in**  
**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before 15-10-2025 up to 11:00 AM. and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) from 13-10-2025 to 14-10-2025 up to 5:00 P.M and the application for issue of tender form shall be received on 13-10-2025 up to 5:00PM.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Repair of community Hall near Matti Ward No-04 G.P. in Gharoh.(Deposit work). (S.H:- Providing and Laying Brick masonry and flooring work etc.)	95821/-	1950/-	Two Months	350/-
2	Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800 (S.H:-C/o wire crate wall with C.C.Pusta at RD 11/857 to 11/858.50).( Under PDNA)	98393/-	2000/-	Two Months	350/-
3	C/o Path from road to Gupal house ward No-03 in G.P Kaliada(VKV/2024/1578) (Deposit work)(S.H:-Providing and Laying interlocking paver block).	93976/-	1900/-	Two Months	350/-
4	C/o Path along with interlocking tile from road towards Ravinder Pathania house ward No-02 in G.P Kaliada(VKV/2025/469) (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/00 to 0/025).	71135/-	1500/-	Two Months	350/-
5	Stock storage under HP.PWD Sub Division Gaggal.(S.H:-Providing and laying prepainted roof Right and left side).	94815/-	1900/-	Two Months	350/-
6	Recovery and Reconstruction on Rulehar to Lam road KM 0/00 to 3/800 (Under PDNA).(S.H:-Widindig of Damages and Construction of Unlined road at RD 0/850 to 0/895/-.	98891/-	2000/-	One Month	350/-
7	Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800 (S.H:-C/o wire crate wall with C.C.Pusta at RD 11/855 to 11/856.50).( Under PDNA)	99428/-	2000/-	Two Months	350/-
8	Repair and Restoration of various roads under Shahpur Sub Division.(S.H:- Hiring of rock Breaker under Shahpur Section).	99200/-	2000/-	Two Months	350/-
9	C/o Path along with interlocking tile from road towards Ravinder Pathania house ward No-02 in G.P Kaliada(VKV/2025/469) (Deposit work)(S.H:-Providing and Laying interlocking paver block at RD 0/026 to 0/050).	71280/-	1500/-	Two Months	350/-
10	Restoration of Rain damages on various Roads under Charri Section under Gaggal Sub Division.(S.H:- Removal of slips in various Reaches).	99450/-	2000/-	One Month	350/-
11	Repair of community Hall near Matti Ward No-04 G.P. in Gharoh.(Deposit work). (S.H:- Providing and Laying frame work for door & plastering, flooring work etc.)	95701/-	1950/-	Two Months	350/-
12	Recovery and Reconstruction on Rulehar to Lam road KM 0/00 to 3/800 (Under PDNA).(S.H:-Widindig of Damages and Construction of Unlined road at RD 0/900 to 0/945	98891/-	2000/-	One Month	350/-
13	Restoration of Rain damages on various Roads under Gaggal Section under Gaggal Sub Division.(S.H:- Removal of slips in various Reaches).	99125/-	2000/-	One Month	350/-
14	Restoration of Rain Damages in Chambi to Dharamshala road (MDR) Km 0/00 to 12/800 (S.H:-C/o wire crate wall with C.C.Pusta at RD 11/ 858.70 to 11/860).( Under PDNA)	98276/-	2000/-	Two Months	350/-
15	Recovery and Reconstruction on Rulehar to Lam road KM 0/00 to 3/800 (Under PDNA).(S.H:-Widindig of Damages and Construction of Unlined road at RD 0/950 to 0/995	98891/-	2000/-	One Month	350/-
16	Restoration of Rain damage on Dohab to Kurrella road KM 0/00 to 4/00 (S.H: C/o Protection of abutment at KM 0/832 to 1/103).( Under PDNA)	73373/-	1500/-	Two Months	350/-

17	C/o Retaining wall to the land of Sh. Subhash Chand S/o Hari Chand Vill Bhairu G.P. Nerti Tehsil Shahpur (Under VKV/2025/760)( Deposit work).(S.H:- Retaining wall at RD 0/037 to 0/044.50).	99581/-	2000/-	Two Months	350/-
18	Restoration of Rain Damages in Chambli to Dharamshala road (MDR) Km 0/00 to 12/800 (S.H:-C/o wire crate wall with C.C.Pusta at RD 11/850 to 11/852.50). (under PDNA)	98510/-	2000/-	Two Months	350/-
19	Restoration of Rain damages on various Roads under Gaggal Section under Gaggal Sub Division.(S.H:- Removal of slips in various Reaches).	97500/-	2000/-	One Month	350/-
20	Restoration of Rain damages on Salli Khari Behi Road Km 0/000 to 9/570.(S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
21	Restoration of Rain damages on Kutharna to Kareri Road Km 0/000 to 8/720.(S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
22	Restoration of Rain damage on Dohab to Kurrella road KM 0/00 to 4/00 (S.H: C/o Protection of abutment at KM 0/640 to 0/830).( Under PDNA)	73279/-	1500/-	Two Months	350/-
23	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P) Under SCSP.(S.H:- Construction of V-Shape Drain at RD 0/852 to 0/861 ( Both side RHS & LHS).	97445/-	1950/-	Two Months	350/-
24	Restoration of Rain Damages in Chambli to Dharamshala road (MDR) Km 0/00 to 12/800 (S.H:-C/o wire crate wall with C.C.Pusta at RD 11/852.70 to 11/854).( Under PDNA)	98970/-	2000/-	Two Months	350/-
25	C/o Retaining wall to the land of Sh. Subhash Chand S/o Hari Chand Vill Bhairu G.P. Nerti Tehsil Shahpur (Under VKV/2025/760)( Deposit work).(S.H:- Retaining wall at RD 0/028.50 to 0/036).	99231/-	2000/-	Two Months	350/-
26	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250 (S.H:- Retaining wall in C.C 1:4:8 and wire crate at KM 13/276.80 to 13/279.20).( Under PDNA)	93296/-	1900/-	Two Months	350/-
27	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P) Under SCSP.(S.H:- Providing and laying G-II & G-III at RD.0/815 to 0/900).	99532/-	2000/-	Two Months	350/-
28	C/o Retaining wall to the land of Sh. Subhash Chand S/o Hari Chand Vill Bhairu G.P. Nerti Tehsil Shahpur (Under VKV/2025/760)( Deposit work).(S.H:- Retaining wall at RD 0/020 to 0/027.50).	99581/-	2000/-	Two Months	350/-
29	Special repair of Vetnary Hospital Gohju in Tehsil Shahpur at Distt Jangra H.P.(S.H:- C/o Boundary wall).	99786/-	2000/-	Two Months	350/-
30	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250 (S.H:- Retaining wall in C.C 1:4:8 and wire crate at KM 13/279.20 to 13/280.60).( Under PDNA)	93058/-	1900/-	Two Months	350/-
31	Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780 (S.H:- C/o Wire crate wall at RD 4/130 to 4/135).( Under PDNA)	97980/-	2000/-	Two Months	350/-
32	Restoration of Rain damages on various roads under Shahpur Sub Division (S.H:- Providing and laying WBM G-III on Rait to Kohla road at RD 4/800 to 4/875).(Under MMSRRY).	98730/-	2000/-	Two Months	350/-
33	Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250 (S.H:- Retaining wall in C.C 1:4:8 and wire crate at KM 13/273.40 to 13/275.80).( Under PDNA)	92708/-	1900/-	Two Months	350/-
34	Restoration of Rain damages on Link road Gharh Garh Matti KM 0/00 to 2/500 (S.H:-C/O V-Shape Drain at Rd 1/500 to 1/587).( Under PDNA)	97024/-	1950/-	Two Months	350/-
35	Restoration of Rain damages on Charri to Bhitlu road KM 0/00 to 5/780 (S.H:- C/o Wire crate wall at RD 4/137 to 4/141).( Under PDNA)	97980/-	2000/-	Two Months	350/-
36	Restoration of Rain damages on various roads under Shahpur Sub Division (S.H:- Providing and laying WBM G-III on Rait to Kohla road at RD 4/950 to 5/025).(Under MMSRRY)	98730/-	2000/-	Two Months	350/-
37	Construction of Link road link road Palwala to Lanjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P) Under SCSP.(S.H:- Providing and laying G-II & G-III at RD 0/415 to 0/478).	99250/-	2000/-	Two Months	350/-
38	Construction of Link road Rajol to Gharoh KM 0/00 to 6/00.(S.H:- C/o U-shape drain at RD 1/220 TO 1/248).( Under PDNA)	98469/-	2000/-	Two Months	350/-
39	Restoration of Rain damages on Sudher to Dhar road KM 0/00 to 1/500 (S.H:- C/o Wire crate wall at RD 0/325 to 0/345).( Under PDNA)	99015/-	2000/-	Two Months	350/-
40	Improvement of Black spot on Nerti Bherun Sandh Road KM 0/000 to 3/600 in Tehsil Shahpur Distt Kangra (H.P). S.H:- C/o Breast wall at RD 0/405 to 0/420).	97563/-	2000/-	Two Months	350/-

41	Restoration of Rain damages on Shahpur Chakban Lajpura road KM 0/00 to 20/250 (S.H:- Retaining wall in C.C 1:4:8 and wire crate at KM 13/320 to 13/322.54).( Under PDNA)	95692/-	1950/-	Two Months	350/-
42	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555.(S.H:- C/o RCC Wall at Rd 8/416 to 8/417.50. ( Under PDNA)	99312/-	2000/-	Two Months	350/-
43	Improvement of Black spot on Neri Bherun Sandh Road KM 0/000 to 3/600 in Tehsil Shahpur Distt Kangra (H.P). S.H:- C/o Breast wall at RD 0/422 to 0/432).	63875/-	1300/-	Two Months	350/-
44	Restoration of Rain damages on Link road Gharh Garh Mutti KM 0/00 to 2/500 (S.H:-C/o R/wall at RD 1/160 to 1/615.80).	98917/-	2000/-	Two Months	350/-
45	A/R & M/O various road under Gaggal Sub Division (S.H:- Painting and writing letters, Figures etc.)	99755/-	2000/-	One Month	350/-
46	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555.(S.H:- RCC Wall at Rd 8/414.40 to 8/415.90.	99758/-	2000/-	Two Months	350/-
47	Construction of Link road link road Palwala to Lunjot in G.P Durgella Km 0/000 to 0/900 in Tehsil Shahpur Distt Kangra (H.P) Under SCSIP.(S.H:- Construction of V-Shape Drain at RD 0/840 to 0/850 ( Both side RHS & LHS).	98680/-	2000/-	Two Months	350/-
48	A/R & M/O various road under Gaggal Sub Division (S.H:- Providing, Fixing and Painting of Kilometer stone writing letters etc.)	90522/-	1850/-	One Month	350/-
49	Recovery and Reconstruction on Shahpur Kiari Chattrer Road Km 0/00 to 8/900 ( Under PDNA)(S.H:-C/o R/Wall at RD 8/161.50 8/167.	91099/-	2000/-	Two Months	350/-
50	Construction of Link road Rajol to Gharoh KM 0/00 to 6/00.(S.H:- C/o U-shape drain at RD 1/250 to 1/280	99582/-	2000/-	Two Months	350/-
51	Construction of Link road link road NH 154 to Dhanotu via Bad Basti KM 0/00 to 3/670 Distt Kangra (H.P) Under RIDF -XXX (Nabard).(S.H:- Providing Board and Painting and writing lettering, figures etcetra).	99708/-	2000/-	One Month	350/-
52	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555.(S.H:- RCC Wall at Rd 8/417.60 to 8/419. ( Under PDNA)	98990/-	2000/-	Two Months	350/-
53	Restoration of Rain damages on various Roads under Darini Section under HP.PWD Darini I Sub Division.(S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
54	C/o Link road Grappa Mod Bagru Basnoor Sheelta Mata Purana Road KM 0/00 to 3/550 in Tehsil Shahpur Distt Kangra (H.P). (S.H:-C/o U-Shape Drain at RD 3/188 to 3/215 & R/wall at RD 3/188 to 3/195 RHS.	99184/-	2000/-	Two Months	350/-
55	Restoration of Rain damages on various Roads under Charri Section under Gaggal Sub Division.(S.H:- Removal of slips in various Reaches).	98800/-	2000/-	One Month	350/-
56	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).(S.H:- C/o Irrigation drain at Rd 2/995, P/L WBM G-III from Rd 2/985 to 3/000 and Rd 2/916.30 to 2/930, C/o Doublr row 300 MM Dia NP3 hume pipe culvert at Rd 2/920 and C/o Single Row 450 MM Dia NP3 hume pipe culvert at Rd 2/850.	95875/-	1950/-	Two Months	350/-
57	Restoration of Rain Damages on Various roads under Boh Section HP.PWD Darini Sub Division.(S.H:- Hiring of Excavator cum loader for removal of slips and tractor for Shifig and earriage of material at various RDs.	98940/-	2000/-	One Month	350/-
58	C/o Link road Grappa Mod Bagru Basnoor Sheelta Mata Purana Road KM 0/00 to 3/550 in Tehsil Shahpur Distt Kangra (H.P). (S.H:-C/o U-Shape Drain at RD 3/200 to 3/222 & R/wall at RD 3/232 to 3/240 LHS).	98974/-	2000/-	Two Months	350/-
59	Recovery and Reconstruction on Charri to Ghera Road KM 0/00 to 8/855.(Under PDNA).(S.H:- C/o C.C. Pusta at RD 6/150 to 6/153.80(1st Stage).	99987/-	2000/-	Two Months	350/-
60	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).(S.H:- C/o C.C. Pavement at RD 2/916.30 to 2/930.	99458/-	2000/-	Two Months	350/-
61	Recovery and Reconstruction on Shahpur Kiari Chattrer Road Km 0/00 to 8/900 ( Under PDNA)(S.H:-C/o R/Wall at RD 8/144.50 to 8/152).	91449/-	2000/-	Two Months	350/-
62	Recovery and Reconstruction onThehar to Pargod Rond KM 0/00 to 9/000.(Under PDNA).(S.H:- C/o Breast wall at RD 1/662 to 1/681.10).	99493/-	2000/-	Two Months	350/-
63	Restoration of Rain damages on Link road Salli to Konal road KM 0/00 to 2/250 (S.H:- Construction of R/Wall with wire crate and C.C Pusta at RD 0/520 to 0/525).	99510/-	2000/-	Two Months	350/-
64	Restoration of Rain damages on Charri to Ghera road KM 0/00 to 8/555.(S.H:- RCC Wall at Rd 8/419.10 to 8/420.20.( Under PDNA)	99037/-	2000/-	Two Months	350/-

65	Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700.(Under PDNA).(S.H:- C/o C.C. Pavement at RD 2/985 to 3/00).	99160/-	2000/-	Two Months	350/-
66	Recovery and Reconstruction on Thehar to Pargod Road KM 0/00 to 9/000.(Under PDNA).(S.H:- C/o Breast wall and U-Shape drain at RD 0/900 to 0/918.86).	98010/-	2000/-	Two Months	350/-
67	Recovery and Reconstruction on Shahpur Kiari Charer Road Km 0/00 to 8/900 (Under PDNA)(S.H:-C/o R/Wall at RD 8/154 to 8/159.50).	91423/-	2000/-	Two Months	350/-
68	Restoration of Rain damages on Link road Salli to Konal road KM 0/00 to 2/250(S.H:- Construction of R/Wall with wire crate and C.C Pusta at RD 0/526 to 0/530).	99473/-	2000/-	Two Months	350/-
69	Restoration of Rain Damages on Various roads under Boh Section HP.PWD Darini Sub Division.(S.H:- Hiring of Excavator cum loader for removal of slips and tractor for Shiflig and carriage of material at various RDs.	98940/-	2000/-	One Month	350/-
70	Restoration of Rain Damages on Rulchar to Lam road 0/000 to 3/885.(S.H:- Hiring of Excavator cum loader for removal of slips and tractor for Shiflig and carriage of material at various RDs.	98940/-	2000/-	One Month	350/-
71	Recovery and Reconstruction on Shahpur Kiari Charer Road Km 0/00 to 8/900 (Under PDNA)(S.H:- C/o R/Wall at RD 8/135 to 8/142.50).	91413/-	2000/-	Two Months	350/-
72	Repair and Restoration of various roads under Shahpur Sub Division.(S.H:- Hiring of rock Breaker under Shahpur Section).	99200/-	2000/-	One Month	350/-
73	Restoration of Rain damages on various roads under Rait Section under HP.PWD Shahpur sub- Division .(S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
74	Restoration of Rain damages on Rait Neri Balla Tatwani Road (S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
75	A/R & M/O various roads under Shahpur Sub Division (S.H:- Hiring of Excavator cum loader for removal of slips).	99000/-	2000/-	One Month	350/-
76	Restoration of Rain damages Darini to Bhaler Road KM 0/00 TO 5/325. (S.H:- Hiring of Excavator cum loader for removal of slips at various RD.).	99000/-	2000/-	One Month	350/-
77	Restoration of Rain damages on various road under Darini Sub-Division(S.H:- Hiring of Excavator cum loader for removal of slips at various RD.).	99000/-	2000/-	One Month	350/-
78	Special repair of Vetnary Hospital Gohju in Teshil Shahpur at Distl. Kangra Himachal Pradesh. (SH:- Providing and fixing fencing in Boundary wall)	99000/-	2000/-	Two Month	350/-

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions:-

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer  
Shahpur Division  
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

Dated: 03/10/25

No.PWD/SD/Tender/NIT/2025-26/-

3904-13

Copy to following for information and necessary action:-

1. The Superintending Engineer 5<sup>th</sup> Circle HPPWD Palampur.
2. The Executive Engineer (IT) Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board

Executive Engineer  
Shahpur Division  
HP.PWD Shahpur.



SCHEDULE OF QUANTITY

Serno-345

(2)

ESTIMATED COST :- ₹ 98393.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (MOR) Km 0/00 to 12/800.  
 SUB-HEAD :- C/O Wire Gate wall with C.C.Pusla at RD 11/857 to 11/859.50. (PDRM)

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MOR technical specification clause 305.1 and as per the directions of the Engineer-In-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.10	350.00	Rupess Three Hundred Fifty Only	Per cubic metre	1785.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M:ten) nominal mix 1:3:6 (one cement two sand and six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.35	5380.00	Rupess Five Thousand Three Hundred Eighty Only	Per cubic metre	34163.00
3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.10	3450.00	Rupess Three Thousand Four Hundred Fifty Only	Per cubic metre	62445.00
<b>TOTAL :-</b>						<b>98393.00</b>
<b>Quoted Rate In Figure (%)</b>		<b>(Amount to be quoted by the contractor in figure)</b>				
<b>Quoted Rate In Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

134  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


342  
3

NAME OF WORK :- C/o Path from road to Gural house ward No-03 in G P Kallada. (VKV/2024/1578) Deposit work).  
SUB-HEAD :- Providing and Laying interlocking Paver Block.

ESTIMATED COST :- ₹ 93976.00  
EARNEST MONEY :- ₹ 1900.00  
TIME LIMIT : Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and purging and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350	Rupees Three Hundred Fifty Only	Per cubic metre	315.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M4en) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.25	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	6725.00
3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.44	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	6840.00
4	Providing and laying 60 mm thick interlocking M-40 grade Concrete paver block pavement conforming to ISI 15558:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	67.00	1100.00	Rupees One Thousand One Hundred Only	Per square metre	73700.00

5	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all	1.04	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	6356.00
11	Types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to					
12	two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water					
13	including curing complete for 14 (fourteen) days pumping or baling out water dewatering removal of slush as					
14	required at site which may arise at the time of laying under water complete for all heights / depths including the cost					
15	of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,805,807,1202 and 1204					
16	as per the directions of Engineer-In-Charge Including carriage of materials within all leads, lifts and other incidental.					
17	The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.					
TOTAL :-						
Quoted Rate in Figure (%)		[Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		[Amount to be quoted by the contractor in words]				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

340  
M

ESTIMATED COST:- ₹ 71135.00  
 EARNEST MONEY:- ₹ 15000.00  
 TIME LIMIT: Two Months

NAME OF WORK :- C/o Path along with interlocking tile from road towards Ravinder Pathania house ward No-02 In G.P Kallada (VKV/2025/469) Deposit work).  
 SUB HEAD :- Providing and Laying Interlocking Paver Block at RD 0/000 to 0/025.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.84	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	3990.00
2	Providing and laying 60 mm thick Interlocking M-40 Grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	56.40	1100.00	Rupees One Thousand One Hundred Only	Per square metre	62040.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.83	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	5105.00
<b>TOTAL :-</b>						<b>71135.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- 24215.00  
 EARNEST MONEY :- 1500.00  
 TIME LIMIT :- TWO MONTHS

**NAME OF WORK :-** Stock storage under HP.PWD Sub Division Gaggal.

**SUB-HEAD :-** Providing and laying prepainted Roof Right and left side.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal / Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with prepainted G.I. Impel and bitumen washers complete with all accessories as required within all leads, lifts of materials and other, incidentals as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	14.50	750.20	Rupees Seven Hundred Fifty And Paise Twenty Only	Per running metre	10878.00
2	Steel work welded in built up sections of Tr/Tr/Sail joists channels, angles, tees with connection plates or angles, cleat as in busses, russed purlins main and cross beams, hips jack rafters, purlins connected to common rafters and the like in building including cutting, fixing, lifting, hoisting and placing in position complete and applying a coat of red lead paint within all leads, lifts of materials and other incidentals, as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	715.20	105.00	Rupees One Hundred Five Only	Per kilogram	75095.00
3	Painting with satin enamel paints of Asian/Nerolac Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture complete as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	125.40	70.50	Rupees Seventy And Paise Fifty Only	Per square metre	8841.00
<b>TOTAL :-</b>						<b>94815.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shabpur Division,  
 HPPWD Shabpur

5

**SCHEDULE OF QUANTITY**

Sr No-280

(6)

ESTIMATED COST :- ₹ 98891.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- One Month

**NAME OF WORK :-** Recovery and Reconstruction on Rulerhar to Lam road KM 0/00 to 3/800. (Under PDNA).

**SUB-HEAD :-** Windridge of Damages and Construction of Unlined road at RD 0/850 to 0/895.00.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	4	5	6	7
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions, Excavated material to be used in embankment with a lift upto 3 metre and lead of 50 metre (average lead 25 metre) as per technical specification clause 307. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	40.00	65.00	Rupees Sixty Five Only	Per cubic metre	2600.00
<b>TOTAL :-</b>						<b>98891.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

Ser no - 346

7

NAME OF WORK :- Restoration of Rain Damages in Chambi to Dharamshala road (WDR) Km 0/00 to 12/800.

SUB-HEAD :- c/o Wire Gate wall with C.C.Pussa at RD 13/855 to 11/856.50. (Under PDNA)

ESTIMATED COST :- ₹ 99422.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.75	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2013.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement iso three sand iso six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in for under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34970.00
3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.10	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	62445.00
<b>TOTAL :-</b>						<b>99422.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


238

8

ESTIMATED COST :- ₹ 99200.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF** Repair and Restoration of various roads under shahpur sub Division  
**SUB-HEAD :-** Hiring of rock Breaker under Shahpur section

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Rock Breaker having 2 to 4 tonne hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulders etc and other similar road works requiring breaking of rock and boulders on road in various reaches up to any height, depth and disposal of material up to 20.00 meters lead in all kind and classification of soil including rocky portion as per direction and entire satisfactions of Engineer- in charge. The Rock Breaker should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring period/execution of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff will be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer in Charge. The rate is inclusive of GST and all other type taxes, royalties etc imposed by central or state government.	32.00	3100.00	Rupees Three thousand and one hundred only	Per Hour	99200.00
<b>TOTAL :-</b>						<b>99200.00</b>
<b>Quoted Rate In Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure</b>
<b>Quoted Rate In Words (%)</b>						<b>(Amount to be quoted by the contractor In words)</b>

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 71280.00  
 EARNEST MONEY :- ₹ 1500.00  
 TIME LIMIT :- Two Months

341

**NAME OF WORK :-** C/o Path along with interlocking tile from road towards Ravinder Pathania house ward No-02 In G.P Kailada .(VKV/2025/469)Deposit work).

**SUB-HEAD :-** Providing and Laying interlocking Paver Block at RD 0/025 to 0/050.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.84	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	3990.00
2	Providing and laying 60 mm thick Interlocking M-40 grade Concrete paver block pavement confirming to ISI 15658:2006 having thickness 60mm (sixty millimetre) as per drawings and Technical Specification Clause 1504 (The execution of interlocking paver block shall be allowed after duly testing from the authorized labs) and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	56.70	1100.00	Rupees One Thousand One Hundred Only	Per square metre	62370.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths Including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.80	6150.00	Rupees Six Thousand One Hundred Fifty Only	Per cubic metre	4920.00
<b>TOTAL :-</b>						<b>71280.00</b>
<b>Quoted Rate In Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

237

ESTIMATED COST :- ₹ 89450.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF** Restoration of Rain damages on various Roads under Charri Section under Gaggal Sub Division  
**SUB-HEAD :-** Removal of slips in various Reaches.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials within lift upto 1.50 mtrs (One decimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 302.3.5 and 1611 within all leads, lifts of materials and other Incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge, The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1530.00	65.00	Rupees sixty Five only	per Cum	99450.00
<b>TOTAL :-</b>						<b>99450.00</b>
<b>Quoted Rate in Figure (%)</b>						(Amount to be quoted by the contractor in Figure )
<b>Quoted Rate in Words (%)</b>						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shapaur Division,  
 HPPWD Shabaur

**SCHEDULE OF QUANTITY**

ESTIMATED COST:- ₹ 95701.00  
 EARNEST MONEY :- ₹ 1920.00  
 TIME LIMIT : Two Months

344

**NAME OF WORK :-** Repair of community Hall near Matti ward No-04 In G.P Gharoh.(Deposit work).  
**SUB-HEAD :-** Providing and laying frame work for door & plastering, flooring work etc.

S. No.	Description of items	Quantity	RATES			Unit	Amount
			In fig	In words			
1	15 mm (fifteen millimeter) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering up to all floor levels including angles, chamfers and rounded angles not exceeding 80mm (Eighty millimeter) in girth and finished even and smooth with cement mortar 1:6 (One cement (six sand) as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3	230.50	Rupees Two Hundred Thirty And Paise Fifty Only	Per cubic metre	32180.00	
2	Providing and laying Size of (800x 600mm) vetnifed tiles of Resilite/Nico /Rak/Kajaria / Orient -Bell/AGU/Simpolio /Johnson/Somanyas per approved shade and design of the office (thickness to be specified by the manufacturer) with water absorption less than 0.08% ( zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm ( Twenty millimetres) thick cement mortar 1:4 (one cement (six coarse sand), joining with grey cement slurry @ 3.3 kg/ sqm ( three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etc., complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	27.67	1360.70	Rupees One Thousand Three Hundred Sixty And Paise Seventy Only	Per square metre	37651.00	
3	Providing 2nd class Decodar wood wood work in frames of doors/windows, clerestory, windows and other frames wrought/framed and fixed in position, within all leads, lifts of materials and other incidentals, as per approved specification, drawing, design and as directed by the Engineer-In-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	0.28	99500.00	Rupees Ninety Nine Thousand Five Hundred Only	Per cubic metre	25870.00	
<b>TOTAL :-</b>							<b>95701.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor In Figure )	
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)	

  
 Executive Engineer,  
 Shajapur Division,  
 HPPWD Shajapur

①

**SCHEDULE OF QUANTITY**

Sc 2020 - 381

12

ESTIMATED COST :- ₹ 98291.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF WORK :-** Recovery and Reconstruction on Rulerhar to Lam road Km 0/00 to 3/800. (Under PDNA).

**SUB-HEAD :-** Widening of Damages and Construction of Unlined road at RD 0/900 to 0/945.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In Fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	370.35	260.00	Rupees Two Hundred Sixty Only	Per cubic metre	98291.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3 metre and lead of 50 metre (average lead 25 metre) as per technical specification clause 307. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	40.00	65.00	Rupees Sixty Five Only	Per cubic metre	2600.00
<b>TOTAL :-</b>						<b>98891.00</b>
<b>Quoted Rate in Figure (%)</b>						(Amount to be quoted by the contractor in Figure )
<b>Quoted Rate in Words (%)</b>						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shahpur Division,  
 HPPVVD Shajohar

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99125.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

336

(18)

**NAME OF** Restoration of Rain damages on various Roads under Gaggal Section under Gaggal Sub Division  
**SUB-HEAD :-** Removal of slips In various Reaches.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials withn lift upto 1.50 mtrs (One declimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 302.3.5 and 1611 within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by theEngineer-in-Charge, The rate is inclusive, toll taxes, GST and any othertaxes imposed by the Government.	1525.00	65.00	Rupees sixty Five only	per Cum	99125.00
<b>TOTAL :-</b>						<b>99125.00</b>
<b>Quoted Rate In Figure (%)</b>		<b>(Amount to be quoted by the contractor In Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor In words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

14

Ser no - 343

ESTIMATED COST :- ₹ 92216.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Restoration of Rain Damages in Chambal to Dharamshala road (MOR) Km 0/00 to 12/800.  
**SUB-HEAD :-** C/o Wire Gate wall with C.C.Pusta at RD 11/858.70 to 11/860 (Under PDWA)

5. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MOR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.20	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1820.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement : six three sand : six crushed stone aggregate 40 mm (forty millimeter) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.45	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34701.00
3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (five millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.90	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61755.00
<b>TOTAL :-</b>						<b>98276.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure.)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


15  
50 mo - 382

ESTIMATED COST :- ₹ 98891.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF WORK :-** Recovery and Reconstruction on Rulehar to Lam road KM 0/00 to 3/800 (Under PDNA).

**SUB-HEAD :-** Widning of Damages and Construction of Unlined road at RD 0/950 to 0/995.

S.No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging cut of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	370.35	250.00	Rupees Two Hundred Sixty Only	Per cubic metre	96291.00
2	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3 metre and lead of 50 metre (average lead 25 metre) as per technical specification clause 307. The rate includes octroi,royalty,Malkana,Tol tax, GST or any other taxes imposed by the Government.	40.00	65.00	Rupees Sixty Five Only	Per cubic metre	2600.00
<b>TOTAL :-</b>						<b>98891.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shahur Division,  
 HPPWD Shahur

SCHEDULE OF QUANTITY

(16)

ESTIMATED COST: ₹ 73373.00  
 EARNEST MONEY ₹ 1500.00  
 TIME LIMIT Two Months

NAME OF WORK :- Restoration of Rain Damage on Dohab to Kurrella road KM 0/00 to 4/000.

SUB-HEAD :- C/Protection of abutment at KM 0/832 to 1/103. (Under P.D.M.F)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge Including scutting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting, and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.80	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2380.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in too wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800, 900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	12.95	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	69283.00
3	Filling with Stone boulder under floors including ramming, consolidating and dressing complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	1710.00
<b>TOTAL :-</b>						<b>73373.00</b>
		Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)		
		Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)		

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Srinagar

SCHEDULE OF QUANTITY


(17)

ESTIMATED COST :- ₹ 99581.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : : : : : Two Month

NAME OF WORK :- Construction of Retaining wall to the Land of Sh. Subhash Chand S/o Hari Chand Vill Bhairu G.P. Nerti Tehsil Shahpur. Under-VKV/2025/760)  
 (Deposit Work).  
SUB-HEAD :- Retaining wall at RD 0/037 to 0/044.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MQRD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.87	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	90761.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H).One vertical : Twenty Horizontal) towards drainage, face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.00	350.00	Rupees Three Hundred Fifty Only	Each	3150.00
TOTAL :-						
	Quoted Rate in figure (%)	(Amount to be quoted by the contractor in figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD, Shampdi

SCHEDULE OF QUANTITY

Sr no - 383

(18)

ESTIMATED COST :- ₹ 98510.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages in Chamal to Dharamshala road (MDR) Km 0/00 to 12/800.  
 SUB-HEAD :- C/o Wire Gate wall with C.C.Purta at RD 11/850 to 11/852.50. (Under PDMA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In /sq	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chipping / weighing wet rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5 10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1785.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement : two three sand : six crushed stone aggregate 40 mm (forty millimeter) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.50	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34970.00
3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (five millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimeter) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.90	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61755.00
<b>TOTAL :-</b>						<b>98510.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

Executive Engineer,  
 Shapur Division,  
 HPPWD Shapur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97500.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various Roads under Gaggal Section under Gaggal Sub Division  
SUB-HEAD :- Removal of slips in various Reaches.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials within lift upto 1.50 mtrs (One decimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 302.3.5 and 1611 within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1500.00	65.00	Rupees sixty Five only	per Cum	97500.00
<b>TOTAL :-</b>						<b>97500.00</b>
<u>Quoted Rate in Figure (%)</u>						(Amount to be quoted by the contractor in Figure )
<u>Quoted Rate In Words (%)</u>						(Amount to be quoted by the contractor in words)

*Yash*  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on Salli Kharl Behi Road km 0/000 to 9/570

SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor In all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<u>Quoted Rate in Figure (%)</u>		<u>(Amount to be quoted by the contractor in Figure )</u>				
<u>Quoted Rate in Words (%)</u>		<u>(Amount to be quoted by the contractor in words)</u>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

334

200

SCHEDULE OF QUANTITY


333

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

B1

**NAME OF** Restoration of Rain damages on Kutharna to Kareeri Road km 0/000 to 8/720  
**SUB-HEAD :-** Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shabapur

**SCHEDULE OF QUANTITY**

ESTIMATED COST: ₹ 73279.00  
 EARNEST MONEY ₹ 1500.00  
 TIME LIMIT Two Months

301/22

NAME OF WORK :- Restoration of Rain Damage on Dohab to Kurella road Km 0/00 to 4/000.  
 SUB-HEAD :- Protection of abutment at Km 0/540 to 0/530. (INDURDNT)

S No.	Description of items	Quantity	RATES		Unit	Amount
			In Fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including cartage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2329.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement, two three sand and six crushed stone aggregate 40 mm (forty millimetres) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including cartage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	12.56	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	65335.00
3	Filling with Stone boulder under floors including leveling ramming, consolidating and dressing complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including cartage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.80	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	2710.00
<b>TOTAL :-</b>						<b>73279.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahnour Division,  
 HPPWD Shikhar

SCHEDULE OF QUANTITY

23-51

ESTIMATED COST: - ₹ 97445.00  
 EARNEST MONEY :- ₹ 1950.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot In G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.). (Under S.C.S.P)

SUB-HEAD :- Construction of V-Shape Drain at RD 0/852 to 0/861 (Both side RHS & LHS).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any head and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted (thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any head and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted (thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	58.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	20300.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	13.70	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	73295.00

03251

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1						
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	350.00	Ruppes Three Hundred Fifty Only	Each	3850.00
<b>TOTAL :-</b>						<b>97445.00</b>
	Quoted Rate In Figure (%)	(Amount to be quoted by the contractor In Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor In words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98970.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : 1 Year Months

Sr no - 585  
 (24)

NAME OF WORK :- Restoration of Rain Damages In Chambi to Dharamshala road (MDR) Km 0/00 to 12/800.  
 SUB-HEAD :- C/O Wire Gate wall with C.C.Pusta at RD 11/852.70 to 11/854. (MDRPPDNF)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.15	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1803.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement iso three sand iso six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, or other taxes imposed by the Government.	6.55	5350.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	34725.00
3	Providing and laying of boulder apron or Gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4526 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 20 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.95	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	61925.00
<b>TOTAL :-</b>						<b>98970.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in figure )
Quoted Rate In Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

55


ESTIMATED COST :- ₹ 99231.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Month

**NAME OF WORK :-** Construction of Retaining wall to the Land of Sh. Subhash Chand S/o Hari Chand Vill Bhalru G.P. Neri Tehsil Shahpur. Under-VKV/2025/760  
 (Deposit Work).

**SUB-HEAD :-** Retaining wall at RD 0/028.50 to 0/036.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	16.87	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	90761.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	8.00	350.00	Rupees Three Hundred Fifty Only	Each	2800.00
TOTAL :-						99231.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Sindh

SCHEDULE OF QUANTITY

25 287


ESTIMATED ₹ 93296.00  
 EARNEST MONEY ₹ 1900.00  
 TIME LIMIT Two Months

NAME OF WORK :- Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250.

SUB-HEAD :- Retaining wall in C/C 1:4:8 and Wire grate at Km 13/276.80 to 13/279.20 (Under PUMP)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.63	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2671.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.95	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	28263.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.89	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	757.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry; plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
5	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boundaries weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.74	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60905.00
<b>TOTAL :-</b>						<b>93296.00</b>
			<b>Quoted Rate in Figure (%)</b>			
			<b>Quoted Rate in Words (%)</b>			

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shabkar

SCHEDULE OF QUANTITY

27

ESTIMATED COST :- ₹ 99532.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link Road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P). (Under S.C.S.P)

SUB-HEAD :- Providing and laying G-II & G-III at RD 0/815 to 0/900 .

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty -one hundred) KN static roller to meet requirement of Table 300.2 complete as per MORO technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3789.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II [75mm (seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.20 cum (zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum (zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	26.95	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	57943.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1						
2	Providing laying spreading and compacting by motor-driven means stone aggregate size 50mm to 22.5mm (75 to 90mm millimeter to twenty two point five millimeter) Grading in situ (75mm average five millimeter) constructed thickness to cover below minimum specification including spreading in uniform thickness using mechanical hand packing rolling with three wheel 800 X 500 (rough standard) K.M. stable roller to prepare grade and surface, applying and broasting stone screening type B of size 11.25mm (average four millimeter) material also at the rate of 0.45 cum/cum front sighters table method per 10 Sqm (one ten square meter) and to fill up the thickness of coarse aggregate, watering and compacting to the required density as per MCO (technical specifications section 433) and as per the work satisfaction and direction of Engineer-in-Charge including carriage of materials within all roads, lifts and other incidental the rate is including other royalty Materials will be GST and any other taxes imposed by the Government	16.80	2250.00	Two Thousand Two Hundred & Fifty Only	Per cubic metre	37500.00
	Quotest Rate in figure (%)		[Amount to be quoted by the contractor in figure]			
	Quotest Rate in word (%)		[Amount to be quoted by the contractor in words]			
<b>TOTAL =</b>						<b>37500.00</b>

  
 Executive Engineer,  
 Sanitary Division,  
 H.P.P.W.D. Shyambagar

SCHEDULE OF QUANTITY

28


ESTIMATED COST: . . . ₹ 99581.00  
 EARNEST MONEY : . . . ₹ 2000.00  
 TIME LIMIT : . . . Two Month

NAME OF WORK :- Construction of Retaining wall to the Land of Sh. Subhash Chand S/o Harl Chand Vill Bhairu G.P. Nerti Tehsil Shahpur. Under-(VKV/2025/760) (Deposit Work).

SUB-HEAD :- Retaining wall at RD 0/020 to 0/027.50.

S.No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.87	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	90761.00

<p>3 Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.</p>	9.00	350.00	Rupees Three Hundred Fifty Only	Each	3150.00
TOTAL :-					99581.00
Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: 299,34.55  
 ELEMENT MONEY: 205,55  
 TIME LIMIT: 2  
 TIME MONITOR: 2

NAME OF WORK :- Special repair of Veterinary Hospital Gohju in Tehsil Shahpur of Distt. Kangra Himachal Pradesh.  
 SUBHEAD :- C/O Boundary wall.

S. No.	Description of Work	Quantity	UNIT		RATE	AMOUNT
			IN SQ	IN WORDS		
1	Providing and laying mechanically mixed and vibrated lean cement concrete as per drawings and V.O. and technical specifications section 350, 350, 1250 and 1550 general and 142 (One corner 500 four and two eight grassed/curved stone aggregate) from 5000 millimeters) normal size, for all type of concrete like retaining wall / Steps wall etc. Retaining wall of height upto 1.5m and other concrete as per the direction of Engineer-in-charge Retaining structure of height upto 1.5m. This of work shall be done in accordance with the rate in retaining work, rate for, cost and any other work incurred by the Government.	375	4755.00	125000	Per cubic	7755.00
2	Work on above mentioned concrete structure (retaining wall) to be done with 1:2:4 concrete with 10% excess quantity in foundation and other retaining walling up with cement concrete 1:2:12 (one corner) for work : Twelve grassed stone aggregate 50mm (height) millimeter normal size mechanical mixed concrete 1:2:4 (one corner for work) as per the entire specification and direction of the Engineer-in-charge Retaining structure of height upto 1.5m. This and other work shall be done in accordance with the rate in retaining work, rate for, cost and any other work incurred by the Government.	15.50	4255.50	125000	Per cubic	3197.25
TOTAL :-						9952.25
Quoted Rate in Figure (%)		Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		Amount to be quoted by the contractor in words)				

  
 Engineer-in-Charge,  
 Station Division,  
 Himachal Pradesh

SCHEDULE OF QUANTITY

96

288


NAME OF WORK :- Restoration of Rain damages on Shahpur Chakban Lapiana road KM 0/00 to 20/250.

UB-HEAD :- Retaining wall In C/C 1:4:8 and Wire crate at Km 13/279.20 to 13/280.60 (w/bv PDN F)

ESTIMATED ₹ 93058.00  
EARNEST MONEY ₹ 1900.00  
TIME LIMIT Two Months

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.63	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2671.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement 1st0 Four sand 1st0 Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.90	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	28025.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	0.89	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	757.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3		5	6	7
2						
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
5	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.74	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60905.00
		<b>TOTAL :-</b>				<b>93058.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**


ESTIMATED COST :- ₹ 97525.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : : Two Months

NAME OF WORK :- Restoration of Rain Damage on Charri to Bhitlu road KM 0/00 to 5/780.

SUB-HEAD :-

C/o Wire Crate wall at RD 4/130 to 4/135. (Under PDNA)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4926 in 100mm x100mm (Hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.40	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	97320.00
	<b>TOTAL :-</b>					<b>97380.00</b>
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 H.P. Shahpur

SCHEDULE OF QUANTITY

32

327


ESTIMATED COST :- ₹ 98730.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK : Restoration of Rain Damage on various roads under Shahpur Sub Division.

SUR-HEAD : Providing and laying WBM G-III on Raft to Kohla Road at RD 4/800 to 4/875.

(under MMSRD)

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm( seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	43.88	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	98730.00
		<b>TOTAL :-</b>				<b>98730.00</b>
<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in Figure )				
<u>Quoted Rate in Words (%)</u>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 H.P.D.O Shahpur

SCHEDULE OF QUANTITY

ESTIMATED ₹ 92708.00  
 EARNEST MONEY ₹ 1900.00  
 TIME LIMIT Two Months

286  
 (33)

NAME OF WORK :-

Restoration of Rain damages on Shahpur Chakhan Lohana road KM 0/00 to 20/250.

SUB-HEAD :-

Retaining wall in C/C 1:4:8 and wirecrete at Km 13/273.40 to 13/275.80 (MADY PDNA)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and punning and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.63	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2671.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement iso Four sand iso Eight graded/crushed stone aggregate) 40mm (Forty millimeters) nominal size) for all type of structure like retaining wall / breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octrol, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.90	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	28025.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octrol, toll tax, GST or any other taxes imposed by the Government.	0.89	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	757.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.00	350.00	Rupees Three Hundred fifty Only	Each	350.00
5	Providing and laying of boulder apron or gabin walls laid in wire crates with 5mm (five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.74	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60905.00
<b>TOTAL :-</b>						<b>92708.00</b>
	<b>Quoted Rate in Figure (%)</b>	<b>(Amount to be quoted by the contractor in Figure )</b>				
	<b>Quoted Rate in Words (%)</b>	<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shajpur Division,  
 HPPWD Shajpur

**SCHEDULE OF QUANTITY**

**34**


**290**

**NAME OF WORK :** Restoration of Rain drainages on Link road Garoli Garh Matil Km 0/00 to 2/500.

**ESTIMATED COST :** ₹ 97024.00  
**EARNEST MONEY :** ₹ 1950.00  
**TIME LIMIT :** Two Months

**SUB-HEAD :** C/O V-Shape Drain at RD 1/500 to 1/557. (Under PDNH)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3				
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	17.10	5380.00	Rupess Five Thousand Three Hundred Eighty Only	Per cubic metre	91995.00
<b>TOTAL :-</b>						<b>97024.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in figure)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


85  
85

ESTIMATED COST :- ₹ 97980.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Restoration of Rain Damage on Charri to Bhillu road KM 0/00 to 5/780.

SUB-HEAD :- C/o Wire Gate wall at RD 4/137 to 4/141. (Under PDWA)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.40	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	97980.00
<b>TOTAL :-</b>						<b>97980.00</b>
<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in figure )				
<u>Quoted Rate in Words (%)</u>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shajpur Division,  
 HPWD Shajpur


SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 98730.00  
 EARNEST MONEY : ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damage on various roads under Shahpur Sub Division.

SUB-HEAD :- Providing and laying WBM G-III on Rait to Kohla Raod at RD 4/950 to 5/025. (under MMSRY)

S No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size (75mm) seventy five millimeters) compacted thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming. stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORO technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrol, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government..	43.88	2250.00	Rupees Two thousand Two Hundred Fifty Only	Per cubic metre	98730.00
<b>TOTAL :-</b>						<b>98730.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shahpur Division,  
 Hapur Shahpur

36  
328

SCHEDULE OF QUANTITY

370246


ESTIMATED COST: - ₹ 99250.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT: Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot In G.P. Durgolla KM 0/00 to 0/900 In Tehsil Shahpur Distt. Kangra (H.P.). (Under S.C.S.P)

SUB-HEAD :- Providing and laying G-II & G-III at RD 0/415 to 0/478.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads. transporting to site. spreading, grading by mechanical means to required slope and compacted with three wheel 80-100 (eighty -one hundred) KN static roller to meet requirement of Table 300.2 complete as per MORD technical Specification section 400 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	3	91.30	Rupees Ninety One And Paise Thirty Only	Per cubic metre	3800.00
2	Providing, laying, spreading and compacting by mechanical means crushed stone aggregate size 63mm to 4.5mm ( sixty three millimetre to forty five millimetre) Grading-II (75mm ( seventy five millimetres) consolidated thickness) to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm ( eleven point two millimetres) nominal size at the rate of 0.20 cum ( zero point two zero cubic metres) per ten square metres and binding material at the rate of 0.06 cum ( zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications section 400 and as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	26.50	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per cubic metre	56975.00

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3	4	5	6	7
3	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-II size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	17.10	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	38475.00
<b>TOTAL :-</b>						<b>99250.00</b>
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shalique

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 98469.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

S r no - 378

58

NAME OF WORK : C/O Link road Rajol To Gharon Km 0/00 to 6/00.

SUB-HEAD : C/O U-shape Drain at RD 1/220 to 1/248 (Under PDM)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chipping/ wedging out rocks (where blasting is prohibited) as per drawings and MQRD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted (thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantity of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.71	350.00	Rupees Three Hundred Fifty only	Per cubic metre	3399.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement 150 three sand 150 six crushed stone aggregate 40 mm (forty millimeter) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in toe wall etcetera as per drawings and M.Q.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.50	5380.00	Rupees five Thousand Three Hundred eighty only	Per cubic metre	88770.00
	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MQRD technical specification section 700 and 1200 and as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.00	350.00	Rupees Three Hundred Fifty only	each	6300.00
<b>TOTAL :-</b>						<b>98469.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD, Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 99015.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months:

39

**NAME OF WORK :-** Restoration of Rain Damage on Sudher to Dhar road KM 0/00 to 1/500.

**SUB-HEAD :-** C/o Wire Crate wall at RD 0/325 to 0/345. (Under PDNA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying of boulder apron of gabin walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4825 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone bounders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	28.70	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	99015.00
<b>TOTAL :-</b>						<b>99015.00</b>
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

1357  
 Executive Engineer,  
 Shalpur Division,  
 HPPWD Shalpur

SCHEDULE OF QUANTITY

ESTIMATED COST : ₹ 97563.00  
 EARNEST MONEY : ₹ 2000.00  
 TIME LIMIT : 2 Months  
 470

NAME OF WORK :- Improvement of Black spot on Nertl Dherun Sandh Road KM 0/00 to 3/600 in Tehsil Shahpur Distt Kangra (H.P).  
 SUB-HEAD :- C/o Breast wall at RD 0/405 to 0/420.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising; of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and balling out water (surface and sub soil water) upto any depth any quantum of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	15.75	350.00	Ruppes Three Hundred Fifty Only	Per cubic metre	5513.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-In-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.20	5250.00	Ruppes Five Thousand Two Hundred Fifty Only	Per cubic metre	85050.00

<p><b>3</b> Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weed holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, return walls and retaining/breast walls extended through the full width of the structure with slope (V) 20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and M.O.R.D technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malana, toll tax, GST and any other taxes imposed by the Government.</p>	20.00	350.00	Rupees Three Hundred Fifty Only	Each	7000.00
<p>Quoted Rate in Figure (%)</p>	TOTAL :- 97565.00				
<p>Quoted Rate in Words (%)</p>	(Amount to be quoted by the contractor in figure ) (Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 MPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED ₹ 95692.00  
 EARNEST MONEY ₹ 1950.00  
 TIME LIMIT Two Months


Sr no - 348  
 41

NAME OF WORK :- Restoration of Rain damages on Shahpur Chakhan Lapiana road KM 0/00 to 20/250.

SUB-HEAD :- Retaining wall in C/C 1:4:8 and Wire crate at Km 13/320 to 13/322.54 (under PDR)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.07	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2825.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.35	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	30163.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	2.21	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	1879.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.00	350.00	Rupees Three Hundred Fifty Only	Each	700.00
5	Providing and laying of boulder apron or gabn walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, 95 per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.50	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per cubic metre	60125.00
TOTAL :-						95692.00
		(Amount to be quoted by the contractor in Figure )				
		(Amount to be quoted by the contractor in words)				
		Quoted Rate in Figure (%)				
		Quoted Rate in Words (%)				

  
 Executive Engineer,  
 Shahpur Division,  
 H.P.W.B. Shahpur

**SCHEDULE OF QUANTITY**

Semo - 375


(42)

ESTIMATED COST :- ₹ 99312.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Chhario Ghera road Km 0/00 to 8/555.  
 SUB-HEAD :- RCC Wall at RD 8/416 to 8/417.50. (under PDNA)

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1540.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.19	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	903.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.40	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	52910.00

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	463.80	90.50	Rupees Ninety And Paise Fifty Only	Per Killogram	41974.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.10	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	935.00
TOTAL :- 99312.00						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shajapur Division,  
 H.P.B.M.O Shajapur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 63875.00  
 EARNEST MONEY :- ₹ 1300.00  
 TIME LIMIT :- Two Months

43

**NAME OF WORK :-** Improvement og Black spot on Nertl Bherun Sandh Road KM 0/00 to 3/600 In Tehsil Shahpur Distt Kangra (H. P).  
**SUB-HEAD :-** C/o Breast wall at RD 0/422 to 0/432.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantum of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement 1sto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	10.80	5250.00	Rupces Five Thousand Two Hundred Fifty Only	Per cubic metre	56700.00

<p>3 Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe every 10m in brick masonry/stone masonry, plain / reinforced concrete Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V:20) (One vertical : Twenty Horizontal) towards draining face complete as per drawing and M.O.R.D technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all heads, lifts and other expenses. The rate is including octroi, royalty, Mahara, salt tax, GST and any other taxes imposed by the Government.</p>	10.00	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
<b>TOTAL :-</b>					
Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shaque Division,  
 MPWD Saurashtra

**SCHEDULE OF QUANTITY**

**NAME OF WORK :-** Restoration of Rain damages on Link road Garh Garh Matti Km 0/00 to 2/500.


**SUR-HEAD :-** C/O R/Wall at RD 1/160 to 1/615.80.

ESTIMATED COST :- ₹ 98917.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

414  
291

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.87	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3105.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 200, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.21	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	88443.00

3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00	350.00	Rupees Three Hundred Fifty Only	Each	1750.00	
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.51	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5619.00	
TOTAL :-							
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in figure)					98917.00
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)					

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**


655

ESTIMATED COST : ₹ 93755.00  
 EARNEST MONCY : ₹ 2000.00  
 TIME LIMIT : Two Months

NOTE ON WORK :- Annual repair and maintenance of various roads under Union HP, PW, Sub Division Gargal.

SCHEDULE :- Painting and writing lettering, figures and kilometre stone etc. (under Harchankin Section.)

S. No.	Description of items	Quantity	RATE		Unit	Amount
			Rs	Paise		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint including to give an even shade including cleaning the surface to remove all dirt, dust and other foreign matter with enamel paint other than white including cartage of materials within all limits, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.00	23.00		Per square metre	875.00
2	Painting two or more coats of Nerolac/Asian paint/ Berger (excluding priming coat) on previously concrete based surface with enamel paint white to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stoping, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer in-Charge including cartage of material within all limits, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	35.00	52.00		Per square metre	1820.00
3	Writing letters on any surfaces with synthetic enamel paint (other than white) stops, corners, hydrants and the like not to be measured and paid separately, Block letters, Indian letters / figures, etc. including cartage of materials within all limits, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3660.00	2.65		Per letter per centimetre height	9699.00
<b>TOTAL :-</b>						<b>93755.00</b>
(Amount to be quoted by the contractor in Figure ) (Amount to be quoted by the contractor in words)						

  
 I certify Engineer,  
 Harchankin Division,  
 Rewari District.

SCHEDULE OF QUANTITY

Sr no - 379

45

NAME OF WORK :- Restoration of Rain damages on Charrri to Gherra road Km 0/00 to 8/555.

SUB-HEAD :- RCC Wall at RD S/A14.410 to 8/A15.90. (Under PDNA)

ESTIMATED COST :- ₹ 99758.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing; removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4.65	Rupees Three Hundred Fifty Only	Per cubic metre	1628.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement 1sto Four sand 1sto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.19	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	903.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.45	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	53268.00

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	463.80	50.50	Rupees Ninety And Paise Fifty Only	Per Killogram	41974.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORC technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.10	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	935.00
TOTAL :-						99758.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shajpur Division,  
 Hapurid Shikhar

SCHEDULE OF QUANTITY

256

ESTIMATED COST :- ₹ 93680.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Link road Palwala to Lanjot in G.P. Durgella KM 0/00 to 0/900 in Tehsil Shahpur Distt. Kangra (H.P.). (Under S.C.S.P)

SUB-HEAD :- Construction of V-Shape Drain at RD 0/040 to 0/050 (Both side RHS & LHS).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORR technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	60.00	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	21000.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	13.80	5350.00	Rupees Five Thousand Three Hundred Fifty Only	Per cubic metre	73830.00

No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1		3				
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORR technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	11.00	350.00	Rupees Three Hundred Fifty Only	Each	3850.00
<b>TOTAL :-</b>						<b>98680.00</b>
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Shahpur


## Schedule of quantity

**NAME OF WORK:-** A/R & M/O various road under Sub- Division Chingal  
( Sit.- Providing Fixing And Painting of Kilometer Stone, writing letters, etc.)

Estimate cost:- 90522.00/-  
Earnest Money:- 1850.00/-  
Time limit: One Month

(48)

Sr.No.	Description of item	Qty	Rate	Unit	Amount
1	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703. As per direction of Engineer -in-Charge. The rate including octroi, Mulkann , toll tax ,GST or other taxes imposed by the Government .				
(i)	Ordinary KM Stone	8.00	2620.00	Each	20960.00
(ii)	200 Mtr Stone	12.00	800.00	Each	9600.00
2	Painting one or more coat (excluding priming coat) on previously painted concrete plastered surface masonry wall with enamel paints of approved brand and manufacture for on floor to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering as required with in all leads, and other incidental.	130	46.90/-	Per/sqm	6097.00
3(i)	Writing letter or figures on any surface with synthetic enamels other than white stop, commas hyphens and the like not to be measured and paid for separately with in all leads, lifts of material and incidentals. i) Indians letters/ figures	7150	2.10/-	Per letter per cm height	15015.00
3(ii)	(ii) Block letters / figures	18500	2.10/-	Per letter per cm height	38850.00
Total Rs:-					<b>90522.00</b>
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)			
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)			

  
 Executive Engineer  
 Sheshpur Division  
 HANMANGI, SIKHAR

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 91099.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months


(49)

NAME OF WORK :- Recovery and Reconstruction on Shahpur Kiari Charter Road Km 0/00 to 8/900 (Under PDNA)

SUB-HEAD :- C/o R/Wall at RD 8/16L50 8/167.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.63	850.00	Rupees Eight Hundred fifty Only	Per cubic metre	4786.00
<b>TOTAL :-</b>						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				
						91099.00

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

ESTIMATED COST : - ₹ 99582.00  
 EARNEST MONEY : - ₹ 2000.00  
 TIME LIMIT : Two Months

Sr no - 319

50

NAME OF WORK : C/O Link road Rajol To Sharoh km 0/00 to 6/00  
 SUB-HEAD : C/O U-shape Drain at RD 1/250 to 1/280

5 No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chipping/ wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of slides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.20	350.00	Rupees Three Hundred fifty only	Per cubic metre	3220.00
2	Providing and laying mechanically mixed and vibrated plain concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement 1:30 three sand 1:50 six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800/900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	16.61	5380.00	Rupees five Thousand Three Hundred eighty only	Per cubic metre	89362.00
	Providing and laying 100mm (one Hundred millimetre) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	20.00	350.00	Rupees Three Hundred Fifty only	each	7000.00
<b>TOTAL :-</b>						<b>99582.00</b>
<b>Quoted Rate In Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure)</b>				
<b>Quoted Rate In Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Sharoh Division,  
 HPPWD Sharohpur

SCHEDULE OF QUANTITY

NAME OF WORK :- Construction of Link road link NH 154 To Dhantnu via Bad Basti km 0/00 to 3/670 Dist Kangra (H.P.), Under RIDE-XXX (NABARD)

SUB-HEAD :- Providing Record and Printing and writing Lettering, Figures etcetra.

ESTIMATED COST: ₹ 99708.00  
 EARNEST MONEY: ₹ 2000.00  
 UNIT LIMIT : One Month

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Painting two coats (excluding priming coat) on previously steel and other metal surfaces with enamel paint by adding to give an even shade including cleaning the surface to remove all dirt and other foreign matter with enamel paint other than white including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	45.00	36.10	Rupees Thirty Six And Paise Ten Only	Per square metre	1624.50
2	Providing and erecting direction and place identification retro-reflective sign boards, as per IRC-67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3, fixed over aluminium sheeting width, 2 mm (two millimeters) thick with area not exceeding 0.50 sqm (zero point nine zero) supported on mild steel iron post 75 mm x 75 mm x 6 mm, (seventy five into seventy five into six millimeters), 2 Nos. (two numbers) firmly fixed to the ground by means of properly designed foundation with M-15 grade (forty-five grade) cement concrete 250x450x500mm (four hundred fifty into four hundred fifty into six hundred millimetre), 600mm (six hundred millimetre) below ground level as per approved drawings and technical specification section 1700, including painting angle iron post with primes and two coats of Epoxy paint as per specification and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	10500.00	Rupees Ten Thousand Five Hundred Only	Each	10500.00
3	Writing letters or figures on any surfaces with synthetic enamel paint (other than white) stops, commas, hyphens and the like not to be measured and paid separately, Block letters, Indian letters / figures etc including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	33050.00	2.65	Rupees Two And Paise Sixty Five Only	Per letter per centimetre high	87583.00
<b>TOTAL :-</b>						<b>99708.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Executive Engineer,  
 Shahpur Division,  
 HPPVID Shahpur

(51)

KISHU Khanday

**SCHEDULE OF QUANTITY**

ESTIMATED COST : ₹ 93999.00  
 EARNEST MONEY : ₹ 2000.00  
 TIME LIMIT : Two Months


NAME OF WORK : Restoration of Rain damages on Chert to Ghera road km 0/00 to 1/555.  
 SITE/HEAD : RCC Wall at RD 8/417.60 to 8/419. (Circular PDM)

S No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shooting and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including: shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise; out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1575.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, F-1200 and 1600 nominal mix 1:1.5:3 (One cement 150 Four sand 150 Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-Charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.19	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	903.00
3	Providing and Laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetres) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802, 804, 806, 807, 1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.35	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	52553.00

Ser no - 376

52

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, Including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkana, Octroi, toll tax, or any other taxes imposed by the Government.	463.80	90.50	Rupees Ninety And Paise Fifty Only	Per kilogram	41974.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Rupees Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.10	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	935.00
TOTAL :-						98990.00
Quoted Rate In Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 H.P. W. Shahpur

SCHEDULE OF QUANTITY

8000-385

53

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- One Month

NAME OF Restoration of Rain damages on various roads under Darini section under HP.PWD Darini Sub- Division.  
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

54  
8r no - 353

ESTIMATED COST :- ₹ 99184.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Link road Grappa Mod Bagru Basnoor Sheelta Mata Purana Road KM 0/00 to 3/550 in Tehsil Shahpur Distt Kangra (H.P).  
SUB-HEAD :- C/o U-Shape Drain at RD 3/188 to 3/215 & R/wall at RD 3/188 to 3/195 RHS.

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets eccetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedgeing out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge Including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not executing 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth any quantam of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete In open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall eccetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government	7.29	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	38273.00

3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.18	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	51765.00
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe wecp holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.36	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2856.00
TOTAL :-						
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor In Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor In words)				
99184.00						

  
 Executive Engineer,  
 Shapurkhan  
 H.P.O. Shapurkhan

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98800.00  
 EARNEST MONEY : - ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on various Roads under Charri Section under Gaggal Sub Division  
SUB-HEAD :- Removal of slips In various Reaches.

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materials within lift upto 1.50 mtrs (One decimal fifty metres) and lead upto 1000 mtrs (One thousand metres) as per technical specification 302.3.5 and 1611 within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge, The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	1520.00	65.00	Rupees sixty Five only	per Cum	98800.00
<b>TOTAL :-</b>						<b>98800.00</b>
<u>Quoted Rate in Figure (%)</u>						(Amount to be quoted by the contractor In Figure )
<u>Quoted Rate in Words (%)</u>						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

  
 Sr. Insp.

**SCHEDULE OF QUANTITY**

**56**

**Semo-356**

ESTIMATED COST: ₹ 95875.00  
 EARNEST MONEY: ₹ 1950.00  
 TIME LIMIT: Two Months

**NAME OF WORK :-** Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700. (Under PDNA).

**SUB-HEAD :-** C/o Irrigation drain at Rd 2/995, P/L WBM G-III from Rd 2/985 to 3/000 and Rd 2/916-30 to 2/930, C/o Double row 300 MM Dia NP3 hume pipe culvert at Rd 2/920 and C/o Single Row 450 MM Dia NP3 hume pipe culvert at Rd 2/950.

5 No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.35	350.00	Rupees Three Hundred Fifty Only	Per cubic Metre	3623.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement into four sand into Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	1.54	4850.00	Rupees four Thousand Eight Hundred Fifty Only	Per cubic Metre	7469.00
3	Providing and laying (to level or slope) 300 mm dia (Four hundred fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102 and as per direction of Engineer - In- Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government (labour Rate).	5.00	450.00	Rupees Four Hundred Fifty Only	Per Running Metre	2250.00

4	Providing and laying (to level or slope) 450 mm dia. (Four hundred fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102 and as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government (Labour Rate).	10.00	225.50	Rupees Two hundred twenty Five and Paise Fifty Only	Per Running Metre	2255.00
5	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement fixo three sand fixo six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.28	5400.00	Rupees Five Thousand Four Hundred Only	Per cubic Metre	28512.00
6	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-fill size (75mm) seventy five millimeters) compacted (thickness) to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	10.16	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic Metre	22860.00
7	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel, laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovelshakes, compacting using needled, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, admixtures as approved, curing, primer, sealant, dowel bars, nea approaches to bridge/culverts and construction joints, admixtures as approved, curing of slab for 14 days, Curing compound (where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501.PCC Grade M-30 Each panel is (1.25x1.25) Thickness 160mm. as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	3.88	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic Metre	28306.00
<b>TOTAL :-</b>						<b>95375.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,  
Shahpur Division,  
HPPWD Sanganol

SCHEDULE OF QUANTITY

(57)

Jeno-367

ESTIMATED COST :- ₹ 98940.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- One Month

NAME OF

Restoration of Rain damages on various roads under Boh section HP.PWD Darini Sub-Division.

SUB-HEAD :-

Hiring of Excavator cum loader for removal of slips and Tractor for shifting and Carriage of material at various RDs

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government	62.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	68200.00
2	Hiring of Tractor for carriage of slips/muck including boulders and carriage of material for patch work etc. in all leads and lifts as per direction the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	53.00	580.00	Rupees Five Hundred Eighty Only	Per Hour	30740.00
<b>TOTAL :-</b>						<b>98940.00</b>
<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in Figure )				
<u>Quoted Rate in Words (%)</u>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

58


Sr no - 355

ESTIMATED COST :- ₹ 98974.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

**NAME OF WORK :-** C/o Link road Grappa Mod Bagru Basnoor Sheela Mata Purana Road KM 0/00 to 3/550 In Tehsil Shahpur Distt Kangra (H.P).  
**SUB-HEAD :-** C/o U-Shape Drain at RD 3/200 to 3/222 & R/wall at RD 3/232 to 3/240 LHS.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drain and Parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 and as per direction of the Engineer- In - Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and lift including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layer not exceeding 150 mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth any quantum of water including cleaning of slush which may arise out during dewatering complete as per direction of Engineer- In-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4890.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.25	5250.00	Rupees Five Thousand Two Hundred Fifty Only	Per cubic metre	38063.00

3	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1:10 (One cement 1sto five sand 1sto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	12.18	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	51765.00	
4	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORO technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00	
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.36	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	2856.00	
<b>TOTAL :-</b>							<b>98974.00</b>
<b>Quoted Rate In Figure (%)</b>		<b>(Amount to be quoted by the contractor in figure )</b>					
<b>Quoted Rate In Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>					

  
 Executive Engineer,  
 Shahpur Division,  
 H.P.P.W.D. Shahpur

**SCHEDULE OF QUANTITY**

59

Semo - 359

**NAME OF WORK :-** Recovery and Reconstruction on Charri to Chera Road KM 0/00 to 8/555. (Under PDNA).  
**SUB-HEAD :-** C/O C.C.Pusta at RD 6/150 TO 6/153.80 (1st stage).

**ESTIMATED COST:-** ₹ 99987.00  
**EARNEST MONEY :-** ₹ 2000.00  
**TIME LIMIT :-** Two Months

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all types of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all types of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any 5% including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.99	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1747.00
2	Providing and laying mechanically mixed and vibrated plain concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (44:10) nominal mix 1:3:6 (one cement (50 three sand (50 six crushed stone aggregate 40 mm (forty millimetre) nominal size on grounds in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site, which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800.900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	18.00	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	96840.00
3	Providing and laying 100mm (one hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H) (One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.00	350.00	Rupees Three Hundred Fifty Only	Each	1400.00
<b>TOTAL :-</b>						<b>99987.00</b>
<b>Quoted Rate in Figure (%)</b>						<b>(Amount to be quoted by the contractor in Figure)</b>
<b>Quoted Rate in Words (%)</b>						<b>(Amount to be quoted by the contractor in words)</b>

  
 Executive Engineer,  
 Shahpur Division  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

60


8670-357

ESTIMATED COST :- ₹ 99458.00  
 EARNEST MONEY :- ₹ 2000.00

TIME LIMIT : Two Months

**NAME OF WORK :-** Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700. (Under PDNA).  
**SUB-HEAD :-** C/o C.C. Pavement at RD 2/916.30 to 2/930.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel, laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovel/srakes, compacting using gneedel, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, neera approaches to bridge/culverts and construction joints, admixtures as approved, curing of slab for 14 days, Curing compound (where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501.PCC Grade M-30 Each panels (1.25x1.25) Thickness 160mm. as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	13.35	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	99458.00
<b>TOTAL :-</b>						<b>99458.00</b>
	<b>Quoted Rate in Figure (%)</b>	<b>(Amount to be quoted by the contractor in Figure )</b>				
	<b>Quoted Rate In Words (%)</b>	<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

61  
Serno-874

ESTIMATED COST :- ₹ 91449.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Recovery and Reconstruction on Shahpur Kiarl Chatter Road Km 0/00 to 8/900 (Under PDNA)  
 SUB-HEAD :- C/o R/Wall at RD 8/144.50 to 8/152.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.50	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	3675.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with In all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.63	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4786.00
<b>TOTAL :-</b>						
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate In Words (%)	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

Serial - 363

ESTIMATED COST :- ₹ 99493.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- Two Months

NAME OF WORK :- Recovery and Reconstruction on Thechar to Pargod Road KM 0/00 to 9/000 (Under PDNA).  
 SUB-HEAD :- C/o Breast Wall at RD 1/662 to 1/681.10

S.No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and structing and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.34	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	7209.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	16.81	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	79848.00

Sl. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and laying 100mm (one Hundred millimeter) dia D.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete. Abutments; Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi;royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	17.00	350.00	Rupees Three Hundred Fifty Only	Each	5950.00
<b>TOTAL :-</b>						<b>99493.00</b>
	Quoted Rate in Figure (%)	[Amount to be quoted by the contractor in Figure ]				
	Quoted Rate in Words (%)	[Amount to be quoted by the contractor in words]				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

63

Ser no - 365


ESTIMATED COST :- ₹ 99510.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages on Link road Salli to Konal road Km 0/0 to 2/250.

SUB-HEAD :- Construction of R/ wall with wire crate and C.C. Pusta at RD 0/520 to 0/525)

5. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work In excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	17.10	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5985.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORO technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.80	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	22800.00

3	Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (Five millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	20.50	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	70725.00	
<b>TOTAL :-</b>							
	Quoted Rate in Figure (%)	h	(Amount to be quoted by the contractor in Figure )				99510.00
	Quoted Rate in Words (%)	h	(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

64  
Ser no - 377


ESTIMATED COST: - ₹ 99037.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain damages on Chhatri to Ghera road Km 0/00 to 8/555.

SUB-HEAD :- RCC Wall at RD 8/419.10 to 8/420.20. (Under PDNA)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetera including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	0.20	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	950.00
3	Providing and laying mechanically mixed and vibrated concrete for plain / reinforced concrete in sub structure for all types of structure of plain cement concrete grade M-20 (twenty) with minimum nominal mix 1:2:4 (one cement is to two sand is to four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in or under water including curing complete for 14 (fourteen) days pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,804,806,807,1202 and 1204 as per the directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including the octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government.	7.35	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	52553.00

4	Supplying fitting and placing HYSD bar reinforcement (Fe 415) in sub structure complete as per drawing and M.O.R.D. technical specifications section 1000 and 1200 including cutting, bending, binding and placing in position complete in all respect including the cost of binding, wire upto all heights and depths and as per direction and entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads lifts and other incidental. The rate is including Royalty, Malkhana, Octroi, toll tax, or any other taxes imposed by the Government.	463.80	90.50	Ruppes Ninety And Paise Fifty Only	Per Killogram	41974.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORR technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government.	3.00	350.00	Ruppes Three Hundred Fifty Only	Each	1050.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, GST or any other taxes imposed by the Government.	1.10	850.00	Ruppes Eight Hundred Fifty Only	Per cubic metre	935.00
TOTAL :-						99037.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shapur Division,  
 H.P. Shah

SCHEDULE OF QUANTITY

65

Ser no - 358

ESTIMATED COST : - ₹ 99160.00  
 EARNEST MONEY : - ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Recovery and Reconstruction on Bhanalla Pucca Tiala Road KM 0/00 to 3/700. (Under PDNA).  
**SUB-HEAD :-** C/o C.C. Pavement at RD 2/985 to 3/000.

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of panel concrete plain cement concrete pavement, thickness as per design, over a prepared sub-base with 43 Grade cement or any other type as per clause 1501.2.2 M30 Grade course and fine aggregate conforming to IS: 383. Maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.2 Cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side framework (Steel channel, laying and fixing of 125 micron thick Polythene film, wedges steel plates including levelling form work as per drawing), spreading the concrete with shovel/srakes, compacting using needle, screed and plate vibrators and finishing continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, nera approaches to bridge/culverts and construction joints, admixtures as approved, curing of slab for 14 days, Curing compound (Where specified) and water specified to lines and grade as per drawing and technical specifications clause 1501.PCC Grade M-30 Each panels (1.25x1.25) Thickness 160mm, as per the entire satisfaction and directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	13.31	7450.00	Rupees Seven Thousand Four Hundred Fifty Only	Per cubic metre	99160.00
<b>TOTAL :-</b>						99160.00
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

2020-364

66

ESTIMATED COST :- 98010.00  
 EARNEST MONEY :- 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Recovery and Reconstruction on Thahar to Pargod Road KM 0/00 to 9/000. (Under PDNA).  
 SUB-HEAD :- C/o Breast Wall and U-Shape drain at RD 0/900 to 0/918.86.

S.No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5415.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	14.90	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	70775.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 ( M-ten) nominal mix 1:3:5 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetra as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	3.21	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	17270.00

1	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
2	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete. Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	13.00	350.00	Rupess Three Hundred Fifty Only	Each	4550.00
<b>TOTAL :-</b>						<b>98010.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shabbur

**SCHEDULE OF QUANTITY**

67

8x100 - 372


ESTIMATED COST :- ₹ 91423.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Recovery and Reconstruction on Shahpur Kiarl Charter Road Km 0/00 to 8/900 (Under PDNA)

**SUB-HEAD :-** C/o R/Wall at RD 8/154 to 8/159.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:5:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other Incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	7.00	350.00	Rupees Three Hundred Fifty Only	Each	2450.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-In-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	5.60	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	4760.00
TOTAL :-						91423.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

68

8870-344


ESTIMATED COST: - ₹ 99473.00  
 EARNEST MONEY: - ₹ 2000.00  
 TIME LIMIT : Two Months

NAME OF WORK :- Restoration of Rain Damages on Link road Sallit to Konal road Km 0/0 to 2/250.

SUB-HEAD :- Construction of R/ wall with wire crate and C.C. Pusta at RD 0/526 to 0/530)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	5775.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge Including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	4.80	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	22800.00

<p>Providing and laying of boulder apron or gabion walls laid in wire crates with 5mm (five millimetre) dia GI wire conforming to IS:280 and IS14826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 40 Kg (forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.</p>	20.55	3450.00	Rupees Three Thousand Four Hundred fifty Only	Per cubic metre	70898.00
<p>Quoted Rate in Figure (%)</p>	<p>TOTAL :- 99473.00</p> <p>(Amount to be quoted by the contractor in Figure )</p>				
<p>Quoted Rate in Words (%)</p>	<p>(Amount to be quoted by the contractor in words)</p>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

69  
Semo - 268

ESTIMATED COST :- ₹ 98940.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT :- One Month

NAME OF Restoration of Rain damages on various roads under Boh section HP.PWD Darini Sub-Division.  
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips and Tractor for shifting and Carriage of material at various RDS

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc. in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	62.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	68200.00
2	Hiring of Tractor for carriage of slips/muck including boulders and carriage of material for patch work etc. in all leads and lifts as per direction the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	53.00	580.00	Rupees Five Hundred Eighty Only	Per Hour	30740.00
<b>TOTAL :-</b>						<b>98940.00</b>
			<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in Figure )	
			<u>Quoted Rate in Words (%)</u>		(Amount to be quoted by the contractor in words)	

Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

20

Sr no - 369

ESTIMATED COST :- ₹ 98940.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF Restoration of Rain damages on Rulehar to Lam road 0/00 to 3/885.  
 SUB-HEAD :- Hiring of Excavator cum loader for removal of slips and Tractor for shifting and Carriage of material at various RDS

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	62.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	68200.00
2	Hiring of Tractor for carriage of slips/muck including boulders and carriage of material for patch work etc. in all leads and lifts as per direction the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	53.00	580.00	Rupees Five Hundred Eighty Only	Per Hour	30740.00
<b>TOTAL :-</b>						<b>98940.00</b>
<b>Quoted Rate in Figure (%)</b>			<b>(Amount to be quoted by the contractor in Figure )</b>			
<b>Quoted Rate in Words (%)</b>			<b>(Amount to be quoted by the contractor in words)</b>			

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY

51

Sera- 370


**NAME OF WORK :-** Recovery and Reconstruction on Shahpur Kiari Chatter Road Km 0/00 to 8/900 (Under PDNA)

**SUB-HEAD :-** C/o R/Wall at RD 8/135 to 8/142.50.

**ESTIMATED COST :-** ₹ 91413.00  
**EARNEST MONEY :-** ₹ 2000.00  
**TIME LIMIT :** Two Months

5. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3	4	5	6	7
2	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1.5:1:10 (One cement isto five sand isto ten graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	18.95	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per cubic metre	80538.00
3	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	6.00	350.00	Rupees Three Hundred Fifty Only	Each	2100.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	6.00	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5100.00	
<b>TOTAL :-</b>							
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure )					<b>91413.00</b>
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)					

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

**SCHEDULE OF QUANTITY**

(72)

ESTIMATED COST : ₹ 99200.00  
 EARLIEST MONEY : ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF WORK :** Repair and Restoration on various roads under III, PWD Bhatnagar Sub-Division,  
**SUB-HEAD :** Hiring of rock Breaker under Road Section.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Rock Breaker having 2 to 4 tonne Hammer capacity for removal of boulder slips, rock cutting for drains, removal of boulders from catchpits, opening of blocked drains due to boulders etc and other similar road works requiring breaking of rock and boulders on road in various reaches up to any height, depth and disposal of material up to 20.00 meters load in all kind and classification of soil including rocky portion as per direction and entire satisfaction of Engineer-in-charge. The Rock Breaker should work minimum 8.00 hours daily. Any loss to the public property or any accident etc happened during the course of hiring performance of work, shall be the absolute responsibility of the Rock Breaker owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff will be provided by the owner. The repair, spare and watch and ward of Rock Breaker will also be born by the Contractor/Owner. The daily log book will be maintained at site which should be duly certified by the Engineer in Charge. The rate is inclusive of GST and all other type taxes, royalties etc imposed by central or state government.	3	3100.00	Three thousand and one hundred only	Per hour	99200.00
<b>TOTAL :-</b>						<b>99200.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure)</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shapur Division,  
 HPPWD Shapur

**SCHEDULE OF QUANTITY**

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF** Restoration of Rain damages on various roads under Rait Section under H.P.PWD Shahpur Sub- Division.  
**SUB-HEAD :-** Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, cleaning road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks work done etc. completely as per inspection of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand one hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor In Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor In words)</b>				

*V.P.*  
 Assistant Engineer  
 Shahpur Sub Division  
 H.P. P.W.D. Shahpur

*H.S.*  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

73


SCHEDULE OF QUANTITY

(74)

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : - One Month

**NAME OF** Restoration of rain damages on Rait Nerti Balla Takwani Road  
**SUB-HEAD :-** Hiring of Excavator cum loader on various RDS

S. No	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure )				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

  
 Assistant Engineer  
 Shahpur Sub Division  
 H.P P.W.D. Shahpur

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


SCHEDULE OF QUANTITY

75

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

NAME OF A/R & M/O various roads under HP.PWD Shahpur Sub- Division.  
SUB-HEAD :- Hiring of Excavator cum loader for removal of slips.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road opening of drains and catchpits etc, in all kind of soil like boulder, rocks done etc, completely as per instruction of engineer-in-charge. Any loss to the public property or accident etc, happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner of machinery. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees one thousand and or hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in Figure )				
<u>Quoted Rate In Words (%)</u>		(Amount to be quoted by the contractor in words)				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


**SCHEDULE OF QUANTITY**

(76)

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF** Restoration of Rain damages on Darfni to Bhaler road 0/00 to 5/325.  
**SUB-HEAD :-** Hiring of Excavator cum loader for removal of slips at various Rd.

S. No	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks work done etc. completely as per inspection of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government	90.00	7100.00	Rupees One Thousand one hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur


**SCHEDULE OF QUANTITY**

77

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : One Month

**NAME OF** Restoration of Rain drainages on various road under Darini Sub-Division.  
**SUB-HEAD :-** Hiring of Excavator cum loader for removal of slips at various Rd.

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of Excavator cum loader required for removal of slips, clearing road such opening of drains and catchpits etc. In all kind of earths, boulder, rocks work done etc. completely as per inspection of engineer-in-charge and minimum 25 (Twenty-five) cubic per hours output for slips / removal activates. Any loss to the public property or accident etc. happened during the course of hiring period/execution shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for excavator will be provided by the owner. The repair and spare watch and ward of excavator also born by the contractor. The daily log book will be maintained at site which should be verified by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, sale tax, toll tax, GST and all type of other taxes imposed by the Government.	90.00	1100.00	Rupees One Thousand one hundred only	Per Hour	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
<b>Quoted Rate in Figure (%)</b>		<b>(Amount to be quoted by the contractor in Figure )</b>				
<b>Quoted Rate in Words (%)</b>		<b>(Amount to be quoted by the contractor in words)</b>				

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur

SCHEDULE OF QUANTITY


78

395

ESTIMATED COST :- ₹ 99000.00  
 EARNEST MONEY :- ₹ 2000.00  
 TIME LIMIT : Two Months

**NAME OF WORK :-** Special repair of Veterinary Hospital Gohju in Tehsil Shahpur at Distt. Kangra Himachal Pradesh.  
**SUB-HEAD :-** Providing and fixing fencing in Boundary wall.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia. 4 mm. outer dia not less than 5 mm in required colour and shade with 40x40x5 mm angle. complete as per the direction of Engineer-in-charge including cartage of material. within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	180.00	550.00	Rupees Five Hundred Fifty Only	Per square metre	99000.00
<b>TOTAL :-</b>						<b>99000.00</b>
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure )
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

  
 Executive Engineer,  
 Shahpur Division,  
 HPPWD Shahpur