

Himachal Pradesh
Public Works Department

No. PW-SD-I-CTR-Tender-NIT/2025-2026-

13006-07 Dated:- 15-10-2025

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .



Executive Engineer,
Shimla Division No-I.,
HPPWD., Shimla-3.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 27-10-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 27-10-2025 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 28-10-2025 .up to 10:30 AM |
| 4. Date of opening of tender:- | 28-10-2025 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	Restoration of Rain Damages on Challanda to piran road km. 0/00 to 28/00 (SH;- Removal of slips between RD. 21/780 to 22/900).	98000/-	2000/-	350/-	30 days	Class-D
2	Restoration of Rain Damages on Challanda to piran road km. 0/00 to 28/00 (SH;- Removal of slips between RD. 24/900 to 25/700).	98700/-	2000/-	350/-	30 days	Class-D
3	Restoration of Rain damages on Sanjulli to Dhalli bye pass road in km. 0/00 to 3/786 (SH;- Removal of slips of slips at Rd. 0/00 to 1/150).	97320/-	2000/-	350/-	30 Days	Class-D
4	A/R & M/O to Type-I to VI Qtrs at Mehli Kasumpti Shimla (SH;- P/L Tile work toilet kitchen set No.2 and 8 Servant Qtrs at mehli Shimla).	99328/-	2000/-	350/-	30 Days	Class-D
5	A/R & M/O various roads under Dhalli section (SH;- Providing Staff for maintenance of various roads under Dhalli section w.e.f. 15/10/2025 to 14/11/2025 (one month).	95700/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O various roads under Lakkar Bazar section (SH;- Providing staff for maintenance of various roads under lakkar section w.e.f.15-10-2025 to 14-11-2025 (one Month)	95700/-	2000/-	350/-	30 days	30 Days
7	A/R & M/O to type-I to VI qtrs. At mehli Shimla-9 (SH;- PVC flooring work in type set No.35 & 31 Transit accommodation set nO.7 type-II Mehli Shimla).	95323/-	2000/-	350/-	30 days	30 Days
8	Restoration of Rain Damages on paboo to Dumi road km. 0/00 to 2/120 (SH;- Removal of slips at RD. 0/120 to 1/990).	99300/-	2000/-	350/-	30 Days	Class-D
9	Restoration of Rain damages on kalti to cheri via Nehari 0/00 to 3/700 (SH;- Removal of slips at Rd. 0/00 to 1/800).	95800/-	2000/-	350/-	30 Days	Class-D
10	A/R & M/O various roads under Bharari section (SH;- Providing Staff for maintenance of various roads under Bharari section w.e.f 15.10.2025 to 14-11-2025 (One month)	95700/-	2000/-	350/-	30 Days	Class-D
11	A/R & M/O of Eversunny to pagogRaod km. 0/00 to 5/00 (SH;- Providing and laying WBM G-III at RD. 4/00 to 4/500 RD. 4/00 to 4/050, 4/130 to 4/180, 4/360 to 4/410	93150/-	1900/-	350/-	30 Days	Class-D
12	Restoration of Rain Damages on Various road under sub Division No-I (SH;- Removal of slips at various road on Khalinivihar road km. 0/00 to 2/250 and Bhatakuffer AIM55 road km. 0/00 to 2/400).	98700/-	2000/-	350/-	30 Days	Class-D
13	Restoration of Rain damages on various roads under Shimla Dhalli Section (SH;- Removal of slips at Various road km. 0/00 to 3/756).	99855/-	2000/-	350/-	30 Days	Class-D
14	Restoration of Rain Damages on various roads under sub Division No-I (SH;- Removal of slips at various road on road kelti to Cheri km. 0/00 to 3/780).I	99750/-	2000/-	350/-	30 Days	Class-D
15	A/R & M/O of Eversunny to pagog road km. 0/00 to 5/00 (SH;- Providing and laying WBM G-III at RD. 4/00 to 4/500 RD. 4/510 to 4/560, 4/780 to 4/830,4/920 to 4/970).	93150/-	1900/-	350/-	30 Days	Class-D
16	A/R & M/O to various type-I to Type-VI Qtrs of GAD at kasumpti Shimla-9 (SH;- Construction of Retaining wall below type-I set NO.1 to 18 under kasumpti Section).	99260/-	2000/-	350/-	30 Days	Class-D
17	A/R & M/O various Type-III & Type-IV GAD at Kasumpti, Shimla-171009. (SH;- Pr50 viding and fixing Cupboard in Type-II set No.21 and 23 under Kasumpti Division.)	98913/-	2000/-	350/-	30 Days	Class-D
18	A/R & M/O Various Type-I to Type VI GAD Residential qtrs. at Kasumpti Shimla-9 (SH;- Renovation of Garage No.2 at Mehli Shimla (Converted to servant qtrs.).	98965/-	2000/-	350/-	30 Days	Class-D
19	Annual Repair Maintenance road on Mehli to IAS Colony road in KM. 0/00 to 2/00(SH;- Supplying and laying pot seal bags cold mix in km. 0/00 to 2/00).	99000/-	2000/-	350/-	30 Days	Class-D
20	Annual Repair Maintenance on old Kasumpti Junga road in Km.0/00 to 11/00 (SH;- Supplying and laying pot seal bags cold mix in km. 0/00 to 5/00).	98175/-	2000/-	350/-	30 Days	Class-D
21	Annual Repair Maintenance on Bhatta Kuffer to Koti road in km. 0/00 to 6/385 (Supplying and laying pot seal bags cold mix in km. 0/00 to 1/00).	99825/-	2000/-	350/-	30 Days	Class-D
22	Annual Repair Maintenance on old Junga to Bharandi road in km. 0/00 to 2/00 (Supplying and laying pot seal bags cold mix in km. 0/00 to 2/00).	99825/-	2000/-	350/-	30 Days	Class-D
23	Annual Repair maintenance on Cheri to Kyarkoti road in km. 0/00 to 5/00 (Supplying and laying pot seal bags cold mix in various portion km.0/00 to 5/00).	99000/-	2000/-	350/-	30 Days	Class-D
24	A/R & M/O Various Type-III & Type-IV GAD at Parimahal, Kasumpti, Shimla-171009. (SH;- Covering of Balcony in Type-III 09,70,74 etc. and P/F accessories in Type-III set	99988/-	2000/-			



	no 650 under Kasumpti Sub-Division).					
25	Restoration of Rain Damages on Koti to Satlai road in km. 0/00 to 15/000. (SH: - Construction of wire create at RD 2/045 to 2/048). (Balance work).	83724/-	1700/-	350/-	30 Days	Class-D
26	A/R & M/O Various Type-III & Type-IV GAD at Kasumpti, Shimla-171009. (SH:- Converting of Balcony Covering etc. in type-II set No. 607 and 608 under Kasumpti).	93720/-	1900/-	350/-	30 Days	Class-D
27	Restoration of Rain Damages on Various roads under Shimla Dhalli Section. (SH: - Removal of Slips at various Roads.).	99855/-	2000/-	350/-	30 Days	Class-D
28	Restoration of Rain Damages on Koti to Satlai road in km. 0/00 to 15/000. (SH: - Construction of wire create at RD 2/051). (Balance work).	94171/-	1900/-	350/-	30 Days	Class-D
29	Repair and Maintenance of AIMSS (IGMC Phase-II Hospital) at Chamyana (SH:- Supply of Surgical sink fitting fixtures civil works items for items for routine maintenance.).	99460/-	2000/-	350/-	30 Days	Class-D
30	Restoration of Rain Damages Various roads under AIMSS Section.(SH:- Providing Staff for Maintenance of various roads under AIMSS section w.e.f. 15-10-2025 to 14-11-2025. (one Month).	99000/-	2000/-	350/-	30 Days	Class-D
31	Repair and Maintenance of AIMSS (IGMC Phase-II Hospital) at Chamyana (SH:- Supply of fitting fixtures civil works items for items for routine Maintenance.).	99605/-	2000/-	350/-	30 Days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.
- 14.

Executive Engineer,
Shimla Division No-I.,
HPPWD. Shimla-3.

No.PW-SD-I/CB-Tender/2025-2026-
Copy forwarded to:-

13008-28

Dated :- 15-10-2025

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Shimla Division No-I.,
HPPWD. Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA						Estimated Cost:- 98,000.00	
Name of Work :- Restoration of Rain Damages on Challanda to Piran road Km 0/000 to 28/000						Earnest Money :- 2,000.00	
(SH:- SH:- Removal of slips between Rd 21/780 to 22/900).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount.
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with all leads & lift. The work shall be executed as per the direction of the Engineer-in-Charge.	490.00	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	98000.00
						Total	98000.00

CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.
5. Dumping site will be arranged by the contractor at his own risk and cost .

D/NR No 502 T/S No 11644-45 dt 3-10-25
Ant to Rs 1,00,940/-

Executive Engineer
Shimla Division No. I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-						Estimated Cost:- 98,700.00	
Name of Work :- Restoration of Rain Damages on Challanda to Piran road Km 0/000 to 28/000						Earnest Money :- 2,000.00	
(SH:- SH:- Removal of slips between Rd 24/900 to 25/700).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with all leads & lift. The work shall be executed as per the direction of the Engineer-in-Charge.	493.50	Cum	200.00	Rupees Two Hundred Only	Per Cubic Meter	98700.00
						Total	98700.00

D/INR-No. 502 T/S 11642-43 dt 3-10-25

CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.
5. Dumping site will be arranged by the contractor at his own risk and cost .

Ant to R 101661/

Executive Engineer,
Shimla Division No. 1,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 97,320.00	
Name of Work :-- Restoration of Rain damages on Sanjauli to Dhalli Bye Pass road in km. 0/00 to 3/786. (SH:- Removal of Slips at RD 0/00 to 1/150) .						Earnest Money :- 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with all leads & lift. The work shall be executed as per the direction of the Engineer-in-Charge.	486.60	cum	200.00	Rupees Two Hundred Only	Per Cubic Metre	97320.00
						Total	97320.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

DINR.No. 5047/SN. 11638-39 d/t 3-10-25

And to Rs 10,0240/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 99328.00		
Name of Work :- A/R & M/O to Type - I to VI Qtrs. At Mehli Kasumpti Shimla. (SH : P/L Tile work					Earnest Money :- 2000.00		
Toilet Kitchen Set No. 2 and 8 Servent Qtrs. At Mehli Shimla).					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	0.480	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	552.00
2	Dismantling tile work in floors and floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer - in- Charge. (i) For thickness of tiles 10mm to 25 mm	7.920	Sqm	45.00	Rupees Forty Five Only	Per Square Metre	356.00
3	Providing and fixing CPVC pipe including fitting including fitting including carriage of materials in all leads and lifts as per directionns of the Engineer- in - Charge. (i) 29mm thick	13.60	Rmt	650.00	Rupees Six Hundred Fifty Only	Per Square Metre	8840.00
4	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 110 mm	4.000	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Square Metre	1400.00
	(b) 75mm dia	7.300	Rmt	250.00	Rupees Two Hundred Fifty	Per Running Metre	1825.00
5	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and marking good thewall and floors etc. Complete including carriage of materials with all leads and lifts and as per the direction of Engineer- in - charge. (i) 110 mm x 75 mm	3.000	Nos	350.00	Rupees Three Hundred Fifty Only	Nos	1050.00
6	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. Complete including carriage of nmaterials in all leads and lifts as per direction of the Engineer- in - Charge. (a) 110 mm (One hundred ten milimetre) dia.	2.000	Nos	350.00	Rupees Three Hundred Fifty Only	Nos	700.00
	(b) 75mm dia	3.000	Nos	250.00	Rupees Two Hundred Fifty Only	Nos	750.00
7	Providing and fixing PVC plain bend isi marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per direction of the Engineer- in - Charge.(I) 75 mm dia.	2.000	Nos	250.00	Rupees Two Hundred Fifty Only	Nos	500.00
8	Proving and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer - in - Charge. (i) 110 mm dia	4.000	Nos	250.00	Rupees Two Hundred Fifty Only	Nos	1000.00
	(b) 75mm dia	5.000	Nos	200.00	Rupees Two Hundred Only	Nos	1000.00

9	Proving and laying in position cement concrete of specified grade including the cost of centering and shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size).	1.160	Cum	6400	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	7424.00
10	Providing and laying Ceramic glazed wall tiles of size 300x 300mm (thick to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, grey, fume Red Brown, laid on 20mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	13.15	Sqm.	1140	#NAME?	Per Square Metre	14991.00
11	Providing and laying Ceramic glazed wall tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:3 (1 Cement : 3 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete including carriage of materials in all leads as per directions of the	2.85	Sqm.	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	3249.00
12	Providing and fixing vitreous china work down water down water closet. (European Type - WC Pan) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) Ordinary closet.	1.000	Nos	3000.00	Rupees Three Thousand Only	Each	3000.00
13	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1) SOLID TYPE (a) White plastic seat and cover.	1.00	Nos	600.00	Rupees Six Hundred Only	Each	600.00
14	Providing and fixing C.P Jet spray of approved quality & colours with 1.50 metre tube including screw etc. complete in all respects 8 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	1.000	Nos	450.00	Rupees Four Hundred Fifty Only	Each	450.00
15	Providing and fixing c.p brass angle cock/stop cock without nuts and pipe including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm (fifteen millimetre) dia	8.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	6800.00
16	Providing and fixing PVC connection with brass unions complete including carriage of materials in all leads and lifts as per directions of Engineer-in-Charge (a) 454cms length (i) 15mm nominal bore.	7.00	Nos	200.00	Rupees Two Hundred Only	Each	1400.00
17	Providing and fixing 100mm sand cast Iron grating for gully trap including carriage of materials in all leads as per directions of the Engineer-in-Charge	3.00	Nos	200.00	Rupees Two Hundred Only	Each	600.00
18	Providing and fixing CP brass waste pipe for basin & sink including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 15mm dia.	2.00	Nos	180.00	Rupees One Hundred Eighty Only	Each	360.00
19	Providing and fixing C.P Sink mixture arrangement including carriage of material in all leads and lifts as per directions of the Engineer-in-Charge. MAKE ESS ESS	1.00	Nos	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00

20	Providing fixing C.P wall mixer arrangement including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. MAKEESS ESS.	1.00	Nos	4500.00	Rupees Four Thousand Five Hundred Only	Each	4500.00
21	Providing and fixing vetreous China wash basin with single hole for pillar tap with C.I or M.S brackets painted white including cutting goles and making good the same but excluding fittings including carriage of materials in all leads as per direction of the Engineer-in-Charge	1.00	Nos	2200.00	Rupees Two Thousand Two Hundred Only	Each	2200.00
22	Providing and fixing Acrylic conrner shelves complete with C.P BRASS brackets fixed plugs with C.P brass screws complete including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge	1.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	550.00
23	Providing and fixing C.p brass Towel rod complete with c.p Brass brackets fixed to wooden plugs with C.P Brass screw including carriafe of materials in all leads and lifts as per direction of the Engineer-in-Charge . (i) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm weighing not less than 190grms.	1.00	Nos	600.00	Rupees Six Hundred Only	Each	600.00
24	Providing and fixing C.P Brass Towel ring complete with C.P Brass brackets fixed to wooden plugs with c.P brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	550.00
25	Providing and fixing 600mmx450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C sheet or plywood sheet and fixed to wooden plugs with C.P Brass screw and washers bincluding carriage of materials in all lead and lifts as per directions of the Engineer-in-Charge.	1.00	Nos	1020.00	Rupees One Thousand Twenty Only	Each	1020.00
26	Providing and fixing chromium plated brass soap dish with C.P Brass brackets fixed to wooden plugs with C.P Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in -Charge.	3.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	1650.00
27	Providing and fixing Glass shelves including carriage of materials in all leads and lifts as per direction of the Engineer-inb-Charge	1.00	Sqm	1400.00	Rupees One Thousand Four Hundred Only	Per Square Metre	1400.00
28	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor all level including arrises,internal rounded angles,chamfers and/or rounded angles not exceeding 30mm(thirty milimetre) in girth and finished even and smooth including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6(one cement:six sand)	13.19	Sqm	270.00	Rupees Two Hundred Seventy Only	Per Square Metre	3561.00
29	Removing dry or oil dound distemper, water proofing, water proofing cement proofing cement paint and the like by scrapping, sand sand papering and preparing the surface smooth including necessary repairs to scratches etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	45.00	Sqm	10.00	Rupees Ten Only	Per Square Metre	450.00

30	Applying priming coat over wood and wood based surface after and i/c preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (a) Ready mixed paint brushing wood primer pink.	75.00	Sqm	40.00	Ropees fourty only	Per Square Metre	3000.00
31	Painting two coat (excluding priming coat) on new wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of the matewrials in all leads aqnd lifts as per direction of the Engineer-in-Charge.	50.00	Sqm	70.00	Rupees Seventy Only	Per Square Metre	3500.00
32	Applying Birla white wall care putty over plaster surface thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters and papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	100.00	Sqm	60.00	Rupees Sixty Only	Per Square Metre	6000.00
33	Distempering with oil bound washable distemper of approved brand and manufactureand of required shade on undecorated wall surface to give an even shade Old work (one or more coats). Including carriage of materials in all leads and lifts as per direction of the Engineer-in -Charge.	200.00	Sqm	45.00	Rupees Forty Five Only	Per Square Metre	9000.00
						Total	99328.00

D/NR No. 505 T/S No. 11646-47 dt 31.01.25 Amt 102,308/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-95,700.00	
Name of Work :-A/R & M/O various roads under Dhalli section.(SH:- Providing Staff for maintenance of various roads under Dhalli section w.e.f. 15.10.2025 to 14.11.2025.(one Month)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 6 Nos. Beldar for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer.(Six No. Beldar for one month)T&P, will be supplied by the department as per the direction of the Engineer-in-Charge.	174.00	Days	550.00	Rupees Five Hundred Fifty Only	Per Days	95700.00
						Total	95700.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

DIN R.N. 5067/SN 211634-354+3-10-25

Amt to Rs 98571/

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 95,700.00	
Name of Work :--A/R & M/O various roads under Lakkar Bazar section.(SH:- Providing Staff for maintenance of various roads under Lakkar section w.e.f. 15.10.2025 to 14.11.2025.(one Month)						Earnest Money : 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 6 Nos. Beldar for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other miscellaneous works assigned by Junior Engineer.(Six No. Beldar for one month)T&P, will be supplied by the department as per the direction of the Engineer-in-Charge.	174.00	Days	550.00	Rupees Five Hundred Fifty Only	Per Days	95700.00
						Total	95700.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR.No. 5077/S No. 11636-37 of B-10-25

Ant to RS 98,571/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 95,323.00	
Name of Work :- A/R & M/O to type-1 to VI Qtrs at Mehli Shimla-9. (SH:- PVC Venyl flooring work in						Earnest Money :- 2,000.00	
Type- Set No. 35& 31 Transit Accommodation Set No.7 type-II Mehli Shimla).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC. antistatic venyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	100.34	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	95323.00
						Total	95323.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

D/N R.M. 508 T/S 11632-3343-10-25

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Amnt to Rs 98,183

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99,300.00		
Name of Work :-- Restoration of Rain damages on Powboo to Dumi road km. 0/00 to 2/120.(SH:- Removal of Slips at RD.0/120 to 1/990) .					Earnest Money :-2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with all leads & lift. . The work shall be executed as per the direction of the Engineer-in-Charge.	496.50	cum	200.00	Rupees Two Hundred Only	Per Cubic Metre	99300.00
						Total	99300.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

S/NR No 509 T/D No. 11630-31 dt 30-7-25

Rs 1,02,279/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
Shimla Division No.I.
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 95,800.00	
Name of Work :-- Restoration of Rain damages on Kalti to Cheri via Nehari 0/00 to 3/700.(SH:- Removal of Slips at RD.0/00 to 1/800).						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with all leads & lift. . The work shall be executed as per the direction of the Engineer-in-Charge.	479.00	cum	200.00	Rupees Two Hundred Only	Per Cubic Metre	95800.00
						Total	95800.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR. NG/0-7/DN/0.11628-294-3-10-2025

Amtd to Rs 98674/

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-95,700.00	
Name of Work :--A/R & M/O various roads under Bharari section.(SH:- Providing Staff for maintenance of various roads under Bharari section w.e.f. 15.10.2025 to 14.11.2025.(one Month)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 6 Nos. Beldar for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer.(Six No. Beldar for one month)T&P, will be supplied by the department as per the direction of the Engineer-in-Charge.	174.00	Days	550.00	Rupees Five Hundred Fifty Only	Per Days	95700.00
						Total	95700.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

S/NR.No 496 T/S No 115 84-82041-10-25 Amt 98,571/1

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer
 Shimla Division No.I,
 HP PWD Shimla-3.

7/3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 93,150.00	
Name of Work :- A/R&M/O of Every sunny to Pagog Road km. 0/00 to 5/00 (SH:-Providing and Laying						Earnest Money : 1900.00	
WBM GIII at Rd.4/00 to 4/500) Rd.4/00 to 4/050, 4/130 to 4/180, 4/360 to 4/410.						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3(three) as per Technical Specification Clause 405 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) By Mechanical Means	40.50	Cum	2300.00	Rupees Two Thousand Three Hundred Only	Per Cubic Metre	93150.00
						Total	93150.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 98,700.00	
Name of Work :- Restoration of Rain damages on various roads under sub division No.I. (SH:-Removal of Slips at various Roads on Khalini Vihar road km. 0/00 to 2/250 and Bhatta kuffer AIMSS road km. 0/00 to 2/400						Earnest Money : 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	94.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hour	98700.00
						Total	98700.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

7 13								SCHEDULE OF QUANTITY			
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.							Estimated Cost: 99,855.00				
Name of Work :- Restoration of Rain damages on various roads under Shimla Dhalli Section. (SH:-							Earnest Money : 2,000.00				
Removal of Slips at various Roads between km. 0/00 to 3/756)							Time:- One Month.				
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount				
				In figures	In words						
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.10	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hour	99855.00				
						Total	99855.00				
	Quated rates Percentage in figures										
	Quoted rates Percentage in words										
						G.Total					

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer,
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 99,750.00	
Name of Work :- Restoration of Rain damages on various roads under sub division No.I. (SH:-Removal of Slips at various Roads on road Kelti to Cheri km. 0/00 to 3/780)						Earnest Money : 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour. other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hour	99750.00
						Total	99750.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 93,150.00	
Name of Work :- A/R&M/O of Every sunny to Pagog Road km. 0/00 to 5/00 (SH:-Providing and Laying WBM GIII at Rd.4/00 to 4/500) Rd.4/510 to 4/560, 4/780 to 4/830, 4/780 to 4/830, 4/920 to 4/970.						Earnest Money : 1900.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
I	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3(three) as per Technical Specification Clause 405 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) By Mechanical Means	40.50	Cum	2300.00	Rupees Two Thousand Three Hundred Only	Per Cubic Metre	93150.00
						Total	93150.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.

2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.

Estimated Cost:- 99,260.00

Name of Work :- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Construction of Retaining wall below Type-I Set No. 1 to 18 Under Kasumpti Section).

Earnest Money :- 2,000.00

Time:- One Month.

Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (i) In cement mortar	13.84	Cum	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Cubic Metre	17300.00
2	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2.36	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	767.00
3	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	3.68	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1472.00

4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	0.37	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	1998.00
5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: Five sand: Ten graded stone agg.40mm nominal size).	1.21	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	4598.00
6	Random rubble masonry/polygonal rubble masonry(un-coursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement:Six sand:twelve graded stone aggregate 20mm (twenty milimetre)nominal size) in cement mortar 1:6 (One cement: Six sand) in breast wall and retaining walls including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	13.00	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per Cubic Metre	62400.00
7	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	15.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	2700.00
8	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	1.76	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	1848.00
9	Disposal of excavated earth work by debris material upto site on approved dumping siteapproved by M.C. including carriage of inaterials in all leads and lifts as per directions of the Engineer-in-Charge.	2.42	Cum	600.00	Rupees Six Hundred Only	Per Cubic Metre	1452.00

10	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Thermo Mechanically Treated bars of grade Fe-500D or more.	45.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	4725.00
						Total	99260.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

(T/S No. 15731-32 Dated 22-9-25 Amount to Rs. 1,02,237/-)

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 98913.00	
Name of Work :- A/R & M/O various Type-III & Type-IV GAD at Kasumpti, Shimla-171009. (SH:- Pr5oviding and						Earnest Money :- 2000.00	
fixing Cupboard in Type-II set No. 21 and 23 under Kasumpti Division.)						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	43.46	Sqm.	1350.00	Rupees One Thousand	Per square metre	58671.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	13.37	Sqm	900.00	Rupees Nine Hundred	Per square metre	12033.00
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	10.64	Sqm	650.00	Rupees Six Hundred Fifty Only	Per square metre	6916.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	48.00	Rtm.	90.00	Rupees Ninety Only	Per Running Metre	4320.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	30.00	Nos.	50.00	Rupees Fifty Only	Each	1500.00
6	Providing and fixing bright/matt finished stainless steel handles of approved quality & make with necessary scews etc. all complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. i) 125 mm.	30.00	Nos.	150.00	Rupees One Hundred	Each	4500.00
7	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position including carriage of mateirals in all leads and lifts as per directions of the Engineer-in-Charge.(i) 2nd class deodar wood	0.04	Cum	90000.00	Rupees Ninety Thousand	Per Cubic Metre	3150.00
8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	43.46	Sqm.	70.00	Rupees Seventy Only	Per square metre	3042.20
9	Applying priming coat over new wood and wood based surfaces after and i/c preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand papering and knotting including carriage of mateirals in all leads and lifts as per directions of the Engineer-in-Charge	43.46	Sqm.	40.00	Rupees Forty Only	Per square metre	1738.40

10	Painting two coats (excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering & stopping including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint.	43.46	Sqm.	70.00	Rupees Seventy Only	Per square metre	3042.20
					Total		98913

D/NR No. ~~84~~ 5447/8N6 12178 79 dt 9-10-25

And does 101880 only

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-98965=00		
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 (SH:- Renovation of Garrage NO - 2 at Melhi Shimla (converted to servent qtrs)					Earnest Money :-2000=00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Half brick masonry with non modular fly ash bricks of class designation 10, conforming to IS :12894, in super structure above plinth and upto floor V level. (i) Cement mortar 1 : 4 (One cement : four coarse sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge.	10.15	Sqm	1020.00	Rupees One Thousand Twenty Only	Per Square Metre	10353.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size	0.97	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	6208.00
3	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm(three hundred into three hundred millimetre) or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetre) thick cement mortar 1:4 (one Cement: four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.01	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	4571.40
4	Kota stone slab flooring 25 mm thick in risers of steps, skirting dado and pillars laid on 12mm (average) thick base of cement mortar 1:3 (One cement : Three sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing with Grenite polish complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	13.50	Sqm	1300.00	Rupees One Thousand Three Hundred Only	Per Square Metre	17550.00
5	Providing and fixing 19mm thick water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	7.52	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square meter	10152.00
6	Providing and fixing 1.00mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	3.09	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	2626.50
7	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 9mm thick	2.37	Sqm	900.00	Rupees Nine Hundred Only	Per Square Meter	2133.00
8	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) (i) For fixed portion (a) Powder coated aluminium (minimum thickness of powder coating 50 micron)	28.00	Kgs	680.00	Rupees Six Hundred Eighty Only	Per Kilo- gram	19040.00
9	Providing and fixing Aluminium Pannel sheet 3.00 thick for doors, windows including carriage of materials in all leads and lifts as per directions of Engineer-in-charge	1.46	Sqm	800.00	Rupees Eight Hundred Only	Per Square Meter	1168.00
10	Providing and fixing aluminium handles anodized transparent or dyed to required colour & shade with necessary screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	2.00	Nos	80.00	Rupees Eighty Only	Each	160.00

11	Providing and fixing anodized aluminium sliding door bolt anodized colour and shade with bolts and nuts screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 250x16mm	1.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	250.00
12	Providing and fixing aluminium tower bolts (berrel type) anodized trans parent or dyed to required shade and colour with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 200x10mm	3.00	Nos	70.00	Rupees Seventy Only	Each	210.00
13	Providing and fixing bright finished brass handles with screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 100mm (One hundred milimetre)	5.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	750.00
14	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arises,internal rounded angles,chainfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:4 (one Cement Four Sand)	17.11	Sqm	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	4790.80
15	Providing and fixing PVC sheet ceiling including carriage of materials in all leads and lifts as per directions of the Engineer - in - charge . (6mm thick)	14.30	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	13585.00
16	Providing and fixing PVC Corner 18x6 mm thick ceiling including carriage of materials in all leads and lifts as per directions of the Engineer - in - charge .	18.10	Rmt	80.00	Rupees Eighty Only	Per Running metre	1448.00
17	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	16.96	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	763.20
18	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enenal paint.	16.96	Sqm	70.00	Rupees Seventy Only	Per Square Meter	1187.20
19	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	17.11	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	1112.15
20	Distempering with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade. Old work (one or more coats). including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	17.11	Sqm	53.00	Rupees Fifty Three Only	Per Square Metre	906.83
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
BD							
						G.Total	98965.08

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before

T/s No 11304-05 dated 27.9.25 Amounting to Rs. 1,01,933/-

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.

18
9

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99000.00	
Name of Work :- Annual Repair Maintenance road on Melhi to IAS Colony road in KM 0/00 to 2/00 (Supplying and laying pot seal Bags cold mix in km 0/00 to 2/00)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying Pot seal bags of 25 kg cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer - in - Charge .	120.00	Cum	825.00	Rs Eight hundred twenty five only	Per Cubic Metre	99000.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	99000.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-

DNIT approved for Rs.99000/- Only vide DNIT Register Sr.No. 539 the financial year 2025-26 T/S No 12168

Amt for 10/970/-

dt 9/10/25

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY						
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-98175.00	
Name of Work :- Annual Repair Maintenance on Old Kasumpti Junga road in KM 0/00 to 11/00 (Supplying and laying pot seal Bags cold mix in km 0/00 to 5/00)					Earnest Money :-2000.00	
					Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit
				In figures	In words	
1	Supplying and laying Pot seal bags of 25 kg cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer - in - Charge .	119.00	Cum	825.00	Rs Eight hundred twenty five only	Per Cubic Metre
	Quated rates Percentage in figures					
	Quoted rates Percentage in words					
						G.Total
						98175.00

DNIT approved for Rs.98175/- Only vide DNIT Register Sr.No. 542 the financial year 2025-26 / SN 12171
dt 9-10-25

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-

Amr to Rs 101120/-

Executive Engineer
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99825.00	
Name of Work :- Annual Repair Maintenance on Bhatta kuffer to Koti road in KM 0/00 to 6/385 (Supplying and laying pot seal Bags cold mix in km 0/00 to 1/00)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying Pot seal bags of 25 kg cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer - in - Charge .	121.00	Cum	825.00	Rs Eight hundred twenty five only	Per Cubic Metre	99825.0
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	9982

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-

DNIT approved for Rs.99825/- Only vide DNIT Register Sr.No. 542/543 the financial year 2025-26 T/8 No 12171

Amt to Rs 102820/-

dt 9-10-2025

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99825.00	
Name of Work :- Annual Repair Maintenance on Old Junga to Bharandi road in KM 0/00 to 2/00 (Supplying and laying pot seal Bags cold mix in km 0/00 to 2/00)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying Pot seal bags of 25 kg cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer - in - Charge .	121.00	Cum	825.00	Rs Eight hundred twenty five only	Per Cubic Metre	99825.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	99825

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-

DNIT approved for Rs.99825/- Only vide DNIT Register Sr.No. ⁵⁴¹ the financial year 2025-26 T/S No 1217
dt-9-10-2025

And to Rs 102,820/-

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99000.00		
Name of Work :- Annual Repair Maintenance on Cheri to Kyarkoti road in KM 0/00 to 5/00 (Supplying and laying pot seal Bags cold mix in various portion km 0/00 to 5/00)					Earnest Money :-2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying Pot seal bags of 25 kg cold mix including carriage of materials in all leads and lifts as per the directions of the Engineer - in - Charge .	120.00	Cum	825.00	Rs Eight hundred twenty five only	Per Cubic Metre	99000.0
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	9900

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-

DNIT approved for Rs.99000/- Only vide DNIT Register Sr.No. 540 the financial year 2025-26 T/S No 1217
dt 9-10-25

Amt to Rs 1,01,970/-

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.


SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99988.00		
Name of Work :- A/R & M/O various Type-III & Type-IV GAD at Parimahal, Kasumpti, Shimla-171009. (SH:- Covering of Balcony in Type-III 09,70,74 etc. and P/F accessories in Type-III set no 650 under Kasumpti Sub-Division.)					Earnest Money :-2000.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) In gratings, framed guards bars ladders, railing, brackets and similar work.	80.88	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	8492.40
2	Supplying and fixing welding mesh to wood or steel members in partitions etc including on coat of priming coat. 25x25x3mm	4.20	Sqm	600.00	Rupees Six Hundred Only	Per square metre	2520.00
3	Painting two coats (excluding priming coat on new steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters (i) Enamel paint other than white	70.80	Sqm	65.00	Rupees Sixty Five Only	Per square metre	4602.00
4	Providing and fixing Copper oxidised fittings (iron) (i) Butt hinges: 75x47x1.70 mm	8.00	Nos.	100.00	Rupees One Hundred	Each	800.00
5	Providing and fixing oxidized M.S sliding door bolts with nuts and screws etc. complete. (i) 250x16 mm	2.00	Nos.	265.00	Rupees Two Hundred Sixty Five Only	Each	530.00
6	Providing and fixing oxidised M.S tower bolts (barrel type) with necessary screws etc. Complete (i) 150x10mm	4.00	Nos.	1750.00	Rupees One Thousand Seven	Each	7000.00
7	Providing and fixing polycarbonate sheet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 2.00 mm thick	26.09	Sqm	2150.00	Rupees Two Thousand One Hundred Fifty Only	Per square metre	56093.50
8	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I or M.S. brackets painted white including cutting holes and making good the same but excluding fittings (a) Flat back (i) 550 mmx400mm MAKE ESSESS or Equivalent	1.00	Nos.	3500.00	Rupees Three Thousand Five	Each	3500.00

9	Providing and fixing 32mm (thirt two milimetre) dia C.P brass wastefor wash basin or sink complete with all leads, lifts of materials and other incidentals.	1.00	Nos.	450.00	Rupees Four Hundred Fifty Only	Each	450.00
10	Providing and fixing white vitreous China pedestal for wash basin completely rexessed at the back for the reception of pipes and fittings.	1.00	Nos.	3000.00	Rupees Three Thousand	Each	3000.00
11	Providing and fixing one hole basin mixing Faucet. MAKE ESSESS or Equivalents	1.00	Nos.	4000.00	Rupees Four Thousand Only	Each	4000.00
12	Providing and fixing 15 mm mixer for kitchen sink with top/ bottom swinging spout . MAKE ESS ESS or Equivalent.	2.00	Nos	4500.00	Rupees Four Thousand Five Hundred	Each	9000.00
					Total		99988

P/NR No 531 / ISN 12152-53 dt 9-10-25 Amt 1,02,988/-
 Amt - 1,02,988

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 Shimla Division No.1,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 83,724.00	
Name of Work :-Restoration of Rain Damages on Koti to Satlai road in Km. 0/00 to 15/000. (SH:-						Earnest Money :- 1,700.00	
Construction of wire create at RD 2/045 to 2/048). (Balance work).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg. (twenty five) kilograms each as per drawing and technical specifications Clause 1301 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	27.65	Cum	3028.00	Rupees Three Thousand Twenty Eight Only	Per Cubic Meter	83724.00
						Total	83724.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR.No. 532 TIS No. 12154-55 dt 9-10-25 Amt 86,236/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I,				Estimated Cost:-		93720.00	
Name of Work :- A/R & M/O various Type-III & Type-IV GAD at Kasumpti, Shimla-171009.				Earnest Money :-		1900.00	
(SH :- Converging of Balcony Covering etc. in Type-II set No. 607 and 608 under Kasumpti				Time:-		One month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and rafters, purlins connected to common rafters and the like.	480.53	Kgs	105.00	Rupees One Hundred Five Only	Per Kilo-gram	50455.65
2	Suppling and fixing welded mesh 225x25x3mm to wood or steel members in partitions etc.	22.14	Sqm	600.00	Rupees Six Hundred Only	Per Square meter	13284.00
3	Providing fixing Copper oxidised fittings (iron): (i) Butt hinges: 75x1.70mm	24.00	Nos	100.00	Rupees One Hundred Only	Nos	2400.00
4	Providing an fixing Copper oxidised fittings (iron): (i) Tower bolts (barrel type): 100x100mm	20.00	Nos	70.00	Rupees Seventy Only	Nos	1400.00
5	Applying priming coat over new steel & other metal surface after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes fine steel wool scrapers and sand paper complete. (i) With ready mixed priming paint brushing red lead, Red - oxide/ zine oxide chrome.	22.14	Sqm	40.00	Rupees Forty Only	Per Square meter	885.60
6	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint, brush in to give an even shade i/c cleaning the surface of all dirt, dust and other foreign matters including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Enamel paint other than white.	39.49	Sqm	70.00	Rupees Seventy Only	Per Square meter	2764.30
7	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws	2.00	Sqm	300.00	Rupees Three Hundred Only	Per Square meter	600.00
8	Providing and fixing polycarbonate sheet including carriage of materials in all lead and lifts as per directions of the Engineer-in-Charge. (i) 2.00 mm thick	10.20	Sqm	2150.00	Rupees Two Thousand One Hundred Fifty	Per Square meter	21930.00
						Total	93720.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should conform to Bureau of Indian

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.

D/NR No. 52 T/S No. 11862-63 dt 6-10-25 Amt 96,532)

SCHEDULE OF QUANTITY


Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost: 99,855.00	
Name of Work :- Restoration of Rain damages on various roads under Shimla Dhalli Section. (SH:-						Earnest Money : 2,000.00	
Removal of Slips at various Roads.)						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantities of stone from removal of slips shall have to be neatly stacked along road side on road burns, minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.10	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hour	99855.00
						Total	99855.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR/V 534 T/S No. 12188

12158-59 dt 9-10-25 Amt 10,2851/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.


 Executive Engineer
 Shimla Division No. I,
 HP PWD Shimla-3.


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 94,171.00	
Name of Work :-Restoration of Rain Damages on Koti to Satlai road in Km. 0/00 to 15/000. (SH:-						Earnest Money :- 1,900.00	
Construction of wire create at RD 2/048 to 2/051). (Balance work).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and laying of boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 Kg. (twenty five) kilograms each as per drawing and technical specifications Clause 1301 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	31.10	Cum	3028.00	Rupees Three Thousand Twenty Eight Only	Per Cubic Meter	94171.00
						Total	94171.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR-No 533 T/PN..12156-57 of 9-10.25A at 96,996/-

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in


 Executive Engineer,
 Shimla Division No.I,
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:-99460.00		
Name of Work :- Repair and Maintenance of AIMSS (IGMCI Phase - II Hosipital) at					Earnest Money :- 2000.00		
Chamyana (SH:- Supply of Sergical sink fitting fixtures Civil works items for items for					Time:- One Month.		
routine maintenance .							
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate	Unit	Unit	Amount
				In figures			
1	Door Stoper	20.00	Nos	175.00	Rupees One Hundred Seventy Five Only	Each	3500.00
2	Measuring Tape 3 mtrs	1.00	Nos	290.00	Rupees Two Hundred Ninety Only	Each	290.00
3	Trap cleaning Pump Plastic	2.00	Nos	190.00	Rupees One Hundred Ninety Only	Each	380.00
4	SS pegs 4 in one	33.00	Set	480.00	Rupees Four Hundred Eighty Only	Per set	15840.00
5	SS pegs 6 in one	13.00	Set	720.00	Rupees Seven Hundred Twenty Only	Per set	9360.00
6	Concrete Bit Hammering 6 MM	2.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	300.00
7	Hydraulic door closer	2.00	Nos	1950.00	Hundred Fifty Only	Each	3900.00
8	Tile / Toilet cleaner	1.00	pack	180.00	Rupees One Hundred Eighty Only	per pack	180.00
9	sliding Door bolt Brass 250 mm	3.00	Nos	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Each	5850.00
10	Brass Para colome with screws	3.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	450.00
11	CPVC over cross 15 mm	4.00	Each	190.00	Rupees One Hundred Ninety Only	Per pack	760.00
12	Plug 15 mm	10.00	Each	20.00	Rupees Twenty Only	Each	200.00
13	CPVC reducer 25x20	2.00	Each	240.00	Rupees Two Hundred Forty Only	Each	480.00
14	Plain tee 25 mm	2.00	Each	160.00	Rupees One Hundred Sixty Only	Each	320.00

15	Tank Nipple 25mm	1.00	Each	290.00	Rupees Two Hundred Ninety Only	Each	290.00
16	Union 25 mm	1.00	Each	220.00	Rupees Two Hundred Twenty Only	Each	220.00
17	Ball Valve 25 mm	1.00	Each	590.00	Rupees Five Hundred Ninety Only	Each	590.00
18	Elbow 25 mm	2.00	Each	120.00	Rupees One Hundred Twenty Only	Each	240.00
19	Reducer 32x20	1.00	Each	190.00	Rupees One Hundred Ninety Only	Each	190.00
20	Tee 32mm	1.00	Each	280.00	Rupees Two Hundred Eighty Only	Each	280.00
21	Elbow 32 mm	1.00	Each	290.00	Rupees Two Hundred Ninety Only	Each	290.00
22	Wheel vave 32mm	1.00	Each	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	1750.00
23	Union 32 mm	1.00	Each	390.00	Rupees Three Hundred Ninety Only	Each	390.00
24	Tank Nipple 32mm	1.00	Each	480.00	Rupees Four Hundred Eighty Only	Each	480.00
25	Tank Nipple 20mm	2.00	Each	190.00	Rupees One Hundred Ninety Only	Each	380.00
26	GI Hooks	50.00	Each	20.00	Rupees Twenty Only	Each	1000.00
27	Taflon tape	6.00	No	40.00	Rupees Forty Only	No	240.00
28	Consealed cock	1.00	Each	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	1250.00
29	Sergical Singal lever sink mixer SS	1.00	Each	9800.00	Rupees Nine Thousand Eight Hundred Only	Each	9800.00
30	Fastner 6mm	30.00	Each	70.00	Rupees Seventy Only	Each	2100.00

31	Surgical steel sink 37x18x10 inch	2.00	Each	14900.00	Rupees Fourteen Thousand Nine Hundred Only	Each	29800.00
32	Silding door bolt 300 mm	4.00	Each	2090.00	Rupees Two Thousand Ninety Only	Each	8360.00
						Total	99460.00
					Add 3% contigency charges		2938.00
							102398.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.

2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved for Rs.99460.00/- Only vide DNIT Register Sr.No. 537 the financial year 2025-26
T/s No. 12164-65 dated 9-10-25 Amounting to Rs. 102,443.00

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.

14
9

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99,000.00	
Name of Work :--Restoration of Rain damages various roads under AIMSS section.(SH:- Providing Staff for maintenance of various roads under AIMSS section w.e.f. 15.10.2025 to 14.11.2025.(one Month)						Earnest Money :-2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 6 Nos. Beldar for any of duties assigned by Engineer in charge for routine maintainence of roads, unskilled jobs such as earth work, brooming of roads, cleaning of drains, opening of culverts, clearing of minor slips, carriage/loading of material, cleaning and washing of areas, assisting plumber, carpenter etc cutting of grass and other miscellaneous works assigned by Engineer in charge. All requisit T&P, Tool, dress safety, equipment etc. As per work required shall be provided by the contractor and as per the direction of the Engineer-in-Charge. The contractor shall provide the Labour as and when required and in case of urgency contractor is bound to provide additional labour on the agreement rates and shall be payable as per deployed workers..(Six No. Beldar for one month)	180.00	Days	550.00	Rupees Five Hundred Fifty Only	Per Days	99000.00
						Total	99000.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

D/NR. No. 5357/S No. 12160-61 dt 9-10-25

Amt to Rs. 1,02,851 only

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
Shimla Division No.1.
HP PWD Shimla-3.

17

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I,					Estimated Cost:-99605.00		
Name of Work :- Repair and Maintenance of AIMSS (IGMC Phase - II Hosipital)					Earnest Money :-2000=00		
at Chamyana (SH: Supply of fitting fixtures Civil works items for items for routine maintenance .					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate In figures	Unit	Unit	Amount
1	Tirpal 18x24 feet	1.00	Nos	3500.00	Rupees Three Thousand Five Hundred Only	Each	3500.00
2	CPVC pipe 50 mm dia	15.00	Nos	1950.00	Rupees One Thousand Nine Hundred Fifty Only	Each	29250.00
3	CPVC socket 50 mm dia	12.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	4200.00
4	CPVC Elbow 50 mm dia	10.00	Nos	350.00	Rupees Three Hundred Fifty Only	Each	3500.00
5	CPVC Clamps 50 mm dia	20.00	Nos	50.00	Rupees Fifty Only	Each	1000.00
6	Seal jet	3.00	Nos	280.00	Rupees Two Hundred Eighty Only	Each	840.00
7	Pvc pipe 4 inch 6 feet	1.00	Nos	1000.00	Rupees One Thousand Only	Each	1000.00
8	vetrified tiles 600x 600 (superior quality)	20.00	box	2320.00	Rupees Two Thousand Three Hundred Twenty Only	box	46400.00
9	PVc coller 4 inch	3.00	Nos	225.00	Rupees Two Hundred Twenty Five Only	Each	675.00
10	CPVC Tee 3x2 inch	2.00	Nos	1600.00	Rupees One Thousand Six Hundred Only	Each	3200.00
11	M- seal	10.00	pack	30.00	Rupees Thirty Only	Per pack	300.00
12	CP angle cock	2.00	Nos	950.00	Rupees Nine Hundred Fifty Only	Each	1900.00

13	VPVC ball valve 20 mm	1.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	450.00
14	Glass cutter	1.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	1800.00
15	CPVC socket 20 mm	2.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	240.00
16	wall valve 15 mm	3.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	1350.00
	Total						99605.00

CONDITION:-

1. Rates should be quoted for all heights including all le: T/s No 12166-67 dated 9-10-25 Amounting to Rs. 103593/-
2. Sample of all the material to be used on work shall be got

Executive Engineer,
Shimla Division No.I,
HP PWD Shimla-3.