



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26-

10427-32

Dated:- 17/10/25

To

The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	23.10.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	24.10.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	25.10.2025	Upto 10.30 P.M.
4	The date of opening of tender	25.10.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 25.10.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1	Restoration of rain damage on various roads under Oachghat sub-division (SH: Hiring of Excavator cum loader for removal of debris, slips, clearance of unlined drain & maintenance of berms)	98700/-	2000/-	One Month	Rs.350/-
2	Restoration of rain damage on various roads under Oachghat sub-division (SH: Hiring of Excavator cum loader for removal of debris, slips, clearance of unlined drain & maintenance of berms in Jatoli section)	98700/-	2000/-	One Month	Rs.350/-
3	Restoration of rain damage on various roads under Oachghat sub-division (SH: Hiring of tipper for carriage of debris to remove slips and dump at specified site in Gaura Section)	96600/-	2000/-	One Month	Rs.350/-
4	Restoration of rain damage on Jatoli Gadog road km 0/0 to 5/590(SH: Hiring of tipper for carriage of debris to remove slips and dump at specified sites)	96600/-	2000/-	One Month	Rs.350/-
5	Repair and maintenance of Assistant Engineer's office HPPWD, sub-division Kandaghat in Tehsil Kandaghat Distt. Solan (Deposit work) (SH: Repair of plaster of patches, wall painting, door & windows painting)	97442/-	2000/-	One Month	Rs.350/-
6	Repair and maintenance of Assistant Engineer's office HPPWD, sub-division Kandaghat in Tehsil Kandaghat Distt. Solan (Deposit work) (SH: Repair to frame of doors, windows and roofing work etc.)	85332/-	1700/-	One Month	Rs.350/-
7	Repair and maintenance of type-II quarter block No. 11 Jawahar park colony at Solan (SH: Painting and distempering and roofing sheet etc.)	237078/-	4800/-	One Month	Rs.350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

Executive Engineer,
B&R Division,
HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/20025-26-10427-32 Dated: 17/16/25 are of emergent nature of work and in public interest.

Dated:-

Place:- Solan

Executive Engineer
B&R Division
HPPWD, Solan

1

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED One Month

Name of Work :- Restoration of rain damages on various roads under Oachghat Sub Division (SH :- Hiring of Excavator cum Loader for removal of debris , slips , clearance of unlined drain & maintenance of berms)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-				Rupees Ninety Eight Thousand Seven Hundred Only		
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor

Executive Engineer
B&R HPPWD Division
Solana

(2)

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 98,700.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

Name of Work :- Restoration of rain damages on various roads under Oachghat Sub Division (SH :- Hiring of Excavator
Cum Loader for removal of debris, slips, clearance of unlined drain & maintenance of berms in Jatoli Section)

Sr. No.	Description of item	Quantity (Hours)	Rate (Rs.) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow, removal of debris and dressing of berms with minimum capacity of 45 cum per hour, minimum 6 hours per day including pay of operator, POL charges, maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	94.00	1050.00	Rupees One Thousand and Fifty Only	Per Hour	98700.00
TOTAL						Rs. 98700.00
Total in Words :-		Ninety Thousands Seven Hundred Fifty Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor

Executive Engineer
B&R HPPWD Division
Solani

(3)

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 96,600.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

N.O.W. :- Restoration of rain damages on various roads under Oachghat Sub Division (SH :- Hiring of tipper for carriage of debris to remove slips and dump at specified sites in Gaura Section)

Sr. No.	Description of item	Quantity (Days)	Rate (Rs.)	Rate in Words	Unit	Amount
1	Hiring of tipper for removal of snow/ slips with minimum capacity of 5.5 cum per trip , minimum 6 hours per day. The contractor / owner of tipper shall bear the expenses of POL charges, repair of machinery. Any accident and other damages to private and government property occur during working hour is the whole responsibility of contractor and disposal within all leads , lifts as per the direction of Engineer - in - charge.	23.00	₹ 4,200.00	Rupees Four Thousand Two Hundred Only	per Day	₹ 96,600.00
TOTAL						₹ 96,600.00
Total in Words :-		Rupees Ninety Six Thousand Six Hundred Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Hiring charges shall be payable only after signing of agreement and completion of work as per the directions of Engineer-in-charge.

Executive Engineer

PPD, Muzaffarpur, Bihar

(4)

SCHEDULE OF QUANTITY

ESTIMATED COST ₹ 96,600.00
EARNEST MONEY ₹ 2,000.00
TIME ALLOWED Two Months

N.O.W. :- Restoration of rain damages on Jatoli Gadog road Km.0/00 to 5/590 (SH :- Hiring of tipper for carriage of debris to remove slips and dump at specified sites)

Sr. No.	Description of item	Quantity (Days)	Rate (Rs.)	Rate in Words	Unit	Amount
1	Hiring of tipper for removal of snow/ slips with minimum capacity of 5.5 cum per trip , minimum 6 hours per day. The contractor / owner of tipper shall bear the expenses of POL charges, repair of machinery. Any accident and other damages to private and government property occur during working hour is the whole responsibility of contractor and disposal within all leads , lifts as per the direction of Engineer - in - charge.	23.00	₹ 4,200.00	Rupees Four Thousand Two Hundred Only	per Day	₹ 96,600.00
TOTAL						₹ 96,600.00
Total in Words :-		Rupees Ninety Six Thousand Six Hundred Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

Conditions :-

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Hiring charges shall be payable only after signing of agreement and completion of work as per the directions of Engineer-in-charge.

Executive Engineer
B&R HPWD Division
Solani

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Name of Work :- Repair and maintenance of Assistant Engineer's Office HPPWD Sub Division Kandaghat in Teh. Kandaghat Distt. Solan (Deposit work) (SH:- Repair of plaster of patches, wall painting, door & windows painting)						
				Estimated Cost: -		97442.00
				Earnest Money: -		2000.00
				Time limit :-		One month
Job No. 75						
1	Distemping with oil bound washable distemper of New work (two or more coats) over and including water thinnable priming coat with cement primer of approved brand and manufacture to give an even shade etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	117.45	Per Square Meter	89.50	Rupees Eighty Nine and Paise Fifty Only	10512.00
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	466.41	Per Square Meter	85.10	Rupees Eighty Five and Paise Ten Only	39691.00
3	White washing with lime to give an even shade Old work (two or more coats) complete as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	517.71	Per Square Meter	10.50	Rupees Ten and Paise Fifty Only	5436.0
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	466.41	Per Square Meter	8.50	Rupees Eight and Paise Fifty Only	3964.1
5	Distemping Old work (one or more coats) with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	466.41	Per Square Meter	35.45	Rupees Thirty Five and Paise Forty Five Only	16534.

ing Old work (one or more coats) with oil type wood preservative of approved brand manufacture complete as per direction of Engineer in Charge and as per HP.PWD. ification including carriage of all labour, equipment and material to various locations ough all modes of transportation in all leads and lifts and all incidental charges.

pairs to plaster of thickness 12 mm to 20 mm (twelve to twenty millimeter) thick with nent mortar 1:4 (one cement is to four sand) in patches of area 2.5 sq. meters and der, including cutting the patch in proper shape, raking out joints and preparing and astering the surface of the walls complete, including disposal of rubbish to the dumping ound, all complete as per direction of Engineer-in-Charge.

	299.00	Per Square Meter	25.90	Rupess and Paise Only	264.35	Per Square Meter	Rupess Two Hundred Sixty Four and Paise Thirty Five Only	13561.00
	51.30							
Total:-								
Rupess Ninety Seven Thousand Four Hundred Forty Two Only								
Quoted Percentage rate upto Three Digits :-		(+) / (-)						97442.00

T/S No. 226 for the ~~2025-26~~
 Sr. No. ~~387~~ for the year 2025-26

~~Executive Engineer~~
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
<p>Name of Work :- Repair and maintenance of Assistant Engineer's Office HPPWD Sub Division Kandaghat in Teh. Kandaghat Distt. Solan</p> <p>(Deposit work) (SH:- Repair to frame of door, windows and roofing work etc.)</p>						
<p>Job No. :- ②</p>						
				Estimated Cost :-		85332.00
				Earnest Money :-		1700.00
				Time limit :-		One month
1	Providing wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position in Sal wood wood as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	0.225	Per Cubic Meter	95763.05	Rupees Ninety Five Thousand Seven Hundred Sixty Three and Paise Five Only	21547.00
2	Providing and fixing Second class teak wood 35 mm thick shutters panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note:- Butt hinges and necessary screws shall be paid separately as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	6.300	Per square meter	3122.60	Rupees Three Thousand One Hundred Twenty Two and Paise Sixty Only	19672.00
3	Providing frosted glass panes 4 mm thick instead of ordinary float glass panes 4 mm thick in doors, windows and clerestory window shutters. (Area of opening for glass panes excluding portion inside rebate shall be measured) as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges	5.99	Per Square Meter	214.05	Rupees Two Hundred Fourteen and Paise Five Only	1282.00
4	Dismantling doors, windows and clerestory windows, ventilators (steel or wood) shutters including chaukhats, architraves, hold fasts and other attachments etc. complete in all respects not exceeding 3.00 (three) square meter in area etc. as per direction of Engineer in Charge and as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	3.00	Each	156.25	Rupees One Hundred Fifty Six and Paise Twenty Five Only	469.00

5	Dismantling of G.S. Sheet roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of: as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	31.50	Per square meter	69.80	Rupees Sixty Nine and Paise Eighty Only	2199.00
6	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester(RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating fixing with prepainted iron J or L hooks, bolts and nuts 6mm diameter with prepainted limpet and rubber washers complete with all accessories as per H.P.PWD. Specification including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	31.50	Per square meter	1275.00	Rupees One Thousand Two Hundred Seventy Five Only	40163.00
Total:-						85332.00
Rupees Eighty Five Thousand Three Hundred Thirty Two Only						
Quoted Percentage rate upto Three Digits :-						
			(+) / (-)			

T/S No. 224 for the year ~~2025-26~~
 Sr. No. ~~386~~ for the year 2025-26

Executive Engineer
 B&R Division, HP.PWD. Solan.

Draft Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 7				Estimated Cost: -		237078.00
				Earnest Money: -		4800.00
				Time limit: -		One Month

Name of Work :- Repair and maintenance of Type-II quarter block no.11 Jawahar Park colony at Solan (SH:- Painting and distemping and roofing sheet etc.)

1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	656.160	Per Square Meter	116.70	Rupees One Hundred Sixteen and Paise Seventy Only	76574.00
2	Distemping Two coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	218.180	Per Square Meter	72.46	Rupees Seventy Two and Paise Forty Six Only	15809.00
3	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts.	656.16	Per square meter	16.64	Rupees Sixteen and Paise Sixty Four Only	10919.00
4	Wall painting Two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacturer, including applying additional coats wherever required to achieve even shade and colour complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts.	438.00	Per Square Meter	106.40	Rupees One Hundred Six and Paise Forty Only	46603.00
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	49.93	Per square meter	114.60	Rupees One Hundred Fourteen and Paise Sixty Only	5722.00
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	463.41	Per Killogramm	107.45	Rupees One Hundred Seven and Paise Forty Five Only	49793.00

<p>7 Providing corrugated G.S. sheet roofing 0.63 mm thick with zinc coating not less than 275 gm/ m² including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.</p>	30.15	Per square meter	1050.00	Ruppes One Thousand Fifty Only	31658.00
<p>Total:-</p>					237078.00
<p>Ruppes Two Lakhs Thirty Seven Thousand Seventy Eight Only</p>					

T/S No. 225 for the 2025-26
 Sr. No 38 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 237078.00 only.

Executive Engineer
 B&R Division, HP.PWD. Solan.