Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023

Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

No. PW/TDD/GA/Tender/2025-26 10295-10346 Dated: - 24.10.2025

To

The Executive Engineer(IT Cell),
Nigam Vihar HP Shimla-171002.

Subject: - Publication of Tender Notice

Enclosed please find herewith the tender notice of various works given in the Notice Inviting Tender . As per Notification Pr.Secy.(PW) to the Govt Himachal Pradesh Letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July 2021 as works mentioned in the tender Notice are of urgent nature and in public interest, the sa may be uploaded on the departmental website

ECL: -Notice Inviting Tender/ Scheduled of Quantity and Certificate.

Yours faithfully,

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Copy forwarded to the following for information: -

1. The Engineer-in-Chief HPPWD., Shimla
2. The Chief Engineer (HZ), HP.PWD, Hamirpur
3. The Deputy Commissioner Hamirpur
4. The Superintending Engineer, 8th Circle HP.PWD, Hamirpur
5. The B.D.O Tauni Devi
6. All the Assistant Engineer working in this Division.
7. Notice Board.
8. AB & DB.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of

EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@nic.in

CERTIFICATE

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/ emergency in calling these tender without press vide this office letter No. No. PW/TDD/GA/Tender/2025-26 /10295-10346 dated 24.10.2025

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Office of
EXECUTIVE ENGINEER TAUNI DEVI DIVISION
H.P. Public Works Department, TAUNI DEVI 177023
Telephone. 01972-278422, e.mail: ee-tou-hp@gov.in

Tender Notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Tauni Devi Division, H.P. PWD, Tauni Devi on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/firms enlisted in HP PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the HP General Sales Tax Act 1968 so as to reach in his office on or before **03.11.2025 up to 10.30 AM** And the same shall be opened on the same day at **11.00 AM** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) up to **01.11.2025** up **to 3.00 PM** and the application for issue of tender form shall be received up **31.10.2025 up to 4.00 PM**. The earnest money in the shape of NSC/Time deposit account/saving account of the post office in HP duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S.No	*Name of work*	*Estimated cost*	*Earnest money*	*Time*
1	Restoration of rain damages on link road to Narwalan-Di-Dar to Bouru road via Lambran-Di-Dhar Km 0/00 to 2/130. (SH:- Construction of retaining wall at RD 1/770 to 1/783) **(Under PDNA)**	414966.00	8300.00	Two Months
2	Restoration of rain damages on link road to Village Sukhani Km. 0/00 to 2/00 (SH:- Construction of retaining wall at RD 1/510 to 1/525) **(Under PDNA)**	498071.00	10000.00	Two Months
3	Restoration of rain damages on Barara to Bakkar Khad via Patnoun road Km 0/00 to 8/00 (SH:- Construction of retaining wall at RD 2/720 to 2/735) **(Under PDNA)**	300443.00	6000.00	Two Months
4	Restoration of rain damages on Baru Tapre road Km 5/265 to 8/705 (SH:- Construction of retaining wall at RD 7/210 to 7/220) **(Under PDNA)**	351025.00	7100.00	Two Months
5	Restoration of rain damages on Langwan Tauni Devi road Km 3/345 to 7/305 (SH:- Construction of retaining wall at RD 5/680 to 5/690) **(Under PDNA)**	231924.00	4700.00	Two Months.
6	Restoration of rain damages on Bouru to Chamarda road Km. 0/00 to 3/00 (SH:- Construction of V-shape drain including edge wall RD's 1/900 to 2/020 **(Under PDNA)**	2,54,544.00	5100.00	Two Months.
7	Restoration of rain damages on link road Shiv Mandir to Chaptehar KM. 0/00 to 0/500 (SH:- Construction of Brest wall at RD 0/047 to 0/062 & V-shape drain including edge wall) **Under PDNA**	4,26,545.00	8500.00	Two Months
8	Restoration of rain damages on link road to Village Lohar Balli Km. 0/00 to 1/900 (SH:- Providing and laying of wire crate in Km. 0/550 to 0/561) **Under PDNA**	4,86,822.00	9800.00	Two Months.
9	Restoration of rain damages on link road Lambari Nalahi Asthota road km. 0/00 to 6/00.(SH:- C/O PCC left side wing wall at RD. 0/725 to 0/733) .**(Under PDNA).**	2,63,093.00	5500.00	Two Months
10	Restoration of rain damages on Chariyan Di Dhar to Lambran-Di-Dhar via Bouru road km. 0/00 to 2/00. (SH:- P/L hume pipe culvert at RD. 0/730).**(Under PDNA).**	2,76,177.00	5500.00	Two Month
11	Restoration of rain damages on link road Harizan Basti Chalokhar km. 0/00 to 0/500)(SH:- C/O 900mmm dia hume pipe culvert at RD. 0/240 and patch work).**(Under PDNA).**	2,57,429.00	5500.00	Two Months
12	Restoration of rain damages on link road to village Sapahal KM 0/0 to 1/500.(SH:- C/O PCC V-shape drain, unlined drain and P/L patch work at various RD's).**(Under PDNA).**	2,35,932.00	5000.00	Two Months
13	Restoration of rain damages on link road to village Gahra KM 0/0 to 1/200.(SH:- C/O hume pipe culvert 900mm dia at RD. 0/480 with catch pit and toe wall on U/S and D/S side).**(Under PDNA).**	1,29,353.00	2600.00	Two Months
14	Restoration of rain damages on Baru Jhatour road road Km 0/00 to 1/750 (SH:- Construction of retaining wall at RD 0/060 to 0/090, 1/075 to 1/082 and 1/150 to 1/158) **Under PDNA)**	4,55,775.00	9200.00	Two Months
15	Restoration of rain damages on link road from Pungh Khad to Chamyola KM 0/0 to 1/610.(SH:- C/O cement concrete pavement at RD. 0/410 to 0/450).**(Under PDNA).**	162824.00	3500.00	Two Months

Scanned with CamScanner

16	Restoration of rain damages on Hamirpur Sujanpur road Km. 16/0 to 24/870 (SH:- Providing and laying patch work at various RD's (Under SDRF)	498613.00	10000.00	Two Months
17	Restoration of rain damages on Hamirpur Sujanpur road Km. 2/600 to 24/870 (SH:- Providing and laying patch work at various RD10/0 to 16/0 (Under SDRF)	495771.00	10000.00	Two Months.
18	Restoration of rain damages on Hamirpur Sujanpur road Km. 2/600 to 24/870 (SH:- Providing and laying patch work at various RD 2/600 to 10/0 (Under SDRF)	495963.00	10000.00	Two Months
19	A/R&M/O various roads under Tauni Devi Sub-Division (Section Uhal) (SH:- Painting & writing letters of information sign boards, Km stone and other road side furniture etc.	98929.00	2000.00	Two Months
20	A/R&M/O various roads under Tauni Devi Sub-Division (Section Tauni Devi) (SH:- Painting & writing letters of information sign boards, Km stone and other road side furniture etc.	98825.00	2000.00	Two Months
21	Restoration of rain damages on various road under Sujanpur Sub-Division HPPWD., Sujanpur (SH:- Providing supply and stacking road Bond (Ready mix pot seal) and Emulsion drum RS-I) Under PDNA	495500.00	10000.00	Two Months
22	Restoration of rain damages on various road under Tauni Devi Sub-Division HPPWD., Tauni Devi (SH:- Providing supply and stacking road Bond (Ready mix pot seal) and Emulsion drum RS-I) Under PDNA	495500.00	10000.00	Two Months
23	Restoration of rain damages on link road from Ansla to Saud Pungh Khad Km. 0/00 to 4/015(SH:- C/o PCC drain at various RDs and patch work at various RDs (Under PDNA)	494993.00	10000.00	Two Months
24	Restoration of rain damages on link road from Ansla to Saud Pungh Khad Km. 0/00 to 4/015(SH:- C/o PCC drain at various RDs and patch work at various RDs (Under PDNA)	488093.00	10000.00	Two Months

Certifed that above works are of urgent nature and tenders are being called in exigency of works and in public interest.

Executive Engineer
Tauni Devi Division
HPPWD, Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME O. WORK:- Restoartion of rain damages on link road to Narwalan-Di-Dar to Bouru road via Lambran-Di-Dhar Km 0/00 to 2/130. (SH:- Construction of retaining wall at RD 1/770 to 1/783) (Under PDNA)	Estimated Cost:-	Rs.414966.00
	Earnest Money:-	Rs. 8300.00
	Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	24.22	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	7027.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	88.73	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	377103.00
3.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	23.40	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	16380.00
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	52.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	14456.00
					Total	**414966.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 60 for the year 2025-26 duly approved for Rs. 4,14,966/-(Rupees four lacs fourteen thousand nine hundred sixty six only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

(2)

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on link road to Village Sukhani Km 0/00 to 2/00. (SH:- Construction of retaining wall at RD 1/510 to 1/525) (Under PDNA)

Estimated Cost:-	Rs.498071.00
Earnest Money:-	Rs. 10000.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	20.25	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	5876.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	110.70	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	470475.00
3.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	7.20	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	5040.00
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	60.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	16680.00
					Total	**498071.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 63 ..... for the year 2025-26 duly approved for Rs. 498,071/-(Rupees four lacs ninety eight thousand seventy one only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on Barara to Bakkar Khad via Patnoun road Km 0/00 to 8/00 (Sri:- Construction of retaining wall at RD 2/720 to 2/735) (Under PDNA)

Estimated Cost:-	Rs.300443.00
Earnest Money:-	Rs. 6000.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	15.75	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	4570.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	65.63	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	278928.00
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	6116.00
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	15.47	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	10829.00
					Total	300443.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 66 for the year 2025-26 duly approved for Rs. 3,00,443/-(Rupees three lacs four hundred forty three only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Scanned with CamScanner

4

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Baru Tapre road Km 5/265 to 8/705 (SH:- Construction of retaining wall at RD 7/210 to 7/220) (Under PDNA)

Estimated Cost:-	**Rs.351025.00**
Earnest Money:-	**Rs. 7100.00**
Time:-	**Two Months**

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	10.90	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	3163.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	80.28	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	341190.00
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	6672.00
					Total	**351025.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....69..... for the year 2025-26 duly approved for Rs. 3,51,025/-(Rupees three lacs fifty one thousand twenty five only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

5

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on Langwan Tauni Devi road Km 3/345 to 7/305 (SH:- Construction of retaining wall at RD 5/680 to 5/690) (Under PDNA)

				Estimated Cost:-	Rs.231924.00	
				Earnest Money:-	Rs. 4700.00	
				Time:-	Two Months	
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	34.06	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	9883.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	49.89	4250.00	Rupees four thousand two hundred fifteen and paise zero only.	Per cubic metre	212033.00
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	36.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	10008.00
					Total	**231924.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 70 for the year 2025-26 duly approved for Rs. 2,31,924/-(Rupees two lacs thirty one thousand nine hundred twenty four only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

(6)

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on Bouru to Chamarda road Km 0/00 to 3/00(SH:- Construction of V-shape drain including edge wall RD's 1/900 to 2/020) (Under PDNA)

Estimated Cost:-	Rs.254544.00
Earnest Money:-	Rs. 5100.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	76.80	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	22284.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	47.40	4900.00	Rupees four thousand nine hundred and paise zero only.	Per cubic metre	232260.00
					Total	254544.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No....39.... for the year 2025-26 duly approved for Rs. 2,54,544/-(Rupees two lacs fifty four thousand five hundred forty four only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

(7)

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on link road shiv Mandir to Chaptehar Km 0/00 to 0/500(SH:- Construction of breast wall at RD 0/047 to 0/062 & V-Shape drain including edge wall) (Under PDNA)

Estimated Cost:-	Rs.426545.00
Earnest Money:-	Rs. 8500.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	63.20	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	18337.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	63.71	4650.00	Rupees four thousand six hundred twenty and paise zero only.	Per cubic metre	296252.00
4.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	22.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	6116.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	21.60	4900.00	Rupees four thousand nine hundred and paise zero only.	Per cubic metre	105840.00
					Total	426545.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....00..... for the year 2025-26 duly approved for Rs. 4,26,545/-(Rupees four lacs twenty six thousand five hundred forty five only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoartion of rain damages on link road to Village Lonar Balli Km 0/00 to 1/900(SH:- Providing and laying of wire crate in Km 0/550 to 0/561) (Under PDNA)

Estimated Cost:-	Rs.486822.00
Earnest Money:-	Rs. 9800.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	20.97	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	6084.00
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia GI wire conforming ot IS:280 and IS:4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications Clause 1301as per drawing and technical specification clauses 614, 709, 1204.3.7 and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	153.29	2950.00	Rupees two thousand nine hundred fifty and paise zero only.	Per cubic metre	452206.00
3.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	40.76	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	28532.00
					Total	486822.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....01..... for the year 2025-26 duly approved for Rs. 4,86,822/-(Rupees four lacs eighty six thousand eight hundred twenty two only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road Lambari Nalahi Asthota road km. 0/00 to 6/00.(SH:- C/O PCC left side wing wall at RD. 0/725 to 0/733) .(Under PDNA).

Estimated Cost:-	Rs. 263093.00
Earnest Money:-	Rs. 5500.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octroi, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	40.32	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	11699.00
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	57.32	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	243610.00
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	28.00	278.00	Rupees two hundred seventy eight only	Each.	7784.00
					Total	**263093.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 143 for the year 2025-26 duly approved for Rs. 263,093/-(Two lac. sixty three thousand ninety three) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restroation of rain damages on Charlyan-Di-Dhar to Lambran-Di-Dhar via Bouru road Km 0/00 to 2/00. (SH:- Construction of Hume pipe culvert at RD 1/450)(Under PDNA)	Estimated Cost:-	Rs.276177.00
	Earnest Money:-	Rs.5500.00
	Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical menus including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302,1603.1,1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts.	44.16	350.00	Rupees three hundred fifty and paise zero only.	Per cubic metre	15456.00
2.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.00	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	1451.00
3.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand : six graded stone aggregate 20 mm (twenty millimetre)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	1.61	4900.00	Rupees four thousand nine hundred and paise zero only.	Per cubic metre	7889.00

Scanned with CamScanner

4.00	Providing and laying cement concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation complete as per drawing and technical specification clause 802,803,1202& 1203. PCC grade M-15(M-Fifteen) nominal mix 1:2.5:5(one cement : two point five sand: five graded crushed stone aggregate) 40mm (forty millimeters) nominal size as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	11.67	5533.00	Rupees five thousand five hundred thirty three and paise zero only.	Per cubic metre	64570.00
5.00	Laying concret cradle bedding with M-15 grade cement concret as per Clause 1105 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	1.78	5362.00	Rupees five thousand three hundred sixty two and paise zero oly.	Per cubic metre	9544.00
6.00	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	0.452	7293.10	Rupees seven thosuand two hundred ninety three and paise ten only.	Per square metre	3296.00
7.00	Providing and laying non-pressure NP2 class (light duty) reinforced cement concrete pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : fine sand) including testing of joints etc. complete 900 mm(nine hundred millimetre) dia. reinforced cement concrete pipe as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	7.50	3800.00	Rupees three thousand eight hundred and paise zero only.	Per running metre	28500.00
8.00	Filling in foundation trenches as per drawing and technical specification clause 305.3.9 Earth filling (for marshy soil) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	6.68	265.10	Rupees two hundred sixty five and paise ten only.	Per running metre	1771.00
9.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	6.54	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	4578.00

Scanned with CamScanner

10.00	Providing and laying non-pressure NP2 class (light duty) reinforced cement concrete pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement : fine sand) including testing of joints etc. complete 300 mm(three hundred millimetre) dia. reinforced cement concrete pipe as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2.50	2197.00	Rupees two thosuand one hundred ninety seven and paise zero only.	Per running metre	5493.00
11.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	12.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	3336.00
12.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one Cement : four coarse sand) : eight graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	28.02	4650.00	Rupees four thousand six hundred twenty and paise zero only.	Per cubic metre	130293.00
					Total	**276177.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 79 for the year 2025-26 duly approved for Rs.2,76,177/-
(Rupees two lacs seventy six thousand one hundred seventy seven only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Draft Schedule of Quantity

AME OF WORK:- Restoration of rain damages on link road Harizan Basti Chalokhar km. 0/00 to 0/500)(SH:- C/O 900mmm dia hume pe culvert at RD. 0/240 and patch work).(Under PDNA).

Estimated Cost:-	Rs. 257429.00
Earnest Money:-	Rs. 5500.00
Time:-	Two Months

r.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift uplo 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	38.31	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	11116.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	2.09	4900.00	Rupees four thousand nine hundred only	Per cubic metre	10241.00
3	Providing and laying cement concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation completed as per M-15 (M-fifteen) nominal mix 1:2.5:5 (one cement: two point five sand: five graded crushed stone aggregate) 40mm (forty millimeters) nominal size as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	13.36	5533.00	Rupees five thousand five hundred thirty three only	Per Cubic metre	73921.00
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar joints with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 900mm(nine hundred millimeters) dia as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	7.50	3800.00	Rupees three thousand eight hundred only	Per running metre	28500.00
5	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing: 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size). as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	0.68	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	2890.00
6	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	4.00	278.00	Rupees two hundred seventy eight only	Each.	1112.00
7	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	11.44	2150.00	Rupees two thousand one hundred fifty only	Per cubic metre	24596.00
8	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	304.50	345.00	Rupees three hundred forty five only	Per square metre	105053.00
					Total	257429.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 93 for the year 2025-26 duly approved for Rs 2,57,429/-(Two lac fifty seven thousand four hundred twenty nine) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Sapahal KM 0/0 to 1/500.(SII:- C/O PCC V-shape drain, unlined drain and P/L patch work at various RD's).(Under PDNA).

Estimated Cost:-	Rs. 235932.00
Earnest Money:-	Rs. 5000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift uplo 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of matenal within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government	45.00	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	13057.00
2	Providing and laying in cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of matenal within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	20.25	4900.00	Rupees four thousand nine hundred only	Per cubic metre	99225.00
3	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a)By manual means, as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals.	310.00	65.00	Rupees sixty five only	Per running metre	20150.00
4	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	300.00	345.00	Rupees three hundred forty five only	Per square metre	103500.00
					Total	**235932.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 112 for the year 2025-26 duly approved for Rs. 2,35,932/-(Two lac thirty five thousand nine hundred thirty two) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

(12) (3)

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road to village Gahra KM 0/0 to 1/200.(SH:- C/O hume pipe culvert 900mm dia at RD. 0/480 with catch pit and toe wall on U/S and D/S side).(Under PDNA).

Estimated Cost:-	Rs. 129353.00
Earnest Money:-	Rs. 2600.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	24.30	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	7051.00
2	Providing and laying cement concrete in retaining walls,return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping bed blocks, anchor blocks, plain window sills,fillets, sunken floor etc., up to floor any level, including the cost of centering, shuttering and finishing 1:5:10 (one cement : five coarse sand) : ten graded stone aggregate 40 mm (forty millimeters nominal size) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	0.72	4250.00	Rupees four thousand two hundred fifty only	Per Cubic metre	3060.00
3	Providing and laying in cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	16.58	4900.00	Rupees four thousand nine hundred only	Per cubic metre	81242.00
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar joints with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 900mm(nine hundred millimeters) dia as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	10.00	3800.00	Rupees three thousand eight hundred only	Per running metre	38000.00
					Total	**129353.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 14 ..... for the year 2025-26 duly approved for Rs. 129,353/-(One lac twenty nine thousand three hundred fifty three) Only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

13

Scanned with CamScanner

(14)

Draft Schedule of Quantity

NAME OF WORK:- Restroration of rain damages on Baru jhataur road Km 0/00 to 1/750 (SH:- Construction of retaining wall at RD 0/060 to 0/090, 1/075 to 1/082 & 1/150 to 1/158)(Under PDNA)	Estimated Cost:-	Rs. 4,55,775.00
	Earnest Money:-	Rs. 9,200.00
	Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m(fifty metre) dressing of sides and bottom and backfilling in trenches with excavated suitable material ordinary soil upto 3m(three metre) depth as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	61.89	290.15	Rupees two hundred ninety and paise fifteen only.	Per cubic metre	17957.00
2.00	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate 40 mm(forty millimetre) nominal size)as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	95.70	4200.00	Rupees four thousand two hundred and paise zero only.	Per cubic metre	401940.00
3.00	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 100mm(one hundred millimetre) dia PVC pipe made of finolex pipe having pressure not less than 4kg/Cm2. (four kilogram per centimetre square) extending through the full width of the structures with slopes of I(V): 20(H) one vertical twenty horizontal towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7 as per direction of Engineer- in -Charge, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	65.00	278.00	Rupees two hundred seventy eight and paise zero only.	Each	18070.00
4.00	Backfilling Granular material behind abutment, wing wall and return wall complete as per drawing& technical specification clause 1204.3.8, and as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	25.44	700.00	Rupees one thousand two hundred eighty one and paise thirty only.	Per cubic meter	17808.00
					Total	**455775.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....56..... for the year 2025-26 duly approved for Rs. 4,55,775/-(Rupees four lacs fifty five thousand seven hundred seventy five only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Scanned with CamScanner

15

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Pungh Khad to Chamyola KM 0/0 to 1/610.(SH:- C/O cement concrete pavement at RD. 0/410 to 0/450).(Under PDNA).

Estimated Cost:-	Rs. 162824.00
Earnest Money:-	Rs. 3500.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	28.00	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	8124.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (one cement: four sand: eight graded stone aggregated 40mm (forty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	14.00	4650.00	Rupees four thousand six hundred fifty only	Per Cubic metre	65100.00
3	Providing and laying cement concrete of specified grade incliding the cost of centering and shuttering - All work up to plinth level 1:1.5:3 (one cement : one point five coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	14.00	6400.00	Rupees six thousand two hundred thirty only	Per Cubic metre	89600.00
					Total	162824.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 113 for the year 2025-26 duly approved for Rs. 1,62,824/-(One lac. sixty two thousand eight hundred twenty four) Only.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujanpur road km. 16/00 to 24/870.(SH:- Providing and laying patch work at various RD's).(Under SDRF).

				Estimated Cost:-	Rs. 498613.00	
				Earnest Money:-	Rs. 10000.00	
				Time:-	Two Months	
Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	9.40	2130.70	Rupees two thousand one hundred thirty and paise seventy only	Per cubic metre	20029.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1387.20	345.00	Rupees three hundred forty five only	Per square metre	478584.00
					Total	498613.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 163 for the year 2025-26 duly approved for Rs.4,98,613/- (Four lac. ninety ninety eight thousand six hundred thirteen) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Scanned with CamScanner

17

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujampur road km. 2/600 to 24/870.(SH:- Providing and laying patch work from RD. 10/000 to 16/00).(Under SDRF).

Estimated Cost:-	Rs. 495771.00
Earnest Money:-	Rs. 10000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	13.28	2130.70	Rupees two thousand one hundred thirty and paise seventy only	Per cubic metre	28296.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1355.00	345.00	Rupees three hundred forty five only	Per square metre	467475.00
					Total	495771.00

Terms and Condition

1. Work shall be executed as per PWD specification.

2.The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 165 for the year 2025-26 duly approved for Rs.4,95,771/- (Four lac. ninety five thousand seven hundred seventy one) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on Hamirpur Sujanpur road km. 2/600 to 24/870.(SH:- Providing and laying patch work from RD. 2/600 to 10/00).(Under SDRF).

Estimated Cost:-	**Rs. 495963.00**
Earnest Money:-	**Rs. 10000.00**
Time:-	**Two Months**

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN (eighty into hundred) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etcetra as per Tables 400.11 & 400.12 and Technical Specification Clause 406 by mechanical means in two layers, and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals.The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, good service tax or other taxes imposed by the Government.	13.50	2130.70	Rupees two thousand one hundred thirty and paise seventy only	Per cubic metre	28764.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1354.20	345.00	Rupees three hundred forty five only	Per square metre	467199.00
					Total	**495963.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

2. The bitumen/emulsion will be procured by the contractor himself and receipt of procurement have to be produce at the time of final bill.

DNIT No 164 for the year 2025-26 duly approved for Rs.4,95,963/- (Four lac. ninety five thousand nine hundred sixty three) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Draft Schedule of Quantity

NAME OF WORK:- A/R & M/O various roads under Tauni Devi Sub-Division (Section Uhal) (SH:- Painting & writing letters of information sign boards, km stone and other road side furniture etc)	Estimated Cost:-	Rs. 98,929.00
	Earnest Money:-	Rs. 2,000.00
	Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	62.85	73.99	Rupees seventy three and paise ninety nine only.	Per square metre	4650.00
2.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to given an even shade two or more coats on new work over and under coat of suitable shade with ordinary paint of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	46.44	119.90	Rupees one hundred nineteen and paise ninty only.	Per square metre	5568.00
3.00	Lettering with black Japan paint of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	23976.00	3.70	Rupees three and paise seventy only.	Per Letter per centimetre	88711.00
					Total	**98929.00**

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No.....91..... for the year 2025-26 duly approved for Rs 98,929/-(Rupees ninety eight thousand nine hundred twenty nine only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner

Scanned with CamScanner

20

Draft Schedule of Quantity

NAME OF WORK:- A/R & M/O various roads under Tauni Devi Sub-Division (Section Tauni Devi-II) (SH:- Painting & writing letters of information sign boards, km stone and other road side furniture etc)

Estimated Cost:-	Rs. 98,825.00
Earnest Money:-	Rs. 2,000.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade one or more coats on old work as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	66.13	73.99	Rupees seventy three and paise ninety nine only.	Per square metre	4893.00
2.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to given an even shade two or more coats on new work over and under coat of suitable shade with ordinary paint of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	35.09	119.90	Rupees one hundred nineteen and paise ninty only.	Per square metre	4207.00
3.00	Lettering with black Japan paint of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	24250.00	3.70	Rupees three and paise seventy only.	Per Letter per centimetre	89725.00
					Total	98825.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No. 92 for the year 2025-26 duly approved for Rs. 98,825/-(Rupees ninety eight thousand eight hundred twenty five only)

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

(21)

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Sujanpur Sub-Division, HP:PWD., Sujanpur. (SH:- Providing supplying and stacking road Bond (Ready mix pot seal) and Emulsion drum RS-1). (under PDNA)

				Estimated Cost:-	Rs. 495500.00	
				Earnest Money:-	Rs. 10000.00	
				Time:-	Two Months	
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing Supply and stacking road bond for patch work (Ready mix pot seal) packing of 25 kg/bag (twenty five kilogram per bag) complete including entire carriage of material within all leads and lifts and as per drawings and technical specifications as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	570.00	650.00	Rupees six hundred fifty only	Per Bag	370500.00
2	Providing Supply and stacking HINCOL Emulsion RS-1, specially designed water based bitumen emulsion with low viscosity and fast setting time ideal product for spray application, HINCOL emulsion I RS-1 should be strictly manufactured as per IS 8887: 2004 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	10.00	12500.00	Rupees Twelve thousand five hundred only	Per Drum.	125000.00
					Total	495500.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 16 for the year 2025-26 duly approved for Rs. 4,95,500/-
(Four lac. ninety five thousand five hundred) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

22

Draft Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on various road under Tauni Devi Sub-Division, IP:PWD., Tauni Devi. (SH:- Providing supplying and stacking road Bond (Ready mix pot seal) and Emulsion drum RS-1). (under PDNA)

Estimated Cost:-	Rs. 495500.00
Earnest Money:-	Rs. 10000.00
Time:-	Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing Supply and stacking road bond for patch work (Ready mix pot seal) packing of 25 kg/bag (twenty five kilogram per bag) complete including entire carriage of material within all leads and lifts and as per drawings and technical specifications as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	570.00	650.00	Rupees six hundred fifty only	Per Bag	370500.00
2	Providing Supply and stacking HINCOL Emulsion RS-1, specially designed water based bitumen emulsion with low viscosity and fast setting time ideal product for spray application, HINCOL emulsion I RS-1 should be strictly manufactured as per IS 8887: 2004 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	10.00	12500.00	Rupees Twelve thousand five hundred only	Per Drum.	125000.00
					Total	495500.00

Terms and Condition

1. Work shall be executed as per PWD specification.

DNIT No 162 for the year 2025-26 duly approved for Rs. 4,95,500/-
(Four lac. ninety five thousand five hundred) only

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi

Scanned with CamScanner

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Ansla to Saud Pungh Khad km. 0/00 to 4/015.(SH:- C/O PCC drain at various RD's and patch work at various RD's).(Under PDNA).

Estimated Cost:-	Rs. 494993.00
Earnest Money:-	Rs. 10000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m.(fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	24.00	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	6964.00
2	Providing and laying in cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.10	4900.00	Rupees four thousand nine hundred only	Per cubic metre	24990.00
3	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a)By manual means, as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals.	100.00	65.00	Rupees sixty five only	Per running metre	6500.00
4	Providing and laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) 75mm (seventy five millimetre) consolidated thick to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100KN (eight to hundred) static roller in stages to proper grade and camber applying and booming, stone screening of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density of grading-III as per technical specification and clause 405 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.81	1900.00	Rupees one thousand nine hundred only	Per cubic metre	90839.00
5	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1060.00	345.00	Rupees three hundred forty five only	Per square metre	365700.00
					Total	**494993.00**
	Quoted Rate (in Figures) Percentage	Excess(+)			%	
		Less(-)			%	
	G.Total in Figures					
	G.Total in Words					

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division

Scanned with CamScanner

Schedule of Quantity

NAME OF WORK:- Restoration of rain damages on link road from Ansla to Saud Pungh Khad km. 0/00 to 4/015.(SH:- C/O PCC drain at various RD's and patch work at various RD's).(Under PDNA).

Estimated Cost:-	Rs. 488093.00
Earnest Money:-	Rs. 10000.00
Time:-	Two Months

Sr.No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m(one point five metre) in width or 10 sqm(ten square metre on plan),including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m (fifty metre) as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	24.00	290.15	Rupees two hundred ninety and paise fifteen only	Per cubic metre	6964.00
2	Providing and laying in cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana,toll tax, GST or other taxes imposed by the Government.	5.10	4900.00	Rupees four thousand nine hundred only	Per cubic metre	24990.00
3	Construction of un-lined surface drain of average cross sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in in embankments with a lift upto 3mtr. and lead of 50mtr. (average lead 25m) as per technical specification clause 307 (a)By manual means, as per direction of Engineer- in -Charge, including carriage of materials within all leads and lifts and other incidentals.	100.00	65.00	Rupees sixty five only	Per running metre	6500.00
4	Providing and laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) 75mm (seventy five millimetre) consolidated thick to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100KN (eight to hundred) static roller in stages to proper grade and camber applying and booming, stone screening of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density of grading-III as per technical specification and clause 405 and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax or other taxes imposed by the Government.	47.81	1900.00	Rupees one thousand nine hundred only	Per cubic metre	90839.00
5	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 (ten) as per MORD specification clause 1904.2,503 and 508.1 including entire carriage of material within all leads and lifts and as per entire satisfaction and direction of Engineer-in-Charge . The rates are inclusive of octroi, royality, Malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	1040.00	345.00	Rupees three hundred forty five only	Per square metre	358800.00
					Total	**488093.00**
	Quoted Rate (in Figures) Percentage	Excess(+)			%	
		Less(-)			%	
	G.Total in Figures					
	G.Total in Words					

Terms and Condition

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Devi.

Scanned with CamScanner