

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2025-26 5612-20

Dated:- 14/10/2025


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/B are hereby invited by the Executive Engineer Arki Division H.P.P.W.D, Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **22.10.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **21.10.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **21.10.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/PDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall In km. 22/080 to 22/100(PDNA)	1,86,735/-	3800/-	2 months	350/-
2.	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall In km. 34/550 to 34/575(PDNA)	2,33,967/-	4700/-	2 months	350/-
3	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall In km. 36/280 to 36/295(PDNA)	1,40,978/-	2900/-	2 months	350/-
4	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall In km. 36/310 to 36/325(PDNA)	1,40,978/-	2900/-	2 months	350/-



5	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall in km. 36/620 to 36/640(PDNA)	1,87,991/-	3800/-	2 months	350/-
6	Restoration of rain damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road km. 0/0 to 56/200(SH:-C/o R/wall in km. 38/590 to 38/610(PDNA)	1,87,991/-	3800/-	2 months	350/-
7	Restoration of rain damages on Buila Koel Sanog road km. 0/0 to 28/000 (SH:-C/o R/wall in km. 14/930 to 14/990(PDNA)	4,01,622/-	8100/-	2 months	350/-
8	Restoration of rain damages on Cheod khad Jaghoon road km. 0/0 to 18/0(SH:-C/o R/wall in km. 2/300 to 2/360(PDNA)	4,01,573/-	8100/-	2 months	350/-
9	R/R damages on Arki Khararhatti road km. 0/00 to 8/805 (SH:- Hiring of JCB for removal of slips in various locations in between km. 3/000 to 4/000)	99,000/-	2,000/-	1 months	350/-
10	R/R damages on Arki Khararhatti road km. 0/00 to 8/805 (SH:- Hiring of Tipper for removal of slips in various locations in between km. 1/000 to 3/00)	97,500/-	2000/-	1 Month	350/-
11	R/R damages on Arki Khararhatti road km. 0/00 to 8/805 (SH:- Hiring of JCB for removal of slips in various locations in between km. 1/00 to 2/00)	99,000/-	2000/-	1 Month	350/-
12	R/R damages on Arki Khararhatti road km. 0/00 to 8/805 (SH:- Hiring of JCB for removal of slips in various locations in between km. 2/00 to 3/00)	99,000/-	2000/-	1 Month	350/-
13	R/R damages on Manjyat Patti Deora-Paplota road km. 0/0 to 7/0 (SH:- Removal of slips in km. 0/00 to 1/375)	91,380	2000/-	1 Month	350/-
14	R/R damages on KBSB road portion km.0/0 to 8/0 under PDNA(SH:-C/o B/wall at RD 5/375 to 5/390)	1,75,914/-	4000/-	1 Month	350/-
15	R/R damages on link road to village Namol km. 0/0 to 1/270 under PDNA(SH:-C/o R/wall at km. 0/075 to 0/081)	1,59,719/-	4000/-	1 Month	350/-
16	R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar road portion km. 0/0 to 8/0(SH:- C/o B/wall at RD 6/820 to 6/835)	1,79,027/-	4000/-	1 Month	350/-



17	R/R damages on Sayawan Rinvi Behli road km 0/0 to 1/360 under PDNA(SH:-C/o R/wall at km. 0/320 to 0/325	1,30,735/-	3000/-	1 Month	350/-
18	Restoration of rain damages on Cheod Khad Jaghoon road km. 0/0 to 18/0(SH:-C/o R/wall in km. 6/700 to 6/725)PDNA	1,67,746/-	3400/-	2 Months	350/-
19	Restoration of rain damages on Kainth Ka Pani Chandpur Kalyanpur sehrol road km. 0/0 to 2/780(SH:-C/o R/wall in km. 2/850 to 2/890)PDNA	2,67,619/-	5400/-	2 Months	350/-
20	Restoration of Shivghatti to Bajheri km. 0/0 to 1/500 (SH:- Removal of Slips/dressing of road by Hiring of JCB)	50,000/-	1000/-	15 Days	350/-
21	Restoration of ran damage on SKRN road portion km. 47/0 to 60/500(SH:-C/o R/wall at RD 58/635 to 58/640)Under PDNA	1,36,034/-	3000/-	1 Month	350/-
22	R/R damages on SKRN road Portin km. 47/0 to 60/500 (SH:- C/o R/wall at RD 50/810 to 50/816) Under PDNA	1,65,095/-	4,000/-	1 Month	350/-
23	Restoration of ran damage on SKRN road portion km. 47/0 to 60/500 under PDNA 2023(SH:-C/o R/wall at RD 49/105 to 49/109.50)Under PDNA	1,22,409/-	3000/-	1 Month	350/-
24	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road km. 0/0 to 26/0(SH:-C/o R/wall in km. 16/220 to 16/235(PDNA)	1,40,978/-	2900/-	2 Months	350/-
25	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road km. 0/0 to 26/0(SH:-C/o R/wall in km. 14/370 to 14/385(PDNA)	1,40,978/-	2900/-	2 Months	350/-
26	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road km. 0/0 to 26/0(SH:-C/o R/wall in km. 13/520 to 13/535(PDNA)	1,40,978/-	2900/-	2 Months	350/-
27	Restoration of rain damages on Arki Dhundan Bhararighat road km. 0/0 to 18/600(SH:-C/o R/wall in km. 0/500 to 0/515(PDNA)	1,40,978/-	2900/-	2 Months	350/-
28	Restoration of rain damages on Buila Koel Sanog road km. 0/0 to 28/600(SH:-C/o R/wall in km 27/630 to 27/650 (PDNA)	1,33,480/-	2700/-	2 Months	350/-
29	Restoration of rain damages on Buila Koel sanog road km. 0/0 to 28/00(SH:-C/o R/wall in km. 6/780 to 6/800 (PDNA)	1,33,480/-	2700/-	2 Months	350/-

Leaf

42	R/R damages on Darla Sub-Divn (SH:- Hiring of JCB for removal of slips in various roads under Shalaghat Section Job No. 8	99,000/-	2000/-	1 Month	350/-
43	R/R damages on Darla Sub-Divn (SH:- Hiring of Tipper for removal of slips in various roads under Shalaghat section Job No. 5	97,500/-	2000/-	15 days	350/-
44	R/R damages on Darla Sub-Divn (SH:- Hiring of Tipper for removal of slips in various roads under Shalaghat section Job No. 4	97,500/-	2000/-	15 days	350/-
45	R/R damages on Shimla Kunihar Ramshehar Nalagarh road portion km. 47/000 to 60/500 (SH:- C/o R/wall at RD 59/510 to 59/518) Under PDNA	64,301/-	2000/-	1 Month	350/-
46	R/R damages on Arki Sub-Division HPPWD Arki under Bhumti Section (SH:- Removal of slips/dressing of roads by hiring of JCB in various roads) Job No. 6	99,000/-	2000/-	15 days	350/-
47	R/R damages on Shimla Kunihar Ramshehar Nalagarh road portion km. 47/000 to 60/500 (SH:- C/o R/wall at RD 59/915 to 59/930) Under PDNA	92,816/-	2000/-	1 Month	350/-
48	R/R damages on various roads under Kunihar Sub-Divn. HPPWD Kunihar under Mann section (SH:- Hiring of JCB for removal of slips in various roads)	99,000/-	2000/-	1 Month	350/-
49	R/R damages on various roads under Kunihar Sub-Divn. HPPWD Kunihar under Mann section (SH:- Hiring of JCB for removal of slips in various roads)	99,000/-	2000/-	1 Month	350/-
50	R/R damages on various roads under Kunihar Sub-Divn. HPPWD Kunihar under Mann section (SH:- Hiring of JCB for removal of slips in various roads)	99,000/-	2000/-	1 Month	350/-
51	R/R damages on Shimla Kunihar Ramshehar Nalagarh road portion km. 47/000 to 60/500 (SH:- C/o R/wall at RD 60/150 to 60/170) Under PDNA	97,376/-	2000/-	1 Month	350/-
52	R/R damages on various roads under Kunihar Sub-Divn. HPPWD Kunihar under Mann section (SH:- Hiring of Tipper of Carriage of slips/debris etc.) Job No. 1	98,800/-	2000/-	15 days	350/-

62

53	R/R damages on various roads under Darla Suh Divn. Mangal Section (SH: Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.) Job No.-VI	99,000/-	2000/-	1 Month	350/-
54	R/R damages on various roads under Darla Suh Divn. Mangal Section (SH: Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.) Job No.-VII	99,000/-	2000/-	1 Month	350/-
55	R/R damages on Mann section under Kunihar Sub-Divn (SH:- Removal of Minor slips, Cleaning of drain and Catch Pits by hiring of JCB) Job no. -IV	99,000/-	2000/-	1 Month	350/-
56	R/R damages on Darla Sub-Divn. (SH:- Hiring of Tipper for removal of slips at Km. 8/555 to 8/590 in Manju Khanalag road) Job No.-2	97,500/-	2000/-	15 days	350/-
57	R/R damages on Darla Sub-Divn. (SH:- Hiring of JCB for removal of slips at Km. 8/555 to 8/590 in Manju Khanalag road) Job No.-2	99,000/-	2000/-	15 Days	350/-
58	R/R damages on Darla Sub Division (SH:- Hiring of Tipper for removal of slips in various roads under Darla Section) Job No. 2	97,500/-	2000/-	15 Days	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


 Executive Engineer
 Arki Division,
 H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2025-26-

Dated:-

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


 Executive Engineer
 Arki Division
 H.P.P.W.D. Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 58(Fifty Eight) jobs are due to exigencies/emorgoney of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D, Arki.

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINI KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200 (UNDER PDNA)

Estimated Cost = Rs. 1,86,735/- only

Earnest Money = Rs. 3800/- only

SH:- C/O PCC R/Wall between KM 22/080-22/100

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT
			In figures	In words	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	37.57	171.40	Rupees One Hundred Seventy One and Paise Forty only	6439.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including cartage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	39.44	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	173165.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204,3.7.	26.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	7131.00
	TOTAL				186735.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


Executive Engineer

B&R Division

HPPWD AAKI

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINU KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200 (UNDER PDNA)

Estimated Cost = Rs. 2,33,967/- only

Earnest Money = Rs. 4700/- only


SH:- C/O PCC R/Wall between KM 34/550-34/575

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	AMOUNT	RATE	IN FIGURES	IN WORDS
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	16.38	cum	2808.00	Rupees One Hundred Seventy One and Paise Forty only	171.40	Rupees One Hundred Thirty and Paise Sixty only
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	50.40	cum	221286.00	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	4390.60	Rupees Two Hundred Seventy Four and Paise Twenty Five only
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	36.00	Rmt	9873.00	Rupees Two Hundred Seventy Four and Paise Twenty Five only	274.25	Per running metre
				TOTAL			
				233967.00			

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINJI KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200

(UNDER PDNA) *36/280 to 36/295*

SH:- C/O PCCR/Wall between KM 36/340-36/325

Estimated Cost = Rs. 1,40,978/- only

Earnest Money = Rs. 2900/- only

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
			In figures	In words	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 Including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.98	171.40	Rupees One Hundred Seventy One and Paise Forty only	1711.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	30.72	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	134879.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	16.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	4388.00
	TOTAL				140978.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words



Executive Engineer

B&R Division

HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINJ KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200
(UNDER PDNA)

Estimated Cost = Rs. 1,40,978/- only

Earnest Money = Rs. 2900/- only


SH:- C/O PCC R/Wall between KM 36/280-36/295

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT	
			In figures	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.98	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1711.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 (including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	30.72	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	134879.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	16.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	4388.00
TOTAL			140978.00			140978.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,87,991/- only

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINI KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200
(UNDER PDNA)

Earnest Money = Rs. 3800/- only

SH:- C/O PCC R/Wall between KM 36/620-36/640

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	RATE	Unit	AMOUNT	
			In figures	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing; removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	13.26	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	2273.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	40.80	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	179136.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	24.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	6582.00
	TOTAL					187991.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words

Executive Engineer

B&R Division

HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KUNIHAR BAINJI KI HATTI SHELLY BRAHMPUKHAR ROAD KM 0/00-56/200 (UNDER PDNA)

Estimated Cost = Rs. 1,87,991/- only


SH:- C/O PCC R/Wall between KM 38/590-38/610

Earnest Money = Rs. 3800/- only
Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT	
			In figures	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	13.26	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	2273.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	40.80	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	179136.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	24.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	6582.00
TOTAL			187991.00			187991.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 4,01,622/- only

NAME OF WORK:- R/R DAMAGES ON BUELA KOEL SANOG ROAD KM 0/00-28/000 (UNDER PDNA)

Earnest Money = Rs. 8100/- only

SH:- C/O PCC R/Wall between KM 14/930-14/990

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	In figures	RATE	In words	Unit	AMOUNT
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORO Specification directed by Engineer in Charge.	28.31	cum	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	4852.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	87.12	cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	382509.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORO clause 614, 709, 1204.3.7.	52.00	Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	14261.00
	TOTAL						401622.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 4,01,573/- only

NAME OF WORK:- R/R DAMAGES ON CHOED KHAD JAGHOON ROAD KM 0/00-18/000 (UNDER PDNA)

Earnest Money = Rs. 8100/- only

SH:- C/O PCC R/Wall between KM 2/300-2/260

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT		
1	2	3	In figures	In words	6		
7							
1	Earthwork In excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	36.58	cum	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	6270.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	87.91	cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	385978.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	34.00	Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	9325.00
	TOTAL						401573.00

Quoted rate Percentage in Figures

Quoted rate Percentage In Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on Arki Khararhatti road km 0/00 to 8/805(Sh :Hiring of JCB for removal of slips in various locations in between km 3/00 to 4/00)

Estimated Cost :- Rs 99,000.00


Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hour	1000.00	Per Hour	99000.00
					Total	99000.00

(i) Rates quoted percentage in figure.

(ii) Rate quoted percentage in Words.


 Executive Engineer
 Arki Division (B&R)
 HP, PWD, Arki.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Drainages on Arki Kharwarhadi road km 0/00 to 3/000
SR/05, (Sh) Hiring of Tipper for removal of slips in various locations in between km 1/00 to 3/000


Estimated Cost :- Rs 97,500.00
 Earned money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	Hiring of tipper for carriage of land slide/debris with minimum capacity of 5.50 cum per trip and minimum working six hours per day. The contractor/owner of the tipper shall bear the expenses of P.O.L. charges, repair of tipper. Any accident and other damages to the govt and private property occurred during the working hours will be responsibility of the contractor and debris disposed with in all leads and lifts and as per the direction of Engineer in charge.	150.00	150	650.00	Rupees Six hundred fifty and paise nil Only	Per Hours	97500.00
						Total	97500.00

(i) Rates quoted percentage in figure.

(ii) Rate quoted percentage in Words.


 Executive Engineer
 Arki Division (B&R)
 HP, PWD, Arki.

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain Damages on Arki Khararhathi road km 0/00 to 8/805(Sh : Hiring of JCB for removal of slips in various locations in between km 1/00 to 2/00)

Estimated Cost :- Rs 99,000.00
 Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Unit	Amount	Rate	
					In words	Per
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	99000.00	1000.00	Per piece/ Only
Total				99000.00		

(i) Rates quoted percentage in figure.
 (ii) Rate quoted percentage in words.


 Executive Engineer
 Arki Division (B&T)
 HP, PWD, Arki

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain Damages on Arki Khararhatti road km 0/00 to 8/805(Sh : Hiring of JCB for removal of slips in various locations in between km 2/00 to 3/00)

Estimated Cost :- Rs 99,000.00
 Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
					Total	99000.00

- (i) Rates quoted percentage in figure.
 (ii) Rate quoted percentage in Words.


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Maniyat-Patti-Deora-Paplaota Road Km 0/00 to 7/00 . (SH:-Removal of Slips in Km 0/00 to 1/375)

Estimated Cost: -Rs91380/- only


Earnest Money :-Rs2000/-only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Figure	Rate In		Unit	Amount	
					Words				
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposals of cut material with in lift upto 1.50m and lead upto 1000 meter as per technical specification 302.3.5 and 16.11. The usefull material for disposing at dumping site (to be arranged by the contractor) to the satisfaction of Engineer-in-charge through all modes of transportation including head load, animal load or mechanical means alongwith its levelling line dressing and with all kinds of labour, mechanies tools equipments and safety measures and incidental necessary to complete the work by mechanical means and labour if required. All usefull materials shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation as per the direction of Engineer-in-charge during the course if execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respect including all incidental charges.	1072.54	Cum	85.20	Rupees eighty five and paise twenty only.	P. Cum	91380		
			3						
							Total		91380

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of work :- R/R damages on KBSB Road Portion Km 0/0 to 8/00 under PDNA (SH:-
C/O B/ Wall at RD 5/375 to 5/390)

Estimated Cost :- Rs 1,75,914.00
Earnest money :- Rs 4,000.00
Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate	Unit		Amount
				In figure	In words	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	15.05	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6	2580.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	38.91	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	6	170838.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	9.10	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	6	2488.00
Total						175914.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Link Road to Village Namol Km 0/0 to 1/270 under PDNA
(SH:-C/O R/ Wall at Km 0/075 to 0/081)

Estimated Cost :- Rs 1,59,719.00
Earnest money :- Rs 4,000.00
Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORC Specification and as per the direction of Engineer-In-Charge	15.66	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre 2884.00
2	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand iso ten groved crushed stone aggregate 40 millimetre/ forty millimetre) nominal size for main reinforced concrete in open foundation complete as per drawings and technical specifications clause SQ2, SQ3, 1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge	34.01	Cum	4250.50	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre 144524.00
3	Providing and laying weapones in brick masonry /stone masonry /plain reinforced concrete acument wing wall return wall with 100mm (one surarec)thimetre dia P.V.C pipe extending through the full width of the structures with SQR of 1/1/20 (4) towards drawing less complete as per drawings and technical specifications MORC clause 514, 705, 1204, 57 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge	12.54	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre 3436.00
4	Supply return acument wing wal and returnng wal of granular material complete as per drawings and technical specifications MORC clause 1204, 2.5 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge	3.33	Cum	1205.50	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre 4012.00
TOTAL						148719.00

Quantity Rate Percentage in Figure

Quantity Rate Percentage in Words


 Engineer In Charge
 The District Engineer
 W.P. Road, etc.

SCHEDULE OF QUANTITY


Name of work :-R/R damages on Kunihar Bainji Ki Hatti Shelly Brampukhar Road portion
Km 0/0 to 8/0 UNDER PDNA (SH:-C/O B/ Wall at RD 6/820 to 6/835)

Estimated Cost :- Rs 1,79,027.00
Earnest money :- Rs 4,000.00
Time: One month

Sr.No	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3			6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	30.10	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	5159.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre (forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	38.91	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	170838.00
3.00	Providing and laying weepholes in brick masonry /stone masonry /plain reinforced concrete abutment. wing wall return wall with 100mm (one hundred millimetre dia PVC pipe extending through the full width of the structures with slope of 1(V),20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614, 709,1204,3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	11.05	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3030.00
Total							179027.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP PWD Arki

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Sayawan Rinvl Behli Road Km 0/0 to 1/360 under PDNA
 (SH:-C/O R/ Wall at Km 0/320 to 0/325)

Estimated Cost : Rs. 1,30,735.00
 Earnest money :- Rs 3,000.00
 Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	In figure	Rate	In words	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of slumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	3	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	2192.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	27.77	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	121927.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614, 709,1204,3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	11.40	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	3126.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204,3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	2.90	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	3490.00
	Total						130735.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP PWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,67,746/- only

NAME OF WORK:- R/R DAMAGES ON CHEOD KHAD JAGHOON ROAD KM 0/00-18/000 (UNDER PDNA)

Earnest Money = Rs. 3400/- only


SH:- C/O PCC R/Wall between KM 6/700-6/725

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	RATE		Unit	AMOUNT
			In figures	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	3	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	2005.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	36.00	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	158062.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	28.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	7679.00
TOTAL			167746.00			167746.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON KAINTH KA PANI CHANDPUR KALYANPUR SEHROL ROAD KM 0/00-4/000

(UNDER PDNA)

Estimated Cost = Rs. 2,67,619/- only

Earnest Money = Rs. 5400/- only

SH:- C/O PCC R/Wall between KM 2/850-2/890

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT	
1	2	3	In figures	In words	6	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	54.15	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	9281.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	56.84	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	249562.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	32.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	8776.00
	TOTAL					267619.00

Quoted rate Percentage in Figures


Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY							Estimated Cost: 50000.00
Name of Work:- Restoration of Shivhatti to Bagheri km 0/0-1/500 (SH:- Removal of slips/dressing of road by hiring of JCB)						Earnest Money: 1000.00	Time Period: 15 Days
S. No	Sub head and items of work	Qty	In figures	Rate In words	Unit	Amount	
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause 302.3.5 and 1611 including carriage of materials upto all leads, lifts and as per direction of Engineer in charge.	3	50.00	Hour 1000.00	Per Hour	50000.00	
Total=						50000.00	
Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki


SCHEDULE OF QUANTITY
NAME OF WORK:- R/R DAMAGES ON SHIMLA KUNIHAR RAMSEHAR NALAGARH ROAD KM 47/00-60/500
(UNDER PDNA)

Estimated Cost = Rs. 1,36,034/- only
 Earnest Money = Rs. 3000/- only
 Time Period = One Months

S.NO	DESCRIPTION OF ITEM	QTY	In figures	RATE		Unit	AMOUNT
				In words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	10.00	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1714.00	
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (1) 1:5:10 (40 mm nominal size stone aggregates)	28.34	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	124430.00	
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment; wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	7.50	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	2057.00	
4	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawing and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads , lifts and as per the direction of Engineer in Charge.	6.51	1203.30	Rupees One Thousand Two Three and Paise Thirty only	Per cubic metre	7833.00	
	TOTAL		136034.00			136034.00	

Quoted rate Percentage in Figures

Quoted rate Percentage In Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON SHIMLA KUNIHAR RAMSEHAR NALAGARH ROAD KM 47/00-60/500

(UNDER PDNA)

SH:- C/O PCC R/Wall between KM 50/810-50/816

Estimated Cost = Rs. 1,65,095/- only

Earnest Money = Rs. 4000/- only

Time Period = One Months

S.NO	DESCRIPTION OF ITEM	QTY	In figures	RATE		Unit	AMOUNT
				In words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	11.88	cum	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	2036.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	34.01	cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	149324.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	10.11	Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	2773.00
4	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawing and technical specifications MORD clause 1204.3.8 Including carriage of materials within all leads , lifts and as per the direction of Engineer In Charge.	9.11	cum	1203.30	Rupees One Thousand Two Three and Paise Thirty only	Per cubic metre	10962.00
	TOTAL						165095.00

Quoted rate Percentage In Figures

Quoted rate Percentage In Words



Executive-Engineer

B&R Division

HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK: W/4 DAMAGE'S ON SHIBLA KUNDHAR HAWSEHAI DAM ASHRI ROAD R/W 47/100 60/500

(NUMBER POINT)

DATE: 10/07/2014 M/Wall between KM 49/105 TO/109.50

Sl. No.	DESCRIPTION OF ITEM	QTY	UNIT	In figures	In words	Rate	Amount
1	1. All works in an section for stone masonry as per drawing and for the of Spec. Sh. above channel. 300. 1. No. of working and construction of abutment and In m/sq. removal of concrete and other deteriorated material and disposal upto all levels and also dressing of sides and foundation and base filling to top level with use approved suitable materials as per (IS: 2111) Spec. Sh. above the level by Engineering for change.	4.22	CUM	111.80	Fourteen One Hundred Eleven and Eight Only	10000.00	1118000.00
2	2. Providing and laying plain/curbed and concrete in open foundations comprising as per drawing and for the of concrete above R/O, R/O 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13 No. of working and for the of concrete upto all levels and (1) 15:1 to (40) 1000 provision steel reinforcement.	28.51	CUM	4330.60	Fourteen Thousand Three Hundred Thirty and Sixteen Only	10000.00	4330600.00
3	3. Providing and laying 150mm bricks in concrete/brick masonry/plain concrete and concrete abutment, wing wall, return walls with 100 mm (one hundred and millimetre) thick 10% paper extending through full width of stone masonry with slopes of (vertically 20% horizontal) towards channel as per drawings and for the of concrete above R/O 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24.	6.20	HRM	274.25	Two Hundred Seventy Four and Twenty Five Only	10000.00	2742500.00
4	4. Work filling finished abutment, wing wall and retaining wall of provision material complete as per drawing and for the of concrete above R/O 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100.	6.15	CUM	1203.30	Twelve Thousand Two Hundred Three and Thirty Only	10000.00	12033000.00
	TOTAL						12246600.00

(Worked rate per volume in figures)

(Worked rate per volume in words)

Contract Cost = Rs. 1,22,46,600/- only

Contract Agency = Rs. 3000/- only

Time provided = Three Months

(Signature)
Executive Engineer

B&M Division
BPPWD ARI

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON SHALAGHAT ARKI KUNI HAR BAROTIWALA ROAD KM 0/00-26/000 (UNDER PDNA)

Estimated Cost = Rs. 1,40,978/- only

Earnest Money = Rs. 2900/- only


SH:- C/O PCC R/Wall between KM 16/220-16/235

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	RATE		Unit	AMOUNT	
			In figures	In words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.98	cum	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1711.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1.5:10 (40 mm nominal size stone aggregates)	30.72	cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	134879.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	16.00	Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	4388.00
	TOTAL						140978.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON SHALAGHAT ARIKI KUNIHAR BAROTIWALA ROAD KM 0/00-26/000 (UNDER PDNA)

SH:- C/O PCC R/Wall between KM 14/370-14/385

Estimated Cost = Rs. 1,40,976/- only
 Earnest Money = Rs. 29097/- only
 Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE	In figures	In words	Unit	AMOUNT
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal (upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MDRB Specification directed by Engineer in Charge.	9.98	CUM	111.00	111.00	Hundred and one rupees only	per cubic meter	1111.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 301,303,3202 & 3203 including cartage of materials upto all leads and lifts (1) 1:5:10 (40 mm nominal size aggregate)	30.72	CUM	430.00	13207.20	Thirteen thousand three hundred and thirty rupees only	per cubic meter	13207.20
3	Providing and laying deep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with R/R (one hundred millimetres) dia P.C. pipes extending through full width of structures with stops of masonry/dilatation joints towards drainage faces complete as per drawings and technical specifications MDRB clause 611, 613, 620, 3.1.	46.63	IND	214.75	9999.75	Ninety nine thousand six hundred and forty five rupees only	per running meter	9999.75
TOTAL								24317.95

Checked by: *[Signature]*
 Checked by: *[Signature]*
 Checked by: *[Signature]*


 Director
 Public Works
 Government of India

SCHEDULE OF QUANTITY

AME OF WORK:- R/R DAMAGES ON SHALAGHAT ARKI KUNIHAR BAROTIWALA ROAD KM 0/00-26/000 (UNDER PDNA)

Estimated Cost = Rs. 1,40,978/- only

Earnest Money = Rs. 2900/- only

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT	
1	2	3	In figures	In words	6	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.98	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1711.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	30.72	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	134879.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	16.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	4388.00
	TOTAL					140978.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words



Executive Engineer
B&R Division
HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,40,978/- only

NAME OF WORK:- R/R DAMAGES ON ARKI DUNDHAN BARARIGHAT ROAD KM 0/00-18/600 (UNDER PDNA)

Earnest Money = Rs. 2900/- only

SH:- C/O PCC R/Wall between KM 0/500-0/515

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	RATE		Unit	AMOUNT
			In figures	In words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.98	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1711.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (1) 1:5:10 (40 mm nominal size stone aggregates)	30.72	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	134879.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	16.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	4388.00
TOTAL			140978.00			140978.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 Arch Division
 IIPWRI Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON BUELA KOEL SANOG ROAD KM 0/00-28/000 (UNDER PDNA)

Estimated Cost = Rs. 1,33,480/- only
 Earnest Money = Rs. 2700/- only
 Time Period = Two Months

SH:- C/O PCC R/Wall between KM 27/630-27/650

NO	DESCRIPTION OF ITEM	QTY	in figures	RATE	In words	Unit	AMOUNT
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MOHD Specification directed by Engineer in Charge.	9.52	cum	171.40	Ruppes One Hundred seventy One and Paise forty only	per cubic metre	1632.08
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 202,203,202 & 205 including carriage of materials upto all leads and lifts (1) 1:2:10 (40 mm nominal size stone aggregates)	29.28	cum	4350.60	Ruppes four thousand three hundred thirty and Paise sixty only	per cubic metre	128557.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1:vertical:25(horizontal) towards drainage face complete as per drawings and technical specifications MOHD clause 63A,703,1204,3.1,	12.00	Perk	274.25	Ruppes two hundred seventy four and Paise twenty five only	Per running metre	3291.00
			TOTAL				132401.00

Quoted rates Percentage in Figures

Quoted rates Percentage in Words



PRADEEP K. SINGH
 BSR Engineer
 MPPWD AFS

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,33,480/- only

NAME OF WORK:- R/R DAMAGES ON BUELA KOEL SANOG ROAD KM 0/00-28/000 (UNDER PDNA)

Earnest Money = Rs. 2700/- only

SH:- C/O PCC R/Wall between KM 6/780-6/S00

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	Rate	Unit	AMOUNT	
1	2	3	In figures	In words	6	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 505.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer In Charge.	9.52	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1632.00
2	Providing and laying plain/enforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (1) 1:5:10 (40 mm nominal size stone aggregates)	29.28	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	128557.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614/09,1204.3.7.	12.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	per running metre	3291.00
	TOTAL					133480.00

(quoted rate percentages in figures)

(quoted rate percentages in words)


Prashant Singh
 Head Engineer
 JPR/M/A/11

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,33,480/- only

NAME OF WORK:- R/R DAMAGES ON CHAMAKRIPUL TO DUNDHAN ROAD KM 0/00-5/000 (UNDER PDNA)

Earnest Money = Rs. 2700/- only


SH:- C/O PCC R/Wall between KM 0/600-0/620

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	AMOUNT	RATE	In figures	In words	Unit	AMOUNT
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.52	cum	1632.00	Rupees One Hundred Seventy One and Paise Forty only	171.40	Per cubic metre		
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	29.28	cum	128557.00	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	4390.60	Per cubic metre		
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	12.00	Rmt	3291.00	Rupees Two Hundred Seventy Four and Paise Twenty Five only	274.25	Per running metre		
	TOTAL			133480.00					

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R DAMAGES ON CHAMAKRIPUL TO DUNDHAN ROAD KM 0/00-5/000 (UNDER PDNA)

Estimated Cost = Rs. 1,33,480/- only


SH:- C/O PCC R/Wall between KM 0/400-0/420

Earnest Money = Rs. 2700/- only
Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	AMOUNT
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.52	cum	171.40
			Ruppes One Hundred Seventy One and Paise Forty only	per cubic metre
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802.803.1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	29.28	cum	4390.60
			Ruppes Four Thousand Three Hundred Ninely and Paise Sixty only	Per cubic metre
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	12.00	Rmt	274.25
			Ruppes Two Hundred Seventy Four and Paise Twenty Five only	Per running metre
	TOTAL			133480.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,33,480/- only

NAME OF WORK:- R/R DAMAGES ON KAINITH KA PANI CHANDPUR ROAD KM 0/00-2/780 (UNDER PDNA)

Earnest Money = Rs. 2700/- only


SH:- C/O PCC R/Wall between KM 0/690-0/710

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	AMOUNT	RATE	IN WORDS	UNIT	AMOUNT
1	2	3	4	5	6	7	8	9
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.52	cum	1632.00	171.40	Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1632.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	29.28	cum	12857.00	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	12857.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	12.00	Rmt	3291.00	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	3291.00
	TOTAL			133480.00				133480.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,33,538/- only

NAME OF WORK:- R/R DAMAGES ON CHEOD KHAD JAGHOON ROAD KM 0/00-18/000 (UNDER PDNA)


Earnest Money = Rs. 2700/- only
Time Period = Two Months

SH:- C/O PCC R/Wall between KM 5/600-5/620

S.NO	DESCRIPTION OF ITEM	QTY	RATE	Unit	AMOUNT
1	2	3	In figures In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.36	171.40 Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1604.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (i) 1:5:10 (40 mm nominal size stone aggregates)	28.80	4390.60 Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	126449.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614, 709, 1204.3.7.	20.00	274.25 Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	5485.00
TOTAL					133538.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY

Estimated Cost = Rs. 1,33,538/- only

NAME OF WORK:- R/R DAMAGES ON CHEOD KHAD JAGHOON ROAD KM 0/00-18/000 (UNDER PDNA)

Earnest Money = Rs. 2700/- only


SH:- C/O PCC R/Wall between KM 4/360-4/380

Time Period = Two Months

S.NO	DESCRIPTION OF ITEM	QTY	UNIT	AMOUNT	
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer in Charge.	9.36	cum	171.40	
			Rupees One Hundred Seventy One and Paise Forty only	Per cubic metre	1604.00
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including cartage of materials upto all leads and lifts (I) 1:5:10 (40 mm nominal size stone aggregates)	28.80	cum	4390.60	
			Rupees Four Thousand Three Hundred Ninety and Paise Sixty only	Per cubic metre	126449.00
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7.	20.00	Rmt	274.25	
			Rupees Two Hundred Seventy Four and Paise Twenty Five only	Per running metre	5485.00
	TOTAL				133538.00

Quoted rate Percentage in Figures

Quoted rate Percentage in Words


 Executive Engineer
 B&R Division
 HPPWD Arki

SCHEDULE OF QUANTITY


**Name of work :-R/R damages on Kunihar Bainj Ki Hatti Shelly Brampulchar Road portion
Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O R/ Wall at 1/150 to 1/156.10)**

Estimated Cost :- Rs 99,479.00
Earnest money :- Rs 2,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	In figure	Rate		Unit	Amount
				In words			
1	2	3	171.40	Rupees One Hundred Seventy One and Forty paise Only		6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORDD Specification and as per the direction of Engineer-In-Charge	8.65	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	92071.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre (forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge	20.97	Cum	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	2688.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1 (v);20 (H) towards drawing face complete as per drawings and technical specifications MORDD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	9.80	Rmt	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	3237.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORDD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	2.69	Cum			Per cubic metre	3237.00
				Total			99479.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

**Name of work :- R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion
Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O R/ Wall at RD 6/405 to 6/450)**

Estimated Cost :- Rs 91,210.00
Earnest money :- Rs 2,000.00
Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Rate	Unit	Amount
1	2	3	In Figure In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORDD Specification and as per the direction of Engineer-In-Charge.	10.43	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1788.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto five sand isto ten graded crushed stone aggregate 40 millimeter/ forty millimetre) nominal size for plain/reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	19.37	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	85046.00
3.00	Providing and laying weaphotes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred) millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORDD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	5.95	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	1632.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORDD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	2.28	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	2744.00
				Total	91210.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words

601

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Name of work :- R/R damages on Kunihar Bainj Ki Hatti Shelly Brampukhar Road portion Km 0/0 to 8/0 UNDER PDNA 2023 (SH:-C/O damaged Wing wall at Rd 2/060 to 2/067)


Estimated Cost :- Rs 99,479.00
 Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3			6	7	
1.00	Earlwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deteriorious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	8.65	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1483.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement is to Five sand is to ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain/reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 & 1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	20.97	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	92071.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred) millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	9.80	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	2688.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	2.69	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	3237.00
					Total		99479.00

Quoted Rate Percentage in Figures

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD, Arki.

SCHEDULE OF QUANTITY


Name of work :-R/R damages on Talab (Rau Khad) Behli Road Km 0/0 to 2/170 under
PDNA (SH:-C/O R/wall at RD 0/090 to 0/105)

Estimated Cost :- Rs 4,94,811.00
Earnest money :- Rs 10,000.00
Time: One month

Sr.No	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3	6	7			
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	41.11	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	7046.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802.803.1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	104.97	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	460881.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614.709.1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	56.17	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise-Only	Per running metre	15405.00
4.00	Back filling behind abutment wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	9.54	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	11479.00
						Total	494811.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY


Name of work :-R/R damages on Talab (Rau Khad) Behli Road Km 0/0 to 2/170 (SH:-C/O R/wall at RD 0/105 to 0/120) (Under PDNA)

Estimated Cost :- Rs 4,94,811.00
 Earnest money :- Rs 10,000.00
 Time: One month

Sr.No	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of slumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	41.11	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre 7046.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	104.97	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre 460881.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(V):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614.709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	56.17	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre 15405.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	9.54	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre 11479.00
	Total					494811.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki

SCHEDULE OF QUANTITY


Name of work :- R/R damages on Shalaghat Arki Kunihar Barotiwala Road portion Km 17/500 to 26/000 UNDER PDNA (SH:-C/O Wire Crate at RD 20/640 to 20/650)

Estimated Cost :- Rs 2,39,717.00
 Earnest money :- Rs 5,000.00
 Time: One month

Sr.No	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1		3			6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	29.06	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	4981.00
2.00	Providing and Laying of boulder apron laid in wire crate with 4 mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100 mm mesh(wovendiagonally) i.e. 10% extra for laps and joint with stone boulder weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete. complete as per HP. PWD specifications of 1990 volume-1 including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in-Charge..	78.14	Cum	3004.05	Rupees Three Thousand Four and Five paise Only	Per cubic metre	234736.00
	Total						239717.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

2/12

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of JCB for removal of slips in Various Roads Under Shalaghat Section Job No-9)

Estimated Cost - ₹ 99000/- only


Earned Money - ₹ 22000/- Only

Time - One Month

S No	Sub head and items of work	Qty.		Figure	Rate In Words	Unit	Amount
		3	4				
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift up to 1.50 meter and lead up to 1000 meters as per technical specification 302.3.5 and 157.1. including cartage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand only	P Hour.	990000
Total							99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of JCB for removal of slips in Various Roads Under Shalaghat Section Job No-8

Estimated Cost: -Rs99000/- only


Earnest Money :-Rs2000/-only

Time :-One Month

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Words	Figure		
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift up to 1.50 meter and lead up to 1000 meters as per technical specification 302.3.5 and 1611,including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand only	P.Hour.	99000
			3	4		5	6
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Various Roads Under Shalaghat Section Job No-5

Estimated Cost: -Rs97500/- only

Earnest Money :-Rs2000/-only

Time :-Fifteen Days

S. No	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred and fifty only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY


Name of Work:- Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Various Roads Under Shalaghal Section Job No-4

Estimated Cost: -Rs97500/- only
 Earnest Money :-Rs2000/-only
 Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount	
				Figure	Words			
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expansion of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur during the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred and fifty only	P.Hour.	97500	
			3			4	5	6
							Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki


SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Shimla Kunihar Ramsehar Nalagarh road Portion Km 47/00 to 60/500.(Sh :Construction- 59/510 to 59/518) Under PDNA of R/wall at Rd

Estimated Cost :- Rs 64,301.00
 Earnest money :- Rs 2,000.00
 Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1		3			6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including scutting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MOR D Specification and as per the direction of Engineer-In- Charge	5.21	Cum	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	893.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	13.44	Cum	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	59010.00
3.00	Providing and laying wearholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(V):20 (H) towards drawing face complete as per drawings and technical specifications MOR D clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge	1.25	Rmt	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	343.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MOR D clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	3.37	Cum	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	4055.00
					Total	64301.00

- (i) Rates quoted percentage in figure.
 (ii) Rate quoted percentage in Words.


 Executive Engineer
 Arki Division (B&R)
 HP, PWD, Arki.

SCHEDULE OF QUANTITY

Name of Works:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Bhumati Section

Estimated Cost: 99000.00
Earnest Money: 2000.00


(SH:- Removal of slips/dressing of roads by hiring of JCB in various roads) Job No - 6

Time Period: 15 Days

S. No	Sub head and items of work	Qty		Rate		Unit	Amount
		In figures	In words	In figures	In words		
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause S023.5 and 1011 including carriage of materials upto all leads lifts and as per direction of Engineer in charge.	3	Hour	1000.00	Rupees one thousand and paise nil only	Per Hour	99000.00
	Total=						99000.00
Conditions: (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.							

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Shimla Kunihar Ramschar Nalagarh road Portion Km 47/00 to 60/500.(Sh : Construction of R/wall at Rd 59/915 to 59/930) Under PDNA


Estimated Cost :- Rs 92,816.00
Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	2	3			6	7	
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	9.95	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	1705.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre (forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	19.31	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	84782.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(V):20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	3.42	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	938.00
4.00	Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	4.48	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	5391.00
					Total		92816.00

(i) Rates quoted percentage in figure.

(ii) Rate quoted percentage in Words.


Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.


SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on various roads under Kunihar sub division HP, PWD Kunihar under Mann Section. (Sh :Hiring of JCB for removal of slips in various roads)

Estimated Cost :- Rs 99,000.00
 Earnest money :- Rs 2,000.00
 Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cur materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
					Total	99000.00

- (i) Rates quoted percentage in figure.
 (ii) Rate quoted percentage in Words.


Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on various roads under Kunihar sub Division HP.PWD Kunihar under Mann Section.(Sh : Hiring of JCB for removal of slips in various roads)

Estimated Cost :- Rs 99,000/-
 Earnest money :- Rs 2,000/-

Time: One month

Sr. No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and deposit of cut materials with in lift upto 1.50 meters and land upto 1000 meters as per technical specification 502.2.5 and 1611 including carriage of materials upto all lands and lifts and as per the direction of Engineer in charge.	09 00	1000.00	Rs. One thousand and hundred Only	Per hours	99000.00
					Total	99000.00

(i) Rates quoted percentage in figure.
 (ii) Rate quoted percentage in words.


Executive Engineer
 Arki Division (BAR)
 HP, PWD Arki.

SCHEDULE OF QUANTITY


Name of Work:- Restoration of rain Damages on various roads under Kunihar sub division HP, PWD Kunihar under Mann Section.(Sh :Hiring of JCB for removal of slips in various roads)

Estimated Cost :- Rs 99,000.00
 Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate		Unit	Amount
			In figure	In words		
1	2	3			6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	1000.00	Ruppes One thousand and paisenil Only	Per Hours	99000.00
					Total	99000.00

- (i) Rates quated percentage in figure.
 (ii) Rate quated percentage in Words.


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain Damages on Shimla Kunihar Ramschar Nalagarh road Portion Km 47/00 to 60/500.(Sh : Construction of R/wall at Rd 60/150 to 60/170) Under PDNA

Estimated Cost :- Rs 97,376.00
Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.	Rate	Unit	Amount
1	2	3	In figure In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In-Charge	7.82	Ruppes One Hundred Seventy One and Forty paise Only	Per cubic metre	1340.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 millimetre(forty millimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802.803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	20.21	Ruppes Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	88734.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	4.51	Ruppes Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	1237.00
4.00	Charge Back filling behind abutment, wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.04	Ruppes One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6065.00
	Total				97376.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.
(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

DNTT duly Approved for Rs 97,376=00/- only (Ruppes Ninety Seven thousand three hundred seventy six and paise zero) only for the year 2025-26. Entered at Register Sr. No. 979

Executive Engineer
Arki Division (B&R)
HP, PWD, Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages of Kunihar Sub Division HP PWD Kunihar Under Mann
 Section (SH):-Hirring of Tipper for Carriage of Slips/debris et.) Job No-1

Estimated Cost :-Rs98800/- only


Earnest Money :-Rs2000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount	
				Figure	Words			
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expansion of P. O. L. charges . repair of machineres . Any accident and other damages to be the private and govt. property occur during the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	152.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	98800	
			3			4	5	
							6	
							Total	98800

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Mangal Section (SH:-
Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) (Job No-VI)

Estimated Cost:-Rs 99,000/- only
Earnest Money : Rs 2000 /-only
Time -One Months

S.No.	Sub head and Items of work	Qty.	Rate	Unit	Amount
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	3	1000.00	Per hour	99000.00
				Total:-	99000.00

Quoted rate percentage in figures
Quoted rate percentage in words


Executive Engineer
H.P. PWD (B&R)
Division Arul


specification
leads and lifts and as per

DRAFT SCHEDULE OF QUANTITY

Name of Work: Restoration of rain damages on various roads under Darla Sub Division Mangal Section (SH:-
Hiring of JCB for removal of slips dressing of roads, cleaning of drains etc.) (Job No-VII)

S.No.	Sub head and items of work	Qty.	Hours	Rate		Unit	Amount
				In figure	In words		
1	2	3		1000.00	Rupees One Thousand Only	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3 5 and 1011 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00				Per hour	99000.00
Total:-							99000.00

quoted rate % in figures
quoted rate % in words.


Executive Engineer
Division,
HPPV, -KI

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages in Mann Section Under Kunihar Sub Division (SH:-

Estimated Cost -Rs99000/- only
Earnest Money -Rs2000/-only

Removal of Minor Slips, Cleaning of Drain and Catch Pits by hiring of JCB) (Job No-IV)

Time -Fifteen Days

S No	Sub head and items of work	Qty		Rate In		Unit	Amount
				Words			
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in all leads and lifts as per technical specification 302 3.5 and 1611) including carriage of materials in all leads and lifts and as per the direction of Engineer-In-Charge	99 00	Hour	1000 00	Rupees One Thousand and paise nil only	P Hour	99000
			3	4		5	6
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY


Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips at Km 8/555 to 8/590 in Manju Khanalag Road.) (Job No-2)

Estimated Cost: -Rs97,500/- only
Earnest Money :-Rs2000/-only
Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit		Amount	
				Figure	Words				
1	2			3		4		5	6
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expansion of P.O.L. charges , repair of machinerfes . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500		
Total								97500	

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of JCB for removal of slips at Km 8/555 to 8/590 in Manju Khanalag Road.) (Job No-2)

Estimated Cost: -Rs99000/- only


Earnest Money :-Rs2000/-only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611 ,including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
			3		4	5	6
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Various Roads Under Darla Section.) (Job No-2)

Estimated Cost: -Rs97,500/- only


Earnest Money :-Rs2000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Words			
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expansion of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500
			3		4	5	6
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki