



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **18-10-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 17-10-2025 up to **4.00 P.M** and the application for issue of tender form shall be received on 17-10-2025 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Parour Dheera Naura upto Purba road (Under PDNA)	96,777/-	1900/-	Three Month	350/-
2	Restoration of rain damages on Tamloh Bharanta road (Under PDNA)	99,824/-	2000/-	Three Month	350/-
3	Restoration of rain damages on Nagni Gharana road (Under PDNA)	77,930/-	1600/-	Three Month	350/-
4	Restoration of rain damages on Nagni Gharana road (Under PDNA)	99,200/-	2000/-	Three Month	350/-
5	Restoration of rain damages on Nagni Gharana road (Under PDNA)	99,600/-	2000/-	Three Month	350/-
6	Restoration of rain damages on Dheera Sihotu road (Under PDNA)	99,075/-	2000/-	Three Month	350/-
7	Restoration of rain damages on Dheera Sihotu road (Under PDNA)	98,880/-	2000/-	Three Month	350/-
8	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (Under PDNA)	73,485/-	1500/-	Three Month	350/-
9	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (Under PDNA)	73,635/-	1500/-	Three Month	350/-
10	Restoration of rain damages on Bhawarna Khera Alampur road (Under PDNA)	99,200/-	2000/-	Three Month	350/-
11	Restoration of rain damages on Bhawarna Khera Alampur road (Under PDNA)	99,600/-	2000/-	Three Month	350/-
12	Restoration of rain damages on Thural Bharanta road (Under PDNA)	99,824/-	2000/-	Three Month	350/-
13	Restoration of rain damages on Dadh Malan Massal Rajhoon road (Under PDNA)	99,192/-	2000/-	Three Month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

*[Signature]*  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh  
Dated:- 9/10/2025

No. PWD/BWD/TA/NIT/2025-26/

7604-12

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


*[Signature]*  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-7604-12 dated: 9-10-2025.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Schedule of Quantity


Name of Work :- Restoration of rain damages on Parour Dheera Naura upto Purba road (Under PDNA).

Estimated Cost :-Rs. 96,777/-

Earnest Money :-Rs. 1900/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	C/o V-shape drain in Km 6/755 to 6/791 & U-shape drain in Km 6/840 to 6/851.20					
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	21.60	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	5400.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement-concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	18.46	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	91377.00
	<b>Quoted rates percentage in figures</b>					
	<b>Quoted rates percentage in words</b>					
<b>Total :-</b>						<b>96777.00</b>

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity


Work :- Restoration of rain damage on Tantihi Bhanaris road (UHDA: PWD)

Estimated Cost :- Rs. 99,824/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figures	In Words		
						Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets abutts in all types of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging and rills. When blasting is prohibited as per drawings and M.O.R.D. technical specification section 303 and 304 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stones and other deleterious material and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 100mm (one hundred fifty millimeter) compacted thickness of each layer including shoring and strutting and piling, and sealing out water (surface and sub soil water) upto any depth and any quantum of water including clearing of silt which may arise or during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including extra, royalty, Malkana, toll tax, site tax, GST or other taxes imposed by the Government.	18.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4050.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS 280 and IS 4322 + 100mm x 100mm (Hundred millimetre size hundred millimetre) mesh (woven diagonally) including 10 per cent extra for lap and joints laid with stone boulders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including extra, royalty, Malkana, toll tax, site tax, GST or other taxes imposed by the Government.	32.40	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	90720.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1203 and 1004 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate is including extra, royalty, Malkana, toll tax, site tax, GST or other taxes imposed by the Government.	6.08	200.00	Rupees Seven Hundred Only	Per Cubic metre	1216.00
4	Construction of embankment with approved material deposited at site from road way cutting and excavation from drains and foundation of other structures or other sources graded and compacted in 200mm two hundred millimetre thickness in every layer and compacted with three Wheel Road Roller 80-100 (eighty hundred) KN static weight roller as per the requirement of tables 200.1 and 200.2 as per M.O.R.D. technical specification clause 307 and 300.1 and as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including extra, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.00	80.00	Rupees Eighty Only	Per Cubic metre	160.00
<b>Total :-</b>						<b>99824.00</b>
Quoted rates percentages in figures						
Quoted rates percentages in words						

  
 Executive Engineer  
 Bhawana Division  
 HP PWD Bhawana

## Schedule of Quantity

3


Work :- Restoration of rain damages on Nagni Gharana road Km. 0/00 to 10/00. (SH:- C/o Edge Wall in Km. 2/370 to 2/386). (Under PPAIA)

Estimate Cost :-Rs. 77,930/-

Earnest Money :-Rs. 1600/-

Time Limit :- Three Months

Sr. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	9.44	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	2360.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M O R D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.08	4000.00	Rupees Four Thousand Only	Per Cubic metre	72320.00
3	Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V) : 20 (H) (one vertical, twenty horizontal) towards draining face complete as per drawing and M O R D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	13.00	250.00	Rupees Two Hundred Fifty Only	Each	3250.00
<b>Total :-</b>						<b>77930.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

4

of work:- Restoration of Rain damages on Nagni Gharana road (Under PDNA)


Estimate Cost :- Rs. 99,200/-

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

(SW:- Providing and fixing Road studs at Various Rds).

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	248.00	400.00	Rupees Four Hundred Only	Each	99200.00
<b>Total:-</b>						<b>99200.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

me of work:- Restoration of Rain damages on Nagni Gharana road (Under PDNA)


Estimate Cost :- Rs. 99,600/-

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

(SW:- Providing and fixing Road studs at Various Rds).

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	249.00	400.00	Rupees Four Hundred Only	Each	99600.00
Total:-						99600.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

6

ne of Work :- Restoration of rain damages on Dheera Sihotu road (Under PDNA)


Estimated Cost :-Rs. 99,075/-

Earnest Money :-Rs. 2000/-

Time Limit :- Two Months

(SH:- C/o U-shape drain in Km 0/375 to 0/457) (RHS)

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	31.98	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	7995.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	18.40	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	91080.00
<b>Total :-</b>						<b>99075.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

of Work :- Restoration of rain damages on Dheera Sihotu road (Under PDNA).


Estimated Cost :-Rs. 98,880/-

Earnest Money :-Rs. 2000/-

Time Limit :- Two Months

A:- C/O U-Shape Drain in Km 0/457 to 0/537)

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	31.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	7800.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORC technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	18.40	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	91080.00
<b>Total :-</b>						<b>98880.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of quantity

8

of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (under PDNA)


Estimate Cost :- 73,485/-

Earnest Money :- 1500/-

Time Limit :- One Month

SW:- C/o Wire crate R/wall for protection of abutment of bridge at RD 34/743) (L/S)

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	6.90	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	1725.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS 280 and IS 4826 in 150mm x150mm (One Hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	27.60	2600.00	Rupees Two Thousand Six Hundred Only	Per Cubic metre	71760.00
<b>Total:-</b>						<b>73485.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of quantity

9

Item of Work :- Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (under PDNA)


Estimate Cost :- 73,635/-

Earnest Money :- 1500/-

Time Limit :- One Month

W:- C/o Wire crate R/wall for protection of abutment of bridge at RD 34/748) (L/S)

No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	7.50	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	1875.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS 280 and IS-4826 in 150mm x150mm (One Hundred fifty millimetre into One hundred fifty millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	27.60	2600.00	Rupees Two Thousand Six Hundred Only	Per Cubic metre	71760.00
<b>Total:-</b>						<b>73635.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

10

Name of work:- Restoration of Rain damages on Bhawarna Khera Alampur road (Under PDNA)


Estimate Cost :- Rs. 99,200/-

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

(SW:- Providing and fixing Road studs at Various Rds in between Km 3/00 to 4/500)

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	248.00	400.00	Rupees Four Hundred Only	Each	99200.00
<b>Total:-</b>						<b>99200.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

Name of work:- Restoration of Rain damages on Bhawarna Khera Alampur road (Under PDNA)


Estimate Cost :- Rs. 99,600/-

(SW:- Providing and fixing Road studs at Various Rds in between Km 0/00 to 3/00)

Earnest Money :- Rs. 2000/-

Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and fixing dual Directional retro reflective cat eyes studs made from high quality ABS plastic stud of size 90x100mm (Ninety into one hundred millimetre) provided with fixing to roads by hammering made of gree lite complete as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	249.00	400.00	Rupees Four Hundred Only	Each	99600.00
<b>Total:-</b>						<b>99600.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

Work :- Restoration of rain damages on Tamloh Bharanta road (Under PDNA).


Estimated Cost :-Rs. 99,824/-

Earnest Money :- Rs. 2000/-

Time Limit :- Three Months

12

No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
	Removal of slips, Construction of Wire crate R/wall at RD 0/040 to 0/047.50.					
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government.	16.20	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	4050.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS 280 and IS 4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana toll tax, sale tax, GST or other taxes imposed by the Government	32.40	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	90720.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6.08	700.00	Rupees Seven Hundred Only	Per Cubic metre	4256.00
5	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm( two hundred millimetres) thickness in every layers and compacted with three Wheel Road Roller 80-100 ( eighty-hundred ) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer- In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.98	80.00	Rupees Eighty Only	Per Cubic metre	798.00
<b>Total :-</b>						<b>99824.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of quantity.

13

of Work:- Restoration of Rain damages on Dadh Malan Massal Rajhoon road (Under PDNA)


Estimated Cost :- Rs. 99,192/-

Earnest Money :- Rs. 2000/-

Time Limit :- Two Months

Work:- Painting & Writing on Bridges, Bridges Pedestal, Boards, Rain Shelter and Kilometres stones etc).

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	364.20	6.00	Rupees Six Only	Per Square Metre	2185.00
2	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	9.72	60.00	Rupees Sixty Only	Per Square Metre	583.00
3	Painting one coat (excluding priming coats) on previously painted concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	354.48	65.00	Rupees Sixty Five Only	Per Square Metre	23041.00
4	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surfaces (Two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	26.40	95.00	Rupees Ninety Five Only	Per Square metre	2508.00
5	Writing letters or figures on any surface with black japan paint (stops, comas, hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31500.00	2.25	Rupees Two And Paise Twenty Five Only	Per letter per centimetre height	70875.00
<b>Total :-</b>						<b>99192.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna