



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **23-10-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 22-10-2025 up to **4.00 P.M** and the application for issue of tender form shall be received on 22-10-2025 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Construction of road from Kahanphat Chowk towards Dadu Jathera Temple GP & Tehsil Dhcera Distt. Kangra (SH:- Providing and laying cement concrete pavement in km. 0/0 to 0/116 & Grating work at RD 0/000) DC Deposit (VKV/2024/1305)	4,94,713/-	9900/-	Three Month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

*[Signature]*  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh  
Dated:- 14/10/2025

No. PWD/BWD/TA/NIT/2025-26/

7757-66

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


*[Signature]*  
Executive Engineer,  
Bhawarna Division  
HPPWD. Bhawarna



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-7757-66 dated: 14/10/2025.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Draft Schedule of Quantity

**Name of Work :- Construction of road from Kahanphat Chowk Towards Dadu Jathera Temple GP & Tehsil Dheera District Kangra. (Sh:- Providing Estimated Cost :-Rs. 4,94,713/- and laying Cement concrete pavement in Km 0/000 to 0/116 & Grating work at RD 0/000) (DC Deposit work). VKV/2024/1305), Earnest Money :-Rs. 9900/- Time Limit :- Three Months**

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of machineries, materials, tools, equipment and safety measured and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 13.64 cubic metre quantity at the rate of Rs. 300/- per cum shall be effected from the contractor's running bill on Pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana. toll tax, GST or other taxes imposed by the Government.	272.88	150.00	Rupees One Hundred Fifty Only	Per Cubic metre	40932.00
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	36.60	250.00	Rupees Two Hundred Fifty Only	Per Cubic metre	9150.00
3	Providing, laying, Soling 90 to 45mm ( Ninety to forty five milimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	34.80	2000.00	Rupees Two Thousand Only	Per Cubic metre	69600.00

4	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	7.20	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	35640.00
5	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	52.20	6200.00	Rupees Six Thousand Two Hundred Only	Per Cubic metre	323640.00
6	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in grating framed guard bares ladders railing brackets and similar work etcetra. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	165.80	95.00	Rupees Ninety Five Only	Per Kilogram	15751.00
<b>Total :-</b>						<b>494713.00</b>

*Draft Schedule of Quantity approved for Rs. 494713/only*

Executive Engineer  
Bhawaria Division  
HP PWD Bhawaria