

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2025- 3667-68
To


Dated: - 09-10-2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2


Subject: - Publishing of tender Notice.
Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A (3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.
DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 8 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form : 16.10.2025 up to 05.00 PM
 Date and time of issue/Sale of tender forms against cash Payment : 17.10.2025 (03.00 PM to 5.00 PM)
 Date and time of receipt of tenders : 18.10.2025 up to 11.00 AM
 Date and time of opening of tenders : 18.10.2025 at 11.30 AM


The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-III. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	98771.00	2000.00	One Month	350-	Class-D
2	Repair & Restoration of Rain Damages Link road on Gagret Una road Jadla to Nara Dukki road upto HP boundary Km 0/0 to 3/000 and Link road Gagret Oel Ispur road Km 9/195 to Loharli Upper upto GMS Khad Guzran in km. 0/0 to 3/600 (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	98531.00	2000.00	One Month	350-	Class-D
3	Repair & Restoration of Rain Damages various roads in Gagret Sub Division, (SH: Supplying direction and place identification sign boards and writing, Painting on sign boards etc.)	96450.00	2000.00	Two Month	350-	Class-D
4	Repair & Restoration of Rain Damages Link road Link road Saghnai to Kala Panga Km 0/0 to 4/700, and Link road to village Ghanari to link with Mawa Kohalan Nangal Jarialan road Km 0/0 to 4/000, (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	98131.00	2000.00	One Month	350-	Class-D
5	Repair & Restoration of Rain Damages Link road to Mohalla Gujran in GP Saghnai Km 0/0 to 3/0 and Link road Ambota Bus Stand to Nag Nath Mandir via Mohalla Jindbar km. 0/0 to 3/205 (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	96091.00	2000.00	One Month	350-	Class-D
6	Repair & Restoration of Rain Damages Mehatpur Una Mubarikpur Daulatpur HP Boundary (except NH Portion) N.M.T. road km. 60/675 to 72/555, Link road Pirthipur Junction to Maidangarh Km 0/0 to 4/000 and Link road Marwari to Bakhawa Km 0/0 to 3/000. (SH: Maintenance of Earhen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	98491.00	2000.00	One Month	350-	Class-D

7	Restoration of Rain Damages link road to Harijan Basti Bandu Km 0/0 to 2/0, (SH:- C/O U Shape Drain & Cover Km 1/385 to 1/425)	99908.00	2000.00	Two Month	350-	Class-D
8	Repair & Restoration of Rain Damages Link road Thaplan to Badoh workshop via Bhatian wala Km 0/0 to 5/000 and Link road to village Jadla Keori Km 0/0 to 3/000 (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)	96091.00	2000.00	One Month	350-	Class-D
9	A/R & M/O Non-Residential building under HPPWD Division Daulatpur Chowk Tehsil Ghanari Distt. Una (H.P) (SH: Providing and Fixing Visitor Chair, Table and Almera etc. in Division office)	57400.00	1200.00	One Month	350-	Class-D
10	Repair & Restoration of Rain Damages link road to harijan basti Amlehar Km. 0/00 to 2/700, (SH:- P/L 80 mm thick Cement Concrete paver blocks along approaches of CD between RD 0/780 to 0/840)	95277.00	2000.00	Two Month	350-	Class-D
11	Repair & Restoration of Rain damage on link road Karluhi Athmah Km 0/0 to 4/600, (SH- Construction of Retaining near House of Sh. Mastan Singh, Bhagwan Singh etc.)	99612.00	2000.00	Two Month	350-	Class-D

TE35RMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.


Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.


No. PWD/DPD/CB-Tender/2025-

3660-66

Dated: - 09-10-2025


Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.


Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025- 3660-66 dated 09-10-2025 are required to be carried out immediately being emergent nature of work in the public interest.


Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.


Job-1

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98771/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-III. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	408.50 cubic metre	80.00	Rupees Eighty Only	Per cubic metre	32680.00
Total Amount in Rs.						98771.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-2

DRAFT BILL OF QUANTITY


Estimated Cost: Rs. 98531/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Link road on Gagret Una road Jadla to Nara Dukki road upto HP boundary Km 0/0 to 3/000 and Link road Gagret Oel Ispur road Km 9/195 to Loharli Upper upto GMS Khad Guzran in km. 0/0 to 3/600 (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	405.50 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32440.00
Total Amount in Rs.						98531.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						



Assistant Engineer,
 HPPWD Sub Division,
 Gagret



Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk

Job-4

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98131/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Link road Link road Saghnai to Kala Panga Km 0/0 to 4/700, and Link road to village Ghanari to link with Mawa Kohalan Nangal Jarialan road Km 0/0 to 4/000, (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	400.50 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32040.00
Total Amount in Rs.						98131.00
						% above/below
						Quoted Rate in Figure
						Quoted Rate in Words

Executive Engineer,
HPPWD Division,
Daulatpur Chowk


Job-5

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 96091/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Link road to Mohalla Gujran in GP Saghnaï Km 0/0 to 3/0 and Link road Ambota Bus Stand to Nag Nath Mandir via Mohalla Jindbar km. 0/0 to 3/205 (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	375.00 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	30000.00
Total Amount in Rs.						96091.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						


 Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk


Job-6

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98491/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Mehatpur Una Mubarikpur Daulatpur HP Boundary (except NH Portion) N.M.T. road km. 60/675 to 72/555, Link road Pirthipur Junction to Maidangarh Km 0/0 to 4/000 and Link road Marwari to Bakhawa Km 0/0 to 3/000. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	405.00 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32400.00
Total Amount in Rs.						98491.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						



Executive Engineer,
HPPWD Division,
Daulatpur Chowk

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99908/-
 Earnest Money: Rs. 2000/-
 Time Limit : Two Month

Name of Work:- Restoration of Rain Damages link road to Harijan Basti Bandu Km 0/0 to 2/0, (SH:- C/O U Shape Drain & Cover Km 1/385 to 1/425)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	21.60 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	3888.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORTH technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	17.80 Cubic metre	4100.00	Rupees Four Thousand One Hundred Only	Per cubic metre	72980.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade-M25 (M-Twenty Five) designed mix with minimum cement contents of 400 kgs. (four hundred kilograms) per cubic meter with 20mm (Twenty millimeter) nominal size graded crushed stone aggregate in drain slab and the like up to all heights, including cost of form work and curing complete but excluding the cost of reinforcement for Reinforced work as per drawing and as per CPWD specification 2019 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.80 Cubic metre	6000.00	Rupees Six Thousand Only	Per cubic metre	10800.00
4	Supplying fitting and placing HYSD bar reinforcement in super structure complete as per drawing and MORTH technical specifications section 1600 and 2300 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any heights as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including of Octroi, Royalty, Malkhana, Toll Tax, Sale Tax or other Taxes imposed by the Government.	144.00 Kg	85.00	Rupees Eighty Five Only	Per Kilogram	12240.00
TOTAL						99908.00
			% above/below			
			Quoted Rate in Figure			
			Quoted Rate in Words			


 Executive Engineer,
 HPPWD Division,
 Daultpur Chowk.


Job-8

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 96091/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages Link road Thaplan to Badoh workshop via Bhatian wala Km 0/0 to 5/000 and Link road to village Jadla Keori Km 0/0 to 3/000 (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide at Various RD's)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	375.00 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	30000.00
Total Amount in Rs.						96091.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						


Executive Engineer,
HPPWD Division,
Daultapur Chowk


Job-9

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 57400/-
 Earnest Money: Rs. 1200/-
 Time Limit : One Month.

Name of Work:- **AR & M/O Non-Residential building under HPPWD Division Daultapur Chowk Tehsil Ghanari Distt. Una (H.P) (SH: Providing and Fixing Visitor Chair, Table and Almera etc. in Division office)**

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount	
		Figures	Words	Figures	Words			
1	Providing and Fixing of Visitor Chair without Arm SEAT/BACK ASSEMBLY: The seat and back should be made up of 1.2 ±0.1cm. Thick hot pressed plywood and upholstered with fabric and moulded Polyurethane foam with PVC lipping all around. The back foam should be designed with contoured lumbar support for extra comfort complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	8.00	Each	1800.00	Rupees One Thousand Eight Hundred Only	Number	14400.00	
2	Providing and Fixing office Table having Dimensions: 750cm X 1500cm Material: Top 18 mm Melamine laminated Particle Board & rest 15 mm Paper laminated Particle board. Hardware: Screw, KD Fittings, Slides & Castors. Construction: Knock down. Finish: Melamine laminated Top & rest Paper lamination (Color: Honey) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	1.00	Each	5000.00	Rupees Five Thousand Only	Number	5,000.00	
3	Providing and Fixing compute Table having Dimensions: 450cm X 1200cm Material: Top 18 mm Melamine laminated Particle Board & rest 15 mm Paper laminated Particle board. Hardware: Screw, KD Fittings, Slides & Castors. Construction: Knock down. Finish: Melamine laminated Top & rest Paper lamination (Color: Honey) complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	2.00	Each	4000.00	Rupees Four Thousand Only	Number	8,000.00	
4	Providing and Fixing Powder coated office Steel Godrej File Storage Office Almirah, Size: 7 Foot (ft) Of Shelves: 4 Shelves complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	3.00	Each	10000.00	Rupees Ten Thousand Only	Number	30,000.00	
Total Amount in Rs.								57400.00
Quoted Rate in Figure								
Quoted Rate in Words								
% above/below								


Executive Engineer,
HPPWD Division,
Daultapur Chowk.

Job-10

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 95277/-
Earnest Money: Rs. 2000/-
Time Limit : Two Months

Name of Work:- Repair & Restoration of Rain Damages link road to harijan basti Amlehar Km. 0/00 to 2/700, (SH:- P/L 80 mm thick Cement Concrete paver blocks along approaches of CD between RD 0/780 to 0/840)

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Excavation in earth work in foundation and trenches etcetera in all kind and classification of soil such as pick work, jumper work, pick jumper work, blasting work and hard blasting work and saturated soil any other mixed variety of soil in dry or saturated condition upto any depth and lift upto any height including chiseling/wedging out rocks where blasting prohibited dewatering pumping or bailing out water where required and/ removal of slush seprately as directed which may arise during the execution including stacking the serviceable and unserviceable material and then returning stacked soil in any thickness of layers when required into plinth side of foundation etcetera consolidating each deposited layers by ramming and watering then disposing of all surplus unserviceable excavated earth as specified dumping place as per CPWD specifications 2019 complete and direction of Engineer-in-charge including carriage of materials/machinery required to execute the work in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	7.50	180.00	Rupees One Hundred Eighty Only	Per cubic metre	1350.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) for plain cement concrete in all heights/depths, on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls, Breast Walls etcetera complete as per drawing and CPWD specifications 2019 and as per the direction and entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	8.40	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	31080.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade-M20 (M-Twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimetre) nominal size in or under water in open foundation for all types of structure and the like, including cost of form work and curing complete as per drawing and CPWD specification 2019 including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depths and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	0.56	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	2772.00
4	Providing and laying factory made chamfered edge Cement Concrete paver blocks 80mm (Eighty millimetre) thick of M-30 (thirty) grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm(fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per CPWD specification 2019 including carriage of materials up to all leads, lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government.	67.50	890.00	Rupees Eight Hundred Ninety Only	Per square metre	60075.00
Total Amount						95277.00
					%	above/below
		Quoted Rate in Figure	Quoted Rate in Words			


Executive Engineer,
HPPWD Division,
Daulatpur Chowk

DRAFT BILL OF QUANTITY

Estimated Cost: Rs.99612/-
 Earnest Money:Rs.2000/-
 Time limit:Two Months

Name of Work:- Name of Work:- Repair & Restoration of Rain damage on link Road Karluhi Aathmah in G.P. karluhi at Km.0/0 to 4/600(SH):- Construction of R/wall near House of Sh. Mastan singh, Bhagwan sing ect.)

Sr. No.	Description.	Qty.	Rate	Unit	Amount
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing bottom of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	4.40	180.00	per cum	792.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	25.10	3600.00	per cum	90360.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	16.00	240.00	Each	3840.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	6.60	700.00	per cum	4620.00
Total Amount					99612.00
quoted rate in figure		%above /below			
quoted rate in words					


 Executive Engineer,
 Daulatpur Chowk Division
 HPPWD Daulatpur Chowk