

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in) E mail:- [hp-kin@nic.in](mailto:hp-kin@nic.in)

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2025-  
To

6081-83

Dated:- 27-10-2025


The Executive Engineer (IT Cell),  
HP.PWD. Shimla-2.

**Subject:-**

**Publication of Tender Notice (OFFLINE)**


Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity  
& Certificate.

  
Executive Engineer,  
Kalpa Division,  
HP.PWD. Kalpa.

**Copy forwarded for information to:-**

1. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.

  
Executive Engineer,  
Kalpa Division,  
HP. PWD, Kalpa

**HP.P.W.D. TENDER NOTICE (offline)**

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP,PWD; Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **03-11-2025 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **01-11-2025 upto 4:00 P.M.** No application for issue of tender forms will be received on **01-11-2025 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimate d cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	C/O link road to Village Dabling Km. 0/00 to 4/900 (SH:- Formation cutting from Km. 4/450 to 4/735)	4,98,955/-	10,000/-	Two Months	350/-	D Class
2	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- Removal of slips at various RD's between Km. 4/00 to 9/700)	3,98,886/-	8,000/-	One Month	350/-	D Class
3	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- Repair of pot holes/road surface damaged due to landslides /shooting stones at various RD's between Km. 0/00 to 6/00 and 7/00 to 11/635)	4,81,788/-	10,000/-	One Month	350/-	D Class
4	Annual repair and maintenance of Kalamanch at Chango in District Kinnaur (HP) (SH:- C/O Boundary wall and repair of WS & SI thereof)	3,64,483/-	7,500/-	One Month	350/-	D Class
5	R/R damages on link road from Kalpa Pangi to Tarkhawa in G.P. Telangi Km. 0/00 to 2/00 (SH:- P/F G.I. fencing from Km. 1/650 to 1/725)	4,90,020/-	10,000/-	One Month	350/-	D Class
6	R/R damages on link road from Kalpa Pangi to Tarkhawa in G.P. Telangi Km. 0/00 to 2/00 (SH:- P/F G.I. fencing from Km. 1/725 to 1/805)	4,90,020/-	10,000/-	One Month	350/-	D Class
7	R/R damages on Jeepable road from Chungling Chowk to Khawangi Kanda Km. 0/00 to 2/500 (SH:- C/O R/wall in G.I. wire crate at RD. 0/00 to 0/058)	4,46,319/-	10,000/-	One Month	350/-	D Class
8	R/R damages on Jeepable road from Chungling Chowk to Khawangi Kanda Km. 0/00 to 2/500 (SH:- C/O R/wall in G.I. wire crate over existing R/wall at RD. 0/840 to 0/935 and U-shape drain at Km. 0/775 to 0/840)	4,90,825/-	10,000/-	One Month	350/-	D Class
9	Balance work for Construction of Science Block at Govt. Sr. Sec. School at Pooh in District Kinnaur (HP) (SH:- Providing and laying soling and C.C. work in courtyard and protection work)	4,83,479/-	10,000/-	One Month	350/-	D Class
10	Balance work for Construction of Science Block at Govt. Sr. Sec. School at Pooh in District Kinnaur (HP) (SH:- Providing and laying Interlocking paver block in Courtyard and brick work)	4,96,072/-	10,000/-	One Month	350/-	D Class
11	Balance work for Construction of Science Block at Govt. Sr. Sec. School at Pooh in District Kinnaur (HP) (SH:- C/O Septic Tank, railing and Chequredd tiles thereof)	4,68,117/-	9,500/-	One Month	350/-	D Class

12	Balance work for Construction of Science Block at Govt. Sr. Sec. School at Pooh in District Kinnaur (HP) (SH:- C/O Protection work in R.R. Masonry)	4,91,097/-	9,500/-	One Month	350/-	D Class
13	C/O Indoor Stadium at GSSS Pooh in Distt. Kinnaur HP (SH:- Geotechnical Investigation of soil/Strata)	3,02,000/-	6500/-	One Month	350/-	D Class
14	C/O Indoor Stadium at GSSS Giabong in Distt. Kinnaur HP (SH:- Geotechnical Investigation of soil/Strata)	3,02,000/-	6500/-	One Month	350/-	D Class
15	R/R damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270 (SH:- Formation cutting of washed away road from Km. 1/680 to 1/700)	4,89,141/-	10,000/-	One Month	350/-	D Class
16	R/R damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270 (SH:- Earth filling in washed away road from Km. 1/575 to 1/650)	4,47,695/-	9,000/-	One Month	350/-	D Class
17	R/R damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270 (SH:- Formation cutting of washed away road from Km. 1/700 to 1/725 and earth filling in washed away road from Km. 1/650 to 1/680))	4,68,858/-	10,000/-	One Month	350/-	D Class
18	R/R damages on link road from Pancha to Patka via Panva Km. 0/00 to 6/165 (SH:- C/O B/wall in PCC at RD. 3/550 to 3/657 and R/wall at RD. 3/600 to 3/625)	4,99,779/-	10,000/-	One Month	350/-	D Class
19	Special repair to Khadi Board building (Repair of Toilet) at Reckong Peo in Distt. Kinnaur HP (SH:- Distempering in cold pressed oil hall and repair of glass panes in Khadi board building)	1,42,903/-	3,000/-	One Month	350/-	D Class
20	R/R damages on link road from Brano to Nainpura Km. 0/00 to 3/100 (SH:- C/O R/wall in PCC at RD. 1/795 to 1/882)	4,99,422/-	10,000/-	One Month	350/-	D Class
21	R/R damages (PDNA) on link road from Thangi to Kunnu Charang Km. 0/00 to 20/00 (SH:- Hiring of JCB for removal of slips)	4,68,600/-	9,500/-	Two Months	350/-	D Class
22	R/R damages on link road from Pancha to Patka via Panva Km. 0/00 to 6/165 (SH:- P/L Interlocking paver block from Km. 3/565 to 3/600)	4,90,373/-	10,000/-	One Month	350/-	D Class
23	R/R damages on Jeepable road from Ropa to Thropa Km. 0/00 to 2/500 (SH:- P/L Interlocking paver block from Km. 0/00 to 0/060)	4,76,821/-	10,000/-	One Month	350/-	D Class
24	R/R damages on Jeepable road from Ropa to Thropa Km. 0/00 to 2/500 (SH:- P/L Interlocking paver block from Km. 0/060 to 0/120)	4,41,699/-	9,000/-	One Month	350/-	D Class
25	R/R damages on Jeepable road from Ropa to Thropa Km. 0/00 to 2/500 (SH:- C/O R/wall in GI wire crate at RD. 0/660 to 0/676.80)	2,16,677/-	4,500/-	One Month	350/-	D Class
26	R/R damages on Jeepable road from Brano to Kargail Kame via Shamshanghat in GP Pangri Km. 0/00 to 3/00 (SH:- C/O R/wall in GI wire crate at various portion from Km. 0/00 to 0/800)	4,94,109/-	10,000/-	One Month	350/-	D Class
27	R/R damages on Jeepable road from Brano to Kargail Kame via Shamshanghat in GP Pangri Km. 0/00 to 3/00 (SH:- C/O R/wall in GI wire crate at R.D. 1/495 to 1/516.60 and 1/725 to 1/748)	4,80,326/-	10,000/-	One Month	350/-	D Class
28	R/R damages on link road from Khotang to Gramma (upto Khotang) Km.0/00 to 4/660) (SH:- C/O R/wall in GI wire crate at RD. 1/850 to 1/908)	4,95,680/-	10,000/-	One Month	350/-	D Class
29	R/R damages on link road from Khotang to Gramma (upto Khotang) Km.0/00 to 4/660) (SH:- C/O R/wall in GI wire crate at RD. 2/300 to 2/358)	4,96,588/-	10,000/-	One Month	350/-	D Class
30	R/R damages (PDNA) on NH-22 to Ropa Khas Km. 0/00 to 15/850 (SH:- C/O R/wall in GI wire crate at RD. 12/365 to 12/377)	1,54,603/-	3,500/-	One Month	350/-	D Class
31	R/R damages (PDNA) on NH-22 to Ropa Khas Km. 0/00 to 15/850 (SH:- C/O R/wall in GI wire crate at RD. 7/815 to 7/851)	4,64,100/-	9,500/-	One Month	350/-	D Class

32	R/R damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270 (SH:- Hiring of JCB)	4,95,000/-	10,000/-	One Month	350/-	D Class
33	C/O Jeepable road from Rest House Rarang to Burzi No. 212 Km. 0/00 to 0/750 (SH:- Formation cutting from Km. 0/00 to 0/750)	4,06,366/-	8,500/-	One Month	350/-	D Class
34	Special repair to Residential accommodation of various department in District Kinnaur HP (SH:- P/L of PVC flooring, Painting etc. in Ty-III D.C. Staff quarter)	3,07,054/-	6,500/-	One Month	350/-	D Class
35	R/R damages on link road from Sunnam Hango to Lungfuk Km. 0/00 to 3/00 (SH:- C/O R/wall in GI wire crate at RD. 1/150 to 1/186)	3,11,126/-	6,500/-	One Month	350/-	D Class
36	R/R damages(PDNA) on link road from Hango Bus Stand to Village Hango Km. 0/00 to 1/650 (SH:-C/O R/wall in R.R. Masonry at RD. 0/970 to 0/990)	3,07,473/-	6,500/-	One Month	350/-	D Class
37	R/R damages (PDNA) on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- C/O R/wall in PCC at RD. 3/200 to 3/240)	4,81,705/-	10,000/-	One Month	350/-	D Class
38	R/R damages on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- Hiring of JCB for removal of slips)	4,95,000/-	10,000/-	One Month	350/-	D Class
39	Special repair to Ty-III (Set No. 1 & 2) Judicial Qtr. at Reekong Peo in District Kinnaur (HP) (SH:- Providing painting, wire gauge shutter and steel work thereof)	1,79,105/-	4,000/-	One Month	350/-	D Class
40	R/R damages on Skibba Rispa road Km. 0/00 to 4/270 (SH:- Widening of narrow road by formation cutting between Km. 1/00 to 1/400)	4,93,785/-	10,000/-	One Month	350/-	D Class
41	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- C/O R/wall in PCC at RD. 9/960 to 9/985, edge wall at RD. 4/280 to 4/290 and crash barrier)	4,99,262/-	10,000/-	One Month	350/-	D Class
42	R/R damages (PDNA) on Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- C/O R/wall in PCC at RD. 10/320 to 10/335, edge wall at RD. 10/670 to 10/695 and crash barrier)	4,98,984/-	10,000/-	One Month	350/-	D Class

**Terms and conditions:-**

**Following documents should accompany the application for tenders:-**

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.

No.:- PW/KNR-E-Tender/NIT/2025-

**Copy forwarded for information to:-**

1. The Engineer-in-Chief, HP PWD, Shimla-2
2. The Deputy Commissioner, Kinnaur District at Reekong Peo
3. The Sub Divisional Officer (Civil) Kalpa at Reekong Peo.
4. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reekong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reekong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reekong Peo.
8. Notice Board.

Executive Engineer,  
Kalpa Division,  
HP. PWD; Kalpa.


Dated:- 27-10-2025

Executive Engineer,  
Kalpa Division,  
HP. PWD; Kalpa.

**CERTIFICATE**

Certified that the Tender for work called vide this office

Letter No. PW/KNR/E-Tender/2025-6067-80 dated 27-10-2025 and 42 number  
of works are of urgent nature and public interest.

  
Executive Engineer,  
Kalpa Division,  
HP.PWD. Kalpa.

**DRAFT SCHEDULE OF QUANTITY**

**Work:-** C/O Link road to Village Dabbling Km 0/00 to 4/900  
(SH:-Formation cutting from Km. 4/450 to 4/735).

Estimated Cost :- 4,98,955/-  
Earnest Money :- 10,000/-  
Time :- Two Months

No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 244.235 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	2184.380	₹ 228.42	Rupees Hundred TwentyEight FourtyTwo Only	Two Per Cubic meter	₹ 498,955.00
	<b>Total:-</b>					₹ 498,955.00

*Draft schedule of quantity approved for Rs. 498,955/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

23

1

46  
2

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 3,98,886/-  
Earnest Money :- 8,000/-  
Time :- One Month

**Name of work:-** Restoration of rain damages (PDNA) on Peo Karchham Shilti road Km 0/00 to 11/635  
(SH:-Removal of slips at various RD's between Km. 4/00 to 9/700)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e. breaker etc. including cutting and trimming of slops and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	2500.85	₹ 159.50	Rupees One Hundred FiftyNine Paise Fifty Only	Per Cubic meter	₹ 3,98,886.00
<b>Total:-</b>						₹ 3,98,886.00

*Draft schedule of quantity approved for Rs. 3,98,886/- only.*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

47  
3

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,81,788/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** Restoration of rain damages (PDNA) on Peo Karchham Shiltil road Km 0/00 to 11/635  
**(SH):-** Repair of pot holes/road surface damaged due landslide/shooting stones at various Rds between Km 0/00 to 6/00 and 7/00 to 11/635

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	888.36	₹ 518.32	Rupees Five Hundred Eighteen Paise ThirtyTwo Only	Per Square meter	₹ 4,60,455.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.01	₹ 3,549.65	Rupees Thousand Hundred FortyNine Paise SixtyFive Only	Per Cubic meter	₹ 21,333.00
<b>Total:-</b>						<b>₹ 4,81,788.00</b>

*Draft schedule of quantity approved for Rs. 4,81,788/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

4

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 3,64,483/-  
 Earnest Money :- 7,500/-  
 Time :- One Month


Name of work:- Annual repair and Maintenance of Kalamanch at Chango in Distt. Kinnaur (H.P.)  
 (SH:- Construction of Boundary wall and repair of W.S & S.I. thereof).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.57	₹ 261.05	Rupees Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 1,976.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work-up to plinth level : 1:5:10 (One cement : five coarse sand : ten graded stone aggregate 40 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.73	₹ 4,390.60	Rupees Thousand Hundred Ninety Paise Sixty Only	Per Cubic meter	₹ 29,549.00
3	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:Cement Mortar 1:6 (one cement : six coarse sand). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	18.07	₹ 12,525.00	Rupees Thousand Hundred TwentyFive Only	Per Cubic meter	₹ 2,26,327.00
4	15 mm cement plaster on rough side of single or halfbrick wall of mix1:6 (one cement: six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	75.00	₹ 305.25	Rupees Hundred Five Paise TwentyFive Only	Per Square meter	₹ 22,894.00

5	15 mm cement plaster on fair side of single or halfbrick wall of mix1:6 (one cement: six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	86.50	₹ 275.20	Rupees Hundred Seventy Five Paise Twenty Only	Two Per Square meter	₹ 23,805.00
6	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	161.50	₹ 105.20	Rupees One Hundred Five Paise Only	Per Square meter	₹ 16,990.00
7	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarried on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete in Super-structure for all floors, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	161.50	₹ 105.20	Rupees One Hundred Five Paise Only	Per Square meter	₹ 16,990.00
8	Providing and fixing 3 layer PP-R (Poly propylene Random copolymer) pipes conforming to IS 15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes testing of joints complete, PN - 16 Pipe, 20mm (Twenty millimeter) OD (SDR-7.4), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.00	₹ 220.10	Rupees Hundred Paise Ten Only	Per Running meter	₹ 9,905.00
9	Providing and fixing CP brass bib tap with capastan head 15mm dia. of Jal or its Equivalent, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00	₹ 730.00	Rupees Hundred Only	Each	₹ 4,380.00

10	Providing and fixing C.P Brass pillar tap with Capstan head 15 dia.of jal or its Equivalent including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	8.00	₹ 850.30	Rupees Hundred Fifty Paise Thirty Only	Each	₹ 6,802.00	
11	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931.15 mm nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00	₹ 644.65	Rupees Six Hundred FourtyFour Paise SixtyFive Only	Each	₹ 2,579.00	
12	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S. triangular plate to European type W.C. of quality and make, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00	₹ 395.00	Rupees Hundred NinetyFive Only	Each	₹ 1,580.00	
13	Providing and fixing uplasticsised PVC connection pipe with brass unions : 45 cm length 15 mm nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	8.00	₹ 88.25	Rupees EightyEight Paise TwentyFive Only	Each	₹ 706.00	
<b>Total:-</b>							₹ 3,64,483.00

Draft schedule of quantity approved for Rs. 364483/- only.

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on link road from Kalpa Pangri to Tarakhawa in G.P. Telangi. Km 0/0 to 2/00  
**(SH:-** Providing and fixing G.I. fencing from Km. 1/650 to 1/725).

Estimated Cost :- 4,90,020/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.29	₹ 261.05	Rupees Hundred Paise Five Only	Per Cubic meter	₹ 1,903.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.830	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 35,312.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2307.44	₹ 122.00	Rupees Hundred TwentyTwo Only	Per Kilogram	₹ 2,81,508.00
4	Supplying and fixing wovenplains G.I. wire fencing of mesh 50mm to 150mm to any type of standard rails, straining bolts, etc. including provision of binding wire, staples etc. including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	225.00	₹ 761.32	Rupees Hundred Paise Only	Per Square meter	₹ 1,71,297.00
<b>Total:-</b>						<b>₹ 4,90,020.00</b>

*Draft schedule of quantity approved for Rs. 490020/- only.*

**Executive Engineer  
 Kalpa Division  
 HP. PWD, Kalpa**

## DRAFT SCHEDULE OF QUANTITY

**Name of work:-** Restoration of rain damages on link road from Kalpa Pangri to Tarkhawa in G.P. Telangi. Km 0/0 to 2/00  
**(SH:-** Providing and fixing G.I. fencing from Km. 1/730 to 1/805).

Estimated Cost :- 4,90,020/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.29	₹ 261.05	Rupees Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 1,903.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.830	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 35,312.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2307.44	₹ 122.00	Rupees Hundred TwentyTwo Only	Per Kilogram	₹ 2,81,508.00
4	Supplying and fixing wovenplains G.I. wire fencing of mesh 50mm to 150mm to any type of standard rails, straining bolts. etc. including provision of binding wire, staples etc, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	225.00	₹ 761.32	Rupees Hundred Paise ThirtyTwo Only	Per Square meter	₹ 1,71,297.00
<b>Total:-</b>						<b>₹ 4,90,020.00</b>

*Draft schedule of quantity approved for Rs. 490,020/- only*

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on Jeepable road from Chungling Chowk to Khawangji Kanda Km. 0/00 to 2/500  
**(SH:- C/O R/Wall in G.I. wire crate at RD 0/00 to 0/058).**

Estimated Cost :- 4,46,319/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	41.76	₹ 261.05	Rupees Hundred Paise Five Only	Two Per Cubic meter	₹ 10,901.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04	₹ 2,906.00	Rupees Thousand Hundred Six Only	Two Per Cubic meter	₹ 4,85,418.00
<b>Total:-</b>						<b>₹ 4,96,319.00</b>

*Draft schedule of quantity approved for Rs. 4,96,319/- only*

Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD; Kalpa.

48  
7

49 (8)

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages on Jeepable road from Chungling Chowk to Khawang Kanda Km. 0/00 to 2/500  
**(SH:- C/O R/Wall in G.I. wire crate over existing R/Wall at RD Km. 0/840 to 0/935 & U-Shape drain at Km. 0/775 to 0/840).**

Estimated Cost :- 4,90,825/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.65	₹ 261.05	Rupees Hundred Paise Five Only	Per Cubic meter	₹ 170.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	136.80	₹ 2,906.00	Rupees Thousand Hundred Six Only	Per Cubic meter	₹ 3,97,541.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.48	₹ 7,720.20	Rupees Thousand Hundred Paise Twenty Only	Per Cubic meter	₹ 88,628.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	0.89	₹ 5,040.05	Rupees Thousand Paise Five Only	Per Cubic meter	₹ 4,486.00
<b>Total:-</b>						<b>₹ 4,90,825.00</b>

*Draft schedule of quantity approved for Rs. 49,0825/- only.*

**Executive Engineer  
 Kalpa Division  
 HP. PWD Kalpa**

52

9

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,83,479/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** Balance work for the C/O Science Block in Govt. Sr. Sec. School at Pooch in Distt. Kinnaur (H.P.)  
(SH:- Providing and laying soling and CC work in courtyard and Protection work).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying Boulder filling under floor, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	36.37	₹ 950.00	Rupees Hundred Fifty Only	Per Cubic meter	₹ 34,552.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	83.87	₹ 5,352.65	Rupees Thousand Hundred Paise SixtyFive Only	Five Per Cubic meter	₹ 4,48,927.00
<b>Total:-</b>						₹ 4,83,479.00

*Draft schedule of quantity approved for Rs. 4,83,479/- only*

**Executive Engineer,**  
Kalpa Division (B&R),  
HP. PWD; Kalpa.

53

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,96,072/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Balance work for the C/O Science Block in Govt. Sr. Sec. School at Pooh in Distt. Kinnaur (H.P.)  
 (SH:- Providing and laying interlocking paver block in courtyard and brick work).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying 60mm (Sixty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	222.10	₹ 2,110.05	Rupees Thousand Hundred Ten Paise Five Only	Per Square meter	₹ 4,68,642.00
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement : 4 coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2,190	₹ 12,525.00	Rupees Thousand Hundred TwentyFive Only	Per Cubic meter	₹ 27,430.00
	<b>Total:-</b>					₹ 4,96,072.00

*Draft schedule of quantity approved for Rs. 496,072/- only*

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

54 (11)

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,68,117/-  
 Earnest Money :- 9,500/-  
 Time :- One Month

**Name of work:-** Balance work for the C/O Science Block in Govt. Sr. Sec. School at Pooh in Distt. Kinnaur (H.P.)  
**(SH:- C/O Septic tank, railing and chequered tiles thereof).**

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	186.75	₹ 261.05	Rupees Hundred Paise Five Only	Per Cubic meter	₹ 48,751.00
2	Centering and shuttering including strutting, propping etc. and removal of form for all heights in Suspended floors, roofs, landings, balconies and access platform, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.34	₹ 668.75	Rupees Six Hundred Paise SeventyFive Only	Per Square meter	₹ 13,602.00
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one poimr five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter) nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	2.54	₹ 11,174.85	Rupees Thousand Hundred SeventyFour Paise EightyFive Only	Per Cubic meter	₹ 28,384.00
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo Mechanically Treated bars of grade Fe-500D or more , including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	305.14	₹ 102.10	Rupees One Hundred Two Paise Ten Only	Per Kilogram	₹ 31,155.00
5	Providing and laying 20mm. thick Chequered tiles of size upto 300 x 300 mm (Three hundred fifty into three hundre fifty millimetre) . of specified shade in courtyard laid on a bed of 12mm. thick cement mortar 1:3(1 cement: 3 sand) jointing with cement slurry mixed with pigment to match the shade of tiles, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	15.40	₹ 650.30	Rupees three hundred seventy only	Per Square meter	₹ 10,015.00

11

6	Providing and laying Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25mm thick, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	7.56	₹ 1,750.00	Rupees three hundred seventy only	Per Square meter	₹ 13,230.00
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	544.50	₹ 122.00	Rupees Hundred Twenty Two Only	Per Kilogram	₹ 66,429.00
8	Providing and fixing Plain square edge cover fillet (beading) 40mm x 12 mm section with wood screw in ceiling and lining including mitring at junctions 1st class Deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	84.85	₹ 181.30	Rupees Hundred Eighty One Paise Thirty Only	Per Running meter	₹ 15,383.00
9	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	43.44	₹ 5,240.05	Rupees Thousand Hundred Paise Five Only	Per Cubic meter	₹ 2,27,628.00
10	15 mm cement plaster on fair side of single or half brick wall of mix 1:6 (one cement: six coarse sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	49.20	₹ 275.20	Rupees Hundred Seventy Five Paise Twenty Only	Per Square meter	₹ 13,540.00
<b>Total:-</b>						<b>₹ 4,68,117.00</b>

*Detail schedule of quantity approved for Rs. 4,68,117/- only*



Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

55

12

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,91,097/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** Balance work for the C/O Science Block in Govt. Sr. Sec. School at Pooh in Distt. Kinnaur (H.P.)  
(SH:- C/O Protection work in RR Masonry).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	93.72	₹ 5,240.05	Rupees Thousand Hundred Paise Five Only	Five Per Cubic meter	₹ 4,91,097.00
<b>Total:-</b>						₹ 4,91,097.00

*Draft schedule of quantity approved for Rs. 4,91,097/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

56

12

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 3,02,000/-  
Earnest Money :- 6,500/-  
Time :- One month

Name of work:- C/O Indoor Stadium at GSSS Pooch in Distt. Kinnaur (H.P.)  
(SH:- Geotechnical investigation of soil/strata).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Sub-Soil investigation of all type of soil/starta by drilling bore hole of NX size (75 (seventy five millimeter diameter) ranging from 10 (Ten) meter or above in depth for investigation of soil/rock conditions at site of work i/c mobilization and demobilization for drilling, shifting of machinery to bore site, make platform and water arrangement for drilling, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	40.00	₹ 7,550.00	Rupees Thousand Hundred Fifty Only	Per Running meter	₹ 3,02,000.00
			Total:-			₹ 3,02,000.00

*Draft schedule of quantity approved for Rs. 3,02,000/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

(57)

(14)

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 3,02,000/-

Earnest Money :- 6,500/-

Time :- One month

Name of work:- C/O Indoor Stadium at GSSS Giabong in Distt. Kinnaur (H.P.)  
(SH:- Geotechnical investigation of soil/strata).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Sub-Soil investigation of all type of soil/starta by drilling bore hole of NX size (75 (seventy five millimeter diameter) ranging from 10 (Ten) meter or above in depth for investigation of soil/rock conditions at site of work i/c mobilization and demobilization for drilling, shifting of machinery to bore site, make platform and water arrangement for drilling, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	40.00	₹ 7,550.00	Rupees Thousand Hundred Fifty Only	Per Running meter	₹ 3,02,000.00
<b>Total:-</b>						<b>₹ 3,02,000.00</b>

*Draft schedule of quantity approved for Rs. 3,02,000/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

58

15

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,89,141/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** Restoration of rain damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270  
**(SH:-** Formation cutting of washed away road from Km 1/680 to 1/700).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un -useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted- out and stacked along road side, the quantity of which shall not be less than 226.30 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	2225.90	₹ 219.75	Rupees Hundred Paise SeventyFive Only	Per Cubic meter	₹ 4,89,141.00
<b>Total:-</b>						₹ 4,89,141.00

*Draft schedule of quantity approved for Rs. 489,141/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

59

16

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,47,695/-  
Earnest Money :- 9,000/-  
Time :- One Month

**Name of work:-** Restoration of rain damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270  
**(SH:-** Earth filling in washed away road from Km 1/575 to 1/650).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Backfilling behind abutment, wing wall, road and return wall complete as per drawings & technical specification Clause 1204.3.8 with good earth, compacting filling in road with the static road roller, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1051.05	₹ 425.95	Rupees Hundred TwentyFive Paise NinetyFive Only	Per Cubic meter	₹ 4,47,695.00
<b>Total:-</b>						₹ 4,47,695.00

*Draft schedule of quantity approved for Rs. 4,47,695/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

60

17

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,68,858/-  
Earnest Money :- 10,000/-  
Time :- One Month

Name of work:- Restoration of rain damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270  
(SH:- Formation cutting of washed away road from Km 1/700 to 1/725 and Earth filling in washed away road from Km 1/650 to 1/680

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un -useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 92.94 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	914.18	₹ 219.75	Rupees Two Hundred Nineteen Paise SeventyFive Only	Per Cubic meter	₹ 2,00,893.00
2	Backfilling behind abutment, wing wall, road and return wall complete as per drawings & technical specification Clause 1204.3.8 with good earth, compacting filling in road with the static road roller, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, GST or other taxes imposed by the Government.	629.10	₹ 425.95	Rupees Four Hundred TwentyFive Paise NinetyFive Only	Per Cubic meter	₹ 2,67,965.00
<b>Total:-</b>						<b>₹ 4,68,858.00</b>

*Draft schedule of quantity approved for Rs. 4,68,858/- only*

*Jm*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

18

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,99,779/-  
 Earnest Money :- 10,000/-  
 Time :- One month

**Name of work:-** Restoration of rain damages on link road from Pancha to Patka via Panva Km. 0/00 to 6/165  
 (SH:- C/O B/Wall in PCC at RD 3/550 to 3/657 and R/Wall at RD 3/600 to 3/625).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	35.04	₹ 261.70	Rupees Hundred SixtyOne Paise Seventy Only	Two Per Cubic meter	₹ 9,170.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 &1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	80.090	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 485,105.00
3	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.00	₹ 275.20	Rupees Hundred SeventyFive Paise Twenty Only	Each	₹ 5,504.00
<b>Total:-</b>						<b>₹ 499,779.00</b>

*Draft schedule of quantity approved for Rs. 499,779/- only*

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD; Kalpa.

**SCHEDULE OF QUANTITY**

Sr. No.		Description of items	Qty.	In Fig.	Rate		Unit	Estimated Cost
					In Words	Amount		
<b>Name of work:-</b> Special repair to Khadi Board Building (Repair of toilet) at R/Peo Distt. Kinnaur (H.P.) <b>(SH:-</b> Distempering in Cold Pressed Oil Hall and repair Glass Panes in Khadi Board Building).								
								Estimated Cost :- 1,42,903/-
								Earnest Money :- 3,000/-
								Time :- One Month
1	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two coats including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	214.84	137.45	Rupees One Hundred ThirtySeven Paise FourtyFive Only	Per Square meter	₹ 29,530.00		
2	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour Two coats, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	256.58	130.20	Rupees One Hundred Thirty Paise Twenty Only	Per Square meter	₹ 33,407.00		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	141.61	110.20	Rupees One Hundred Ten Paise Twenty Only	Per Square meter	₹ 15,605.00		
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	471.42	120.20	Rupees One Hundred Twenty Paise Twenty Only	Per Square meter	₹ 56,665.00		

19

5	Renewing glass panes, with wooden fillets wherever necessary: Float glass panes of nominal thickness 4 mm. (weight not less than 10kg/sqm), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.83	1320.00	Rupees One Thousand Three Hundred Twenty Only	Per Square meter	₹ 7,696.00
	<b>Total in figures:-</b>					
	<b>Total in Words:-</b>					
	<b>Quoted Percentage rate upto three Digits :-</b>					
				Rupees One Lakh FourtyTwo Thousand Nine Hundred Three Only		₹ 1,42,903.00
				(+)/( -)		



Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

75

20

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,99,422/-  
Earnest Money :- 10,000/-  
Time :- One month

Name of work:- Restoration of rain damages on Link road from Brano to Nainpur Km 0/00 to 3/100  
(SH:- C/O R/Wall in PCC at RD 1/795 to 1/822).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.76	₹ 261.70	Rupees Two Hundred SixtyOne Paise Seventy Only	Per Cubic meter	₹ 6,218.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 &1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	79,110	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 479,169.00
3	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	51.00	₹ 275.20	Rupees Two Hundred SeventyFive Paise Twenty Only	Each	₹ 14,035.00
					Total:-	₹ 499,422.00

*Draft schedule of quantity approved for Rs. 499,422/- only.*

*[Signature]*  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

(79)

(21)

DRAFT SCHEDULE OF QUANTITY

**Name of work:-** Restoration of rain damages (PDNA) on link road from Thangi to Kunnu Charang Km. 0/00 to 20/00  
(SH:- Herring of JCB for removal of slips).

Estimated Cost :- 4,68,600/-  
Earnest Money :- 9,500/-  
Time :- Two Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	355.00	₹ 1,320.00	Rupees Thousand Hundred Only	Per Hours	₹ 468,600.00
<b>Total:-</b>						₹ 468,600.00

*Draft schedule of quantity approved for Rs. 4,68,600/- only*

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

(62) 22

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,90,373/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** Restoration of rain damages on link road from Pancha to Patka via Panva Km. 0/00 6/165  
(SH:- Providing and laying interlocking paver block from Km 3/565 to 3/600).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	16.10	₹ 5,230.15	Rupees Thousand Hundred Thirty Paise Fifteen Only	Per Cubic meter	₹ 84,205.00
2	Providing and laying 80mm (Eighty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	161.00	₹ 2,328.56	Rupees Thousand Hundred Twenty Eight Fifty Six Only	Per Square meter	₹ 374,898.00
3	Providing and laying in position reinforced cement concrete 1:1.5:3 (One cement : one point five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter) nominal size) excluding the cost of centering, shuttering, finishing and reinforcement in beams, suspended floors, roofs having slope up to 15° (fifteen degree), landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor all level, complete upto all floor level, including entire carriage of materials in all leads and lifts and as per drawing and technical specifications as per the direction of Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2.80	₹ 11,167.71	Rupees Thousand Hundred Sixty Seven Paise Seventy One Only	Per Cubic meter	₹ 31,270.00
<b>Total:-</b>						<b>₹ 490,373.00</b>

*Draft schedule of quantity approved for Rs. 490,373/- only*

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

(76)

(23)

DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,76,821/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Restoration of rain damages on jeepable road from Ropa to Thiropa Km. 0/00 2/500  
 (SH:- Providing and laying interlocking paver block from Km 0/00 to 0/060).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	8.10	₹ 5,230.15	Rupees Thousand Hundred Thirty Paise Fifteen Only	Per Cubic meter	₹ 42,364.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802:803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	8.100	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 49,062.00
3	Providing and laying 80mm (Eighty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	162.00	₹ 2,328.56	Rupees Thousand Hundred TwentyEight Paise FiftySix Only	Per Square meter	₹ 377,227.00
4	Steel work welded in built up sections/ framed work of TATA, SAIL or RASHTRIYA ISPAT or its equivalent, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	67.50	₹ 121.00	Rupees One Hundred TwentyOne Only	Per Kilogram	₹ 8,168.00
<b>Total:-</b>						₹ 476,821.00

*Draft schedule of quantity approved for Rs. 476821/- only*

  
 Executive Engineer,

Kalpa Division (B&R),  
 HP.PWD; Kalpa.

77

24

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,41,699/-  
Earnest Money :- 9,000/-  
Time :- One Month

Name of work:- Restoration of rain damages on jeepable road from Ropa to Thropa Km. 0/00 2/500  
(SH:- Providing and laying interlocking paver block from Km 0/060 to 0/120).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	8.10	₹ 5,230.15	Rupees Thousand Hundred Thirty Paise Fifteen Only	Per Cubic meter	₹ 42,364.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3,650	₹ 6,057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 22,108.00
3	Providing and laying 80mm (Eighty millimeter) thick factory made cement concrete interlocking paver block of NTC M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	162.00	₹ 2,328.56	Rupees Thousand Hundred TwentyEight Paise FiftySix Only	Per Square meter	₹ 377,227.00
	<b>Total:-</b>					<b>₹ 441,699.00</b>

*Draft schedule of quantity approved for Rs 441,699/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

68

25

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 2,16,677/-  
Earnest Money :- 4,500/-  
Time :- One Month

Name of work:- Restoration of rain damages on Link road from ropa to Thropa Km 0/00 to 2/500  
(SH:- C/O R/Wall in G.I. wire crate at RD 0/660 to 0/676.80).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	21.84	₹ 261.05	Rupees Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 5,701.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	72.60	₹ 2,906.00	Rupees Thousand Hundred Six Only	Per Cubic meter	₹ 210,976.00
	<b>Total:-</b>					₹ 216,677.00

*Draft schedule of quantity approved for Rs. 2,16,677/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

72

26

## DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,94,109/-  
Earnest Money :- 10,000/-  
Time :- One Month

Name of work:- Restoration of rain damages on Jeevable road from Brano to Kargil Kame via Shamshan Ghat in G.P. Pangj Km 0/00 to 3/00 (SH:- C/O R/Wall in G.I. wire crate at various portion from Km. 0/00 to 0/800).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	48.30	₹ 261.07	Rupees Hundred Paise Seven Only	Two Per Cubic meter	₹ 12,610.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	165.60	₹ 2,907.60	Rupees Thousand Hundred Seven Paise Sixty Only	Two Per Cubic meter	₹ 481,499.00
	Total:-					₹ 494,109.00

Draft schedule of quantity approved for Rs. 494,109/- only

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

73

27

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,80,326/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Restoration of rain damages on Jeepable road from Brano to Kargil Kame via Shamshan Chat in G.P. Pangi Km 0/00 to 3/00 (SH:- C/O R/Wall in G.I. wire grate at RD 1/495 to 1/516.60 and 1/725 to 1/748).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.39	₹ 261.07	Rupees Hundred SixtyOne Paise Seven Only	Per Cubic meter	₹ 10,545.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	161.57	₹ 2,907.60	Rupees Thousand Hundred Seven Paise Sixty Only	Per Cubic meter	₹ 469,781.00
<b>Total:-</b>						₹ 480,326.00

*Draft schedule of quantity approved for Rs. 4,80,326/- only*

*[Signature]*  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD; Kalpa.

70

DR

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,680/-  
Earnest Money :- 10,000/-  
Time :- One Month

Name of work:- Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660  
(SH:- C/O R/Wall in G.I. wire crate at RD 1/850 to 1/908).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	38.28	₹ 261.07	Rupees Hundred Paise Seven Only	Two SixtyOne	₹ 9,994.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04	₹ 2,907.60	Rupees Thousand Hundred Seven Paise Sixty Only	Two Nine	₹ 485,686.00
	<b>Total:-</b>					₹ 495,680.00

*Draft schedule of quantity approved for Rs. 4,95,680/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

51

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 4,96,588/-  
 Earnest Money :- 10,000/-  
 Time :- One Month

**Name of work:-** Restoration of rain damages on link road from Khotang to Grama (Upto Khotang) Km. 0/00 to 4/660  
 (SH:- C/O R/Wall in G.I. wire crate at RD 2/300 to 2/358).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	41.76	₹ 261.07	Rupees Hundred Paise Seven Only	Per Cubic meter	₹ 10,902.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	167.04	₹ 2,907.60	Rupees Thousand Hundred Seven Paise Sixty Only	Per Cubic meter	₹ 485,686.00
<b>Total:-</b>						₹ 496,588.00

*Draft schedule of quantity approved for Rs. 496,588/- only*

Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** Restoration of rain damages (PDNA) on NH-22 to Ropa Khas road Km 0/00 to 15/850  
(SH:- C/O R/Wall in G.I. wire crate at RD 12/365 to 12/377).

Estimated Cost :- 1,54,603/-  
Earnest Money :- 3,500/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	15.60	₹ 261.05	Rupees Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 4,072.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty filve kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	51.80	₹ 2,906.00	Rupees Thousand Hundred Six Only	Per Cubic meter	₹ 150,531.00
	<b>Total:-</b>					₹ 154,603.00

*Draft schedule of quantity approved for Rs. 154603/- only.*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

(67)

(30)

69

31

### DRAFT SCHEDULE OF QUANTITY

**Name of work:-** Restoration of rain damages (PDNA) on NH-22 to Ropa Khas road Km 0/00 to 15/850  
(SH:- C/O R/Wall in G.I. wire crate at RD 7/815 to 7/851).

Estimated Cost :- 4,64,100/-  
Earnest Money :- 9,500/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	46.80	₹ 261.05	Rupees Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 12,217.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	155.50	₹ 2,906.00	Rupees Thousand Hundred Six Only	Two Per Cubic meter	₹ 451,883.00
<b>Total:-</b>						₹ 464,100.00

*Draft schedule of quantity approved for Rs. 464100/- only*

*Dr.*  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on Skibba Rispa road Km. 0/00 to 4/270  
(SH:- Herring of JCB).

Estimated Cost :- 4,95,000/-  
Earnest Money :- 10,000/-  
Time :- Two Months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00	Rupees Thousand Hundred Only One Three Twenty	Per Hours	₹ 495,000.00
<b>Total:-</b>						₹ 495,000.00

*Draft schedule of quantity approved for Rs. 4,95,000/-*

*[Signature]*  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

65

33

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:-** C/O Jeepable road from Rest House Rarang to Burzi No. 212 Km 0/00 to 0/750  
(SH:-Formation cutting from Km 0/00 to 0/750).

Estimated Cost :- 4,06,366/-  
Earnest Money :- 8,500/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 121.922 cum., failing which 'recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	2438.44	₹ 166.65	Rupees One Hundred SixtySix SixtyFive Only	Per Cubic meter	₹ 406,366.00
<b>Total:-</b>						₹ 406,366.00

*Draft schedule of quantity approved for Rs. 406366/- only*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

(64)

(34)

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :: 3,07,054/-  
 Earnest Money :: 6,500/-  
 Time :: One Month

**Name of work:-** Special repair to residential accommodation of various Deptt. in Distt. Kinnaur (H.P.)  
**(SH:-** Providing and laying of PVC flooring, painting etc. in Type-III DC Staff Qtrs.)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying plaster of paris putty of 2mm (Two millimeter) thickness over plastered surface to prepare the surface. even and smooth complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	411.00	₹ 130.20	Rupees One Hundred Thirty Paise Twenty Only	Per Square meter	₹ 53,512.00
2	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete in Super-structure for all floors, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	411.00	₹ 132.20	Rupees One Hundred ThirtyTwo Paise Twenty Only	Per Square meter	₹ 54,334.00
3	Providing and fixing 2mm (two milimeter) thick PVC antistatic vinyl flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	81.27	₹ 1,736.20	Rupees One Thousand Hundred ThirtySix Paise Twenty Only	Per Square meter	₹ 141,101.00
4	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	45.20	₹ 652.00	Rupees Six Hundred FiftyTwo Only	Per Square meter	₹ 29,470.00
5	Applying priming coat: With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	154.63	₹ 56.60	Rupees FiftySix Paise Sixty Only	Per Square meter	₹ 8,752.00

6	Applying a coat of mordant solution on G.S. sheet: With a solution of 38 gms of copper acetate in a litre of soft water, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	154.63	₹ 54.30	Rupees FiftyFour Paise Thirty Only	Per Square meter	₹ 8,396.00	
7	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade Old work (one or more coats), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	154.63	₹ 74.30	Rupees SeventyFour Paise Thirty Only	Per Square meter	₹ 11,489.00	
<b>Total:-</b>							₹ 307,054.00

*Draft schedule of quantity approved for Rs. 3,07,054/- only.*

*[Signature]*  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

35

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 3,11,126/-  
Earnest Money :- 6,500/-  
Time :- One Month

Name of work:- Restoration of rain damages on Link road from Sunnam Hango to Lungfuck Km. 0/00 to 3/00  
(SH:- C/O R/Wall in G.I. wire crate at RD 1/150 to 1/186).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	37.44	₹ 261.05	Rupees Hundred Paise Five Only	Two Per Cubic meter	₹ 9,774.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	103.70	₹ 2,906.00	Rupees Thousand Hundred Six Only	Two Per Cubic meter	₹ 301,352.00
Total:-						₹ 311,126.00

*Draft schedule of quantity approved for B. 311126/- on 8/11/20*

*[Signature]*  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

63

36

**DRAFT SCHEDULE OF QUANTITY**

Name of work:- Restoration of rain damages (PDNA) on Link road from Hango bus stand to village Hango Km. 0/000 to 1/650. (SH:-C/O R/wall in R.R. Masonry at RD 0/970 to 0/990).

Estimated Cost :- 3,07,473/-  
Earnest Money :- 6,500/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	29.40	₹ 261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 7,675.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803 1202 and 1203. 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimeter) nominal size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	6.20	₹ 4,041.70	Rupees Four Thousand FourtyOne Paise Seventy Only	Per Cubic meter	₹ 25,059.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	52.60	₹ 5,040.05	Rupees Five Thousand Fourty Paise Five Only	Per Cubic meter	₹ 265,107.00
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	35.00	₹ 275.20	Rupees Two Hundred SeventyFive Paise Twenty Only	Each	₹ 9,632.00
<b>Total:-</b>						<b>₹ 307,473.00</b>

*Draft schedule of quantity approved for Rs. 3,07,473/-*

  
Executive Engineer,  
Kalpa Division (B&R),  
HP. PWD, Kalpa.

79

27

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,81,705/-  
Earnest Money :- 10,000/-  
Time :- One month

Name of work:- Restoration of rain damages (PDNA) on Link road from Leo bridge to Hango Km. 0/00 to 16/00  
(SH:- C/O R/Wall in PCC at RD 3/200 to 3/240).

Sr. No.	Description of items	Qty.	In Fig.	Rate		Unit	Amount
				In Words			
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	28.08	₹ 261.70	Rupees Hundred Paise Seventy Only	Two SixtyOne	Per Cubic meter	₹ 7,349.00
2	Providing concrete for plain/reinforced concrete in open foundations, complete as per drawings and technical specifications Clause 802,803, 1202 &1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	76.18	₹ 6,057.00	Rupees Six FiftySeven Only	Thousand	Per Cubic meter	₹ 461,422.00
3	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	47.00	₹ 275.20	Rupees Hundred SeventyFive Paise Twenty Only	Two SeventyFive	Each	₹ 12,934.00
Total:-							₹ 481,705.00

Draft schedule of quantity approved for Rs. 481705.00 only

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

28

### DRAFT SCHEDULE OF QUANTITY

Estimated Cost :- 4,95,000/-  
Earnest Money :- 10,000/-  
Time :- Two Months

Name of work:- Restoration of rain damages on Link road from Leo Bridge to Hango Km. 0/00 to 16/00  
(SH:- Herring of JCB for removal of slips).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Hiring of One No. JCB in good condition, back Howe and front loader on hire charges basis at the site of work for removal of Snow/slips in all classification of soils dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	375.00	₹ 1,320.00	Rupees Thousand Hundred Only	Per Hours	₹ 495,000.00
<b>Total:-</b>						<b>₹ 495,000.00</b>

*Draft schedule of quantity approved for Rs. 4,95,000/-*

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa.

(18)

(39)

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost :- 1,79,105/-

Earnest Money :- 4,000/-

Time :- One Month

**Name of work:-** Special Repair to Type III (Set No. 1 & 2) Judicial Qtr. at Reckong Peo in Distric Kinnaur (H.P.)  
**(SH:-** Providing painting, wire gauge shutter and steel work thereof).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing 600x450mm beveled edge mirror of superior glass (of pproved quality) complete with 6 mm thick hard board groundfixed to wooden cleats with C.P. brass screws and washers complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 950.60	Rupees Nine Hundred Fifty Paise Sixty Only	Each	₹ 1,901.00
2	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	985.00	Rupees Nine Hundred EightyFive Only	Each	₹ 1,970.00
3	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete. 110 mm X 75 mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 1,305.90	Rupees One Thousand Three Hundred Five Paise Ninety Only	Each	₹ 2,612.00
4	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931:15 mm nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 957.60	Rupees Nine Hundred FiftySeven Paise Sixty Only	Each	₹ 1,915.00
5	Providing and fixing C.P. brass long nose bib cock single control of approved quality conforming to IS standards. 15mm nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 1,124.80	Rupees One Thousand One Hundred TwentyFour Paise Eighty Only	Each	₹ 2,250.00

6	Providing and fixing wall mixer. including cost of cutting and making good the walls and floors, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 4,500.00	Rupees Four Thousand Five Hundred Only	Each	₹ 9,000.00
7	Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 143.50	Rupees One Hundred FourtyThree Paise Fifty Only	Each	₹ 287.00
8	Distempereing with oil bound distemper of approved brand and manufacture (two coat) and of required shade on decorated wall surface to give an even shade over and including a priming coat with distemper of approved brand and manufacture after thoroughly brushing the surface free from mortar droppign an other foreign matter and also including preparing the surface even and sand papered smooth with priming coat with distemper primer. Synthetic/Acrylic distemper of asian brand or its equivalent, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	176.90	₹ 110.20	Rupees One Hundred Ten Paise Twenty Only	Per Square meter	₹ 19,494.00
9	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	88.20	109.35	Rupees One Hundred Nine Paise ThirtyFive Only	Per Square meter	₹ 9,645.00
10	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	176.90	₹ 105.20	Rupees One Hundred Five Paise Twenty Only	Per Square meter	₹ 18,610.00

11	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.600 mm (Six hundred millimeter) long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	₹ 588.90	Rupees Five Hundred EightyEight Paise Ninety Only	Each	₹ 1,178.00
12	Providing and fixing 18 mm thick, 150 mm wide pelmet of flat pressed 3 layer or graded wood particle board medium density grade I, IS : 3087 marked, including top cover of 6 mm commercial ply wood conforming to IS: 303 BWR grade, nickel plated M.S. pipe 20 mm dia ( heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. flat 10 cm long fixed to pelmet with hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.70	₹ 421.45	Rupees Four Hundred TwentyOne Paise FourtyFive Only	Per Running meter	₹ 10,831.00
13	Providing and fixing of curtain Gopala fabric cloth size not less than 1.00 mtr. x 2.50 mtr. product have a rich and colourfull style , bright skin texture , soft and easy to cleane , great luxurious , sweet comfortable and healthy envirmont with back side white lining cloth stitching.including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	36.00	710.20	Rupees Seven Hundred Ten Paise Twenty Only	Each	₹ 25,567.00
14	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85g. With wire of dia 0.56mm for doors, windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. 2nd class deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.70	₹ 3,450.60	Rupees Three Thousand Four Hundred Fifty Paise Sixty Only	Per Square meter	₹ 12,767.00
15	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.60	₹ 1,730.20	Rupees One Thousand Seven Hundred Thirty Paise Twenty Only	Per Square meter	₹ 21,801.00

16	Steel work welded in built up sections/ framed work of TATA, SAIL or RASHTRIYA ISPAT or its equivalent, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	324.60	₹ 121.00	Rupees One Hundred TwentyOne Only	Per Kilogram	₹ 39,277.00
Total:-						
₹ 179,105.00						

*Draft schedule of quantity approved for Rs. 179,105/- only*

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.

40


**SCHEDULE OF QUANTITY**

<b>Name of work:-</b> Restoration of rain damages on skibba Rispa road Km. 0/00 to 4/270 (SH:- Widening of narrow road by formation cutting between Km. 1/00 to 1/400).		Estimated Cost :- 4,93,785/- Earnest Money :- 10,000/- Time :- Unit :- One Month			
Sr. No.	Description of items	Qty.	Rate		Unit
			In Fig.	In Words	
1	<p>Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 303.014 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts as per PWD specifications and as per direction of the Engineer-in-charge.</p>	1527.80	₹ 323.20	Rupees Three Hundred TwentyThree Paise Twenty Only	Per Cubic meter
<b>Total in figures:-</b> <b>Total in words:-</b> Rupees Four Lakh NinetyThree Thousand Seven Hundred EightyFive Only					₹ 493,785.00
<b>Quoted Percentage rate upto three Digits :-</b> (+)/(-)					

Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD; Kalpa.

**SCHEDULE OF QUANTITY**

Name of work:-		Restoration of rain damages (PDNA) on Peo Karchham Shiiti road Km 0/00 to 11/635 (SH:- C/O R/Wall in PCC at RD 9/960 to 9/985, edge wall at RD 4/280 to 4/290 and crash barrier).		Estimated Cost :-	4,99,262/-	
				Earnest Money :-	10,000/-	
				Time :-	One Month	
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	22.22	₹ 261.70	Rupees Two Hundred SixtyOne Paise Seventy Only	Per Cubic meter	₹ 5,815.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	66.94	₹ 5,250.15	Rupees Five Thousand Two Hundred Fifty Paise Fifteen Only	Per Cubic meter	₹ 351,445.00
3	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.00	₹ 275.20	Rupees Two Hundred SeventyFive Paise Twenty Only	Each	₹ 12,934.00
4	Providing erecting type "A" W metal Crash barrier comprising of 3mm corrugated sheet metal beam rail 70cm above road/ ground level, fixed an ISMC series channel Vertical post 150x75x5 mm spaced 2 mtr c/c 1.80mtr high 1.1 mtr below ground level all steel parts and fitment to be galvanised by hot dip process, all fittings to conform to IS 1364 metal beam rail to be fixed on the vertical post with a space of channel section 150x75x5 mm 330 mm long complete as per clause 810, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	40.00	3226.70	Rupees Thousand Hundred Paise Seventy Only	Per Running meter	₹ 129,068.00
<b>Total in figures:-</b>						₹ 499,262.00
<b>Total in Words:-</b>						
<b>Quoted Percentage rate upto three Digits :-</b>			<b>Rupees Four Lakh NinetyNine Thousand Two Hundred SixtyTwo Only</b>			
			<b>(+)/( -)</b>			

  
**Executive Engineer,**  
**Kalpa Division (B&R),**  
**HP.PWD; Kalpa.**

