HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2025- 4969-70 Dated: - 27-11-2025

To

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2

Subject: - Publishing of tender Notice.

Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A (3) 1/2024 dated Shimla-2, the 03.01.2025 and Notification No. PWD-B-A0(3)/8/2025- 300858 dated 09.10.2025 regarding relaxation of existing guidelines, as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.

DA/ As above.

Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 8 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Date and time of receipt of applications for the tender form : **05.12.2025 up to 05.00 PM**
Date and time of issue/Sale of tender forms against cash Payment : **06.12.2025 (03.00 PM to 5.00 PM)**
Date and time of receipt of tenders : **08.12.2025 up to 11.00 AM**
Date and time of opening of tenders : **08.12.2025 at 11.30 AM**

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Repair & Restoration of Rain Damages link road Balmandir upper Marwari To Village Babehar km. 0/0 to 3/400, (SH- Construction of Breast wall at RD 2/880 to 2/910 LHS and Breast wall at RD 2/945 to 2/970 RHS) Under PDNA 2023	318790.00	6400.00	Three Month	350-	Class-D
2	Restoration of Rain Damages on link road to Village Chatehar Bouhal Ambota Km 0/0 to 1/0, (SH:- C/O Wire Crate Wall at Km 0/200 to 0/230) Under PDNA 2023	258006.00	5200.00	Three Month	350-	Class-D
3	Repair & Restoration of Rain Damages Link road to village Kuthera Jaswalan km. 0/0 to 1/300, (SH- Construction of Retaining wall between RD 0/795 to 0/825) Under PDNA 2023	499742.00	10000.00	Three Month	350-	Class-D
4	Repair & Restoration of Rain Damages link road To Village Badhera Rajputan km. 0/0 to 1/300, (SH- Construction of Breast wall near House of Smt. Manpreet Kur in G.P. Badhera Rajputan at RD 1/200 to 1/230) Under PDNA 2023	228340.00	4600.00	Three Month	350-	Class-D
5	Repair & Restoration of Rain Damages link road from Badoh workshop to Bhatian wala km. 0/0 to 5/0, (SH- Construction of Retaining wall between RD 2/600 to 2/620) Under PDNA 2023	287610.00	5800.00	Three Month	350-	Class-D
6	Repair & Restoration of Rain Damages link road from Badoh workshop to Bhatian wala km. 0/0 to 5/0, (SH- Construction of Retaining wall between RD 2/630 to 2/640) Under PDNA 2023	99910.00	2000.00	Three Month	350-	Class-D
7	Restoration of Rain Damages on link road to Village Ganu Mandwara Km 0/0 to 2/0, (SH:- C/O Wire Crate Wall at Km 0/110 to 0/145 and 0/180 to 0/200 LHS) Under PDNA 2023	499930.00	10000.00	Three Month	350-	Class-D
8	Repair & Restoration of Rain Damages Daulatpur to Pirthipur Uperla Km 0/0 to 5/0, (SH:- C/O U Shape Drain between Km 0/950 to 1/100) Under PDNA 2023	354685.00	4900.00	Three Month	350-	Class-D

Cont. P-2

TERMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

No. PWD/DPD/CB-Tender/2025- 4962-68 **Dated: -** 27-11-2025

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.

Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025-4962-68 dated 27-11-2025 are required to be carried out immediately being emergent nature of work in the public interest.

Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

Job-1

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 318790/-
Earnest Money: Rs. 6400/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road Balmandir upper Marwari To Village Babehar km. 0/0 to 3/400, (SH- Construction of Breast wall at RD 2/880 to 2/910 LHS and Breast wall at RD 2/945 to 2/970 RHS) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	19.000 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	3420.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	82.500 Cubic metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	305250.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	46.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	10120.00
	TOTAL					318790.00
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-2

BILL OF QUANTITY

Estimate Cost :- Rs. 258006/-
Earnest Money :-Rs. 5200/-
Time Limit :- Three Month.

Name of Work:- Restoration of Rain Damages on link road to Village Chatehar Bouhal Ambota Km 0/0 to 1/0, (SH:- C/O Wire Crate Wall at Km 0/200 to 0/230) Under PDNA 2023

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings. including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	25.20 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	4536.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	86.40 Cubic metre	2800.00	Rupees Two Thousand Eight Hundred Only	Per Cubic metre	2,41,920.00
3	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor–Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	52.50 Cubic metre.	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	11550.00
	TOTAL					258006.00
	Quoted Rate in Figure		% above/below			
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-3

DRAFT BILL OF QUANTITY

Estimated Cost: **Rs. 499742/-**
Earnest Money: **Rs. 10000/-**
Time Limit : **Three Month**

Name of Work:- Repair & Restoration of Rain Damages Link road to village Kuthera Jaswalan km. 0/0 to 1/300, (SH- Construction of Retaining wall between RD 0/795 to 0/825) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	38.400 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	6912.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	125.100 Cubic metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	462870.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	56.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	12320.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	25.200 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	17640.00
	TOTAL					**499742.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job – 4

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 228340/-
Earnest Money: Rs. 4600/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road To Village Badhera Rajputan km. 0/0 to 1/300, (SH- Construction of Breast wall near House of Smt. Manpreet Kur in G.P. Badhera Rajputan at RD 1/200 to 1/230) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	19.500 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	3510.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	59.100 Cubic metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	218670.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	28.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	6160.00
	TOTAL					**228340.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-5

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 287610/-
Earnest Money: Rs. 5800/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road from Badoh workshop to Bhatian wala km. 0/0 to 5/0, (SH- Construction of Retaining wall between RD 2/600 to 2/620) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	24.000 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	4320.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	71.700 Cubic metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	265290.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	36.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	7920.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	14.400 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	10080.00
	TOTAL					**287610.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-06

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99910/-
Earnest Money: Rs. 2000/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages link road from Badoh workshop to Bhatian wala km. 0/0 to 5/0, (SH- Construction of Retaining wall between RD 2/630 to 2/640) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	7.920 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	1426.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORD technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	24.440 Cubic metre	3700.00	Rupees Three Thousand Seven Hundred Only	Per cubic metre	90428.00
3	Providing weep holes in brick masonry/plain /reinforced concrete abutments, wing wall/ return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diamere PVC pipe make of D-Plast/Relpipe, working pressure not less then 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre) , extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	16.000 Number	220.00	Rupees Two Hundred Twenty Only	Each	3520.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORD technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	6.480 Cubic metre	700.00	Rupees Seven Hundred Only	Per cubic metre	4536.00
	TOTAL					**99910.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job - 7

BILL OF QUANTITY

Estimate Cost :- Rs. 499930/-
Earnest Money :-Rs. 10000/-
Time Limit :- Three Month.

Name of Work:- Restoration of Rain Damages on link road to Village Ganu Mandwara Km 0/0 to 2/0, (SH:- C/O Wire Crate Wall at Km 0/110 to 0/145 and 0/180 to 0/200 LHS) Under PDNA 2023

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	47.88 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	8618.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) dia GI wire conforming to IS:280 and IS:4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rates including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	164.16 Cubic metre	2950.00	Rupees Two Thousand Nine Hundred Fifty Only	Per Cubic metre	4,84,272.00
3	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor–Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royality, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	32.00 Cubic metre.	220.00	Rupees Two Hundred Twenty Only	Per cubic metre	7040.00
	TOTAL					499930.00
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

Job-8

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 354685/-
Earnest Money: Rs. 4900/-
Time Limit : Three Month

Name of Work:- Repair & Restoration of Rain Damages Daulatpur to Pirthipur Uperla Km 0/0 to 5/0, (SH:- C/O U Shape Drain between Km 0/950 to 1/100) Under PDNA 2023

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	63.80 Cubic metre	180.00	Rupees One Hundred Eighty Only	Per cubic metre	11484.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete, M-10 Grade (M-Ten) Nominal mix 1:3:6 (one cement isto three sand isto six graded crushed stone aggregate 20mm (Twenty millimeter) nominal size) in or under water in open foundations and the like for all types of structures, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water, for all heights/depths and any quantum of water, including cost of form work and curing complete as per drawing and MORD technical specification section 800, 900 & 1200 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate including Royality, Malkhana, Octroi, Goods Service tax, toll tax, sale tax or any other taxes imposed by the Government.	81.93 Cubic metre	4100.00	Rupees Four Thousand One Hundred Only	Per cubic metre	335913.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade-M25 (M-Twenty Five) designed mix with minimum cement contents of 400 kgs. (four hundred kilograms) per cubic meter with 20mm (Twenty millimeter) nominal size graded crushed stone aggregate in drain slab and the like up to all heights, including cost of form work and curing complete but excluding the cost of reinforcement for Reinforced work as per drawing and as per CPWD specification 2019 complete and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royality, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.55 Cubic metre	6050.00	Rupees Six Thousand Fifty Only	Per cubic metre	3328.00
4	Supplying fitting and placing HYSD bar reinforcement in super structure complete as per drawing and MORTH technical specifications section 1600 and 2300 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any heights as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts. The rate including of Octroi, Royality, Malkhana, Toll Tax, Sale Tax or other Taxes imposed by the Government.	44.00 Kg	90.00	Rupees Ninety Only	Per Kilogram e	3960.00
	TOTAL					**354685.00**
	Quoted Rate in Figure	% above/below				
	Quoted Rate in Words					

Executive Engineer,
HPPWD Division,
Daulatpur Chowk.