

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2025-26- 12482  
To

Dated:- 19.11.2025

✓ The Executive Engineer(IT) Cell,  
HP.PWD,Nirman Bhawan, Nigam Vihar,  
HP.PWD,Shimla-2.


**Subject:                    Regarding publication of Tender notice on department website.**

Sir,

With reference to the notification issued by the secretary (PW) to the Government of Himachal Pradesh No. PBW(B) A(3)I/2024 dated 03/01/2024 & further corrigendum on dated 08/01/2025. Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

**Certified that the work mentioned in the Tender Notice are urgenet in nature.**

DA:- As above

  
Executive Engineer,  
Dharampur Division,  
HP.PWD. Dharampur.

## H.P P W D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

### TENDER SCHEDULE:

- 1 **Date and time of receipt of application for the tender form :** 27-11-2025 upto 4.00 PM
- 2 **Date and time of issue of tender form :** 28-11-2025 upto 4.00 PM
- 3 **Date and time of receipt of tenders:** 29-11-2025 upto 11.00 AM
4. **Date and time of opening of tenders:** 29-11-2025 upto 11.30 AM


The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr. No.	Name of work	Estimated cost ( In Rs.)	Earnest Money(In Rs.)	Time	Eligible Class of Contractor
1	Construction of Staff quarter PHC Cholthra Tehsil Dharampur Distt. Mandi (HP) (SH:- Construction of Balance work of Two No. Type Two Quater)	62,172/-	1300/-	Two Month	"D"
2.	Construction of Link Road from main road Sakoh up to Near House of Sunder Singh Village Sakoh (SH:- Construction of PCC E/wall at RD 0/072 to 0/076, and P/L Cement Concrete pavement at RD 0/0 to 0/019) Under Deposit VKV/2024/1736	94,636/-	1900/-	Two months	"D"
3.	Restoration of Rain damages on various roads under Cholagrah Section HPPWD Sub-Division Tihra (SH:- Deployment/Hiring of Tipper for removal of alnd slide/slips)	94,500/-	2000/-	Two months	"D"
4.	Construction of Link road to Harizan Basti Saklana(SH:-Providing and Laying Cement Concrete pavement 0/0 to 0/030) Under Deposit	95,907/-	2000/-	Two Months	"D"

### Terms and Conditions:-

- 1 The contractors/firms should posses the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (Vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under-signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.

4. The contractor will give affidavit that he has not two or more works in hand for execution, failing which the application shall be rejected.
5. The offer of the tender shall remain valid upto 60 days after the opening.
6. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).


  
Executive Engineer,  
Dharampur Division,  
HP.PWD, Dharampur,  
Distt: Mandi (H.P)

No.PW-DPD-CB-Tender/2025-26/

Dated:-

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer , Hamirpur Zone HP.PWD ,Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur .
3. The Executive Engineer (IT) O/o Engineer-In Chief HPPWD Shimla through [email-eeict-pwd-shi@hp.gov.in](mailto:eeict-pwd-shi@hp.gov.in) & [ee-pwd-hp@nic.in](mailto:ee-pwd-hp@nic.in) for uploading the same on HPPWD web portal.
4. Notice Board.
5. A/B, D/B. Of this office.

  
Executive Engineer,  
Dharampur Division,  
HP.PWD, Dharampur,  
Distt: Mandi (H.P).

**DRAFT SCHEDULE OF QUANTITY**

work :- Construction of staff Quarter PHC Cholthara Tehsil Dharampur Distt. Mandi (H.P.) (Sh :-Construction of work of Two No. Type Two Quarter)

Estimated cost :- 62712  
Earnest Money:- 1300

Time Limit Two month

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
15mm (fifteen millimetre)cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(Eighty millimetre ) in girth and finished even and smooth. in cement mortar 1:6 ( One Cement : Six Sand) in all floor level including carriage of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	35.2	285	Rupees Two Hundred EightyFive Only	Per Square metre	10032
15mm (fifteen millimetre)cement plaster in single coat on the fair side of brick/concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm(Eighty millimetre ) in girth and finished even and smooth. in cement mortar 1:6 ( One Cement : Six Sand) in all floor level including carriage of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	52.98	270	Rupees Two Hundred Seventy Only	Per Square metre	14305
Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth tetetra complete as per HP.PWD specification. 100 mm ( One hundred millimetres) spread thickness (finished work including materials and labour) upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	3.00	1175	Rupees One Thousand One Hundred SeventyFive Only	Per Cubic metre	3525
Providing and laying cement concrete plain/ reinforced concrete 1:3:6 (One cement : three sand : six graded stone aggregate) 40mm (forty millimeter) in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP,PWD technical specification with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	3.00	4950	Rupees Four Thousand Nine Hundred Fifty Only	Per Cubic metre	14850

114  
58

<p>Providing and fixing 15mm (Twenty millimetres) nominal bore to wall ceiling and floor galvanized mild steel tubes Medium (Medium) of Jindal Make tube fitting and clamps including making good the wall ceiling and floor upto all heights including entire carriage of material with in all leads and lifts and as per drawings and technical specifications and the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.</p>	80.00	250	Rupees Two Hundred Fifty Only	Per Running metre	20000
				Total	62712

*Draft schedule of work approved for  
 Rs. 62712/- Vide No. 114/2025-26*

*[Signature]*  
 Executive Engineer,  
 Dharampur Division  
 H.P.W.D., Dharampur

105/62


**DRAFT SCHEDULE OF QUANTITY**

Work :- Construction of link road from main road Sakoh up to near House of Sunder singh Village Sakoh  
 construction of PCC E/wall at RD 0/072 to 0/076, and P/L Cement Concrete Pavement at Rd 0/0 to 0/019) under  
 t VKV/2024/1736

Estimated cost :- 94636  
 Earnest Money:- 1900  
 Time Limit Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
2	3	4	5	6	7
Earthwork in excavation in all kinds classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	0.70	250	Rupees Two Hundred Fifty Only	Per Cubic metre	175
Providing and laying cement concrete 1:5:10 ( One cement: Five sand: Ten graded crushed stone aggregate 40mm (Forty millimeters) Nominal size as per PWD specification in all heights and curing complete including cost of form work in retaining wall/ breast walls with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.78	4375	Rupees Four Thousand Three Hundred SeventyFive Only	Per Cubic metre	16538
Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutment, wing wall and return wall with 100mm ( One Hundred millimetres ) dia PVC pipe extending through the full width of structure with slope of 1:20 ( One vertical twenty horizontal ) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7 including entire carriage of material with in all leads lifts and technical specifications as per the direction of Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1.00	175	Rupees One Hundred SeventyFive Only	Per Running metre	175
Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per HP.PWD specification. 100 mm ( One hundred millimetres) spread thickness (finished work including materials and labour) upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.12	1175	Rupees One Thousand One Hundred SeventyFive Only	Per Cubic metre	10716

<p>Construction of un-reinforced, and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43(Forty three) grade cement or any other type as per Clause 1501.2.2 M25 ((Grade) minimum cement not less than 400 kg/ cum (Four hundred kilogramme per cubic metre) (mix design with plasticizer), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, ( Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum ( Zero point two) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days.( Fourteen days) using curing compound ( where specified ) and water finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.</p>	9.12	7350	Rupees Seven Thousand Three Hundred Fifty Only	Per Cubic metre	67032
<p><i>Draft schedule of quantity approved for</i>  <i>RS.44636/- vide S.O.No. 1052025-16</i></p>				Total	94636

  
 Executive Engineer,  
 Dharampur Division  
 H.P.P.W.D., Dharampur

183  
52

**DRAFT SCHEDULE OF QUANTITY**

Work :- Restoration of rain damages on various roads under Cholangrah Section HPPWD Sub Division Tihra  
 Employment (Hiring of Tipper for removal of land slide /slips)

Estimated cost :- 94500  
 Earnest Money:- 2000

Time Limit Two Months

Description of item/Sub Head	Quantity	Rates		Unit	Amount
		In Figure	In words		
		4	5		
2 Hiring of tipper for disposal of excavated material from cutting having capacity of 5.50 cum (Five point five cubic metre) Per trip and minimum 70 Km (Seventy kilometre) of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30.00	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per Day	94500
				Total	94500

*Draft schedule of quantity approved  
 Rs. 94500/- vide s/n No. 183/2025/26*

*[Signature]*  
 Executive Engineer,  
 Dharampur Division  
 H.P.W.D., Dharampur

187  
54

**DRAFT SCHEDULE OF QUANTITY**

Work :- Construction of link road to Harzen Basti Saklana (Sh:- Providing and laying Cement Concrete  
at 0/0 to 0/030) under Deposit.

Description of item/Sub Head	Quantity	Estimated cost :- 95907		Unit	Amount
		Earnest Money:- 2000			
		Time Limit Two month			
		Rates			
		In Figure	In words		
Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etcetra complete as per HP.PWD specification. 100 mm ( One hundred millimetres) spread thickness (finished work including materials and labour) upto all floor levels in all heights/ depth including entire carriage of material with in all leads lifts and technical specifications as per the direction by the Engineer-in-Charge and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	11.25	1175	Rupees One Thousand One Hundred SeventyFive Only	Per Cubic metre	13219
Construction of un-reinforced, and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43(Forty three) grade cement or any other type as per Clause 1501.2.2 M25 (Grade) minimum cement not less then 400 kg/ cum (Four hundred kilogramme per cubic metre) (mix design with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, ( Twenty five millimstre) mixed in a concrete mixer of not less than 0.2 cum ( Zero point two) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days,( Fourteen days) using curing compound ( where specified ) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	11.25	7350	Rupees Seven Thousand Three Hundred Fifty Only	Per Cubic metre	82688
				<b>Total</b>	<b>95907</b>

*Draft schedule of quantity approved*  
*Rs. 95907 / 187/2024*

Executive Engineer,  
Dharampur Division  
H.P.W.D., Dharampur