

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No:-PW-NCD-E-Tender- Publication/2025-26- 6088-95

Dated:- 4.11.2025

To

✓ The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: -

Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Principal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(36 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.

Copy to Account Branch in this office.

Copy to Drawing Branch in this office.

Notice Board.

✓
Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form **"6&8"** are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **13.11.2025 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 12.11.2025** and tender form will be issued on dated **13.11.2025 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Amblagaloo Ghadyater Sunder Nagar road km 0/0 to 13/600. (SH: Construction of wire crate R/wall at RD 5/891 to 5/896) (Under PDNA-2023).	86019	1600	350	Two Months	"D"
2	Restoration of rain damages on Ratti to Randhara road km 0/0 to 9/0. (SH: Construction of Breast wall at RD 5/030 to 5/036.70).	98131	2000	350	One Month	"D"
3	A/R & M/O various bridges under Chakkar Sub Division HPPWD Nerchowk (SH: - Painting work etc).	44502	1000	350	One Month	"D"
4	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH: Hiring of Tipper for carriage of muck & patch work materials). Nerchowk Section.	97600	2000	350	Two Months	"D"
5	Restoration of rain damages on Chandyal to Chhatru via Shishal Trambi road KM 0/0 to 6/0 (SH: C/o R/wall at RD 0/0 to 0/012)	95382	2000	350	Two Months	"D"
6	C/o Skill Centre National Emergency Life Support (NELS) for SLBSGMC & H at Nerchowk, Distt. Mandi (SH: Preparation of working estimate for preparation of working estimate for C/o National Emergency Life Support (NELS)).	99500	2000	350	Two Months	"D"
7	RRD on various roads under Rewaslar Sub Division HPPWD Rewalsar (Leda Section) (SH: Hiring of Tipper for carriage of muck and patch work material).	96000	2000	350	Two Months	D
8	Restoration of rain damages on Galma Manjhyali road KM 0/0 to 9/0 (SH: Providing B/wall at RD 1/308 to 1/313). (under PDNA-2023).	93635	1900	350	Two Months	D
9	Restoration of rain damages caused by laying of OFC on Shimla Mandi via Tattapani road KM 181/400 to 186/200 (SH: Providing and laying cement concrete paver block in KM 186/173 to 186/181).	99820	2000	350	Two Months	D
10	A/R & M/O various roads under the jurisdiction of Nerchowk Sub Division (SH: Hiring of JCB for removal of slips and other various work) Nerchowk Section.	99000	2000	350	Two Months	D
11	Restoration of rain damages on various roads under the jurisdiction of Chakkar Sub Division, HPPWD Nerchowk (SH: Hiring of Tipper for carriage of material for removal of slips and patch work and other various work) Ratti Section.	99200	2000	350	Two Months	D
12	RRD on various roads under Rewaslar Sub Division HPPWD Rewalsar (SH: Hiring of JCB for clearing of debris drain and dressing of berms etc.).(Rewalsar Section)	88000	2000	350	One Month	D
13	Repair and maintenance of SLBSGMC&H at Nerchowk, Distt. Mandi (HP) (SH: Providing and fixing grating (main gate of Hospital).	99219	2000	350	Two Months	D

14	RRD on various roads under Rewaslar Sub Division HPPWD Rewaslar (Sardhwar Section) (SH: Hiring of Tipper for carriage of muck and patch work material).	96000	2000	350	Two Months	D
15	Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Saayah KM 0/0 to 2/500 (SH: Providing and laying CC paver block in KM 2/125 to 2/131.50).	95801	2000	350	One Month	D
16	Restoration of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk (Ratti Section) (SH: Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).	99000	2000		One Month	D
17	A/R & M/O Shree Lal Bahadur Shastri Medical College & Hospital Nerchowk, Distt. Mandi (HP) (SH: Preparation of working estimate for painting and distempering work in Nursing College, Nursing Students Hostel building, Auditorium and Intern Hostel).	99500	2000	350	Two Months	"D"
18	Restoration of rain damages on various roads under Rewaslar Sub Division HPPWD Rewaslar (SH: Hiring of JCB for clearing of debris drain and dressing of berms etc.). (Sardhwar Section)	99000	2000	350	One Month	D
19	Restoration of rain damages caused by laying of OFC on Shimla Mandi via Tattapani road KM 181/400 to 186/200 (SH: Providing and laying cement concrete paver block in M 186/165 to 186/173).	99176	2000	350	Two Months	D
20	Restoration of rain damages on various roads under Chakkar Sub Division (SH: Hiring of JCB for removal of slips, dressing of berms and clearing of road side drains etc.) (Ratti Section).	99000	2000	350	Two Months	D
21	Restoration of rain damages on various roads under Gagal Section, Chakkar Sub Division, HPPWD Nerchowk (SH: Hiring of Tipper for carriage of muck/debris etc.).	96000	2000	350	Two Months	D
22	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Nerchowk Section) (SH:- Supplying and stacking at site stone aggregate G-III 53mm to 22.4mm for repair of pot holes)	93015	1900	350	15 days	D
23	Restoration of rain damages on various roads Under Chakkar Sub Division, HPPWD Nerchowk (Gagal Section) (SH: Hiring of JCB for removal of slips, Clearance of drains and dressing of berms etc.)	95700	2000	350	One Month	D
24	Annual Repair and maintenance of non-residential buildings of SLBSGMC&H at Nerchowk, Distt. Mandi (HP) (SH: Supply and stacking Accessories items for repair and maintenance work).	99144	2000	350	Two Months	D
25	Restoration of rain damages on link road Rajgarh to Koyla Mata Mandir KM 0/0 to 1/920 (SH: C/o B/wall in PCC 1:5:10 at RD 1/415 to 1/419.80).	97624	2000	350	Two Months	D
26	Restoration of rain damages on link road from Lohara to Rinz KM 0/0 to 0/405 (SH: Repair of pot holes in KM 0/0 to 0/405).	88424	1800	350	One Month	D
27	Restoration of rain damages on Ghour Nallah to Dusra Khabu road KM 0/0 to 6/0 (SH: C/o PCC Retaining wall at RD 3/830 to 3/834.74)	99645	2000	350	Two Months	D
28	Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Saayah KM 0/0 to 2/500 (SH: Providing and laying CC paver block in KM 2/131.50 to 2/138).	95024	2000	350	One Month	D
29	A/R & M/O various roads under Rewaslar Sub Division, HPPWD Rewaslar (Rewaslar Section) (SH: Supplying and stacking at site stone aggregate G-III 53mm to 22.4mm for repair of pot holes).	98280	2000	350	15 days	D
30	Restoration of rain damages on Ghour Nallah to Dusra Khabu road KM 0/0 to 6/0 (SH: C/o PCC Retaining wall at RD 3/155 to 3/163)	99040	2000	350	Two Months	D
31	Restoration of rain damages on Kansa bridge under Chakkar Sub Division, HPPWD Nerchowk, Distt. Mandi (HP) (SH: Painting work on various bridges under Chakkar Sub-Division).	74535	1500	350	One Month	D

32	Restoratoion of rain damages on Majhyali Ghour Sardhwar upto Batahan road km 0/0 to 13/0. (SH:- Repair of Pot holes in km 11/500 to 13/0).	98123	2000	350	One Months	D
33	Construction of Link road from Damka Samloun Galma Pargipul Bag Sidhkothe Beri Samlehar Badhkari Tarwai road KM 0/0 to 2/660 (SH: Providing and laying G-I soling in various reaches in KM 0/0 to 0/135)	99338	2000	350	One Month	D
34	A/R & M/O Chandigarh Mandi Manali road (Old NH-21) (SH: Painting of Dadour bridge).	99468	2000	350	One Month	D
35	Restoration of rain damages on Gutkar Behna Tikker road KM 0/0 to 5/500 and Behna Ropa Baridhar road KM 0/0 to 5/00 (SH: Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).	99000	2000	350	One Month	D
36	Restoration of rain damages on Majhyali Ghour Sardhwar upto Batahan road km 0/0 to 13/0. (SH:- supply and stacking crushed stone aggregate 53mm to 22.4 mm in km 11/500 to 13/0)	90470	2000	350	One Month	D
37	Restoration of rain damages on Mandi Gagal Chailchowk road KM 0/0 to 16/190 (SH: Removal of slips at various RDs).	96511	2000	350	One Month	D
38	Restoration of rain damages on Sardhwar to Bharedka Nalu road km 0/0 to 1/800. (SH:- Repair of pot holes in km 1/0 to 1/800).	99573	2000	350	One Month	D

Note:- The Contractors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT NO 22 for the Year 2015-26

①

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Amblagaloo Ghadyater Sunder Nagar road km. 0/0 to 13/600.
(SH:- Construction of wire crate R/wall at RD. 5/891 to 5/896) (Under PDNA-2023)

Estimated Cost:- 86019.00

Earnest Money :- 1600.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.12	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	4339.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.65	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	79632.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1.95	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	2048.00
					Total	86019.00

Draft schedule of quantity checked & approved for Rs 86,019/-
(Rupees Eighty Six Thousand and Nineteen only)

Executive Engineer,
HPPWD Division,
HPPWD Nerchow

2

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti to Randhara road km. 0/0 to 9/00. (SH:- Construction of Breast wall at RD. 5/030 to 5/036.70)

Estimated Cost:- 98131.00

Earnest Money :-	2000.00
------------------	---------

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	11.99	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	2062.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	8.24	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2365.00
3	Stone masonry in cement mortar in substructure complete as per drawing & technical specification clause 702, 704, 1202 and 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.72	3650.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	61028.00
4	Construction of dry rubble stone masonry for retaining and Breast walls as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.56	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	32676.00
					Total	98131.00

Draft Schedule of Quantity approved for Rs 98/31/- only
(Rupees Ninety Eight Thousand and Hundred Thirty one Paise)

Executive Engineer,
HPPWD Division,

HPPWD Nerchowlo

DNT No 10 for the year 2025-26

(3)

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various bridges under Chakkar Sub Division HPPWD Nerchowk. (SH:- Painting work etc.)

Estimated Cost:- 44502.00
Earnest Money :- 1000.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure	In word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete with in all leads, lifts, carriage of materials and other incidentals and as per the entire satisfaction and direction of Engineer-in-Charge.	346.97	11.15	Ruppes Eleven and paise fifteen only.	Per square Metre	3869.00
2	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre (Fifty gramme per litre) and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. Old work (Two or more coats applied @ 1.67 litre/ 10 sqm (one point six seven litre per ten square metre) Over and including priming coat of exterior primer applied @ 2.20 litre/10 sqm (Two point two zero litre per ten square metre) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	178.20	73.85	Ruppes Seventy three and paise Eighty five only.	Per Square Metre	13160.00
3	Painting with black anti-corrosive bitumastic paint of approved brand and manufacture to give an even shade one or more coats on old work complete with in all leads, lifts, carriage of materials and other incidentals and as per the entire satisfaction and direction of Engineer-in-Charge.	168.77	66.90	Ruppes Sixty Six and paise Ninety only.	Per Square Metre	11291.00
4	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eight zero litre per ten square metre) of approved brand and manufacture including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	180.00	89.90	Ruppes Eighty nine and paise ninety only.	Per square metre	16182.00
					Total	44502.00

Draft Schedule of Quantity checked and approved Jaks 44502 only.
C.B. Forty Four Thousand Five Hundred Two Only.Executive Engineer,
HPPWD Division
Nerchowk

DNIT No (2)

For the Year 2025-26

(1)

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division H.P.PWD Nerchowk

Rs.2000/-

(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Nerchowk Section)

Estimated Cost 97600/-
Earnest Money
Time:- Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	32 Days	3050.00	Rupees Three thousand Fifty only	Per Days	97600.00
Total -						97600.00

Draft Schedule of Quantity approved for Rs 97600 only.

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

DRAFT Sr. No. 90 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chandyal to Chhatru via Shishai Trambi road km. 0/0 to 6/00 (SH:- Construction of R/wall at Rd. 0/0 to 0/012).

Sl. No.	Item Description	Quantity	Unit	Estimated Cost:-		Earnest Money Cost:-	
				Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words	
1	2	3	4	5	6	7	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.68	Per cubic metre	287.00	1343.00	Rupees One Thousand Three Hundred FourtyThree Only	
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.36	Per cubic metre	4895.00	89872.00	Rupees EightyNine Thousand Eight Hundred SeventyTwo Only	
3	Backfilling with granular material behind abutment wing wall and return wall complete as per drawings & technical specification clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.78	Per cubic metre	1102.50	4167.00	Rupees Four Thousand One Hundred SixtySeven Only	
TOTAL:-					95382.00	Rupees NinetyFive Thousand Three Hundred EightyTwo Only	

Draft schedule of quantity checked & approved for Rs. 95,382/- only (Rs. Ninety Five Thousand Three Hundred Eighty Two only).

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT Sr.No. (19) for the year 2025-26

6

Estimated Cost:- Rs. 99500/- only
Earnest Money Cost:- Rs. 2,000/- only

Time:- Two Months

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- Construction of Skill Centre National Emergency Life Support (NELS) for SLBGMC & H at Nerchowk, Distt Mandi

(SH:-Preparation of working estimate for Preparation of working estimate for C/O National Emergency Life Support (NELS))

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P.	Total amount without GST in Rs. P.	Total amount without GST in words
1	Preparation of working estimate for Construction of Skill Centre National Emergency Life Support (NELS) for SLBGMC & H at Nerchowk, Distt Mandi. The Job shall also include supplying detailed estimate as per analysis of rates on based on HPSR 2020 /market rates for all the items appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office / Circle office /CE office (MZ) Mandi complete as per directions of Engineer-in-charge.	3	4	5	7	8
1		1 Job	Per Job	99500.00 ₹	99,500	Rupees Ninety nine thousand five hundred only

Draft schedule of quantity checked & approved for Rs. 99,500/- only
(Rs. Ninety Nine Thousand Five Hundred only)

Executive Engineer
Nerchowk Division
H.P. PWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

MIT S.O. No. (68) for 2025-26

Name of work:- RRD on various roads under Rewalsar Sub Division HPPWD
Rewalsar. (Leda Section) (SH: Hiring of Tipper for carriage of muck & patch work material).

Estimated Cost:- 96000.00
Earnest Money:- 2000.00
Time:- Two Month

S. No	Description of item	Qty.	Rate with in all taxes including GST in Rs.		Unit	Amount
			Figure	Words		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer - in - Charge . The Tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the contractor. The fuel of the Tipper , driver , repair work shall have to be born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer - in Charge .	30.00	3200.00	Rupees Three thousand two hundred only.	Per day	96000.00
Total						96000.00

Draft Schedule of Quantity checked and approved for Rs 96000/- only
(Rupees Ninety Six Thousand only)

1

1

Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

DNIT Ser.No. (112) for the year-2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Galma Manjhyali road km. 0/00 to 9/00 (SH:- Providing B/wall at RD. 1/308 to 1/313). (Under PDNA-2023)

Sl. No.	Item Description	Quantity	Unit	Estimated Cost:-		Total amount with all taxes including GST in words
				Earnest Money Cost:-		
				Time:- Two Months		
				Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	
1	2	3	4	5	6	7
1	Earth work in excavation of foundation of structure as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.60	Per cubic metre	287.00	1607.00	Rupees One Thousand Six Hundred Seven Only
2	Providing And Laying Concrete for Plain / Reinforced Concrete in open Foundations complete as per Drawing and technical specification clauses 802,803, 1202, and 1203 (PCC Nominal mix 1:5:10, Parapets) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.39	Per cubic metre	4895.00	90019.00	Rupees Ninety Thousand Nineteen Only
3	Providing Weep holes in Brick masonry / Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.00	Nos.	287.00	2009.00	Rupees Two Thousand Nine Only
TOTAL:-					93635.00	Rupees NinetyThree Thousand Six Hundred ThirtyFive Only

I Draft schedule of quantity checked & approved for Rs. 93,635/- only.
(Rs. Ninety Three Thousand Six Hundred Thirty Five only).

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNT No 77 For The Year 2025-26 DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages caused by laying of optical fiber cable on Shimla Mandi via Tattapani road km. 181/400 to 186/200. (SH.- Providing and laying cement concrete paver block in km. 186/173 to 186/181).

Sl. No.	Item Description	Quantity	Units	Estimated Cost:-		
				Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1						
2						
1	Providing and laying factory made chamfered edge cement concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size /shape, made by tablevibratory method using PU mould, laid in equired colour & pattern over 50mm thick compacted bed of sand, compacting and proper mbedding/laying using platre vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80mm thick C.C. paver block of M-30 grade with approved colour design and pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	62.00	Per Square Meter	1610	99820.00	Rupees Ninety/Nine Thousand Eight Hundred Twenty Only
TOTAL:-					99820.00	Rupees Ninety/Nine Thousand Eight Hundred Twenty Only

Draft Schedule of Quantity appeared for Rs 99820/-
Rupees Ninety Nine Thousand Eight Hundred Twenty Only,

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT No 78 For the year 2015-16 (10)

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O various roads under the jurisdiction of Nerchowk Sub - Division (SH:- Hiring of JCB for removal of slips and other various work) NERCHOWK section

Estimated cost :- Rs. 99,000/-
Earnest Money:- Rs. 2000/-

Sr.No	Description of item/Sub Head	Quantity		Rates		Unit	Time Limit Two month	Amount
			In Figure		In words			
1	Hiring of Excavator cum loader for removal of slips/debries with a minimum capacity of 45 (forty five) cubic metre per hour. The owner shall bear the expenses of P.O.L charges, repair of machinery, pay of driver and other expenses. Any accident and other damages to private and Govt. property and loss of life occurred during the working hour will be the whole responsibility of the owner of the machinery. The disposal of slips/ debries will be done by the owner of machinery to the disposal point within all leads, lifts and other incidentals as per the direction and entire satisfaction of the Engineer-in-Charge.	90	1100.00	Rupees	one thousand one hundred paise nil	per hour		99000.00

Draft Schedule of Quantity approved for Rs 99000/-
C Rupes Ninety Nine Thousand Only,

Total:- 99000.00

Executive Engineer,
Division Nerchowk,
HPPWD
AC

DNIT Sr.No. 99 for 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under the jurisdiction of Chakkar Sub Division, HPPWD Nerchowk. (SH:- Hiring of Tipper for carriage of material for removal of slips and patch work and other various work) Ratti Section.

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-	
				Earnest Money:-	99200.00
				Time:- Two Months	2000
				Rate with all taxes including GST in Rs. P.	
				In figure	In words
				3200.00	Rupees Three Thousand Two Hundred Only
					99200.00
1	Hiring of Tipper for carriage of premixed material for patchwork and shifting of patchwork material including carriage of excavated earth/ material generated during clearance of drain and removal of slips tipper having capacity of 5.50 cum per trip and minimum 70 km. of trip per day. The contractor/ owner of tipper shall bear the expensive of P.O.L. charges, repair of machinerries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer-in-Charge with in all lead and lifts.	31.00	Per Day		
TOTAL:-					99200.00

Drawl + Schedule of quantity checked & approved for Rs 99,200/- only
(Rs. Ninety Nine Thousand Two hundred only),

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

12

Name of work:- RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Rewalsar Section)

Time:- One month

Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the contractor. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the contractor. The repair and spare including watch and ward of J.C.B. also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.

2007

22

Executive Engineer
HPPWD Division
Nerchowk. 9

DNIT sr.No. (15) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Repair and Maintenance of SLBSCMC&H at Nerchowk, Dist. Mandi (HP) (SH:- Providing and fixing grating {main gate of Hospital}).

Estimated Cost:-	99219.00
Earnest Money :-	2000.00
Time :- Two Months	

S.No.	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Steel work welded in built up section/ framed work, including cutting hoisting fixing in pastia and applying a priming coat of approved steel primer using structural steel etc. as required in grating, frames guard bar, ladder, reallling, bracked gates and similar works including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	923.40	107.45	Rupees One Hundred Seven and Paise Forty only	Kilogrammes	99219.00
					Total	99219.00

Draft schedule of quantity checked and approved for Rs. 99,219/- only (Rs. Ninety Nine Thousand Two Hundred Ninety nine only).

DRAFT SCHEDULE OF QUANTITY

Draft Sr. No. (69) for 2025-26

**Name of work:- RRD on various roads under Rewalsar Sub Division HPPWD
Rewalsar.(Sardhwar section) (SH: Hiring of Tipper for cartage of muck & patch work material).**

**Estimated Cost:- 96000.00
Earnest Money:- 2000.00
Time:- Two Month**

S. No	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer - in - Charge . The Tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public / private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the contractor. The fuel of the Tipper , driver , repair work shall have to be born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer - in Charge .	30.00	3200.00	Rupees Three thousand two hundred only.	Per day	96000.00
Total						96000.00

*Draft Schedule of Quantity checked and approved for
(Rupees Ninety Six Thousand only)*

₹ 96000/- only

Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

DNIT Sr. No. (107) for the year 2025-26
DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Basti Saayah
km. 0/00 to 2/500 (SH:- Providing and laying CC Paver block in km. 2/125 to 2/131.50).

Sr. No.	Item Description	Quantity	Unit	Estimated Cost:-		
				Earnest Money Cost:-	Time:- One Months	
				Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic metre	5	6	7 Rupees Six Thousand Five Hundred Eighty Eight Only
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.63	Per cubic metre	2427	6383.00	Rupees Six Thousand Three Hundred Eighty Three Only
3	Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.36	Per cubic metre	5810	7902.00	Rupees Seven Thousand Nine Hundred Two Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.51	Per cubic metre	5247	18417.00	Rupees Eighteen Thousand Four Hundred Seventeen Only

15

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in equired colour & pattern over 50mm thick compacted bed of sand, compacting and proper mbedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	35.10	Per square metre	1610.00	56511.00	Rupees Fifty Six Thousand Five Hundred Eleven Only
	TOTAL:-				95801.00	Rupees Ninety Five Thousand Eight Hundred One Only

Draft schedule of quantity checked & approved for Rs. 95,801/- only (Rs. Ninety five thousand Eight hundred one only).

auth
Executive Engineer
Nerchowk Division
HPRWD Nerchowk

DRAFT schedule (82) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkarak Sub Division, HPPWD Nerchowk (Ratti Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs.		Amount
				Estimated Cost:-		
				Earnest Money:-		
				Time:- One Month		
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00	Rupees one thousand one hundred only.	99000.00
TOTAL:-						99000.00

Draft schedule of quantity checked and approved for Rs. 99,000 only (Rs. Ninety Nine Thousand only).



Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY (17) for the year 2025-26

Estimated Cost:- Rs. 99500/- only
Earnest Money Cost:- Rs. 2,000/- only

Time:- Two Months

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O Shree Lal Bhadur Shastri Medical College & Hospital Nerchowk, Distt. Mandi HP

(SH:-Preparation of working estimate for Painting and distempering work in Nursing College, Nursing Student hostel building, Auditorium and Intern Hostel)

Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P.	Total amount without GST in Rs. P.	Total amount without GST in words
1		3	4	5	7	8
1	Preparation of working estimate for Painting and distempering of non residential building i.e. Nursing College, Nursing Student hostel building, Auditorium and Intern Hostel. The job shall include preparation of detailed estimate after measuring inner and outer dimentions of the building very precisely. The estimate should be based on HPSR 2020/market rates for non scheduled items. The job work shall include supplying of estimate as per directions of Engineer in Charge.	1 Job	Per Job	99500.00 ₹	99,500	Rupees Ninety nine thousand five hundred only

Draft Schedule of quantity checked & approved for Rs. 99,500/- only
(Rs. Ninety Nine Thousand Five Hundred only).Executive Engineer
Nerchowk Division

H.P. PWD Nerchowk

DNT S.No (73) for the year 2025-26

(18)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD
Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.)
(Sardhwar Section)

Estimated Cost:-	99000.00
Earnest Money:-	2000.00

Time:- One month

S. No	Description of item	Qty.	Rate with all taxes including GST in Rs.		Unit	Amount
			Figure	Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the contractor. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the contractor. The repair and spare including watch and ward of J.C.B. also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1100.00	Rupees One thousand one hundred only.	Per hour	99000.00
Total						99000.00

Draft Schedule of Quantity approved for Rs. 99000/-
(Rupees Ninety Nine Thousand only).

Executive Engineer
HPPWD Division
Nerchowk.

DMT NO 75 For The Year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages caused by laying of optical fiber cable on Shimla Mandi via Tattapani road km. 181/400 to 186/200. (SH:- Providing and laying cement concrete paver block in km. 186/165 to 186/173).

Estimated Cost:-	99176.00
Earliest Money Cost:-	2000.00

Sl. No.	Item Description	Quantity	Units	Time:- Two Months		Total amount with all taxes including GST in words
				Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	
1	Providing and laying factory made chamfered edge cement concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size / shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper imbedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using platte vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80mm thick C.C. paver block of M-30 grade with approved colour design and pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	61.60	Per Square Meter	1610	99176.00	Rupees NinetyNine Thousand One Hundred SeventySix Only
TOTAL:-					99176.00	Rupees NinetyNine Thousand One Hundred SeventySix Only

Draft Schedule of Quantity approved for Rs 99176/-
 Papers Ninety Nine Thousand One Hundred Seventy Six Only.

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNIT Sr. No. 91 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

N.O.W.	SCHEDULE OF QUANTITY					Estimated Cost	99000
	Restoration of Rain Damages on various roads under Chakkar Sub division. (SH:- Hiring of JCB for removal of slips, dressing of Berms & Cleaning of roads side drain etc. (Ratti section))					Earnest Money	2000
S.No						Time Limit	2 month
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	Qty	Unit	Rate		Amount	
		90	Per hours	In figures	In words		
				1100	Rupees eleven hundred only	99000	

Best schedule of quantity checked and approved for Rs. 99,000/- only (Rs. Ninety Nine Thousand only).

Executive Engineer,
B&R Division,
HPPWD Nerchaik.

DNT Sd.No. 89 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Gagal Section, Chakkar Sub-Division, HPPWD Nerchowk (SH:- Hiring of Tipper for carriage of muck/debris etc.).

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				Earnest Money:-		
				Time:- One Month		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. The Tipper should work minimum 8.00 hours (Eight hours) from 9:00 AM to 5:00PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver, repair work shall have to be born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	30.00	Per Day	Rate with all taxes including GST in Rs. P.		96000.00
				In figure	In words	
				3200.00	Rupees Three Thousand Two Hundred Only	
TOTAL:-						96000.00

Prep schedule of quantity checked and approved for Rs. 96,000/- only.
(Rs. Ninety Six Thousand only).


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT Sr.No. (110) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O various roads under Chakkar Sub Division, HPPWD Nerchowk (Nerchowk Section). (SH:- Supplying and stacking at site stone aggregate G-III 53 mm to 22.4 mm for repair of pot holes).

Sl. No.	Item Description	Quantity	Unit	Estimated cost:-		Time:- 15 days	
				Estimated Rate in Rs. P.	Total amount with all taxes including GST in P. Rs.	Total amount with all taxes including GST in words	Estimated money cost:-
1	2	3	4	5	6	7	
1	Supplying and stacking at site graded, crushed stone aggregate 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) nominal size of hard stone free from disintegrated pieces of deleterious and organic matter including loading at crusher site and unloading at site of work with in all leads and lifts carriage of material and other incidentals complete in all respect.	53.00	Per cubic metre	1755.00	93015.00	Rupees Ninety Three Thousand Fifteen Only	93015.00
	TOTAL				93015.00	Rupees Ninety Three Thousand Fifteen Only	1900.00

draft schedule of quantity checked & approved for Rs. 93,015/- only (Rs. Ninety Three Thousand fifteen only).

Executive Engineer
Nerchowk Division
HPPWD Nerchowk


DRAFT Sr.No (184) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkara Sub Division, HPPWD Nerchowk (Gagal Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-	
				Earnest Money:-	95700.00
				Time:- One Month	2000.00
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	87.00	Per Hour	Rate with all taxes including GST in Rs. P.	
				In figure	In words
				1100.00	Rupees One Thousand One Hundred Only
					95700.00
TOTAL:-					95700.00

Draft schedule of quantity checked & approved for Rs. 95,700/- only (Rs. Ninety Five thousand seven hundred only).



AC

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Annual repair and maintenance of non-residential buildings of SLBSGM&H at Nerchowk, Distt. Mandi (HP) (SH:- Supply and Stacking Accessories items for repair and maintenance work.)

Estimated Cost:- 99144.00
Earnest Money :- 2000.00
Time :- Two Months

S.No.	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Supply and stacking of Vitrified Floor Tiles 600X600mm, approved brand (SOMANY/ KAJARIA etc.) and quality at site of work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	77.76	650.00	Rupees Six Hundred Fifty and paise Nil only	Per Square Metre	50544.00
2	Supply and stacking Below Counter Wash-Basin (Oval) 555X450X205 mm at site of work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge (Cascade NXT-C0407 White)- Parryware.	9.00	3000.00	Rupees Three Thousand and paise Nil only	Nos	27000.00
3	Supply and stacking at site clean coarse sharp sand free from dirt, dust disintegrated pieces, deleterious and organic matter in proper stacks at site including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	12.00	1800.00	Rupees One Thousand Eight Hundred and paise Nil only	Per Cubic Meter	21600.00
					Total	99144.00

Proof schedule of quantity checked and approved for Rs. 99,144/- only.
(Rs. Ninety Nine Thousand one hundred forty four only).

DRAFT Sr. No. (63) Jorha Year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road Rajgarh to Koyla Mata Mandir km. 0/00 to 1/920 (SH:- C/O B/wall in PCC 1:5:10 at RD. 1/415 to 1/419.80).

Sl. No.	Item Description	Quantity	Units	Estimated Cost:-	Total amount with all taxes excluding GST in words
				Earnest Money Cost:-	
				Time:- Two Months	
1	1	2	3	4	5
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5m and a lead upto 20m as per technical specification Clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.74	Per cubic metre	172.00	2535.00 Rupees Two Thousand Five Hundred ThirtyFive Only
2	Earth work in excavation for structures as per drawing and technical specifications clause 305 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and back filling in trenches with excavated suitable material, ordinary soil upto 3.00 mtrs depth including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.95	Per cubic metre	287.00	1708.00 Rupees One Thousand Seven Hundred Eight Only
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	21.55	Per cubic metre	4240.00	91372.00 Rupees NinetyOne Thousand Three Hundred SeventyTwo Only
4	Providing weep holes in brick masonry, stone masonry, plain or reinforced concrete abutments, wing walls and return wall with 100mm diameter PVC pipe extended through the full width of the structure with slope of IV:20 H towards draining face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.00	Each	287.00	2009.00 Rupees Two Thousand Nine Only
Total :-				97624.00	Rupees NinetySeven Thousand Six Hundred TwentyFour Only

Draft schedule of quantity checked and approved for Rs. 97,624/- only
C.R. Ninety seven Thousand six Hundred Twenty four only

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT Sr.No. (185) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on construction of link road from Lohara to Rinz km. 0/0 to 0/405 (SH:- Repair of pot holes in km. 0/00 to 0/405) Deposit work.

Estimated Cost:- 88424.00
Earnest Money Cost:- 1800.00

Sl. No.	Item Description	Quantity	Unit	Time:- One Months			Total amount with all taxes including GST in words
				Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs.		
1	2	3	4	5	6		7
1	Providing, laying, spreading and stone aggregate of specific size to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 kN static roller in stages to proper grade and camber, applying and brooming stone screening/binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density G-III as per technical specifications clause 405 by mechanical means including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.64	Per cubic metre	2427.00	20969.00		Rupees Twenty Thousand Nine Hundred SixtyNine Only
2	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat 20mm thick premix carpet and seal coat B specification clause 1904.2, 503 and 508.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	179.88	Per Square metre	375.00	67455.00		Rupees SixtySeven Thousand Four Hundred FiftyFive Only
	TOTAL:-				88424.00		Rupees EightyEight Thousand Four Hundred TwentyFour Only

I say + schedule of quantity checked & approved for Rs. 88,424/- only (Rupees Eighty Eight Thousand Four Hundred Twenty Four only)

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT Sr No 79 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ghour Nallah to Dusra Khabu road Km. 0/0 to 6/00.
(SH:- Construction of PCC Retaining wall at RD 3/830 to 3/834.74)

Estimated Cost:- 99645.00
Earnest Money :- 2000.00
Time :- Two Months

S.N 0	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.86	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	1969.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.76	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	91830.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	2.96	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	3263.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	9.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2583.00
Total						99645.00

Draft Schedule of Quantity checked & approved for ₹ 99645/- only
(Rs Ninety Nine thousand Six Hundred Forty Five only)

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

DNT Sr.No. (119) for the year 2025-26

Name of Work:- Restoration of rain damages on Ner Dhangu and link road from Chandyal to Saayah via SC Basti Saayah km. 0/00 to 2/500 (SH:- Providing and laying CC Paver block in km. 2/131.50 to 2/138).

Estimated Cost:-	95024.00
Earnest Money Cost:-	2000.00

Time:- One Month

Sr. No.	Item Description	Quantity	Unit	Rate including GST in Rs. P.	Total amount including GST in Rs. P.	Total amount with all taxes including GST in words
1	Construction of granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	4 Per cubic metre	5 1877	6 6532.00	7 Rupees Six Thousand Five Hundred ThirtyTwo Only
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.61	Per cubic metre	2427	6334.00	Rupees Six Thousand Three Hundred ThirtyFour Only
3	Cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.36	Per cubic metre	5810	7902.00	Rupees Seven Thousand Nine Hundred Two Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.48	Per cubic metre	5247	18260.00	Rupees Eighteen Thousand Two Hundred Sixty Only

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in equired colour & pattern over 50mm thick compacted bed of sand, compacting and proper mbedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge, 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	34.78	Per square metre	1610.00	55996.00	Rupees FiftyFive Thousand Nine Hundred NinetySix Only
	TOTAL:-				95024.00	Rupees NinetyFive Thousand TwentyFour Only

*Project Schedule of Quantity checked & approved for Rs. 95,024/- only
(Rs. Ninety Five Thousand Twenty Four only).*

and
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNT SxNo (80) for the year 2025-26

(29)

DRAFT SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O various roads under Rewalsar Sub Division, HPPWD Rewalsar (Rewalsar Section). (SH:- Supplying and stacking at site stone aggregate G-III 53 mm to 22.4 mm for repair of pot holes).						
				Estimated cost:-		98280.00
				Earnest money cost:-		2000.00
				Time:- 15 days		
Sl. No.	Item Description	Quantity	Unit	Estimated Rate in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
1	Supplying and stacking at site graded, crushed stone aggregate 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) nominal size of hard stone free from disintegrated pieces of deleterious and organic matter including loading at crusher site and unloading at site of work with in all leads and lifts carriage of material and other incidentals complete in all respect.	56.00	Per cubic metre	1755.00	98280.00	Rupees Ninety Eight Thousand Two Hundred Eighty only
	TOTAL				98280.00	Rupees Ninety Eight Thousand Two Hundred Eighty only

*Draft Schedule of Quantity checked & approved for ₹ 98280/- only
CRs. Ninety Eight thousand Two Hundred Eighty only.*

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

(Signature)

DRAFT SCHEDULE OF QUANTITY

DIT S.No 81 for the year 2025-26

Name of work:- Restoration of rain damages on Ghour Nailah to Dusra Khabu road Km. 0/0 to 6/00.
(SH: - Construction of PCC Retaining wall at RD 3/155 to 3/163)

Estimated Cost:- 99040.00
Earnest Money :- 2000.00
Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.68	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3352.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	18.43	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	90215.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	1.84	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	2029.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	12.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	3444.00
					Total	99040.00

Draft Schedule of Quantity checked and approved for ₹ 99040/- only
(Rs Ninety Nine Thousand Forty only)

Executive Engineer,
HPPWD-Division,
HPPWD Nerchowk

DNT ser.No. (101) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kansa bridge under Chakkar Sub Division, HPPWD Nerchowk, Dist. Mandi (H.P.) (SH:- Painting work on various bridges under Chakkar Sub-division).

Sl. No.	Item Description	Quantity	Unit	Estimated Cost:-			Total amount with all taxes including GST in words
				Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	Earnest Money Cost:-	
				Time:- One Month			
1	2	3	4	5	6		7
1	Finishing walls with Acrylic Smooth exterior paint of required shade. Old work (Two or more coat applied @1.67 ltr/10 sqm) on existing cement paint surface including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	532.04	Per cubic metre	128.75	68500.00		Rupees SixtyEight Thousand Five Hundred Only
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	541.23	Per cubic metre	11.15	6035.00		Rupees Six Thousand ThirtyFive Only
	TOTAL:-				74535.00		Rupees SeventyFour Thousand Five Hundred ThirtyFive Only

Draft schedule of quantity checked & approved for Rs. 74,535/- only (Rs. Seventy Four Thousand Five Hundred Thirty Five only)

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft Sr. box (27) for the year 2025-26 (32)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Manjhyali Ghour Sardhwar upto Batahan road km. 0/0 to 13/00.
(SH:- Repair of pot holes in km. 11/500 to 13/0)

Estimated Cost:- 98123.00
Earnest Money :- 2000.00

Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg./sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm.(One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in- Charge.	261.66	375.00	Rupees Three hundred seventy five and paise zero only.	Per Square Metre	98123.00
					Total	98123.00

Depth Schedule of quantity approved for ₹ 98123/- only.

DNT Sr.No. (117) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Construction of link road from Danka Samloun Galma Pargipul Bag Sidhkothe Beri Samlehar Badhkari Tarwai road km. 0/00 to 2/660 (SH:- Providing and laying G-I soiling in various reaches in km. 0/00 to 0/135).

Sr. No.	Item Description	Quantity	Unit	Estimated Cost:-		
				Time:- One Months	Earnest Money Cost:-	99338.00
				Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
1	Providing, Laying, spreading and compacting stone aggregate of specified sizes to WBM G-I specifications in uniform thickness, hand picking, rolling with 3 Wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	45.36	Per cubic metre	2190	99338.00	Rupees Ninety/Nine Thousand Three Hundred ThirtyEight Only
	TOTAL:-				99338.00	Rupees Ninety/Nine Thousand Three Hundred ThirtyEight Only

Draft schedule of quantity checked & approved for Rs. 99,338/- only (Rs. Ninety Nine Thousand Three Hundred Thirty Eight only).

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DIT Sr.No. (106) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali road (old NH-21) (SH:- Painting of Dadour bridge).

Sl. No.	Item Description	Quantity	Unit	Rate including GST P. Rs.	Total amount with all taxes including GST in Rs.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth exterior paint of required shade: Old work (Two or more coat applied @1.67 ltr/10 sqm) on existing cement paint surface including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	753.00	Per cubic metre	128.75	96949.00	Rupees NinetySix Thousand Nine Hundred FortyNine Only
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	225.90	Per cubic metre	11.15	2519.00	Rupees Two Thousand Five Hundred Nineteen Only
	TOTAL:-				99468.00	Rupees NinetyNine Thousand Four Hundred SixtyEight Only

Total + schedule of quantity checked & approved for Rs. 99468/- only
(Rs. Ninety Nine Thousand Four hundred sixty Eight only)

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DRAFT Sr.No. (115) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Gutkar Behna Tikkar road km. 0/00 to 5/500 and Behna Ropa Baridhar road km. 0/00 to 5/00. (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	99000.00
TOTAL:-						99000.00

Draft schedule of quantity checked & approved for Rs. 99,000/-only (Rupees Ninety Nine Thousand only)

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft No. 89 for the year 2025-26

(26)

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Manihyali Ghour Sardhwar upto Batahan road km. 0/0 to 13/00.
(SH:- Supplying and stacking crushed stone aggregate 53mm to 22.4 in km. 11/500 to 13/0)

Estimated Cost:- 90470.00
Earnest Money :- 2000.00
Time :- 15 days

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
1	Supplying and stacking at site crushed stone aggregate of 53mm to 22.4 mm (fifty three millimetre to twenty two millimetre) size of grading-III from approved quality free from all deleterious and other organic matter. The rate of loading, unloading and carriage of material from quarry to site of work and stacking in proper stacks along the road including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	51.55	1755.00		Rupees One thousand seven hundred fifty five and paise zero only.	Per cubic Metre
						90470.00
					Total	90470.00

Draft Schedule of quantity approved for 2 90470 only

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

DRAFT Sr.No. (114) for the year 2025-26
DRAFT SCHEDULE OF QUANTITY

(37)

Name of work:- Restoration of rain damages on Mandi Gagai Chaitchowk road km. 0/00 to 16/190 (SH:- Removal of slips at various Rd's).

Estimated Cost:- 96511.00
Earnest Money Cost:- 2000.00

Sl. No.	Item Description	Quantity	Unit	Time:- One Months		
				Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs.	Total amount with all taxes including GST in words
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any leads and lift as per technical specification clause 302.3.5 and 1611 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	923.55	Per cubic metre	104.50	96511.00	Rupees NinetySix Thousand Five Hundred Eleven
	TOTAL:-				96511.00	Rupees NinetySix Thousand Five Hundred Eleven Only

Draft schedule of quantity checked & approved for Rs. 96,511/- only
(Rupees Ninety Six Thousand Five Hundred Eleven only)

Executive Engineer
Nerchowk Division
HPPWD-Nerchowk

DNT Sr. No. 85 for the year 2025-26

38

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Sardhwar to Bhredka Nalu road km. 0/0 to 1/800. (SH:- Repair of Pot Holes in Km. 1/0 to 1/800)

Estimated Cost:- 99573.00
Earnest Money :- 2000.00

Time :- One Month

S.N o	Description of Item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Providing, laying, spreading and compacting stone aggregate of sizes 53mm to 22.40mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-III by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	3.49	2427.00	Rupees Two thousand four hundred twenty seven and paise zero only	Per Cubic Metre	8470.00
2	Providing and applying a primer coat with bitumen emulsion (SS-I) on prepared surface of granular base cleaned of dust and extraneous material with hydraulic broom or any other approved equipment and spraying primer at the rate of 0.70-1.00 Kg./Sqm. (zero point seven zero to one point zero zero kilogram per square metre) using mechanical means as per technical specification clause 502 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	46.53	64.00	Rupees Sixty four and paise zero only.	Per Square Metre	2978.00
3	Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300kg./sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm.(One point four six kilogramme per square metre) and seal coat at the rate of 0.58kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	235.00	375.00	Rupees Three hundred seventy five and paise seventy only.	Per Square Metre	88125.00
					Total	99573.00

Draft Schedule of quantity approved for ₹ 99,573/- only

Executive Engineer,
HPPWD Division
Narehwa