



Office 01783-260033

Email : ee-cho-hp@nic.in

No. PW.CHD.CB.E-9/2025-

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
INVITATION FOR BIDS (IFB)

10106-10155

Dated : 26/11/2025

NOTICE INVITING TENDER

Sealed percentage rate tenders are hereby invited by the Executive Engineer HPPWD Chopal District Shimla H.P. in form No. 6 & 8 on behalf of Governor of H.P for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors/firms or their representative who wish to be present.

TIME SCHEDULE OF TENDER

1. Date and time of receipt of application for tender form : 09.12.2025 up to 04:00 PM
2. Date and time of issue of tender form : 09.12.2025 04:00 PM to 05:00 PM
3. Date and time of receipt of tenders : 10.11.2025 11:00 AM
4. Date and time of opening of tender : 10.11.2025 11:30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms.

Sl. No	Name of Work	Estimated Cost	EMD	Cost of tender	Time Limit	Eligible class of contractor
1	R/R damages on Kiarnu Koti Sarain road km 0/0 to 7/300 (SH:- C/O 900mm dia HPC at RD 2/120)	488710.00	9800.00	350.00	One month	Class D
2	R/R damages on Kiarnu Koti Sarain road km 0/0 to 7/300 (SH:- C/O R/Wall at RD 3/900 to 3/919)	483743.00	9700.00	350.00	One month	Class D


TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.
11. The tender forms shall be issued to eligible contractors depending upon their past performance and work experience.
12. The contractor/firm having necessary documents and past adequate experience shall be preferred.

13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. If any kind of holiday to be happened, the tender documents shall be sold/opened on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.

CERTIFICATE

It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWDChopal
On behalf of Governor of H.P

Copy forwarded for information to :-

1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWDShimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division HPPWDChopal



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD.CB.C-9/2025- 10106-10155 dated
26/11/26 are urgent in nature.


Executive Engineer
Chopal Div. HPPWDChopal
On behalf of Governor of H.P.

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs.488710
Earnest money :	Rs. 9800
Time allowed :	One month

Name of work :- R/R damages on keyarnoo Koti to Sarain road KM 0/00 to 7/300.

(SH :- C/O hume pipe Culvert 900mm dia at RD 2/120) .

Sl.No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	82.19	210.00	Rupees two hundred ten and paisa zero only	Per Cubic Meter	17260
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.30	5200.00	Rupees five thousand two hundred and paisa zero only	Per Cubic Meter	17160
3	Providing and laying plain cement concrete 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40 mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	77.11	4500.00	Rupees four thousand five hundred and paisa zero only	Per Cubic Meter	346995
4	Providing and laying plain cement concrete 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate 20 mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curring complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.65	6000.00	Rupees six thousand and paisa zero only	Per Cubic Meter	57900

5	Providing and laying reinforcement cement concrete hume pipe 900mm dia np2 for culvert on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work back filling, concrete and masonry works in head walls and parapets clause 1108 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST 18% or other taxes imposed by the Government.	7.50	5338.07	Rupees five thousand three hundred thirty eight and paisa zero only	Per running Meter	40036
6	Providing weep holes in brick masonry/stone masonry plain/reinforced concrete abutment wingwall return wall with 100 mm dia PVC pipe extending through the full width of the structure with slopes of (1v):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST 18% or other taxes imposed by the Government.	46.80	200.00	Rupees two hundred and paisa zero only	NOS	9360
					Total	488710
	Quoted rate in figure.					
	Quoted rate in words.					

DNIT No..... For the year..25-26
Draft schedule of quantities duly
approved 488710 only
for Rs.....


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated cost :	Rs.483743
Earnest money :	Rs. 9700
Time allowed :	One month

Name of work :- R/R damages on keyamoo Koti to Sarain road KM 0/00 to 7/300.

(SH :- C/O R/Wall at RD 3/900 to 3/919).

Sl.No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains for all all kind of soil and ordinary rocks including dressing of sides ramming of bottoms upto all lifts including getting out the excavated soil and disposal of surplus excavated soil as leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	51.30	210.00	Rupees two hundred ten and paisa zero only	Per Cubic Meter	10773
2	Providing and laying plain cement concrete 1:4:8 (1 cement : 4 sand : 8 graded stone aggregate 20mm nominal dia mixing by machanical concrete mixing 0.4/0.28 cubic metre & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	85.79	5200.00	Rupees five thousand two hundred and paisa zero only	Per Cubic Meter	446108
3	Providing weep holes in brick masonry/stone masonry plain/reinforced concret abutment wingwall return wall with 100 mm dia PVC pipe extending throught the full width of the structure with slopes of i(v):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST 18% or other taxes imposed by the Government.	58.50	200.00	Rupees two hundred and paisa zero only	Per running Meter	11700
4	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	15.96	950.00	Rupees nine hundred fifty and paisa zero only	Per Cubic Meter	15162
DNIT No. For the year. 25-26						
Draft schedule of quantities duly approved					Total	483743
Quoted rate in figure.						
Quoted rate in words.						

HPPWD Chopal