HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 05-01-2026 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 05-01-2026 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender: 06-01-2026 at 10.30 AM.
4. Date of opening of Tender: 06-01-2026 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damage on Una Aghar Mandi road (SH:- C/O B/wall at RD 73/990 to 74/007) (PDNA)	97,498/-	2000/-	Two Months	Rs. 350/-	Class-D
2	Restoration of link road Kalahu More to Bhareri via Gudwin Bhukkar Beri Brahmna Sai Da Ghat Namlakh Jaroh road Km 0/00 to 7/720 (SH:- P/L interlocking paver block at RD 4/100 to 4/440 & 4/700 to 4/740) (PDNA)	4,86,008/-	10000/-	Two Months	Rs. 350/-	Class-D
3	Restoration of link road to Paplah km 0/00 to 2/420 (SH:- P/L interlocking paver block and V-shape drain in km 0/800 to 0/880)(PDNA)	4,94,628/-	10000/-	Two Months	Rs. 350/-	Class-D
4	R/M of Dungi Kanjian Dho road km 0/00 to 5/085 (SH:- Repair maintenance of earthen shoulder, C/O unlined surface drain at various RDs & removal slips)	99,587/-	2000/-	Two Months	Rs. 350/-	Class-D
5	R/M of Panjot to Dharyara road km 0/00 to 4/500 (SH:- Repair maintenance of earthen shoulder, C/O unlined surface drain at various RDs)	99,481/-	2000/-	Two Months	Rs. 350/-	Class-D

6	R/M of Awahdevi Bhamnoh road km, 0/00 to 2/800 (SH:- maintenance of earthen shoulder ,unlined surface drain and removal of slips at various RDs)	99,143/-	2000/-	Two Months	Rs. 350/-	Class-D
7	R/M of Samirpur to Bagwara via Samlehra km 0/00 to 2/200 (SH:- Maintenance of earthen shoulder , unlined surface drain and removal of slips at various RDs)	99,714/-	2000/-	Two Months	Rs. 350/-	Class-D
8	Restoration of Amroh Chandruhi link road km 0/00 to 4/00 (SH:- C/O R/wall at RD 0/357 and interlocking paver block at RD 0/450 to 0/490 and V-shape drain) (PDNA)	3,24,051/-	7000/-	Two Months	Rs. 350/-	Class-D
9	A/R & M/O of RCC Box Girder Bridge at Chamboh and foot Bridge 35.00 mtrs span at Nihar (SH:- Providing and layhing fixing of Inauguration/ Foundation Pedestal i/c Granite stone plate)	99,600/-	2000/-	Two Months	Rs. 350/-	Class-D
10	R/M of Various roads under Samirpur Sub –Division HPPWD Division Bhoranj (Section Chamboh) (SH:- Maintenance of earthen shoulder, Unlined Surface Drain and Removal of Slips	99,537/-	2000/-	Two Months	Rs. 350/-	Class-D
11	R/R damages on Dasmal to Kot Kangri road km 0/00 to 3/550 (Jahu Section) (Maintenance of earthen shoulder km 0/00 to 3/550)	99,496/-	2000/-	Two Months	Rs. 350/-	Class-D
12	R/R damages on various road under Sub Division Bhoranj (SH:- Dressing of site berms etc) in Bhoranj & Patta Section	99,845/-	2000/-	Two Months	Rs. 350/-	Class-D
13	R/R damages on various road under Sub Division Bhoranj (SH:- Dressing of site berms etc) in Bhoranj & Patta Section	99,800/-	2000/-	Two Months	Rs. 350/-	Class-D
14	Repair & maintenance of Dungi Kanjian Dho road km 0/00 to 5/050 (SH:- Maintenance of earthen shoulder , unlined surface drain & removal of slips at various RDs)	99,477/-	2000/-	Two Months	Rs. 350/-	Class-D
15	Restoration of link road vety Houspital to Amroh via Jaroh km 0/00 to 2/00 (SH:- C/O R/wall at RD 0/220 to 0/240) PDNA	4,91,040/-	10000/-	Two Months	Rs. 350/-	Class-D
16	Repair & maintenance of Panjot to Bagwara via Lalyar road Km 0/00 to 4/200 (SH:- Maintenance of earthen shoulder , unlined surface drain & removal of slips at various RDs)	99,643/-	2000/-	Two Months	Rs. 350/-	Class-D

17	Restoration of link road vety Hospital Bhareri to Amorh via Jaroh km 0/00 to 2/000 (SH:- C/O R/wall at RD 0/800 to 0/810, U/V shape drain at various portion) PDNA	4,90,629/-	10000/-	Two Months	Rs. 350/-	Class-D
18	R/R damages on Una Aghar Mandi road km 79/00 to 91/00 (SH:- C/O R/wall at RD 90/500 to 90/518)(PDNA)	4,99,303/-	10000/-	Two Months	Rs. 350/-	Class-D
19	C/O link road to House of Sh. Ranvir Singh from Main Footpath Samshanghat km 0/00 to 0/050 Village Seu, P.O. Kharwar (SH:- C/O R/wall & Cement Conc. Pavement at RD 0/00 to 0/025.) (VKV/2024/542)	2,86,246/-	6,000/-	Two Months	Rs. 350/-	Class-D
20	R/R damages on Hamirpur Jahu road Km 16/500 to 21/780 (Tarkawari to Kehrawin chowk) (SH:- Repair & Maintenance of earthen shoulder , C/O unlined surface drain in Km 18/00 to 19/500)	99,950/-	2000/-	Two Months	Rs. 350/-	Class-D
21	C/O link road to Lower Dadu Km 0/00 to 1/630 (SH:- C/O R/wall PCC 1:5:10 at RD 1/480 to 1/493)	97676/-	2000/-	Two Months	Rs. 350/-	Class-D
22	Restoration on Dadu Chatrial road Km 0/00 to 1/250 (SH:- P/L interlocking Paverblock at RD 1/130 to 1/200)(PDNA)	4,90,970/-	10000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj
For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2025- 15498-15538 Dated:- 29-12-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, NirmanBhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD,Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj ,Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damage on Una Aghar Mandi Road (SH:- C/O B/wll at RD 73/990 to 74/007) (PDNA)

					Estimated Cost	Rs 97,498/-
					Earnest Money	Rs. 2000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	3.76	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.48	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	15.04	Per Cubic Meter			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	12.00	Each			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road Kalahu More to Bhareri via Gudwin Bhukkar Bori Brahmna Sai Da Ghat namlakh Jaroh road km. 0/00 to 7/720. (SH:- P/L interlocking paver block at RD 4/100 to 4/440 &4/700 to 4/740).(PDNA)

Estimated Cost Rs 486008/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.20	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.00	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	240.00	Per Square Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of link road to Paplah Km. 0/00 to 2/420.(SH:-P/L interlocking paver block and V-shape drain in Km.0/800 to 0/880).(PDNA)

Estimated Cost Rs 494628/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	37.20	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.40	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.60	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	244.00	Per Square Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Dungi Kanjain Dho Road km 0/00 to 5/085(SH:- Repair maintenance of earthen shoulder, C/O Unlined Surface drain at Various RDs & removal of Slips.).

Estimated Cost Rs 99,587/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1012.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	260.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	60.00	Per cubic metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HR PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Panjot to Dharyara Road km 0/00 to 4/500(SH:- Repair maintenance of earthen shoulder, C/O Unlined Surface drain at Various RDs).

Estimated Cost Rs 99,481/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1092.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	286.00	Per Running Mtr.			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhora Division
HPPWD Bhorani

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Awahdevi Bamnoh road km. 0/00 to 2/800.
(SH:- Maintenance of earthen shoulder , unlined surface drain and Removal of Slips at various RD'S.)

Estimated Cost Rs. 99143/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	977.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	600.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/M of Samirpur to Bagwara via Samlehra km. 0/00 to 2/200.
(SH:- Maintenance of earthen shoulder , unlined surface drain and Removal of Slips at various RD'S.)

Estimated Cost Rs. 99714/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1005.25	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	540.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of Amroh Chandruhi link road km 0/00 to 4/00 (SH:- c/o r/wall at RD 0/357 and interlocking paver block at RD 0/450 to 0/490 and v shape drain) PDNA.

					Estimated Cost	Rs 324051/-
					Earnest Money	Rs. 7000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	17.40	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	14.85	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.80	Per Cubic Meter			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	90.00	Per Square Meter			
5	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	25.20	Per Cubic Meter			
6	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.80	Per Cubic Meter			
7	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	47.50	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/M of Various roads under Samirpur Sub Division HPPWD Division Bhoranj (Section Chamboh) (SH:- Maintenance of earthen shoulder, Unlined Surface drain and Removal of Slip)

Estimated Cost Rs 99,537/-
Earnest Money Rs. 2000/-
Time 2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	734.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	198.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	260.00	Per Cubic metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damage on Dasmal to Kot Kangri Road Km 0/00 to 3/550 (Jahu Section).
(SH:- Maintenance of Earthen Shoulder Km 0/00 to 3/550).

Estimated Cost Rs 99496/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularlion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carrriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1193.00	Per square metre			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Dungi Kanjain Dho Road Km 0/00 to 5/050
(SH:- Maintenance of earthen shoulder , unlined surface drain & removal of slips at various R.D.S).

Estimated Cost Rs. 99,477/-
Earnest Money 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1050.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	405.00	Per Running Mtr.			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Repair & Maintenance of Panjot to Bagwara via Lalyar Road Km. 0/00 to 4/200.
(SH:- Maintenance of earthen shoulder , unlined surface drain & removal of slips at various R.D.S).

Estimated Cost Rs. 99,643/-
Earnest Money 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1018.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	500.00	Per Running Mtr.			

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: R/R Damages on Una Aghar Mandi road km. 79/00 to 91/00. (SH:- C/O R/Wall at RD 90/500 to 90/518.) (PDNA)

Estimated Cost Rs 4,99,303/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	36.54	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	105.45	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	29.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.49	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: C/O Link road to House of Sh. Ranvir Singh from Main Footpath Samshanghat km 0/00 to 0/050. Village Seu ,P.O Kharwar (SH:- C/O R/Wall & Cement Conc. Pavement at RD 0/00 to 0/025.) (VKV/2024/542)

Estimated Cost Rs 2,86,246/-
Earnest Money Rs. 6000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.02	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.54	Per Cubic Meter			
3	Providing and laying cement concrete 1:4:8 (1cement :4:sand : 8 graded stone aggregates 40mm nominal size) and curing complete including cost of form work in foundation and plinth.as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.25	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.25	Per Cubic Meter			
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	16.00	Each			
6	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.02	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: C/O Link road Chhatrial to lower dadu km. 0/00 to 1/630.(SH:- C/O R/Wall PCC 1:5:10 at RD 1/480 to 1/493.)

Estimated Cost Rs 97676/-
Earnest Money Rs. 2000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.20	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.15	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.07	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration on Dadu-Chatrial road km. 0/00 to 1/250.(SH:- P/L interlocking paverblock at RD 1/130 to 1/200). (PDNA)

Estimated Cost	Rs 4,90,970/-
Earnest Money	Rs. 10000/-
Time	2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	63.21	Per Cubic Meter			
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-ChargeWith material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	36.75	Per cubic Meter			
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade M_{-10}(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.50	Per cubic metre			
4	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks ISI approved and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	210.00	Per square meter			
5	Providing and laying in position specified grade of reinforced cement concrete, encluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.84	Per Cubic Meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division