

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender- Publication/2025-26- 7805-12

Dated:- 26/12/25

To


The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest.


DA: - Notice Inviting Tender.
(25 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDER"

Sealed Percentage rate tenders on form "6&8" are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **06.01.2026 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 05.01.2026** and tender form will be issued on dated **05.01.2026 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-


Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- Repair of 6.00 mtr. span culvert at RD 0/200) Under PDNA-2023.	485054	9200	350	Two Months	"D"
2	Restoration of rain damages on Ratti Pairi Behal road km 0/0 to 8/000. (SH:- C/O PCC R/wall between km 1/640 to 1/652.35) Under PDNA-2023.	199182	4000	350	Two Months	"D"
3	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- Construction of PCC Retaining wall at RD. 5/780 to 5/790 & Breast wall at RD 5/385 to 5/395) Under PDNA-2023.	391464	8000	350	Two Months	"D"
4	Restoration of rain damages on Gurkotha Gadiyatar road km 0/0 to 8/200. (Sub Head:- Construction of PCC Retaining wall with 1:5:10 at RD. 5/315 to 5/330) Under PDNA-2023.	362986	7300	350	Two Months	"D"
5	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- Construction of PCC Retaining wall at RD. 2/390 to 2/400 & Breast wall at RD 1/310 to 1/321) Under PDNA-2023.	496103	10000	350	Two Months	"D"
6	Restoration of rain damages on Talyahar Pingla Thona Sarkaghat road km 11/0 to 22/645 (SH: - Repair of 6.00 mtr. RCC span culvert at RD. 15/235) Under PDNA-2023.	470239	9500	350	Two Months	"D"
7	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/0. (SH:- Construction of PCC R/wall at RD. 1/285 to 1/297) Under PDNA-2023.	365077	7400	350	Two Months	"D"
8	Restoration of rain damages on Chakkar to Challah road km 0/0 to 3/00. (SH:- C/O V-shape PCC drain at RD. 0/045 to 0/330, 1/125 to 1/585, 1/587 to 1/665 & 1/670 to 1/920). Under PDNA-2023	495559	10000	350	Two Months	"D"

9	Restoration of rain damages on Talyahar Pingla Thona Sarkaghat road km 11/0 to 22/645 (SH: - Repair of 2.00 mtr. RCC span culvert at RD. 15/735) Under PDNA-2023.	197355	4000	350	Two Months	"D"
10	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/158 to 4/165) Under PDNA-2023.	341016	7000	350	Two Months	"D"
11	Restoration of rain damages on Chandyal Kandi Tarapur Kharsi Mansa Mata Mandir road km 0/0 to 15/840. (SH:- C/O PCC Retaining wall with 1:5:10 at RD 10/800 to 10/805.20) Under PDNA-2023.	199659	4000	350	Two Months	"D"
12	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/150 to 4/158) Under PDNA-2023.	389979	8000	350	Two Months	"D"
13	Restoration of rain damages on Chakkar to Challah road km 0/0 to 3/00. (SH:- C/O 900 mm dia RCC hume pipe culverts at RD 0/390 & 2/100 and wing walls & C/O R/wall at RD 0/015 to 0/019). Under PDNA-2023	491026	9900	350	Two Months	"D"
14	Restoration of rain damages on Sidhyani to Khetri road km km 0/00 to 5/200. (SH:- Providing B/wall at RD. 4/600 to 4/615.50) Under PDNA-2023	259998	5200	350	Two Months	"D"
15	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/525 to 4/540) Under PDNA-2023.	288000	6000	350	Two Months	"D"
16	Restoration of rain damages on Majhyali Ghour Sardhwar upto village Batahan road km 0/0 to 13/0 (SH: C/o R/wall with PCC 1:5:10 at RD 5/745 to 5/753) under PDNA-2023.	150960	3100	350	Two Months	"D"
17	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/450 to 4/460 & B/wall at RD 4/060 to 4/072) Under PDNA-2023.	457677	9500	350	Two Months	"D"
18	Restoration of rain damages on Majhyali Ghour Sardhwar Kothigehri Batahan road km 0/00 to 13/00. (SH: C/O Retaining wall 1:5:10 at RD 8/325 to 8/340) under PDNA-2023.	263541	5300	350	Two Months	"D"
19	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 1/090 to 1/105, 4/072 to 4/080) Under PDNA-2023.	499327	10000	350	Two Months	"D"
20	Restoration of rain damages on Bhangrotu Nouru Mandal Tikkari road km 0/0 to 4/400. (SH:- Construction of R/wall at RD 1/755 to 1/767) Under PDNA-2023.	193074	3900	350	Two Months	"D"
21	Restoration of rain damages on Rati Meramasit Leda road km 0/0 to 14/580 (SH: Construction of PCC R/wall at RD 12/945 to 12/960) under PDNA-2023.	275880	5600	350	Two Months	"D"

22	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 0/740 to 0/752, 0/860 to 0/872) Under PDNA-2023.	411610	8500	350	Two Months	"D"
23	Restoration of rain damages on Majhyali Ghour Sardhwar Kothigehri Batahan road km 0/00 to 13/00. (SH: C/O Retaining wall 1:5:10 at RD 8/490 to 8/502) under PDNA-2023.	211133	4300	350	Two Months	"D"
24	Restoration of rain damages on Rewalsar Dhiundhar road km 0/0 to 6/00. (SH:- C/O PCC Retaining wall with 1:5:10 at RD 0/820 to 0/840) Under PDNA-2023.	450164	9100	350	Two Months	"D"
25	Restoration of rain damages on Galma to Majhyali road km 0/0 to 9/00. (SH:- C/O PCC R/wall at RD 1/060 to 1/075 & 0/045 to 0/060) Under PDNA-2023	486251	9800	350	Two Months	"D"

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Job No. 1


Draft Schedule of Quantity for the year 2025-26

Name of work:- Restoration of rain damages on Rewalsar Dhundhar road Km. 0/0 to 6/00.
(SH: - Repair of 6.90 mtr. span culvert at RD 0/200) Under PDNA 2023

Estimated Cost:- 485054.00
Earnest Money :- 9200.00
Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.60	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	3042.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	88.62	5247.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	464989.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.44	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	17023.00
Total						485054.00

Draft Schedule of Quantity checked and approved for ₹ 4,85,054/- only.
(Rs. Four Lakh Eighty Five Thousand Fifty Four only)


Executive Engineer,
HPBWD Division,
HPPWD, Merchowk

DNT SR.No. 163 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ratti Patti Behal road km. 0/0 to 8/000 (SH:- C/O PCC R/wall between km. 1/640 to 1/652.35) under PPDNA-2023.

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				Earnest Money:-	199182.00	
				Time:- Two Months		4000.00
				Rate with all taxes including GST in Rs. P.		
				In figure	In words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic meter	5	Rupees Two Hundred Eighty Seven only	176513.70
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.06	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	7088.9
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.70	Each	287.00	Rupees Two Hundred Eighty Seven only	10617.08
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.63	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	199182.00
TOTAL:-						199182.00

Draft schedule of quantity checked & approved for Rs. 1,99,182/- only
 Rs. one Lakh Ninety Nine Thousand one Hundred Eighty Two only


 Executive Engineer
 Nerchowk Division
 IPWD Nerchowk

Job No. 2

DRAFT Sr No (124) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/0 to 6/00. (Sub Head :- Construction of PCC Retaining wall at RD. 5/780 to 5/790 & Breast wall at RD 5/385 to 5/395) Under PDNA-2023

Estimated Cost:- 391464.00

Earnest Money :- 8000.00

Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	19.90	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	3423.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.40	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	8151.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	74.20	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	363209.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	32.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	9184.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	6.80	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	7497.00
					Total	391464.00

Draft Schedule of Quantity approved for ₹ 3,91,464/- only.
(Rs. Three Lakh Ninety One Thousand Four Hundred Sixty Four only)

Executive Engineer,
PCC Division
HPPNB Natchowal

DMIT Sr No (136) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Gurkotha Gadiyatar road km. 0/0 to 8/200.
 (Sub Head :- Construction of PCC Retaining wall with 1:5:10 at RD. 5/315 to 5/330) Under PDNA-2023

Estimated Cost:- 362986.00
 Earnest Money :- 7300.00
 Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	43.35	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	12441.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	68.87	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	337119.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	24.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	6888.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.93	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	6538.00
					Total	362986.00

Draft Schedule of quantity approved for ₹ 3,62,986/- only

Executive Engineer,
 H.P.W.D Division,
 H.P.P.W.D Narchowk

DMIT Sr No 120 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/0 to 6/00. (Sub Head :- Construction of PCC Retaining wall at RD. 2/390 to 2/400 & Breast wall at RD 1/310 to 1/321) Under PDNA-2023		Estimated Cost:- 496103.00				
		Earnest Money :- 10000.00				
		Time :- Two Months				
S.No	Description of item	Quantity	Rate with all taxes including GST in	Unit	Amount	
			Rs In figure			In word
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	21.89	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	3765.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge	33.25	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	9543.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	93.60	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	458172.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical is to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	42.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	12054.00
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause- 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.40	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	12569.00
		Total				496103.00

Draft Schedule of Quantity approved for ₹ 4,96,103/- only
(Rs. Four Lakh Ninety Six Thousand one Hundred Three only)

Executive Engineer,
HPPWD Division,
HPPWD, Merchowki

DNT Sr. No. (126) for the year 2025-26

Job No. 6

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Talhyar Pingla Thona Sarkaghat road Km. 1/10 to 22/645. (SH:- Repair of 6.00 mtr. RCC span culvert at RD. 15/235) Under PDNA-2023

Estimated Cost:- Rs. 470239.00
 Earnest Money :- Rs. 9500.00
 Time :- Two Months

S. No	Description of Item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	3	287.00	Rupees Two thousand eighty seven and paise zero only.	Per Cubic Metre	2563.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.40	5000.00	Rupees Five thousand and paise zero only.	Per Cubic Metre	42000.00
3	Providing and laying concrete mechanically mixed and vibrated mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain/reinforced concrete in abutments, open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.16	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	32149.00
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm (Six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads, lifts/depths or as per the entire satisfaction and direction of Engineer-in-Charge.	10.50	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	61005.00
5	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802.803, 1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.				Total	470239.00

Draft Schedule of quantity approved for ₹ 470,239/- only.

Executive Engineer,
 HEPWD Division,
 Noida

DRAFT SCHEDULE OF QUANTITY

DNIIT Sr No 17 for the year 2025-26

Name of work:- Restoration of rain damages on Rewalsar Dhuniidhar road Km. 0/0 to 6/0.
 (Sub Head : Construction of PCC R/wall at RD. 1/285 to 1/297) Under PDNA-2023

Estimated Cost:- 365077.00
 Earnest Money :- 7400.00
 Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	36.36	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	10435.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803,1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	69.71	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	341230.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204,3,8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.74	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	8533.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3,7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	17.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	4879.00
Total						365077.00

Draft Schedule of Quantity checked & approved for ₹ 3,65,077/- only
 (Rs. Three Lakh Sixty Five Thousand Seventy Seven only)

Executive Engineer,
 HPPWBD Division,
 HPPWD Nerchowk

DNIT Sr.No. (163) for the year 2025-26.

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chakkar Challah road km. 0/0 to 3/00 (SH:- Construction of V-shape PCC drain at RD. 0/045 to 0/330, 1/125 to 1/585, 1/587 to 1/665 & 1/670 to 1/920) under PDNA-2023.

Sr. No.	Description of Item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Estimated Cost:-Rs. Earnest Money:- Rs.	Time:- Two Months
				In Figure	In words		
1	Earth work in excavation of foundation of structures, as per Drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	118.03	Per Cum	287.00	Rupees Two Hundred Eighty Seven only	495559.00 10000.00	33875.00
2	Providing and laying concrete for plain/ reinforcement concrete in open foundation as per drawing and technical specification clause 802, 803, 1202 and 1203 PCC grade M-10 for nominal mix 1:3:6 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	87.99	Per Cum	5247.00	Rupees Five Thousand, Two Hundred Fourty Seven only	461684.00	461684.00
TOTAL							495559.00

Draft schedule of quantity checked and approved for Rs. 495559/- only.
(Rs. Four Lakh Ninety five thousand five hundred fifty nine) only.


Executive Engineer
Nerchowk Division
MPPWD Nerchowk

Vol No. 8

DNT S.No (128) for the year 2025-26

2025.9

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Talhyar Pingla Thona Sarkaghat road Km. 11/10 to 22/645. (SH:- Repair of 2.00 mtr. RCC span culvert at RD. 15/735) Under PDNA-2023

Estimated Cost:- Rs. 197355.00
Earnest Money :- Rs. 4000.00

Time :- Two Months

S. No	Description of item	Quantity	Rate with all taxes including GST in Rs.		Unit	Amount
			In figure	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3	287.00	Rupees Two thousand eighty seven and paise zero only.	Per Cubic Metre	1487.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:4:8 (one cement: four sand : eight graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.50	5000.00	Rupees Five thousand and paise zero only.	Per Cubic Metre	17500.00
3	Providing and laying concrete mechanically mixed and vibrated mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in abutments, open foundations and piers or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	29.57	5247.00	Rupees Five thousand two hundred forty seven and paise zero only.	Per Cubic Metre	155154.00
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm (Six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification Clause 1204.3.8 including carriage of material within all leads, lifts/depts or as per the entire satisfaction and direction of Engineer-in-Charge.	6.30	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	6946.00
5	Providing and laying plain/reinforced cement concrete in foundation/substructure as per drawing and technical specification clause 802, 803, 1202 and 1203 P.C.C nominal mix 1:2:4 (One cement: two sand: four graded stone aggregate) including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	2.80	5810.00	Rupees Five thousand eight hundred ten and paise zero only.	Per Cubic Metre	16268.00
Total						197355.00

Draft Schedule of Quantity approved for 197355/- only
(Rs. One Lakh Ninety Seven Thousand Three Hundred Fifty Five only.)

Executive Engineer,
HPPWD Division,
Nerchowki

DNIT SrNo (27) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

2025.10

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/158 to 4/165) Under PDNA-2023.
 Contract No: Estimated Cost:- Rs. 3,41,016/- only
 Earnest Money :- Rs.7,000/- only
 Time:- Two Months

St. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	41.51	Per cubic metre	287.00	11913.00	Rupees Eleven Thousand Nine Hundred Thirteen Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	64.54	Per cubic metre	4895.00	315923.00	Rupees Three Lakh Fifteen Thousand Nine Hundred TwentyThree Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.00	Each	287.00	4305.00	Rupees Four Thousand Three Hundred Five Only
4	Backfilling with granular material behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.05	Per cubic metre	1102.50	8875.00	Rupees Eight Thousand Eight Hundred SeventyFive Only
TOTAL:-					341016.00	Rupees Three Lakh FourtyOne Thousand Sixteen Only

Draft schedule of quantity approved for ₹ 3,41,016/- only.
 (Rs. Three Lakh Fourty one Thousand Sixteen only)

Executive Engineer
 Nerchowk Division
 HPPWD-Nerchowk

DRAFT NO (159) FOR THE YEAR 2025-26

24/8 No. 11

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Chandyal Kandi Tarapur Kharsi Mansa Mata Mandir road km 0/0 to 15/840. (SH:- C/O P.C.C. Retaining wall with 1:5:10 at RD 10/800 to 10/805.20) Under PDNA-2023

Estimated Cost:- 199659.00
 Earnest Money :- 4000.00
 Time :- Two Months

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	25.38	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	7284.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802,803, 1202 and 1203 in cement concrete 1:5:10 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	37.59	4895.00	Rupees Four thousand eight hundred ninety five and paise zero only.	Per Cubic Metre	184003.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical to twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	12.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	3444.00
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 Granular material and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.47	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	4928.00
					Total	199659.00

Right schedule of quantity checked & approved for Rs. 499,659/- (Rupees One lakh Ninety nine thousand Sixty Hundred Fifty Five) only.

Executive Engineer,
 HPPWD Division,
 PPWD Nerchowk

DNIT SrNo (129) for the year 2025-26

2025.10.12

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.
 Name of Works:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/150 to 4/158) Under PDNA-2023.
 Contract No: _____

Estimated Cost:- Rs. 3,89,979/- only
 Earnest Money :- Rs.8,000/- only
 Time:- Two Months

Sr. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious mater, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	4	5	6	7
1	2	4744	Per cubic metre	287.00	13615.00	Rupees Thirteen Thousand Six Hundred Fifteen Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	73.76	Per cubic metre	4895.00	361055.00	Rupees Three Lakh SixtyOne Thousand FiftyFive Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.00	Each	287.00	5166.00	Rupees Five Thousand One Hundred SixtySix Only
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.20	Cum	1102.50	10143.00	Rupees Ten Thousand One Hundred FortyThree Only
TOTAL:-					389979.00	Rupees Three Lakh EightyNine Thousand Nine Hundred SeventyNine Only

Draft schedule of Quantity approved for ₹ 3,89,979/- only.
 (Rs. Three Lakh Eighty Nine Thousand One Hundred Seventy Nine only)

Executive Engineer
 Nerchowk Division
 HPPWD-Nerchowk

DNIT NO (61) FOR THE YEAR 2025-26

2025 No.13

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chakkar to Challah road km 0/0 to 3/000. (SH:- C/o 900mm dia RCC Hume Pipe Culverts at RD 0/390 & 2/100 and wing walls & C/o R/wall at RD 0/015 to 0/019) Under PDNA-2023

Estimated Cost:- 491026.00
Earnest Money :- 9900.00

Time:- Two months

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs.		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	86.35	287.00	Rupees two hundred eighty seven and paise nil only	Per Cubic Metre	24782.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.40	5000.00	Rupees five thousand and paise ni only.	Per Cubic Metre	27000.00
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	17.27	5247.00	Rupees five thousand two hundred forty seven and paise nil only.	Per Cubic Metre	90616.00
4	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction of Engineer-in-Charge.	15.00	3550.00	Rupees three thousand five hundred fifty and paise nil only	Per Running Metre	53250.00
5	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	57.15	4895.00	Rupees four thousand eight hundred ninety five and paise nil only	Per Cubic Metre	279749.00

Sl. No.	Description of Item	Qty	Rate with all taxes including GST in Rs.		Unit	Amount
			In Figure	In words		
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	20.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	5740.00
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	6.24	1102.50	Rupees One thousand one hundred two and paise fifty only.	Per Cubic Metre	6880.00
8	Demolishing cement concrete manually /by mechanical mens including disposal of material within 50 metres lead as per direction of Engineer-in-Charge.	4.86	619.05	Rupees Six hundred Nineteen and paise zero five only.	Per Cubic Metre	3009.00
TOTAL						491026.00

Right schedule of quantity checked & approved for Rs. 4,91,026/-
Rupees Four Lakh Ninety One Thousand Twenty Six only.

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk


DNT Sr.No. (131) for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sidhyani to Khetri road km. 0/00 to 5/200 (SH:- Providing B/wall at Rd. 4/600 to 4/615.50) under PDNA-2023.

Sl. No.	Item Description	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	17.36	Per cubic metre	287.00	Rupees Two Hundred Eighty Seven Only	4982.32
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:5:10 (1 cement : 5 sand : 10 graded stone aggregate 40 mm nominal size including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	50.69	Per cubic metre	4895.00	Rupees Four Thousand Eight Hundred Ninety Five Only	248127.55
3	Providing and laying weep holes in stone, brick masonry, plain/reinforced concrete abutments/wing wall/return walls with breast walls and retaining walls with 100mm dia PVC pipe extending through the full with the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.00	Nos.	287.00	Rupees Two Hundred Eighty Seven Only	6888.00
TOTAL:-						259998.00

Draft schedule of quantity checked & approved for Rs. 2,15,9,998/- only
 Rs. Two Lacs Fifty Nine Thousand Nine Hundred Ninety Eight only


 Executive Engineer
 Narendrak Division
 HPPWD Nerchowk

DMIT Sono (131) for the year 2025-26

205 100. 15

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/525 to 4/540) Under PDNA-2023.
 Contract No: _____

Estimated Cost:- Rs. 2,88,000/- only
 Earnest Money :- Rs.6,000/- only
 Time:- Two Months

Sr. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slope and disposing of excavated earth with a lift and a lead upto 1000 mtr. as per technical specification clause 1603.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2985	Per cubic metre	172.00	5134.00	Rupees Five Thousand One Hundred ThirtyFour Only
2	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.00	Per cubic metre	287.00	4305.00	Rupees Four Thousand Three Hundred Five Only
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	55.50	Per cubic metre	4895.00	271673.00	Rupees Two Lakh SeventyOne Thousand Six Hundred SeventyThree
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204,3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.00	Each	287.00	6888.00	Rupees Six Thousand Eight Hundred EightyEight Only
TOTAL:-					288000.00	Rupees Two Lakh EightyEight Thousand Only

Draft Schedule of Quantity approved for ₹ 288,000/- only.
 (Rs. Two Lakh Eighty Eight Thousand only.)

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNT Sr No. 57 for the year 2025-26

22.11.15

PERCENTAGE RATE BILL OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP, PWD, Nerchowk.

Name of Work:- Restoration of rain damages on Manjhali Ghour Sardhwar upto village Batahan road km. 0/00 to 13/00 (SH:- C/O R/wall with PCC 1:5:10 at RD. 5/745 to 5/753) Under PDNA-

Contract No:

Estimated Cost:- Rs. 1,50,960/- only

Earnest Money Cost:- Rs. 3100/- only

Time:- Two Months

Sl. No.	Name of the Bidder/Bidding Firm/Company	Item Description	Quantity	Units	Rate including GST in P.	Total amount including GST in P.	Total amount with all taxes including GST in words
1		Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	17.84	Per cubic metre	287.00	5120.00	Rupees Five Thousand One Hundred Twenty Only
2		Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	28.41	Per cubic metre	4895.00	139067.00	Rupees One Lakh ThirtyNine Thousand SixtySeven Only
3		Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.00	Each	287.00	3157.00	Rupees Three Thousand One Hundred FiftySeven Only

4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.28	Per cubic metre	1102.50	3616.00	Rupees Three Thousand Six Hundred Sixteen Only
	TOTAL:-				150960.00	Rupees One Lakh Fifty Thousand Nine Hundred Sixty Only

Percentage rate bill of quantity checked and approved for Rs. 1,50,960/- only (Rs. one lakh Fifty Thousand Nine Hundred sixty only).

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DJIT S-110-133 for the year 2025-26

108 No. 17

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Rewalsar Diundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 4/450 to 4/460 & B/Wall at rd 4/060 to 4/072) Under PDNA-2023.
 Contract No: _____

Estimated Cost:- Rs.4,57,677/- only
 Earnest Money :- Rs.9,500/- only
 Time:- Two Months

Sl. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount including GST in Rs. P.	Total amount with all taxes including GST in words
1	Excavation in soil in Hilly area by mechanical means including cutting and trimming of side slope and disposing of excavated earth with a lift and a lead upto 1000 mtr. as per technical specification clause 1603.1 Including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	23.88	Per cubic metre	172.00	4107.00	Rupees Four Thousand One Hundred Seven Only
2	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	28.65	Per cubic metre	287.00	8223.00	Rupees Eight Thousand Two Hundred TwentyThree Only
3	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications as per direction and satisfaction of Engineer-in-Charge.	85.90	Per cubic metre	4895.00	420481.00	Rupees Four Lakh Twenty Thousand Four Hundred EightyOne Only
4	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614.7/09,1204.3.7 Including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	44.00	Each	287.00	12628.00	Rupees Four Lakh Twenty Thousand Four Hundred EightyOne Only
5	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.10	Cum	1102.50	12238.00	Rupees Twelve Thousand Two Hundred ThirtyEight Only
TOTAL:-					457677.00	Rupees Four Lakh FiftySeven Thousand Six Hundred SeventySeven Only

Draft Schedule of Quantity approved for ₹ 457677/- only.
 (B. Four Lakh FiftySeven Thousand Six Hundred SeventySeven only)

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DRAFT SMO (147) for the year 2025-26

2025.18

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP PWD, Nerchowk

Name of Work:- Restoration of rain damages on Majhyali Chau Sardhwar Kothigehri Barahan road km. 0/00 to 13/00 (SH:-C/O Retaining wall 1:5:10 at RD/8/325 to 8/340) Under PDNA-2023.

Contract No:

Estimated Cost:- Rs.2,63,541/- only

Earnest Money :- Rs.4,300/- only

Time:- Two Months

Sr. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	4 Per cubic metre	5 287.00	6 5060.00	7 Rupees Five Thousand Sixty Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	47.31	Per cubic metre	4895.00	231582.00	Rupees Two Lakh ThirtyOne Thousand Five Hundred EightyTwo Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	26.00	Each	287.00	7462.00	Rupees Two Lakh ThirtyOne Thousand Five Hundred EightyTwo Only
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	17.63	Per cubic metre	1102.50	19437.00	Rupees Nineteen Thousand Four Hundred ThirtySeven Only
TOTAL:-					263541.00	Rupees Two Lakh SixtyThree Thousand Five Hundred FourtyOne Only

Draft schedule of Quantity approved for ₹ 2,63,541/- only
(Rs. Two lakh sixty Three Thousand Five Hundred Fourty one only)

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft same 135 for the year 2025-26

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 1/090 to 1/105, 4/072 to 4/080) Under PDNA-2023.

Contract No: _____

Estimated Cost:- Rs.4,99,327/- only
 Earnest Money :- Rs.10,000/- only
 Time:- Two Months

Sr. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.63	Per cubic metre	287.00	10513.00	Rupees Ten Thousand Five Hundred Thirteen Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	91.30	Per cubic metre	4895.00	446914.00	Rupees Four Lakh FourtySix Thousand Nine Hundred Fourteen Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	45.00	Each	287.00	12915.00	Rupees Four Lakh FourtySix Thousand Nine Hundred Fourteen Only
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	26.29	Cum	1102.50	28985.00	Rupees TwentyEight Thousand Nine Hundred EightyFive Only
TOTAL:-					499327.00	Rupees Four Lakh NineThousand Three Hundred TwentySeven Only

Draft schedule of quantity approved for ₹ 4,99,327/- only.
 (Rs. Four Lakh Ninety Nine Thousand Three Hundred Twenty Seven only)


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DRAFT SR.No. (169) For the year 2025-26
DRAFT SCHEDULE OF QUANTITY


Job No. 20

Name of Work:- Restoration of rain damages on Bhangrotu Nauru Tikkari road km. 0/0 to 4/400 (SH:- C/O R/wall at RD. 1/755 to 1/767) under PDNA-2023.

Estimated cost:- 193074.00
Earnest Money Cost:- 3900.00
Time:- One Month

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST		Amount
				In figure	In words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	4822.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	35.06	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	171619.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	9.36	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	10319.00
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	22.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	6314.00
TOTAL:-						193074.00

Soft schedule quantity checked & approved for Rs 1,93,074/- only (Rs. One Lakh Ninety Three Thousand Seventy four only)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DMIT No 67 for the Year 2025-26

2025 No. 21

PERCENTAGE RATE BILL OF QUANTITY

Name of work:- Restoration of rain damages on Ratti Meramasit Leda road km. 0/00 to 14/580 (SH:-
Construction of PCC R/wall at RD. 12/945 to 12/960) Under PDNA-2023.

Sl. No.	Item Description	Quantity	Units	Rate Including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words	
							Estimated Cost:-
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-In-Charge.	20.55	Per cubic metre	287.00	5898.00	Rupees Five Thousand Eight Hundred and Ninety Eight only	
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-In-Charge.	51.45	Per cubic metre	4895.00	251848.00	Rupees Two Lakh Fifty One Thousand Eight Hundred and Forty Eight only	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-In-Charge.	10.20	Per cubic metre	1102.50	11246.00	Rupees Eleven Thousand Two Hundred and Forty Six only	
4	Providing weap holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-In-Charge.	24.00	Nos.	287.00	6888.00	Rupees Six Thousand Eight Hundred and Eighty Eight only	
Total :-						275880.00	Rupees Two Lakh Seventy Five Thousand Eight Hundred and Eighty only

Percentage Rate Bill of Quantity approved for Rs 275,880/-
Rupees Two Lakh Seventy Five Thousand Eight Hundred Eighty only.

Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Draft Sino (136) for the year 2025-26

Nov 12. 22

(114)

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 0/740 to 0/752,0/860 to 0/872) Under PDNA-2023.

Contract No:

Estimated Cost:- Rs.4,11,610/- only

Earnest Money :- Rs.8,500/- only

Time:- Two Months

Sr. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	26.40	Per cubic metre	287.00	7577.00	Rupees Seven Thousand Five Hundred SeventySeven Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	75.60	Per cubic metre	4895.00	370062.00	Rupees Three Lakh Seventy Thousand SixtyTwo Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614,709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	40.00	Each	287.00	11480.00	Rupees Three Lakh Seventy Thousand SixtyTwo Only
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification of Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.40	Cum	1102.50	22491.00	Rupees TwentyTwo Thousand Four Hundred NinetyOne Only
TOTAL:-					411610.00	Rupees Four Lakh Eleven Thousand Six Hundred Ten Only

Defect Schedule of Quantity approved for ₹ 411610/- only (Rs. Four Lakh Eleven Thousand Six Hundred Ten only.)

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DMIT Sino (145) for the year 2025-26

102 No. 23

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.
 Name of Work:- Restoration of rain damages on Majhyal Chauh Sardhwar Kohlgehr, Barahan road km. 0/00 to 13/00 (SH:- C/O Retaining wall 1:5:10 at RD/8/490 to 8/502) Under PDMA-2023.

Contract No: _____

Estimated Cost:- Rs.2,11,133/- only
 Earnest Money :- Rs.10,000/- only
 Time:- Two Months

Sl. No.	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including selling out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.10	Per metre cubic	287.00	4047.00	Rupees Four Thousand Fourty/Seven Only
2	Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	37.84	Per cubric metre	4895.00	185227.00	Rupees One Lakh Eighty/Seven Thousand Two Hundred Twenty/Seven Only
3	Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614/709,1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	22.00	Each	287.00	6314.00	Rupees One Lakh Eighty/Seven Thousand Two Hundred Twenty/Seven Only
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.10	Cum	1102.50	15545.00	Rupees Fifteen Thousand Five Hundred Fourty/Five Only
TOTAL:-					211133.00	Rupees Two Lakh Eleven Thousand One Hundred Thirty/Three Only

Draft Schedule of Quantity approved for ₹ 2,11,133/- only
 Rs. Two Lakh Eleven Thousand One Hundred Thirty Three only

Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DMIT Sarno (138) for the year 2025-26

2025.10.24

DRAFT SCHEDULE OF QUANTITY

Tender Inviting Authority: Executive Engineer, Nerchowk Division, HP.PWD, Nerchowk.

Name of Work:- Restoration of rain damages on Rewalsar Dhundhar road km. 0/00 to 6/00 (SH:- C/O PCC Retaining wall with 1:5:10 at RD. 0/820 to 0/840) Under PDNA-2023.

Contract No: Estimated Cost:- Rs.4,50,164/- only

Earnest Money :- Rs.9,100/- only

Time:- Two Months

Sr. No.	Name of the Bidder/Bidding Firm/Company	Item Description	Quantity	Units	Rate including GST in Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1		Earth work in excavation for foundation of structures upto as per drawing and technical specifications, including sealing out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, back filling the excavated earth to the extent required and utilizing the remaining earth locally for road work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	33.20	Per cubic metre	287.00	9528.00	Rupees Nine Thousand Five Hundred Twenty Eight Only
2		Providing and laying concrete for plain/ reinforced concrete in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 and 1203 (Nominal mix 1:5:10) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	83.00	Per cubic metre	4895.00	406285.00	Rupees Four Lakh Six Thousand Two Hundred Eighty Five Only
3		Providing weep holes in brick masonry/ stone masonry/ plain reinforced concrete abutments, wing walls, return wall with 100mm diameter PVC pipe extending through the full width of the structures with slope of 1(V):20 (H) towards drawing face complete as per drawing & technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	54.00	Each	287.00	15498.00	Rupees Four Lakh Six Thousand Two Hundred Eighty Five Only
4		Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	17.10	Cum	1102.50	18853.00	Rupees Eighteen Thousand Eight Hundred Fifty Three Only
		TOTAL:-				450164.00	Rupees Four Lakh Fifty Thousand One Hundred Sixty Four Only

Draft schedule of Quantity approved for ₹ 4,50,164/- only.
 (Rs. Four Lakh Fifty Thousand One Hundred sixty four only)

Executive Engineer
 Nerchowk Division
 HP.PWD Nerchowk

DNT ST. No. 170 for the year 2025-26
DRAFT SCHEDULE OF QUANTITY

108 No. 25

Name of Work:- Restoration of rain damages on Galma to Majhyali road km. 0/0 to 9/000 (SH:- C/O PCC R/wall at RD. 1/060 to 1/075 & 0/045 to 0/060) under PPDNA-2023.

Estimated cost:-	486251.00
Earnest Money Cost:-	9800.00
Time:- Two Month	

Sr. No.	Description of items	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	36.38	Per cubic meter	287.00	Rupees Two Hundred Eighty Seven only	10441.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	90.45	Per cubic meter	4895.00	Rupees Four Thousand Eight Hundred Ninety Five only	442753.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	19.05	Per cubic meter	1102.50	Rupees One Thousand One Hundred Two and Paise Fifty only	21003.00
4	Providing Weep holes in Brick masonry /Plain Reinforced Concrete abutment, Wing Wall, Return wall With 100mm Dia PVC Pipe, extending Through the full Width of the Structure With slope Of 1(V): 20(H) Towards Drawing Face complete as per Drawing And technical Specification clauses 614, 709, 1204.03.7 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	42.00	Nos.	287.00	Rupees Two Hundred Eighty Seven only	12054.00
TOTAL:-						486251.00

Staff Schedule of quantity checked & approved for Rs. 4,86,251/- only
(Rs. Four Lacs Eighty six Thousand Two Hundred Fifty one only)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk