

## OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811

E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2025-26- 12901 - 06

Dated:- 01.12.25.

To

✓ The Executive Engineer (IT Cell),  
Nigam Vihar, Nirman Bhawan,  
HPPWD, Shimla-2,  
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19<sup>th</sup> June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer,  
B&R Division,  
HP.PWD, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3<sup>rd</sup> HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,  
B&R Division,  
HP.PWD, Solan.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

**Exigency**

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	05.12.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	06.12.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	08.12.2025	Upto 10.30 P.M.
4	The date of opening of tender	08.12.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 08.12.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1	Restoration of rain damages on Deothi Delgi road under B&R Kandaghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain on Deothi Delgi road from km 10/500 to 13/200)	495600/-	10000/-	One Month	Rs.350/-
2	Restoration of rain damages on Koti Delgi road under B&R Kandaghat sub-division (SH: Hiring of excavator cum loader for removal of debris, slips, clearance of unlined drain on Koti Delgi road from km 0/0 to 1/500)	493500/-	10000/-	One Month	Rs.350/-
3.	Restoration of rain damages on SKRN road Km.22/00 to 38/600 Road Km.0/00 to 9/400 under PDNA (SH:- Construction of PCC Breast Wall at Rd.35/690 to 35/703)	204334/-	4,000/-	Two Month	Rs.350/-
4.	Restoration of rain Damages on Chhob to Bhura road Km.0/00 to 3/510 under PDNA (SH: - Construction of PCC Retaining wall at Rd.0/075 to 0/085)	427846/-	8500/-	Two Month	Rs.350/-
5.	Restoration of rain Damages on link road from Gaura to Reh Ka Katal via Dhar Chakla Km.0/00 to 6/00 under PDNA (SH: - Construction of PCC Retaining wall at Rd.3/475 to 3/487)	508025/-	10,000/-	Two Month	Rs.350/-

**TERMS & CONDITIONS:-**

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.


Executive Engineer  
B&R Division  
HPPWD, Solan

## Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No.PW-SD/CB-Tender/20025-26- 12901-06 Dated: 01.12.2025 are of emergent nature of work and in public interest the as per the provision at Sr. No. 5(I to IV) of Govt. Notification No PBW(B) A(3)1/2020 dated 27.05.2021.

Dated:- 01.12.2025.

Place:- Solan

  
Executive Engineer  
B&R Division  
HPPWD, Solan

**DRAFT SCHEDULE OF QUANTITY**

ESTIMATED COST ₹ 4,95,600.00  
EARNEST MONEY ₹ 10,000.00  
TIME ALLOWED One Months


**Name of Work :-** RR Damages on Deothi Delgi Road road under B&R Kandaghat Sub-Division ( SH :- Hiring of Excavator Cum Loader for removal of Debris, slips, clearance of unlined drain on Deothi Delgi Road from km 10/500 To 13/200 )


Sr. No.	Description of item	Quantity ( Hours )	Rate ( Rs. ) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	472.00	1050.00	Rupees One Thousand and Fifty Only	Rupees per Hour	495600.00
<b>TOTAL</b>		<b>Four Lacs Ninety five Thousands six hundred only</b>				
		<b>Rs. 495600.00</b>				

**Conditions :-**

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor.
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

DNIT No. 422 For the year 2025-26 duly approved.

  
Assistant Engineer  
B&R HPPWD Sub-Division  
Kandaghat

  
Executive Engineer  
B&R HPPWD Division  
Solani

2

**SCHEDULE OF QUANTITY**

ESTIMATED COST ₹ 4,93,500.00

EARNEST MONEY ₹ 10,000.00

TIME ALLOWED One Months

**Name of Work :-** RR Damages on Koti Delgi Road roads under B&R Kandaghat Sub-Division ( SH :- Hiring of Excavator Cum Loader for removal of Debris , slips , clearance of unlined drain on Koti Delgi Road from km 0/000 To 1/500 )

Sr. No.	Description of item	Quantity ( Hours )	Rate ( Rs. ) in Figures	Rate in words	Unit	Amount
1	Hiring of excavator cum loader for removal of snow , removal of debris and dressing of berms with minimum capacity of 45 cum per hour , minimum 6 hours per day including pay of operator , POL charges , maintenance of any minor or major accidents and other damages to private and public property occur during working hours is the whole responsibility of the contractor. The work shall be executed as per the directions of the Engineer - in - charge.	470.00	1050.00	Rupees One Thousand and Fifty Only	Rupees per Hour	493500.00
<b>TOTAL</b>		<b>Four Lacs Ninety Three Thousands five hundred only</b>		<b>Rs. 493500.00</b>		
<b>Quoted Percentage rate upto Three Digits :-</b>		<b>(+), (-)</b>				

**Conditions :-**

1. All POL shall be borne by the contractor.
2. All the repair / maintenance shall be borne by the contractor.
3. Any Accident/ mishap/damage during the course of execution shall be borne by contractor
4. Any damages or loss to Govt. / Private Property during course of work shall have to make good by the contractor.

DNIT No. 401 For the year 2025-26 duly approved.

Executive Engineer  
B&R RPPWD Division  
Solani

## Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 13					Estimated Cost:-	204334.00
					Earnest Money:-	4000.00
					Time limit :-	Two months

**Name of Work :- Restoration of rain damages on SKRN road Km.22/00 to 38/600 Road Km.0/00 to 9/400 under PDNA (SH:- Construction of PCC Breast Wall at Rd.35/690 to 35/703)**

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited). Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	27.30	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	10702.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	39.00	Per Cubic Meter	4816.00	Rupees Thousand Eight Hundred Sixteen Only	187824.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	24.00	Each	242.00	Rupees Two Hundred Forty Two Only	5808.00
Total:-						204334.00
Rupees Two Lakhs Four Thousand Three Hundred Thirty Four Only						
Quoted Percentage rate upto Three Digits :-				(+)/( -)		

T/S No.193 for the 2025-26  
Sr. No. 400 for the year 2025-26

Executive Engineer  
B&R Division, HP.PWD. Solan.

## Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (4)					Estimated Cost: -	427846.00
					Earnest Money: -	8500.00
					Time limit :-	Two months
Name of Work :- Restoration of rain Damages on Chhob to Bhuiara road Km.0/00 to 3/510 under PDNA (SH: - Construction of PCC Retaining wall at Rd.0/075 to 0/085)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own	75.70	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	29674.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	79.50	Per Cubic Meter	4816.00	Rupees Thousand Hundred Sixteen Only	382872.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	36.00	Each	242.00	Rupees Two Hundred Forty Two Only	8712.00
4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	6.00	Per Cubic Meter	1098.00	Rupees Thousand Ninety Eight Only	6588.00
Total:-						427846.00
Rupees Four Lakhs Twenty Seven Thousand Eight Hundred Forty Six Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 167 for the 2025-26  
Sr. No. for the year 2025-26

Executive Engineer  
B&R Division, HP.PWD. Solan.

# Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- (S)					Estimated Cost:-	50802
					Earnest Money:-	1000
					Time limit :-	Two mon

Name of Work :- Restoration of rain Damages on link road from Gaura to Reh Ka Katal via Dhar Chakla Km.0/00 to 6/00 under PDNA (SH: - Construction of PCC Retaining wall at Rd.3/475 to 3/487)

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesons and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall be borne by the contractor.	46.68	Per Cubic Meter	392.00	Rupees Hundred Ninety Two Only	Three Eight Sixteen	18299
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	95.40	Per Cubic Meter	4816.00	Rupees Thousand Hundred Only	Four Eight Sixteen	459446.
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	44.00	Each	242.00	Rupees Two Hundred Forty Two Only		10648.
4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	17.88	Per Cubic Meter	1098.00	Rupees Thousand Ninety Eight Only		19632.0
Total:-							508025.0
Quoted Percentage rate upto Three Digits :-							
			(+)/( - )				
Rupees Five Lakhs Eight Thousand Twenty Five Onl							

T/S No. 168 for the 2025-26  
Sr. No. for the year 2025-26

Executive Engineer  
B&R Division, HP.PWD. Solan.