



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **27-12-2025** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **26-12-2025** up to **4.00 P.M** and the application for issue of tender form shall be received on **26-12-2025** up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on various roads under HPPWD., Sub Division Bhawarna (Section Khaira-I) (SH:- Removal of old debris, C/O Un-lined drain and maintenance of earthen shoulder on various roads)	99,860/-	2000/-	Three month	350/-
2	Restoration of rain damages on various roads under HPPWD., Sub Division Bhawarna (Section Khaira-II) (SH:- Removal of old debris, C/O Un-lined drain and maintenance of earthen shoulder on various roads)	99,655/-	2000/-	Three month	350/-
3	Restoration of rain damages on various roads under HPPWD., Sub Division Thural (Section Thural-I) (SH:- Removal of old debris, C/O Un-lined drain and maintenance of earthen shoulder on various roads)	98,638/-	2000/-	Three month	350/-
4	Restoration of rain damages on various roads under HPPWD., Sub Division Thural (Section Thural-II) (SH:- Removal of old debris, C/O Un-lined drain and maintenance of earthen shoulder on various roads)	98,833/-	2000/-	Three month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna
On behalf of Governor of Himachal Pradesh

No. PWD/BWD/TA/NIT/2025-26/


12099-12108

Dated:-

19/12/2025

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5thCircle, HPPWD.,Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-12099-108 dated: 19-12-2025.



Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Schedule of Quantity

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Bhawarna (Section Khaira-I). (SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimated Cost :-Rs.99,860/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	654.33	90.00	Rupees Ninety Only	Per Cubic metre	58890.00
2	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	550.00	40.00	Rupees Forty Only	Per Running metre	22000.00
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	542.00	35.00	Rupees Thirty Five Only	Per Square metre	18970.00
Total :-						99860.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna

Schedule of Quantity

2

Name of Work :- Restoration of rain damages on various roads under HPPWD Sub-Division Bhawarna (Section Khaira-II). (SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

**Estimated Cost :-Rs.99,655/-
Earnest Money :-Rs. 2000/-
Time Limit :- Three Months**

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removal of Land slide in hilly area in ordinary rock not requiring blasting by machanical means including cutting and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	654.33	90.00	Rupees Ninety Only	Per Cubic metre	58890.00
2	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	530.00	40.00	Rupees Forty Only	Per Running metre	21200.00
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	559.00	35.00	Rupees Thirty Five Only	Per Square metre	19565.00
Total :-						99655.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer
Bhawarna Division
HP PWD Bhawarna


Schedule of Quantity

3

Name of work:- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Thural-I). (SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimate Cost :- Rs. 98,638/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by machanical means including cutti9ng and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	678.48	90.00	Rupees Ninety Only	Per Cubic metre	61063.00
2	Construotion of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	480.00	40.00	Rupees Forty Only	Per Running metre	19200.00
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	525.00	35.00	Rupees Thirty Five Only	Per Cubic metre	18375.00
Total :-						98638.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Bhawarna Division
 HP PWD Bhawarna


Schedule of Quantity

4

Name of work:- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Thural-II). (SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

**Estimate Cost :- Rs. 98,833/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months**

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by machanical means including cutti9ng and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	678.48	90.00	Rupees Ninety Only	Per Cubic metre	61063.00
2	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materiils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) (Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	470.00	40.00	Rupees Forty Only	Per Running metre	18800.00
3	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	542.00	35.00	Rupees Thirty Five Only	Per Cubic metre	18970.00
Total :-						98833.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


Executive Engineer
Bhawarna Division
HP PWD Bhawarna