



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD, Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **05-01-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 03-01-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 03-01-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	Restoration of rain damages on Various roads under HPPWD Sub Division Thural (Section Bagolu da Ghatta) (SH:- Removal of old debris, C/O Un-lined drain and Maintenance of earthen shoulder on various roads)	99,736/-	2000/-	Three month	350/-
2	Restoration of rain damages on Various roads under HPPWD Sub Division Bhawarna (Section Daroh Garh) (SH:- Removal of old debris, C/O Un-lined drain and Maintenance of earthen shoulder on various roads)	99,953/-	2000/-	Three month	350/-
3	Restoration of rain damages on Naura Kiarwan road km. 0/0 to 3/345, Kiarwan Panahar road km. 0/0 to 3/00 & Naura to Chowki road km. 0/00 to 5/00 under Purba Section in r/o Dheera Sub Division (SH:- Un-lined drain and Maintenance of earthen shoulder on various RDs)	98,050/-	2000/-	Three month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna

On behalf of Governor of Himachal Pradesh

No. PWD/BWD/TA/NIT/2025-26/


12506-15


Dated:-

29/12/2025

Copy is forwarded to the following for information and necessary action:-

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
3. All the Assistant Engineers under this Division.
4. The Computer Cell office of the Engineer-in-Chief, HPPWD. Shimla for uploading the NIT on the departmental website.
5. The Drawing /Accounts Branch in this office.
6. Notice Board.


  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

**CERTIFICATE**

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2025-26-  
12506-15 dated 29-12-2025.

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.


## Schedule of Quantity

2

Name of work:- Restoration of rain damages on various roads under HPPWD Sub-Division Bhawarna (Section Daroh Garh).  
(SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimate Cost :- Rs. 99,953/-  
Earnest Money :- Rs. 2000/-  
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by machanical means including cutti9ng and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	654.33	90.00	Rupees Ninety Only	Per Cubic metre	58890.00
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre) In soil to specified lines, grades, level and dimension excavated materiils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) ( Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	530.00	40.00	Rupees Forty Only	Per Running metre	21200.00
3	Maintenance of Earthen shoulder ( Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	567.50	35.00	Rupees Thirty Five Only	Per Square metre	19863.00
<b>Total :-</b>						<b>99953.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

### Schedule of Quantity

Name of work:-Restoration of rain damages on Naura Kairwan road Km 0/00 to 3/345, Kiarwan Panhar road Km 0/00 to 3/00 & Naura to Chowki road Km 0/00 to 5/00 Under Purba Section in r/o Dheera Sub Division. (SH:- Unlined Drain & maintenance of earthen shoulder at various RD).

Estimate Cost :- Rs. 98,050/-  
Earnest Money :- Rs. 2000/-  
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm (zero decimal four zero square metre). In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) ( Average lead 25m) as per technical specification clause 307. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1060.00	40.00	Rupees Forty Only	Per Running metre	42400.00
2	Maintenance of Earthen shoulder ( Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1590.00	35.00	Rupees Thirty Five Only	Per Square metre	55650.00
<b>Total :-</b>						<b>98050.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## Schedule of Quantity

Name of work:- Restoration of rain damages on various roads under HPPWD Sub-Division Thural (Section Bagolu da Ghatta). (SH:- Removal of old debris, C/o Un-lined drain and Maintenance of earthen shoulder on various roads).

Estimate Cost :- Rs. 99,736/-  
Earnest Money :- Rs. 2000/-  
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		Rs.
1	Removal of Land slid in hilly area in ordinary rock not requiring blasting by machanical means including cutti9ng and trimming of slops and disposal of cut material within lift upto 1.50 m and lead upto 1000m as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	678.48	90.00	Rupees Ninety Only	Per Cubic metre	61063.00
2	Consruction of un lined surface drain of average cross sectional area 0.40 Sqm (zéro decimal four zero square metre). In soil to specified lines, grades, le,vel and dimension excavated materils to be used in embankment with a lift upto 3 m (Three metre) and lead of 50m (Fifty metre) ( Average lead 25m) as per technical specification clause 307 The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	500.00	40.00	Rupees Forty Only	Per Running metre	20000.00
3	Maintenance of Earthen shoulder ( Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipemnt at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	533.50	35.00	Rupees Thirty Five Only	Per Square metre	18673.00
<b>Total :-</b>						<b>99736.00</b>
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna