HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 03-01-2026 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 03-01-2026 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender: 05-01-2026 at 10.30 AM.
4. Date of opening of Tender: 05-01-2026 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R Ladrour to Lathwan road km. 0/00 to 0/500 (SH:-C/O R/wall at RD 1/800 to 1/810, B/wall at RD 0/300 to 0/312 & 0/150 to 0/160) (PDNA)	4,99,568/-	10,000/-	Two Months	Rs. 350/-	Class-D
2	R/R Ladrour to Lathwan road. (SH:- P/L CC Pavement at RD 0/190 to 0/220 and V-shape drain with R/wall.) (PDNA)	4,99,976/-	10,000/-	Two Months	Rs. 350/-	Class-D
3	A/R & M/O various roads under Bhoranj Sub Division. (Section Patta) (SH:- Painting & writing letters of information sign boards, km stone and other road side furniture etc.)	99,998/-	2,000/-	Two Months	Rs. 350/-	Class-D
4	A/R & M/O various roads under Samirpur Sub Division, section Barin Mandir (SH:- Painting & writing letters of information sign boards, km stone and other road side furniture etc.)	99,998/-	2,000/-	Two Months	Rs. 350/-	Class-D
5	Restoration of Rain damages on Hamirpur Jahu road (SH:- Dressing and cutting, filling road side Berms / Shoulders at RD 20/780 to 32/00) (PDNA)	4,96,522/-	10,000/-	Two Months	Rs. 350/-	Class-D

6	A/R & M/O HPPWD Rest House at Bhoranj Distt. Hamirpur (HP) (SH:- Providing and supply Referigrator, Swasha fine Bone China Dinner Set &Targrock bone china set etc.)	93,350/-	2,000/-	Two Months	Rs. 350/-	Class-D
7	R/R Damages on Kharwar Mehal via Karah road km 0/00 to 0/500 (SH:- C/O R/wall at RD 3/400 to 3/413) (PDNA)	4,57,978/-	9,500/-	Two Months	Rs. 350/-	Class-D
8	A/R & M/O various road under Samirpur Sub Division Section Samirpur (SH:- Painting and writing letters of information sign boards, km stone and other road side furniture etc.)	99,982/-	2000/-	Two Months	Rs. 350/-	Class-D
9	Restoration on link road Bhareri Hanoh Km. 0/00 to 3/700 (SH:- C/O R/wall at RD, 1/100 to 1/115 and V-shape drain) (PDNA)	4,93,772/-	10,000/-	Two Months	Rs. 350/-	Class-D
10	R/R damages on Hamirpur Jahu road Km 16/500 to 21/780 (Tarkawari to Kehrawin chowk)(SH:- Repair & Maintenance of earthen shoulder , C/O unlined surface drain in Km 16/500 to 17/500)	99,950/-	2000/-	Two Months	Rs. 350/-	Class-D
11	R/R Damages on Jijwin Awahdevi Chamboh road km 0/00 to 9/255 (SH:- C/O wire crate at RD 5/955.65 to 5/961.30)	98,114/-	2,000/-	Two Months	Rs. 350/-	Class-D
12	Balance work for Government collage Library at Bhoranj (Tarkwari) Hamirpur (SH:- P/Applying water proofing on roof)	99,508/-	2,000/-	Two Months	Rs. 350/-	Class-D
13	R/R Damages on Jijwin Awahdevi Chamboh road km 0/00 to 9/255. (SH:- C/O wire crate at RD 5/966.95 to 5/972.60)	98,114/-	2,000/-	Two Months	Rs. 350/-	Class-D
14	Balance work for Government College Library at Bhoranj (Tarkwari), Hamirpur. (SH:-P/Applying water proofing on roof, P/F Water storage Tank & other Sanitary items etc)	86,557/-	1,800/-	Two Months	Rs. 350/-	Class-D
15	Restoration of link road Kalahu more to Bhareri via Gudwin Bhukkar Beri / Brahman Sai Da Ghat km. 0/00 to 7/720 (SH:-Repair of pot hole) (PDNA)	4,98,567/-	10,000/-	Two Months	Rs. 350/-	Class-D
16	Restoration of link road Vety. Hospital Bhareri to Amroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/420, Vety. Hospital Bhareri to Amroh via Jaroh km 0/00 to 2/00 (SH:-Repair of pot holes) (PDNA)	4,99,148/-	10,000/-	Two Months	Rs. 350/-	Class-D
17	Repair/Restoration on link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00 (SH:-C/O R/wall at RD 7/450 to 7/585) (PDNA)	4,99,865/-	10,000/-	Two Months	Rs. 350/-	Class-D

18	Repair/Restoration on link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00 (SH:-C/O R/wall at RD 3/300 to 3/315, 3/350 to 3/382). (PDNA)	4,99,008/-	10,000/-	Two Months	Rs. 350/-	Class-D
19	Restoration of link road Kalahu More to Bharer via Gudwin Bhukkar Beri Brahmna Sai Da Ghat Namlakh Jaroh road km 0/00 to 7/720 (SH:- P/L C.C. Pavement km 5/200 to 5/260 and Interlocking Paver Block at RD 4/800 to 4/855) (PDNA)	4,84,274/-	10,000/-	Two Months	Rs. 350/-	Class-D
20	R/R damages on Kharwar Mehal via Karah km 0/00 to 5/00 (SH:- C/O R/wall at RD 1/190 to 1/208 & V-shape drain at RD 1/00 to 1/200 (PDNA)	4,45,075/-	9000/-	Two Months	Rs. 350/-	Class-D
21	1 R/R damages on Thalotu to ladrour via Khutrin km 0/00 to 5/00 (ii) Thalotu to Ladrour Lathwan via Zangi Mahadev Mandir (iii) Una Aghar Mandi road km 74/00 to 79/00)(SH:- Repair of pot hole on various RDs (PDNA)	4,38,818/-	9000/-	Two Months	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariable be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.

The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

ExecutiveEngineer
Bhoranj Division
HPPWD Bhoranj
For and on behalf of Governor of HP.

No.-PW/BHD/TA/NIT/2025- 15134-174 Dated:- 27-12-2025

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, NirmanBhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD,Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj ,Various Contractors/ Firms.

ExecutiveEngineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: R/R Ladrour to Lathwan road km. 0/00 to 0/500. (SH:- C/O R/Wall at RD 1/800 to 1/810 , B/Wall at RD 0/300 to 0/312 & 0/150 to 0/160.) (PDNA)

Estimated Cost Rs 4,99,568/-
Earnest Money Rs. 10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	40.76	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	109.16	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	38.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	9.00	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Ladrour to Lathwan road. (SH:- P/L C.C.Pavement at RD 0/190 to 0/220 and V-Shape drain with R/Wall .) (PDNA)

Estimated Cost Rs 499,976/-
Earnest Money Rs. 10000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	50.40	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M_{10}(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 40mm(forty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.63	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	15.00	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	64.10	Per Cubic Meter			
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.00	Each			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various roads under Bhoranj Sub Division.(Section Patta)(SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.)

Estimated Cost Rs 99998/-
Earnest Money Rs 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic ename paint of approved brand and manufacture of required colour to give an even shade 13.99.1 one or more coat on old works.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	61.92	Per sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.26	Per Sqm			
3	Re-lettering with black Japan paint of approved brand and manufacture.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24356	Per letter. Per cm ht.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various roads under Samirpur Sub Division. Section Barin Mandir)(SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.)

Estimated Cost Rs 99998/-
Earnest Money Rs 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic ename paint of approved brand and manufacture of required colour to give an even shade 13.99.1 one or more coat on old works.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	61.92	Per sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	31.26	Per Sqm			
3	Re-lettering with black Japan paint of approved brand and manufacture.including entire carriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24356	Per letter. Per cm ht.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of Rain damages on Hamirpur Jahu road.
(SH:- Dressing and Cutting , filling road side Berms/shoulders at RD 20/780 to 32/00.) (PDNA)

Estimated Cost Rs 4,96,522/-
Earnest Money Rs. 10000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5953.50	Per square metre			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R& M/O HPPWD Rest House at Bhoranj Distt. Hamirpur (H.P) (S.H :- Providing and Supply Referigrator,Swasha fine Bone China Dinner Set &Targrock bone china tea Set etc. .)

Estimated Cost Rs 93350/-
Earnest Money Rs 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing Referigrator of standard quality approved brand 243 No including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.00	Each			
2	Providing and Supplying Swasha fine Bone China Dinner Set 51 pices including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.00	Each			
3	Providing and Supplying Prestige presser cooker (stainless steel) 5 letter including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.00	Each			
4	Providing and Supplying Prestige presser cooker (deluxe plus) 12 letter including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1.00	Each			
5	Providing and Supplying borosil glass set six piece including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.00	set			
6	Providing and Supplying Targrock bone china tea Set with 6 cup saucer tea kettle pot,milk pot, sugar pot white with gold line including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2.00	set			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: R/R Damages on Kharwar Mehal via Karah road km. 0/00 to 0/500. (SH:- C/O R/Wall at RD 3/400 to 3/413.) (PDNA)

Estimated Cost Rs 4,57,978/-
Earnest Money Rs. 9500/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.87	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	98.38	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.68	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-A/R & M/O Various roads under Samirpur Sub Division. Section Samirpur)(SH:- Painting & writing letters of information sign boards, km Stone and other road side furniture etc.)

Estimated Cost Rs 99982/-
Earnest Money Rs 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Painting with synthetic ename paint of approved brand and manufacture of required colour to give an even shade 13.99.1 one or more coat on old works.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	55.72	Per sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade 13.62.1 Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	46.74	Per Sqm			
3	Re-lettering with black Japan paint of approved brand and manufacture.including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23920	Per letter. Per cm ht.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: Restoration on link road Bhareri Hanoh Km. 0/00 to 3/700 (SH:- C/O R/wall at RD,1/100 to 1/115 and V-Shape drain). (PDNA)

Estimated Cost Rs 4,93,772-
Earnest Money Rs.10000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	77.25	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	21.72	Per cubic meter			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	74.25	Per Cubic Meter			
4	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	45.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.00	Per Cubic Meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-R/R Damages on Hamirpur Jahu road km. 16/500 to 21/780. (Tarkwari to Kehrawin chowk)(SH:- Repair & Maintenance of earthen shoulder , C/O unlined surface drain in km. 16/500 to 17/500).

Estimated Cost Rs. 99,950
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregulartion on shoulders to the design level by adding fresh approoved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	997.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift uo to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	570.00	Per Running Mtr.			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Jijwin Awahdevi Chamboh road km. 0/00 to 9/255.(SH:- C/O Wire crate at RD.5/955.65 to 5/961.30)

Estimated Cost Rs 98,114/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.83	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm(one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighthing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.49	Per cubic metre			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.51	Per Cubic Meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Balance Work for Government College Library at Bhoranj (Tarkwari),Hamirpur. (SH:-P/Applying water proofing on roof)

Estimated Cost Rs 99,508/-
Earnest Money Rs. 2000/-
Time 2 month

Sr N	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	265.32	Per square meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages on Jijwin Awahdevi Chamboh road km. 0/00 to 9/255.(SH:- C/O Wire crate at RD.5/966.95 to 5/972.60)

Estimated Cost Rs 98,114/-
Earnest Money Rs. 2000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rate in words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includinmg dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.83	Per Cubic Meter			
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeters) dia GI with conforming to IS:280 and IS: 4826 in 100mmx100mm(one hundred millimeters into one hundred millimeters) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulder weighthing not less than 25kg. (twenty five kilogramme) each as per drawing and technical specifications clause 1301 as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	26.49	Per cubic metre			
3	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	10.51	Per Cubic Meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Balance Work for Government College Library at Bhoranj (Tarkwari),Hamirpur. (SH:-P/Applying water proofing on roof ,P/F Water Storage Tank & other Sanitary items etc)

Estimated Cost Rs 86,557/-
Earnest Money Rs. 1800/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a single of 15 mm C.P. brass pillar taps including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Each			
2	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Each			
3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.:15 mm dia nominal bore including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	15.00	Per Running Meter			
4	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms:15 mm nominal bore including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
5	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 15 mm nominal bore	8.00	Each			
6	Providing and fixing brass stop cock of approved quality :15 mm nominal bore including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.00	Each			
7	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete:15 mm nominal bore including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
8	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	2000.00	Per ltr.			
9	Providing and applying fibre reinforced elastomeric liquid water proofing membrane with resilient acrylic polymers having Sun Reflectivity Index (SRI) of 105 on top of concrete roof in three coats @10.76 litre/ 10 sqm. One coat of self-priming of elastomeric waterproofing liquid (dilution with water in the ratio of 3:1) and two coats of undiluted elastomeric waterproofing liquid (dry film thickness of complete application/system not less than 500 microns). The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as per the direction of Engineer-in-Charge including entire carrriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	71.93	Per square meter			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- Restoration of link road Kalahu more to Bhareri via gudwin bhukhar beri brahmna sai da ghat km. 0/00 to 7/720 . (SH:- Repair of pot hole) (PDNA)

Estimated Cost Rs 4,98567-
Earnest Money Rs. 10000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-10 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1197.72	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam spedification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	29.95	Per cubic meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-Restoration of link road vety. Hosital Bhareri t oamroh via Fakruhi Hanoh Garli Bunga road km 0/00 to 2/420,Vety. Hospital Bhareri to amroh via Jaroh km 0/00 to 2/00 (SH:- Repair of pot holes) (PDNA)

Estimated Cost Rs 4,99,148/-
Earnest Money 10000/-
2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1203.29	Per square metre			
2	Providing and laying spreading and compacting stone aggregate of specific size to water bound macadam spedification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	28.68	Per cubic meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HKPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: Repair/Restoration link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00.(SH:- C/O R/wall at RD 7/450 to 7/585.) (PDNA)

Estimated Cost Rs 4,99,865/-
Earnest Money Rs. 10,000/-
Time 2 month

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	81.00	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	103.25	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	120.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK-: Repair/Restoration link road Bassi Bhareri Tatahar Road km. 0/0 to 11/00.(SH:- C/O R/wall at RD 3/300 to 3/315, 3/350 to 3/382.) -(PDNA)

Estimated Cost Rs 4,99,008/-
Earnest Money Rs. 10,000/-
Time 2 month

Sr N	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	47.20	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	109.60	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carrriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	52.00	Each			
	Total					
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-Reastoration of link road Kalahu more to Bhareri via Gudwin Bhukkar Beri Brahmna Sai Da Ghat Namlakh Jaroh road km 0/00 to 7/720 (SH - P/L C.C pavement km 5/200 to 5/260 and interlocking paverblock at RD 4/800 to 4/855)(PDNA)

					Estimated Cost	Rs.4,84,274/-
					Earnest Money	Rs. 10000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23.40	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	23.84	Per Cubic Meter			
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size)as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	18.00	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	7.20	Per Cubic Meter			
5	Providing and laying heavy duty precast cement concrete interlocking paver blocks vibro compacted upto M-50(M-fifty) grade including border or kurb block grey or coloured over sub base of concrete with 25mm (twenty millimeters) thick average thickness of cement 1:4 (one cement: four sand) laid over and jointed with neat cement slurry mixed with pigment to match the shade of blocks including curing rubbing and polishing complete (sub base concrete) floor to be paid for 80mm(eighty millimeters) thick inter locking blocks (ISI approved), and as per direction of the Engineer-in-charge including entire carriage of materials within all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government	165.00	Per Square Meter			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damage on Kharwar Mehal via Karah km 0/00 to 5/00 (SH:- C/O R/wall at Rd 1/190 to 1/208 & v-shape drain at Rd 1/00 to 1/200 (PDNA)

					Estimated Cost	Rs 4,45,075/-
					Earnest Money	Rs. 9000/-
					Time	2 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water inclusing cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	41.26	Per Cubic Meter			
2	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	13.70	Per Cubic Meter			
3	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	74.98	Per Cubic Meter			
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108. 450mm(nine hundred millimeters) dia. as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.00	Per Running meter			
5	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	30.00	Each			
6	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	24.84	Per Cubic Meter			
	Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:-(i) R/R Damages on Thalotu to Ladrour via Khutrin km. 0/00 to 5/00 .(ii) Thalotu to ladrour lathwan via Zangi Mahadev Mandir) (iii) Una Aghar Mandi road km 74/00 to 79/00)(SH:- Repair of Pot Hole on various Rds (PDNA)

Estimated Cost Rs 438818/-
Earnest Money Rs. 9000/-
Time 2Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimeters) thick premix carpet and seal coat type-B with VG-30 bitumen specification clause 1904-2,503 and 508-1 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	1098.00	Per square metre			
2	Providing Laying spreading and compacting stone aggregate of specific size to water bound macadam spedification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying and brooming stone scseening/binding material to fill up the interstices of course aggregate watering and compacting to the required density grading-III as per technical specification clause 405 by manual means, as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royality, Malkana, toll tax,sale tax or other taxes imposed by the Government.	19.35	Per cubic meter			
	Total					

Terms and Condition:-

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj