

Himachal Pradesh  
Public Works Department

\*\*\*\*

No. PWH/HD/CB/T-I/2025-26  
To

8832-34

Dated: - 15/12/2025

The Executive Engineer (IT Cell)  
Nirman Bhawan, Nigam Vihar,  
Shimla-2

Subject: - Publication of Notice inviting tender.

Sir,

Enclosed please find herewith copy of notice inviting tender for publishing on departmental website for favour of further necessary action please.

Encl: As above

Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una HP).

Copy along with copy of notice inviting tender is forwarded for information and necessary action to:-

1. The Superintending Engineer, 15th Circle, HP: PWD, Una.
2. Copy to Notice board.

Executive Engineer,  
HPPWD Division Haroli,  
Distt. Una HP).

### Certificate

Certified that the tenders for the works called vide this office letter No. PWH/HD/CB/T-1/2025-26-~~8~~  
34 dated 15/12/2025 are required to be carried out immediately being emergent nature of work in  
interest.

  
Executive Engineer,  
Haroli Division, HPPWD  
Haroli Dist. Una HP).

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
" NOTICE INVITING TENDERS "**

Percentage rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Haroli Division H.P. on behalf of Governor of H.P. for the following works from the approved and eligible contractors/firms enlisted in PWD Department as per latest instructions, so as to reach and open in his office as per time schedule given below. The offer of the tender will be open for 45 days from the date of opening of tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender form a/w requisite documents: - 20/12/2025 up to 10.30 (AM).
2. Date of issue/sale of tender forms against cash payment(non-refundable): - 22/12/2025 up to 3.00 PM
3. Date of receipt of tenders: - 23/12/2025 up to 10.30 AM
4. Date of opening of tenders: - 24/12/2025 at 11.00 AM

| Sr. No. | Name of work                                                                                                                                                                                                                                                                                                                                            | Estimated cost | EMD    | Time Limit | Cost of tender | Eligible class of contractor |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|--------|------------|----------------|------------------------------|
| 1       | 2                                                                                                                                                                                                                                                                                                                                                       | 3              | 4      | 5          | 6              | 7                            |
| 1       | C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-P/F Door, windows, double acting spring, door stopper, brass unious 45cm, C.P. brass stop cock for basin mixer, waste pipe for sink or wash, G.I. pipes in lab)Deposit Work                                                                                                                    | 96535          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 2       | C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar(SH:-C/OI Edge wall at RD. 0/010 to 0/041) Deposit work                                                                                                                                                                                                      | 88627          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 3       | C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 2/714 to 3/052) Deposit work                                                                                                                                                                                                                    | 99085          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 4       | C/O road from Lower Panjwar covering Saini Mohalla, Dhakki, Dhakki Mohalla up to Daulatpur link road & Nagnoli Petrol Pump via ward No.5 up to Shiv Mandir Panjwar & Maadu ki Nihali se Madun-ka-Ghar Tak village Panjwar km. 0/00 to 8/00(SH:-Preparation of working estimate and DNIT including submission of Hard and soft copies) under NABARD-XXXI | 85000          | 1700/- | 15 day     | 350/-          | Class- C & D                 |
| 5       | C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O R/wall at RHS of Science Lab building)Deposit Work                                                                                                                                                                                                                                         | 99318          | 2000/- | One month  | 350/-          | Class- C & D                 |
| 6       | C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar(SH:-C/OI Edge wall at RD. 0/041 to 0/060 & P/L, Embankment GSB at RD. 0/00 to 0/060)                                                                                                                                                                        | 99661          | 2000/- | One month  | 350/-          | Class- C & D                 |
| 7       | C/O Height & width gauge barricable at entry point to Swan river at Bathri Near Gatta Factory & Tahliwal near ANM School Tehsil Haroli Distt. Una (HP)                                                                                                                                                                                                  | 89216          | 1800/- | One Month  | 350/-          | Class- C & D                 |
| 8       | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-IV                                                                                                                                                                                                                            | 99627          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 9       | C/O Rajiv Gandhi Day Boarding School at Haroli distt. Una (SH:-Preparation of Topographical & Contour site Plan)                                                                                                                                                                                                                                        | 70320          | 1700/- | 15 day     | 350/-          | Class- C & D                 |
| 10      | C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O R/wall at Back side of Science Lab building)Phase-II Deposit Work                                                                                                                                                                                                                          | 96098          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 11      | C/O Link road from Nagnoli to SC Basti Via Chaprian Gaur Bagirian Chotti Khad Gujran Thirkhana Nainan(SH:-P/L 80mm paver blocks in RD. 0/985 to 1/008)Deposit Work                                                                                                                                                                                      | 99764          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 12      | Restoration of rain damage on link road from Village Baliwal to Peersthan km. 0/00 to 3/050(SH:-C/O R/wall at RD. 0/400 to 0/408.50 LHS)                                                                                                                                                                                                                | 97870          | 2000/- | One Month  | 350/-          | Class- C & D                 |
| 13      | C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar(SH:-C/OI Edge wall at RD. 0/020 to 0/040.30)                                                                                                                                                                                                                | 99064          | 2000/- | One Month  | 350/-          | Class- C & D                 |

|    |                                                                                                                                                                                  |       |        |           |       |              |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-----------|-------|--------------|
| 14 | Repair & Restoration of Pandoga Barrier to Panjwar km. 0/00 to 9/00 (SH:- C/O U-Shape drain at RD. 2/648 to 2/708) RHS)                                                          | 97578 | 2000/- | One Month | 350/- | Class- C & D |
| 15 | Restoration of rain damages on link road Saloh Nursary to Harijan Basti Saloh km. 0/00 to 2/00(SH:- Repair of Rain cuts at Various RDs from km. 1/00 to 2/00)                    | 98280 | 2000/- | One Month | 350/- | Class- C & D |
| 16 | Restoration of rain damages on Umrli Singan road km. 0/00 to 6/550(SH:-P/L 60mm thick paver blocks in berm at RD. 1/356.40 to 1/375 BHS)                                         | 98682 | 2000/- | One Month | 350/- | Class- C & D |
| 17 | Repair of pot holes on link road Saloh Nursary to Harijan Basti Saloh km. 0/00 to 2/00 Under 5054-MMSRRY(Balance work(SH:-Repair of pot holes at RD. 1/660 to 2/00)              | 98456 | 2000/- | One Month | 350/- | Class- C & D |
| 18 | C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-C/O R/wall at Back side of Science Lab building)Phase-II Deposit Work.                                                  | 87720 | 2000/- | One Month | 350/- | Class- C & D |
| 19 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-V                                                      | 99385 | 2000/- | One Month | 350/- | Class- C & D |
| 20 | C/O Height & width gauge barricable at entry point to Swan river at Bathri Near Gatta Factory & Tahlial near ANM School Tehsil Haroli Distt. Una (HP)                            | 83033 | 1700/- | One Month | 350/- | Class- C & D |
| 21 | C/O Link road from Nagnoli to SC Basti Via Chaprian Gaur Bagirian Chotti Khad Gujran Thrkhana Nainan(SH:-P/L 80mm paver blocks in RD. 0/939 to 0/962)Deposit Work.               | 99237 | 2000/- | One Month | 350/- | Class- C & D |
| 22 | Restoration of rain damage on link road from Village Baliwal to Peersthan km. 0/00 to 3/050(SH:-C/O R/wall at RD. 0/417.00 to 0/425.50 LHS)                                      | 98190 | 2000/- | One Month | 350/- | Class- C & D |
| 23 | Restoration of rain damages on Umrli Singan road km. 0/00 to 6/550(SH:-P/L 60mm thick paver blocks in berm at RD. 1/337.80 to 1/356.40 BHS)                                      | 98748 | 2000/- | One Month | 350/- | Class- C & D |
| 24 | Restoration of rain damages on link road Saloh Nursary to Harijan Basti Saloh km. 0/00 to 2/00 Under (Balance work(SH:-Repair of Rain cuts at Various RDs from km. 0/00 to 1/00) | 98208 | 2000/- | One Month | 350/- | Class- C & D |
| 25 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-I                                                      | 99243 | 2000/- | One Month | 350/- | Class- C & D |
| 26 | C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar(SH:-P/L 60mm thick paver blocks at RD. 0/00 to 0/020)                                | 97600 | 2000/- | One Month | 350/- | Class- C & D |
| 27 | Restoration of rain damage on link road from Village Baliwal to Peersthan km. 0/00 to 3/050(SH:-C/O R/wall at RD. 0/408.50 to 0/417.00 LHS)                                      | 98030 | 2000/- | One Month | 350/- | Class- C & D |
| 28 | C/O Link road from Nagnoli to SC Basti Via Chaprian Gaur Bagirian Chotti Khad Gujran Thrkhana Nainan(SH:-P/L 80mm paver blocks in RD. 0/916 to 0/939)Deposit Work.               | 99426 | 2000/- | One Month | 350/- | Class- C & D |
| 29 | A/R & M/O link road to Gulaban to Tobba Palkwah km. 0/00 to 1/700 (SH:-C/O R/wall in RD. 1/644 to 1/654 LHS)                                                                     | 98099 | 2000/- | One Month | 350/- | Class- C & D |
| 30 | C/o link road Laluwal to Polian Km 0/0 to 3/400 under 5054-MMSY (SH: P/L 20mm thick premix carpet at RD 1/360 to 1/698)                                                          | 99085 | 2000/- | One Month | 350/- | Class- C & D |
| 31 | Restoration of rain damage on link road from Village Baliwal to Peersthan km. 0/00 to 3/050(SH:-C/O R/wall at RD. 0/425.50 to 0/429.30 LHS & CC on approach road)                | 99222 | 2000/- | 15 day    | 350/- | Class- C & D |
| 32 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-II                                                     | 99268 | 2000/- | One Month | 350/- | Class- C & D |
| 33 | Repair & Restoration of Pandoga Barrier to Panjwar km. 0/00 to 9/00 (SH:-C/O U-Shape drain at RD. 2/708 to 2/735 & C/O Approach road RHS)                                        | 98431 | 2000/- | One Month | 350/- | Class- C & D |

|    |                                                                                                                                                                                           |       |        |           |       |              |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-----------|-------|--------------|
| 34 | C/O Height & width gauge barricable at entry point to Swan river at Pandoga Near bridge on Panjwar Bathri road Tehsil Haroli Distt. Una (HP)                                              | 57453 | 1200/- | One Month | 350/- | Class- C & D |
| 35 | C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar(SH:-P/L 60mm thick paver blocks at RD. 0/040.30 to 0/045 & CC Pavement at RD. 0/045 to 0/060) | 92236 | 2000/- | One Month | 350/- | Class- C & D |
| 36 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-VI                                                              | 99378 | 2000/- | One Month | 350/- | Class- C & D |
| 37 | Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 (SH:-C/O 4.00 mtrs. Span culvert at RD. 32/350)Phase-VI                                                              | 99774 | 2000/- | One Month | 350/- | Class- C & D |
| 38 | Repair & Restoration of Pandoga Barrier to Panjwar km. 0/00 to 9/00 (SH:-C/O U-Shape drain at RD. 2/735 to 2/850 RHS)                                                                     | 99185 | 2000/- | One Month | 350/- | Class- C & D |
| 39 | Restoration of rain damages on Una Rampur Haroli Jaijon road km. 0/00 to 23/00 (SH:-C/O R/wall at 13/700 to 13/712 RHS)                                                                   | 99498 | 2000/- | One Month | 350/- | Class- C & D |
| 40 | Restoration of rain damages on link road from Panjwar Bathri Gondpur Traf Jaichand road to Kuthar Beet km. 0/00 to 3/400(SH:-C/O R/wall at RD. 0/020 to 0/032 LHS)                        | 99498 | 2000/- | One Month | 350/- | Class- C & D |
| 41 | Restoration of rain damages on Una Rampur Haroli Jaijon road km. 0/00 to 23/00 (SH:-C/O R/wall at 13/712 to 13/724 RHS)                                                                   | 99338 | 2000/- | One Month | 350/- | Class- C & D |
| 42 | Restoration of rain damages on link road from Panjwar Bathri Gondpur Traf Jaichand road to Kuthar Beet km. 0/00 to 3/400(SH:-C/O R/wall at RD. 0/032 to 0/044 LHS)                        | 99485 | 2000/- | One Month | 350/- | Class- C & D |
| 43 | A/R & M/O Una Rampur Haroli Palkwah Jaijon road km. 0/00 to 23/00(SH:-P/F railing to Police Guard Post near swan bridge at RD 1/800)                                                      | 99663 | 2000/- | One Month | 350/- | Class- C & D |
| 44 | A/R & M/O PWD Non-Residential Building at Haroli Division & C/O CHC Building at Beetan(SH:-P/F Flex printing glow Sign board Division Haroli & CHC Building Beetan)                       | 65000 | 1500/- | One Month | 350/- | Class- C & D |
| 45 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/807.80 to 4/015.50 LHS)                                                               | 97131 | 2000/- | One Month | 350/- | Class- C & D |
| 46 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/800 to 4/807.40 LHS)                                                                  | 98392 | 2000/- | One Month | 350/- | Class- C & D |
| 47 | Restoration of rain damage on Panjwar Bathri road km. 0/00 to 34/00(SH:-C/O approach road at RD. 1/480, P/L paver block RD. 0/237 to 0/274)                                               | 99623 | 2000/- | One Month | 350/- | Class- C & D |
| 48 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/900 to 4/905 LHS)                                                                     | 99744 | 2000/- | One Month | 350/- | Class- C & D |
| 49 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/00 to 4/009.60 RHS)                                                                   | 84601 | 2000/- | One Month | 350/- | Class- C & D |
| 50 | Restoration of rain damage on Panjwar Bathri road km. 0/00 to 34/00(SH:-C/O approach road at RD. 1/480, P/L paver block RD. 0/200 to 0/237)                                               | 99938 | 2000/- | One Month | 350/- | Class- C & D |
| 51 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/900 to 4/905 RHS)                                                                     | 99744 | 1000/- | One Month | 350/- | Class- C & D |
| 52 | Restoration of Rain damages on Polian Janani road km. 0/00 to 6/00(SH:-C/O Wire crate work at RD. 4/009.60 to 4/019.20 RHS)                                                               | 98616 | 2000/- | One Month | 350/- | Class- C & D |
| 53 | Restoration of Rain damages on Link road from Una Jaijon road to Gulaban da Toba Palkwah km. 0/00 to 1/700 (SH:-C/O Breast wall at RD. 1/010.30 to 1/017 RHS)                             | 98598 | 2000/- | One Month | 350/- | Class- C & D |
| 54 | Restoration of rain damages on Plakwah Lathari Nangal Khurd Jatpur road km. 0/00 to 10/400(SH:-C/O V-shape drain at RD. 7/696 to 7/742.10 LHS)                                            | 98940 | 2000/- | One Month | 350/- | Class- C & D |
| 55 | Restoration of Rain damages on Link road from Una Jaijon road to Gulaban da Toba Palkwah km. 0/00 to 1/700 (SH:-C/O Breast wall at RD. 1/00 to 1/010.30 RHS)                              | 99327 | 2000/- | One Month | 350/- | Class- C & D |

|    |                                                                                                                                                                                |       |        |           |       |              |
|----|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|-----------|-------|--------------|
| 56 | Restoration of rain damages on Plakwah Lalhari Nangal Khurd Jatpur road km. 0/00 to 10/400(SH:-C/O V-shape drain at RD. 7/650 to 7/696 LHS)                                    | 98725 | 2000/- | One Month | 350/- | Class- C & D |
| 57 | Balance work for the repair of pot hole on link road Ispur to Pandoga via Kyarian km. 0/00 to 2/180(SH:-Patch work at RD. 0/00 to 1/500) Under MMSRRY                          | 99073 | 2000/- | One Month | 350/- | Class- C & D |
| 58 | Restoration of rain damages on Plakwah Lalhari Nangal Khurd Jatpur road km. 0/00 to 10/400(SH:-C/O V-shape drain at RD. 7/650 to 7/696 RHS)                                    | 98725 | 2000/- | One Month | 350/- | Class- C & D |
| 59 | Restoration of rain damages on link road from Una Jaijon road to Gulabanda Toba Plakwah km. 0/00 to 1/700(SH:-C/O Breast wall at RD. 1/022 to 1/032.20 RHS)                    | 98390 | 2000/- | One Month | 350/- | Class- C & D |
| 60 | Restoration of rain damages on Plakwah Lalhari Nangal Khurd Jatpur road km. 0/00 to 10/400(SH:-C/O V-shape drain at RD. 7/696 to 7/742, 10 RHS)                                | 98940 | 2000/- | One Month | 350/- | Class- C & D |
| 61 | Restoration of rain damages on Laluwal Gondpur to Singha Jhungian upto Punjab Border road km. 0/00 to 13/575(SH:-Repair of Rain cuts at Various RDs from km. 12/275 to 13/575) | 99215 | 2000/- | One Month | 350/- | Class- C & D |
| 62 | C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH:-P/F sliding door bolt, tower bolts, adjustable friction windows stays, double acting spring hinges etc.)              | 99560 | 2000/- | One Month | 350/- | Class- C & D |
| 63 | Restoration of rain damages on Link road Bathu to Bathri via Goushala km. 0/00 to 1/100 (SH:-Repair of Rain cuts at Various RDs from km. 0/00 to 1/100)                        | 98280 | 2000/- | One Month | 350/- | Class- C & D |

The earnest money in the shape of National Saving certificate/ time deposit/ saving account of any post office or FDR, Nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected. The tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained. The copy of valid enlistment, GST registration No., Income Tax, Pan No. and epf no. must be attached with application.

**SPECIAL CONDITION: -**

1. The contractor should produce a copy of valid enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his resignation and GST No. and copy of same be attached with the application.
3. The earnest money for the above work should be submitted duly pledged in favour of Executive Engineer, Haroli Division HPPWD with the application for the purchase of tender forms. The application received without earnest money shall summarily be rejected.
4. The contractor/firms are required to insert the rate in words as well as figures, failing which Executive Engineer reserves the right to accept/rejects any or all tenders. If any of the date mentioned above happens to be local/gazetted holidays, the same shall be process on next date.
5. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attach with their application a/v proof of ownership of machinery/legal tie up arrangement).
6. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
7. The conditional/ambiguous/telegraphic tenders by fax shall not entertained/considered in any case.

HIM SUCHANA AVAM JAN SAMPARK.

Executive Engineer  
HPPWD Division Haroli  
Distt. Una(HP).Pin Code-177220  
Email: [ee-haroli-hp@hp.gov.in](mailto:ee-haroli-hp@hp.gov.in)  
On behalf of Governor of Himachal Pradesh

# Schedule of quantity

for the C/O Science Lab at Govt. Sr. Sec. School Lohi Tehsil Haroli Distt Una (H.P.)

| Name of work - Balance work for the C/O Science Lab at Govt. Sr. Sec. School Lohi Tehsil Haroli Distt Una (H.P.)                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |        |        |        | Estimated Cost Rs.                              |           |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|--------|--------|-------------------------------------------------|-----------|
| [2H - Providing and fixing Door, windows, double acting spring hinges, door stoppers, brass unions 45cm, C.P. brass stop cock for basin mixer, waste pipe for sink or wash, G.I. pipes in Lab.] |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |        |        |        | Time:                                           | One month |
| S.NO                                                                                                                                                                                            | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty    | Unit   | T Rate | Rate in words                                   | Amount    |
| 1                                                                                                                                                                                               | Providing and fixing oxidised aluminium double acting spring hinges with necessary screws etc. complete. The rate includes sale tax octroi royalty malkhana toll tax, GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                     | 60.00  | Each   | 150.00 | Rupees One Hundred Only                         | 9000.00   |
| 2                                                                                                                                                                                               | Providing and fixing unplasticised PVC connection pipe with brass unions 45cm (forty five centimetre) length 15mm (fifteen millimetre) nominal bore G.I. (galvanised) / malleable / mild steel including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi royalty malkhana toll tax sale tax, GST or other taxes imposed by the Government. | 5.00   | Each   | 165.00 | Rupees One Hundred Sixty Five Paise Ninety Only | 825.00    |
| 3                                                                                                                                                                                               | Providing and fixing 15mm (fifteen millimetre) nominal bore C.P. brass stop cock for basin mixer and geyser points of approved quality conforming to IS:8931 of 'Isapur' (COB-CHE-059851)/Hindware Make including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi royalty malkhana toll tax sale tax, GST or other taxes imposed by the Government     | 30.00  | Each   | 350.00 | Rupees Three Hundred Fifty Only                 | 10500.00  |
| 4                                                                                                                                                                                               | Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete semi rigid pipe 52mm (thirty two millimetre) dia of Hindware or G.I. make including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals The rates are inclusive of octroi royalty malkhana toll tax sale tax, GST or other taxes imposed by the Government            | 50.00  | Each   | 160.00 | Rupees One Hundred Sixty Only                   | 8000.00   |
| 5                                                                                                                                                                                               | Providing and fixing 100 mm dia C.P. flaring including fitting complete for gully floor or main trap. The rate includes sale tax octroi royalty malkhana toll tax, GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                        | 50.00  | Each   | 150.00 | Rupees One Hundred Fifty Only                   | 7500.00   |
| 6                                                                                                                                                                                               | Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit sliver thickness complete. The rate includes sale tax octroi royalty malkhana toll tax, GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                     | 21.00  | Each   | 120.00 | Rupees One Hundred Twenty Only                  | 2520.00   |
| 7                                                                                                                                                                                               | Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plaster float complete 25 mm nominal bore The rate includes sale tax octroi royalty malkhana toll tax, GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                            | 15.00  | Each   | 650.00 | Rupees Six Hundred Fifty Only                   | 9750.00   |
| 8                                                                                                                                                                                               | Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 25 mm dia nominal bore. The rate includes sale tax octroi royalty malkhana toll tax, GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                   | 150.00 | Per ft | 350.00 | Rupees Three Hundred Fifty Only                 | 52500.00  |
|                                                                                                                                                                                                 | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PW (B) (17) 2703012 Dated 07.08.2018                                                                                                                                                                                                                                                                                                                      |        |        |        | Total                                           | 97765     |
|                                                                                                                                                                                                 | Note 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter no. PW (B) (A) (31) 2020 Dated 22.07.2020 & Govt. of HP vide letter no. PW (B) (A) (31) 2020-1 Dated 07.10.2021                                                                                                                                                                                                                                           |        |        |        |                                                 |           |
|                                                                                                                                                                                                 | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |        |        |                                                 |           |
|                                                                                                                                                                                                 | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |        |        |        |                                                 |           |
|                                                                                                                                                                                                 | Note: Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                       |        |        |        |                                                 |           |

Executive Engineer,  
H.F.P.W.D. Division Haroli  
Distt. Una (H.P.)

S49




| SCHEDULE OF QUANTITY                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 |                |                                                |        |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------|----------------|------------------------------------------------|--------|
| Name of work :- C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar. (SH C/O Edge Wall at RD 0/010 to 0/041) (Deposit work ) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | Estimated Cost | 88627/-                                        |        |
|                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | Earnest Money  | 2000/-                                         |        |
|                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 | Time limit     | One month                                      |        |
| Sl. No.                                                                                                                                                              | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit            | Figures        | RATE In Words                                  | AMOUNT |
| 1                                                                                                                                                                    | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803, 1202 & 1203. P.C.C. grade M 10 Nominal Mix 1: 3: 6, including carriage of materials within all leads and lifts and other incidental. . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty, malkhana , toll tax, GST, labour cess or other taxes imposed by the Government .. | 23.02    | Per cubic metre | 3850.00        | Rupees Three Thousand Eight Hundred Fifty Only | 88627  |
|                                                                                                                                                                      | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                             |          |                 |                | Total:                                         | 88627  |
|                                                                                                                                                                      | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |                 |                |                                                |        |
|                                                                                                                                                                      | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                 |                |                                                |        |
|                                                                                                                                                                      | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                         |          |                 |                |                                                |        |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

SLE

**Schedule of quantity**

| Name of work : C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        | Estimated Cost: Rs | Time:- | ₹ 99,085 | One month |
|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|----------------------------------------|--------|--------------------|--------|----------|-----------|
| (SH: Providing & laying 20mm thick premix carpet at Rd. 2/714 to 3/052 )                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        | Earnest Money:-    |        | 2000     |           |
| S.NO                                                                                             | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty    | Unit | T.Rate  | Rate in words                          | Amount |                    |        |          |           |
| 1                                                                                                | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                         | 13.94  | cum  | 1300.00 | Rupees One Thousand Three Hundred Only | 18125  |                    |        |          |           |
| 2                                                                                                | Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                  | 241.67 | sqm  | 55.00   | Rupees FiftyFive Only                  | 13292  |                    |        |          |           |
| 3                                                                                                | Providing laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 241.67 | sqm  | 200.00  | Rupees Two Hundred Only                | 48334  |                    |        |          |           |
| 4                                                                                                | Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                         | 241.67 | sqm  | 80.00   | Rupees Eighty Only                     | 19334  |                    |        |          |           |
|                                                                                                  | Note 1 ) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW/ (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |        |      |         | Total                                  | 99085  |                    |        |          |           |
|                                                                                                  | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW/ (B) (A) (3) 1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW/ (B) (A) (3) 1/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  | Note -Rate entered in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |        |                    |        |          |           |

  
**Executive Engineer,**  
**H.P.P.W.D. Division,**  
**Distt. Una (H.P.)**

Schedule of Quantity

Estimated cost : 85000  
 Earnest Money : 1700  
 Time Limit : 15 day

Name of Work : Construction of road from Lower Panjawar covering Saini Muhalla, Dhakki Muhalla up to Daulatpur link road & Nagdoli Petrol Pump via ward No.5 up to Shiv Mandir Panjawar & Maadu Ki Nihali se Madan-Ka-Ghar Tak village Panjawar Km 0/00 to 8/000 (SH: Preparation of working estimate and DNIT including submission of Hard and soft copies)- under NABARD.-XXXI

| S. No. | Description of item                                                                                                                                                                                                                                                                             | Qty. | Unit | Rate (Rs.) | Rate in words                    | Amount (Rs.) |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|------------|----------------------------------|--------------|
| 1      | Preparation and approval of working estimate and Drafts Schedule of quantity from higher authority including submission of 5-set of estimate and soft copy of estimate .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 1    | Each | 85000      | Rupees Eighty five thousand only | 85000        |
|        | 1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                          |      |      |            | Total =                          | 85000        |
|        | Percentage quoted rate in Figures                                                                                                                                                                                                                                                               |      |      |            |                                  |              |
|        | Percentage quoted rate in words                                                                                                                                                                                                                                                                 |      |      |            |                                  |              |
|        | Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.                                                                                                                                                                                  |      |      |            |                                  |              |

Executive Engineer  
 Haroli Division  
 HPPWD Haroli

520

5

# SCHEDULE OF QUANTITY

Estimated Cost 99318  
Earliest Money 2000/-  
Time limit One month

Name of work: C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH : C/O R/wall at RHS of Science Lab building) - Deposit work

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Unit             | RATE IN |                                         | AMOUNT |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                  | Figures | Words                                   |        |
| 1       | Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil/jumper work and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of claused and 1600 1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi royalty malikhana toll tax GST labour cess or other taxes imposed by the Government | 25.5     | Per cubic metre  | 155     | Rupees One hundred fifty five only      | 3953   |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi royalty malikhana toll tax sale tax GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 21.6     | Per cubic metre  | 170     | Rupees One hundred seventy only         | 3672   |
| 3       | Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 20x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering scrubbing and propping etcetera with wooden battens and baulies for all heights of propping and centering below supporting floor to ceiling not exceeding 4m (four metre) and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as in all thickness including carriage of material entire within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi royalty malikhana toll tax sale tax GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 40.2     | Per square metre | 220     | Rupees two hundred twenty only          | 8844   |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi royalty malikhana toll tax GST labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 24.63    | Per cubic metre  | 3400    | Rupees three thousand four hundred only | 83742  |

| S                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 18 | Each | 17C | Rupees One hundred seventy only | 3660  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|-----|---------------------------------|-------|
| Providing weepholes in brick masonry/ stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana toll tax GST labour cess or other taxes imposed by the Government. |    |      |     | Total:                          | 99318 |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)10(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                        |    |      |     |                                 |       |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                              |    |      |     |                                 |       |
| Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |    |      |     |                                 |       |
| Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |    |      |     |                                 |       |
| Note: - Rate quoted in figures & words are mandatory by the contractor otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |     |                                 |       |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

**Schedule of quantity**

| Name of work :- C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar, |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |                                                | Estimated Cost: Rs | ₹ 99,661  |
|--------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------------|--------------------|-----------|
| ISH- C/O Edge wall at Rd. 0/000 to 0/000 & P/L Embankment GSE at Rd.0/00 to 0/000                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |                                                | Time:-             | One month |
| S.NO                                                                                                         | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Qty   | Unit | T.Rate  | Rate in words                                  | Earnest Money:-    | 2000      |
| 1                                                                                                            | Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 64.80 | Cum. | 240.00  | Rupees Two Hundred Forty Only                  |                    | 15552.00  |
| 2                                                                                                            | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 . including carriage of materials within all leads and lifts and other incidental . . including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                         | 15.68 | Cum  | 3850.00 | Rupees Three Thousand Eight Hundred Fifty Only |                    | 60349.00  |
| 3                                                                                                            | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.          | 21.60 | Cum  | 1100.00 | Rupees One Thousand One Hundred Only           |                    | 23760.00  |
|                                                                                                              | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                           |       |      |         | Total                                          |                    | 99661     |
|                                                                                                              | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                               |       |      |         |                                                |                    |           |
|                                                                                                              | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         |                                                |                    |           |
|                                                                                                              | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |                                                |                    |           |
|                                                                                                              | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                                |                    |           |

**Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)**

**SCHEDULE OF QUANTITY**

Name of work - C/O Height & width gauge barricade at entry point to Swan river at Bathri Near Gatta Factory & Tahliwal near ANM School Tehsil Haroli Distt. Una (HP)

Estimated Cost 89216  
Earnest Money 1800/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Unit             | RATE IN |                                               | AMOUNT |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                  | Figures | Words                                         |        |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                             | 4.02     | Per cubic metre  | 170     | Rupees One hundred Seventy only               | 683    |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 0.46     | Per cubic metre  | 3400    | Rupees three thousand four hundred only       | 1564   |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                       | 1.11     | Per cubic metre  | 4750    | Rupees four thousand seven hundred fifty only | 5273   |
| 4       | Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns, the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 9        | Per square metre | 280     | Rupees two hundred eighty only                | 2520   |
| 5       | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required wherever required, all complete in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                   | 706      | Per Kilogramme   | 110     | Rupees One hundred ten only                   | 77660  |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |                  |     |                            |                          |       |
|----|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|-----|----------------------------|--------------------------|-------|
| ii | Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 11.84 | Per square metre | 128 | Rupees hundred twenty only | one hundred eighty eight | 1516  |
|    | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)03(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                               |       |                  |     | Total:                     |                          | 89216 |
|    | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                   |       |                  |     |                            |                          |       |
|    | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                        |       |                  |     |                            |                          |       |
|    | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                          |       |                  |     |                            |                          |       |
|    | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                            |       |                  |     |                            |                          |       |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

**Draft Schedule of quantity**

| Name of work :-Restoration of rain damages on Panjawaar Bathri road km. 0/00 to 34/00                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|-----------------------------------------|--------|
| (S.H :-Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-IV                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| Estimated Cost: Rs                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Time:- |      |         |                                         |        |
| One month                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 2000   |      |         |                                         |        |
| Draft Schedule of quantity                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| Earnest Money:-                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| S.NO                                                                                                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty    | Unit | T.Rate  | Rate in words                           | Amount |
| 1                                                                                                                                                                        | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Plain Cement concrete grade M15 nominal mix 1:2.5:5, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                             | 13.00  | Cum  | 4800.00 | Rupees Four Thousand Eight Hundred Only | 62400  |
| 2                                                                                                                                                                        | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Reinforced Cement concrete grade M20 nominal mix 1:2:4 in Bed block & dirt wall, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 5.84   | Cum  | 4500.00 | Rupees Four Thousand Five Hundred Only  | 26302  |
| 3                                                                                                                                                                        | Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawings and technical specification Clauses 1002, 1010 and 1202. HPSR 2009 Item No. 13.3, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                            | 115.00 | Kg   | 95.00   | Rupees NinetyFive Only                  | 10925  |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         | Total:                                  | 99627  |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(31)/2020 dated 22.07.20  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| Percentage quoted rate in Figures                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| Percentage quoted rate in words                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         |                                         |        |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

503

Schedule of Quantity

Estimated cost :  
Earnest Money :  
Time Limit :

14000-70320/-  
1700  
15 day

Name of Work : Construction of Rajiv Gandhi Day Boarding School at Haroli Distt. Una ( SH: Preparation of Topographical & Contour site plan )

| S. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                   | Qty. | Unit  | Rate (Rs.) | Rate in words               | Amount (Rs.) |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|------------|-----------------------------|--------------|
| 1      | Preparation of Topographical & Contour site plan of Day Boarding School Gram Panchayat Haroli which include showing all features like road, buildings, sheds, Electrical/ Telephone poles, drain, Manholes, Major trees, water bodies, open land, park, play ground, boundary etc. ( Area = 5.86 Acres). The rate includes sale tax octroi, royalty, malikhana , toll tax, GST, labour cess or other taxes imposed by the Government. | 5.86 | Acres | 12000      | Rupees Twelve thousand only | 70320        |
|        | 1) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                |      |       |            | Total =                     | 70320        |
|        | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                     |      |       |            |                             |              |
|        | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                       |      |       |            |                             |              |
|        | Note:- Rate quoted in figures & words are mandatory by the contractor , otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                        |      |       |            |                             |              |

  
Executive Engineer  
Haroli Division  
HPPWD Haroli

521

# SCHEDULE OF QUANTITY

Name of work: C/O Science Lab GSSS Lalri Tehsil Haroli Distt. Una (SH.C/O R/wall) at Back side of Science Lab building-Phase-II ) - Estimated Cost 96098  
 Deposit work Earnest Money 2000/-  
 Time limit One month.

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Unit             | RATE IN |                                         | AMOUNT |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  | Figures | Words                                   |        |
| 1       | Excavation in fully area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of claused and 1600 1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out, including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government | 93.5     | Per cubic metre  | 155     | Rupees One hundred fifty five only      | 14493  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 13.2     | Per cubic metre  | 170     | Rupees One hundred seventy only         | 2244   |
| 3       | Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick webbed with angle iron in frame of 30x30x5 mm (thirty into thirty five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and bales for all heights of propping and centering below supporting floor to ceiling not exceeding 4m (four metre) and removal of same for in-situ reinforced concrete and plain concrete work in flat surfaces such as in all thickness including carriage of material entire within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 37       | Per square metre | 220     | Rupees two hundred twenty only          | 8140   |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement, four sand eight graded crushed broken stone aggregate 40mm (forty millimeter) nominal size in or under water ground complete including pumping or bailing out water dewatering removal of such as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 24.31    | Per cubic metre  | 3400    | Rupees three thousand four hundred only | 82654  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |     |                                 |       |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|-----|---------------------------------|-------|
| 3 | Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre)dia PVC pipe extending through the full width of the structures with slope of 1(v):20(h)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government. | 18 | Each | 170 | Rupees One hundred seventy only | 3080  |
|   | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)A/31/2020 dated 22.07.20                                                                                                                                                                                                                                    |    |      |     | Total                           | 96098 |
|   | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |    |      |     |                                 |       |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |     |                                 |       |
|   | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |    |      |     |                                 |       |

  
**Executive Engineer,**  
**H.P.P.W.D. Division Haroli**  
**Distt. Una (H.P.)**

11

| SCHEDULE OF QUANTITY                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      |                |                                          |           |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|----------------|------------------------------------------|-----------|
| Name of work: C/o Link rod from Nagnoli to SC Basti Via Chaprian Gaur Bagirian Chotti khad Gujran Thrkhana Nainan (SH:- P/L 80mm paver blocks in RD 0/985 to 1/008 )Deposit work |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      | Estimated Cost |                                          | 99764/-   |
|                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      | Earnest Money  |                                          | 2000/-    |
|                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      | Time limit     |                                          | One month |
| SL No.                                                                                                                                                                           | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | Unit | RATE IN        |                                          | AMOUNT    |
|                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      | Figures        | Words                                    |           |
| 1                                                                                                                                                                                | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement 4 coarse sand) 8 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                                                            | 1.48     | Cum  | 3300 00        | Rupees three thousand three hundred only | 4884      |
| 2                                                                                                                                                                                | Providing and laying of interlocking concrete block pavements having thickness 80mm thick as per drawing and technical specification clause 1504, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                               | 105.80   | Sqm  | 850 00         | Rupees eight hundred fifty only          | 89930     |
| 3                                                                                                                                                                                | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge. | 1.10     | Cum  | 4500 00        | Rupees four thousand five hundred only   | 4950      |
|                                                                                                                                                                                  | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)/6(1712/0212 dated 28.2.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |      |                | Total:                                   | 99764     |
|                                                                                                                                                                                  | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)/A(311/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |      |                |                                          |           |
|                                                                                                                                                                                  | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      |                |                                          |           |
|                                                                                                                                                                                  | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      |                |                                          |           |
|                                                                                                                                                                                  | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |      |                |                                          |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

12

**Schedule of quantity**

| Name of work : Retoration & rain damages on link road from Village Baliwal to Peersthan km. 0/00 to 3/050 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Estimated Cost: Rs | ₹ 92,854 |
|-----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|----------|
| (SH: C/O R/wall Rd. 0/400 to 0/408.50 Lhs)                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Time:-             | 97870    |
|                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Earnest Money:-    | 2000     |
| S.NO                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T.Rate  | Rate in words                            | Amount             |          |
| 1                                                                                                         | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 8.29  | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 1326               |          |
| 2                                                                                                         | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 27.80 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 92204              | 91740/-  |
| 3                                                                                                         | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                   | 16.00 | nos  | 160.00  | Rupees One Hundred Sixty Only            | 2560               |          |
| 4                                                                                                         | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 4.08  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           | 2244               |          |
|                                                                                                           | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         | Total                                    | 97870/-            | 97870/-  |
|                                                                                                           | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |          |
|                                                                                                           | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |          |
|                                                                                                           | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |                    |          |
|                                                                                                           | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |                    |          |

**Schedule of quantity**

|                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          |             |
|------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|-------------|
| Name of work > C/O Sampark marg from Link road to the House of Sh. Ram Asra at Village Kangar G.P. Kangar. |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         | Estimated Cost: Rs                       | ₹ 99,064    |
| (H.V.) 60 mm thick paver blocks at Rd. C/120 to D/160 36)                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         | Unit                                     | (Per month) |
| S.NO                                                                                                       | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                           | Qty   | Unit | T.Rate  | Rate in words                            | Amount      |
| 1                                                                                                          | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of materials within all leads and lifts and other incidental - The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                    | 8.12  | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 26796.00    |
| 2                                                                                                          | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental - The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                           | 81.20 | sqm  | 800.00  | Rupees Eight Hundred Only                | 64960.00    |
| 3                                                                                                          | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malikana, toll tax, sale tax or other taxes imposed by the Government. | 1.62  | Cum. | 4500.00 | Rupees Four Thousand Five Hundred Only   | 7308.00     |
|                                                                                                            | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                     |       |      |         | Total                                    | 99064       |
|                                                                                                            | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                     |       |      |         |                                          |             |
|                                                                                                            | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |             |
|                                                                                                            | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          |             |
|                                                                                                            | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                          |       |      |         |                                          |             |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

5/7

IV

Schedule of quantity


| Name of work:- Repair & Restoration of Pandoga Barrier to panjawar Km. 0/00 to 9/00<br>( SH: C/O U-Shape drain at RD. 2/648 to 2/708 Rhs ). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Estimated Cost: Rs                        | ₹ 97,578  |
|---------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------------------------------------------|-----------|
|                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Time:-                                    | One month |
|                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Earnest Money:-                           | 2000      |
| S.NO                                                                                                                                        | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty   | Unit | T.Rate  | Rate in words                             | Amount    |
| 1                                                                                                                                           | Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government | 28.35 | CUM. | 160.00  | (Rupees one hundred sixty only)           | 4536      |
| 2                                                                                                                                           | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government                                                                                               | 21.60 | CUM. | 3900.00 | (Rupees Three Thousand Nine hundred only) | 84240     |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |       |      |         |                                            |       |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|--------------------------------------------|-------|
| 3 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(1)nominal mix 1:1.5:3. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the | 0.54  | CUM. | 5500.00 | (Rupees Three Thousand Three hundred only) | 2970  |
| 4 | Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government                                      | 64.80 | CUM. | 90.00   | (Rupees Three Thousand Three hundred only) | 5832  |
|   | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)0(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                    |       |      |         | Total:                                     | 97578 |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                       |       |      |         |                                            |       |
|   | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                            |       |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                              |       |      |         |                                            |       |
|   | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                            |       |

Executive Engineer,  
H.P.P.W.D. Division, Haroli

# **Schedule of quantity**

| Name of work: - Restoratin of rain damages on Link road Saloh Nursary to Harijan Basti Saloh km. 0/00 to 2/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Estimated Cost: Rs             | ₹ 98,280  |
|---------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|--------------------------------|-----------|
| (SH: Repair of Rain cuts at Various RDs from km. 1/00 to 2/00)                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Time:-                         | One month |
|                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Earnest Money:-                | 2000      |
| S.NO                                                                                                          | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty    | Unit | T.Rate | Rate in words                  | Amount    |
| 1                                                                                                             | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 409.50 | Cum  | 240.00 | Rupees Two Hundred Fourty Only | 98280     |
|                                                                                                               | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                            |        |      |        | Total:                         | 98280     |
|                                                                                                               | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                              |        |      |        |                                |           |
|                                                                                                               | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |      |        |                                |           |
|                                                                                                               | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |           |
|                                                                                                               | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                       |        |      |        |                                |           |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

507

# SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Umralli Singan road km. 0.00 to 6.550(SH :- P/L 60mm thick paver blocks in term at RD 1/356.40 to 1/375 BHS)

Estimated Cost 98682/-  
Earnest Money 2000/-  
Time limit: One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Unit | RATE IN |                                          | AMOUNT |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|---------|------------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |      | Figures | Words                                    |        |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) 1 manual means in foundation trenches or drains including dressing of sides and ramming of bottoms. lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax sale tax GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                   | 19.05    | cum  | 160.00  | Rupees one hundred sixty only            | 3048   |
| 2       | Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by plant mix method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 kN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification clause 402 for grading -1 material including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax GST labour cess or other taxes imposed by the Government.                                                                      | 7.50     | cum  | 1100.00 | Rupees one thousand one hundred only     | 8250   |
| 3       | Providing and laying mechanically mixed and vibrated concrete for plant/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST labour cess or other taxes imposed by the Government.                           | 7.48     | cum  | 3300.00 | Rupees three thousand three hundred only | 24684  |
| 4       | Providing and fixing heavy duty precast cement concrete inter locking paver block pavements having thickness 60mm ( Sixty millimetre) (ISI mark) including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 75.00    | sqm  | 800.00  | Rupees eight hundred only                | 60000  |
| 5       | Providing and laying mechanically mixed and vibrated concrete for plant/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (Twenty) nominal mix 1:2:4 ( One cement two sand four graded crushed broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST labour cess or other taxes imposed by the Government. | 0.60     | cum  | 4500.00 | Rupees four thousand five hundred only   | 2700   |
|         | <b>TOTAL:-</b> 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)6(1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         | Total:                                   | 98682  |
|         | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B)A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |          |      |         |                                          |        |
|         | Note :- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |      |         |                                          |        |
|         | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |      |         |                                          |        |
|         | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |      |         |                                          |        |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

Schedule of quantity

| Name of work: -Repair of pot holes on link road Saloh Nursery to Harijan Basti Saloh km. 0/00 to 2/00 Under 5054-MMSRRY (Balance work) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         | Estimated Cost: Rs                     | ₹ 98,456  |
|----------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|----------------------------------------|-----------|
| (SH: Repair of pot hole at Rd. 1/660 to 2/000)                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |        |      |         | Time:-                                 | One month |
| S.NO                                                                                                                                   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty    | Unit | T. Rate | Earnest Money:-                        | 2000      |
| 1                                                                                                                                      | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 9.35   | cum  | 1300.00 | Rupees One Thousand Three Hundred Only | 12155     |
| 2                                                                                                                                      | Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                          | 243.10 | sqm  | 55.00   | Rupees FiftyFive Only                  | 13371     |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                          |        |     |        |                           |       |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----|--------|---------------------------|-------|
| 3 | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 243.10 | sqm | 300 00 | Rupees Three Hundred Only | 72930 |
|   | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                        |        |     |        | Total                     | 98456 |
|   | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021                                                                                                                                                                            |        |     |        |                           |       |
|   | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                        |        |     |        |                           |       |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                          |        |     |        |                           |       |
|   | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                             |        |     |        |                           |       |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

Estimated Cost  
87720/-  
Earnest Money  
20000/-  
Time limit  
One month

**SCHEDULE OF QUANTITY**  
Name of work: C/O Science Lab GSSS Laini Tehsil Haroli Distt. Una (SH:C/O R/wall at Back side of Science Lab building- Phase-I ) - Deposit work

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Unit             | RATE IN |                                         | AMOUNT |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  | Figures | Words                                   |        |
| 1       | Excavation in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil/ jumper work and their intermediate classification of soil, setting out true to the required lines, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the technical specification MORD 2014 section 300 of clause and 1600.1 and sorting out useful materials and stacking the same in all leads and lifts on acquired width of road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tool and labour if required. Any loss to the public private property during the course to execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all the cases as per the direction of engineer-in-charge including carriage of material with in all leads and lifts. All useful material such as stone, shingle, sand and slates etcetera shall be sorted out including carriage of material with in all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 85       | Per cubic metre  | 155     | Rupees One hundred fifty five only      | 13175  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | 12       | Per cubic metre  | 170     | Rupees One hundred seventy only         | 2040   |
| 3       | Providing form work with steel plates 3.15mm(three decimal fifteen millimeter) thick welded with angle iron in frame of 30x30x5 mm (thirty into thirty into five millimeter) size so as to give a fair finish including centering shuttering strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling not exceeding 4m (four metre) and removal of same for in situ reinforced concrete and plain concrete work in flat surfaces such as in all thickness including carriage of material entire within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 34       | Per square metre | 220     | Rupees two hundred twenty only          | 7480   |
| 4       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 22.1     | Per cubic metre  | 3400    | Rupees three thousand four hundred only | 75140  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |     |                                 |       |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|------|-----|---------------------------------|-------|
| 5 | Providing weepholes in brick masonry/ stone masonry (plan reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614.709.1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax GST, labour cess or other taxes imposed by the Government. | 18 | Each | 170 | Rupees One hundred seventy only | 3060  |
|   | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(E)1712/02112 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                         |    |      |     | Total                           | 87720 |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No.PBW(B)(A)(3)172020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                             |    |      |     |                                 |       |
|   | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |    |      |     |                                 |       |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |    |      |     |                                 |       |
|   | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |    |      |     |                                 |       |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

79

**Draft Schedule of quantity**

| Name of work :- Restoration of rain damages on Panjavar Bathri road km. 0/00 to 34/00 |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | Estimated Cost: Rs                   |  | ₹ 99,385     |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|--------------------------------------|--|--------------|
| (S.H : Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-V                  |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | Time:-                               |  | One month    |
|                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | Earnest Money:-                      |  | 2000         |
| S. NO                                                                                 | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                         | Qty    | Unit | T. Rate | Rate in words                        |  | Amount       |
| 1                                                                                     | Providing and laying reinforced cement concrete in superstructure complete as per drawings and Technical Specification Clauses 800, 1205.4 and 1205.5 Reinforced Cement Concrete Grade M25 (1:1.5:3) Nominal mix. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 6.40   | Cum  | 6100.00 | Rupees Six Thousand One Hundred Only |  | 39060        |
| 2                                                                                     | Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawings and technical specification Clauses 1002, 1010 and 1202. HPSR 2009 Item No. 13.3, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                | 635.00 | Kg   | 95.00   | Rupees NinetyFive Only               |  | 60325        |
|                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | <b>Total:</b>                        |  | <b>99385</b> |
|                                                                                       | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)6(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                          |        |      |         |                                      |  |              |
|                                                                                       | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                              |        |      |         |                                      |  |              |
|                                                                                       | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                   |        |      |         |                                      |  |              |
|                                                                                       | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         |                                      |  |              |
|                                                                                       | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                       |        |      |         |                                      |  |              |

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

504



**SCHEDULE OF QUANTITY**

Name of work:- C/O Height & width gauge barricade at entry point to Swan river at Bathu & Tahliwal near ANM School Tehsil Haroli Distt. Una (HP)

Estimated Cost 83033  
Earnest Money 1700/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity | Unit             | RATE IN |                                               | AMOUNT    |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                  | Figures | Words                                         |           |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                              | 2.01     | Per cubic metre  | 170     | Rupees hundred Seventy only                   | One 342   |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 40mm (forty millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 0.23     | Per cubic metre  | 3400    | Rupees three thousand four hundred only       | 782       |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 1.01     | Per cubic metre  | 4750    | Rupees four thousand seven hundred fifty only | 4798      |
| 4       | Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 4 5      | Per square metre | 280     | Rupees hundred eighty only                    | 1260      |
| 5       | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required wherever required, all complete in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                             | 662      | Per Kilogramme   | 110     | Rupees hundred only                           | One 72820 |

|                                                                                                                                                                                                                                                                                                                                  |       |                  |     |                            |          |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|-----|----------------------------|----------|
| finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 23.68 | Per square metre | 128 | Rupees hundred twenty only | one 3031 |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B) (17)2/0212 dated 7.8.2018                                                                                                                                                       |       |                  |     | Total:                     | 83033    |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B)A/31/2020 dated 22.07.20                                                                                                                                                           |       |                  |     |                            |          |
| Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                |       |                  |     |                            |          |
| Percentage quoted rate in words                                                                                                                                                                                                                                                                                                  |       |                  |     |                            |          |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                    |       |                  |     |                            |          |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

(21)

| SCHEDULE OF QUANTITY                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         |                                          |        |           |  |  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|---------|------------------------------------------|--------|-----------|--|--|
| Name of work: C/o Link rod from Nagnoli to SC Basti Via Chaprian Gaur Bagirian Chotti khad Gujran Thrkhana Nainan (SH:- P/L 80mm paver blocks in RD 0/939 to 0/962 )Deposit work |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         | Estimated Cost                           |        | 59237/-   |  |  |
|                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         | Earnest Money                            |        | 2000/-    |  |  |
|                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         | Time limit                               |        | One month |  |  |
| Sl. No.                                                                                                                                                                          | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Unit | Figures | Words                                    | Amount |           |  |  |
| 1                                                                                                                                                                                | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement 4 coarse sand) 8 graded stone aggregate 40 mm nominal size) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government                                                                                                                                                                                                                                                                              | 1.44     | Cum  | 3300 00 | Rupees three thousand three hundred only | 4752   |           |  |  |
| 2                                                                                                                                                                                | Providing and laying of interlocking concrete block pavements having thickness 80mm thick as per drawing and technical specification clause 1504, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana toll tax, GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                  | 106.50   | Sqm  | 850 00  | Rupees eight hundred fifty only          | 90525  |           |  |  |
| 3                                                                                                                                                                                | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803, 1202 and 1203 as per the direction of the Engineer-in-charge. | 0.88     | Cum  | 4500 00 | Rupees four thousand five hundred only   | 3960   |           |  |  |
|                                                                                                                                                                                  | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/017/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      |         | Total:                                   | 99237  |           |  |  |
|                                                                                                                                                                                  | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)/A(3)/1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |      |         |                                          |        |           |  |  |
|                                                                                                                                                                                  | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |      |         |                                          |        |           |  |  |
|                                                                                                                                                                                  | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |      |         |                                          |        |           |  |  |
|                                                                                                                                                                                  | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |      |         |                                          |        |           |  |  |

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

**Schedule of quantity**

| Name of work : Retoration & rain damages on link road from Village Baliwal to Peersthan km. 0/00 to 3/050                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                          | Estimated Cost: Rs | ₹ 98,174  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-----------|
| (SH: C/O R/wall Rd. 0/417.00 to 0/425.50 Lhs)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          | Time:-             | One month |
| DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                          | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Qty   | Unit | T.Rate  | Rate in words                            | Amount             |           |
| 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 8.29  | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 1326               |           |
| Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. |       |      |         |                                          |                    |           |
| 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 27.80 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 91740              |           |
| Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  |       |      |         |                                          |                    |           |
| 3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 18.00 | nos  | 160.00  | Rupees One Hundred Sixty Only            | 2880               |           |
| Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               |       |      |         |                                          |                    |           |
| 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 4.08  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           | 2244               |           |
| Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    |       |      |         |                                          |                    |           |
| Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          | Total              | 98174     |
| 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |           |
| Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |           |
| Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |                    |           |
| Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |                    |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

S10

| SCHEDULE OF QUANTITY                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      |         |                                          |        | Estimated Cost | 98748/-   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|---------|------------------------------------------|--------|----------------|-----------|
| Name of work :- Restoration of rain damages on Umralli Singan road km. 0/00 to 6/550(SH :- P/L 60mm thick paver blocks in berm at RD 1/337.80 to 1/356.40 BHS) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      |         |                                          |        | Earnest Money  | 2000/-    |
|                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      |         |                                          |        | Time limit     | One month |
| Sl. No.                                                                                                                                                        | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Unit | RATE IN |                                          | AMOUNT |                |           |
|                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      | Figures | Words                                    |        |                |           |
| 1                                                                                                                                                              | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive of octroi, royalty, Malkana toll tax, sale tax, GST labour cess or other taxes imposed by the Government. | 19.05    | cum  | 160.00  | Rupees one hundred sixty only            | 3048   |                |           |
| 2                                                                                                                                                              | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                  | 7.50     | cum  | 1100.00 | Rupees one thousand one hundred only     | 8250   |                |           |
| 3                                                                                                                                                              | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                             | 7.50     | cum  | 3300.00 | Rupees three thousand three hundred only | 24750  |                |           |
| 4                                                                                                                                                              | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkana, toll tax, GST labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                           | 75.00    | sqm  | 800.00  | Rupees eight hundred only                | 60000  |                |           |
| 5                                                                                                                                                              | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth including carriage of materials within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, Malkana, toll tax, GST labour cess or other taxes imposed by the Government.                                                                                                                                                                      | 0.60     | cum  | 4500.00 | Rupees four thousand five hundred only   | 2700   |                |           |
|                                                                                                                                                                | Total -                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |      |         |                                          | 98748  |                |           |
|                                                                                                                                                                | 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW/B/52(1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                             |          |      |         |                                          |        |                |           |
|                                                                                                                                                                | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |      |         |                                          |        |                |           |
|                                                                                                                                                                | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |      |         |                                          |        |                |           |
|                                                                                                                                                                | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |          |      |         |                                          |        |                |           |
|                                                                                                                                                                | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |      |         |                                          |        |                |           |

  
 Executive Engineer,  
 H.P.P.W.D. Division Haroli  
 Distt. Una (H.P.)

(24)

SCHEDULE OF QUANTITY

| SCHEDULE OF QUANTITY                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      |                  |                               |        |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------|------------------|-------------------------------|--------|
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Estimates cost:- | 98208/-                       |        |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Earnest Money:-  | Rs. 2000/-                    |        |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Time Limit:-     | One Month                     |        |
| Name of work:- Restoration of rain damages on Link road Sahi Nursery to Harijan Basti Sahi km. 0/00 to 2/00 SII: Repair of Rain cuts at Various RDs from km. 0/00 to 1/00) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      |                  |                               |        |
| S. No.                                                                                                                                                                     | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Unit | RATE In          |                               | AMOUNT |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      | Figures          | Words                         |        |
| 1                                                                                                                                                                          | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 150 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 479.20   | cum  | 240.00           | Rupees two hundred forty only | 98208  |
| Note:-                                                                                                                                                                     | NOTE 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)A(3)17/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                          |          |      |                  | Total:-                       | 98208  |
| 1                                                                                                                                                                          | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt of HP vide letter No PBW(B) A(3)14/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3)17/2020-1 dated 7.10.2021                                                                                                                                                                                                                                          |          |      |                  |                               |        |
|                                                                                                                                                                            | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |      |                  |                               |        |
|                                                                                                                                                                            | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |      |                  |                               |        |
|                                                                                                                                                                            | Note: Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                       |          |      |                  |                               |        |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

506

**Draft Schedule of quantity**

| Name of work :- Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                             | Estimated Cost: Rs | ₹ 99,243     |
|--------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------------------------------------|--------------------|--------------|
| (S.H :- Construction of 4.00 mtrs span culvert at Rd. 32/350) (Phase-I)              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                             | Time:-             | One month    |
| S.NO                                                                                 | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Qty   | Unit | T.Rate  | Rate in words                               | Earnest Money:-    |              |
|                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                             | 2000               | Amount       |
| 1                                                                                    | Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix). Including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                           | 60.83 | Cum. | 950.00  | Rupees Nine Hundred Fifty Only              |                    | 57788        |
| 2                                                                                    | Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in trenches with excavated suitable material. Ordinary soil upto 3.00 metre depth. Including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 61.78 | Cum. | 160.00  | Rupees One Hundred Sixty Only               |                    | 9884         |
| 3                                                                                    | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                       | 4.99  | nos  | 3600.00 | Rupees Three Thousand Six Hundred Only      |                    | 17971        |
| 4                                                                                    | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and Technical Specification Clauses 802, 803, 1202 and 1203. Plain Cement concrete grade M10 Nominal mix 1:3:6. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                             | 3.20  | Cum. | 4250.00 | Rupees Four Thousand Two Hundred Fifty Only |                    | 13600        |
|                                                                                      | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(e)(172)/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         | <b>Total:</b>                               |                    | <b>99243</b> |
|                                                                                      | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                               |       |      |         |                                             |                    |              |
|                                                                                      | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                             |                    |              |
|                                                                                      | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                             |                    |              |
|                                                                                      | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         |                                             |                    |              |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

10/3

**Schedule of quantity**

Name of work - C/O Sampark marg from Link road to the House of Sh. Ram Aasra at Village Kangar G.P. Kangar.

(Sh. P/L 60 mm thick gaver blocks at Ee u/uo re U/020)

| Estimated Cost: Rs |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         | 2000                                     |
|--------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|
| Year:-             |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         | Grand month                              |
| Earnest Money:-    |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         | Amount                                   |
| S.NO               | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                           | Qty   | Unit | T. Rate | Rate in words                            |
| 1                  | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                       | 8.00  | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only |
| 2                  | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                             | 80.00 | sqm  | 800.00  | Rupees Eight Hundred Only                |
| 3                  | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 804, 1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government. | 1.60  | Cum. | 4500.00 | Rupees Four Thousand Five Hundred Only   |
|                    | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                     |       |      |         | Total                                    |
|                    | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                         |       |      |         | 97600                                    |
|                    | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |
|                    | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          |
|                    | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                          |       |      |         |                                          |

  
 Executive Engineer,  
 P.W.D. Division Haridwar  
 Distt. Una (H.P.)

97

### Schedule of quantity

| Name of work : Retoration & rain damages on link road from Village Baliwal to Peerthan km. 0/00 to 3/050                                                                                                                                          |       |      |         |                                          | Estimated Cost: Rs | 960144    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-----------|
| (SH: C/O R/wall Rd. 0/408.50 to 0/417.00 Lhs)                                                                                                                                                                                                     |       |      |         |                                          | Time:-             | One month |
| DESCRIPTION                                                                                                                                                                                                                                       |       |      |         |                                          | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                                                                                                                              | Qty   | Unit | T.Rate  | Rate in words                            | Amount             |           |
| 1                                                                                                                                                                                                                                                 | 8.29  | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 1326               |           |
| 2                                                                                                                                                                                                                                                 | 27.80 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 917440             |           |
| 3                                                                                                                                                                                                                                                 | 17.00 | nos  | 160.00  | Rupees One Hundred Sixty Only            | 2720               |           |
| 4                                                                                                                                                                                                                                                 | 4.08  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           | 2244               |           |
|                                                                                                                                                                                                                                                   |       |      |         | Total                                    | 980301             | 98014     |
| Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                 |       |      |         |                                          |                    |           |
| 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021 |       |      |         |                                          |                    |           |
| Percentage quoted rate in figures                                                                                                                                                                                                                 |       |      |         |                                          |                    |           |
| Percentage quoted rate in words                                                                                                                                                                                                                   |       |      |         |                                          |                    |           |
| Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                      |       |      |         |                                          |                    |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

SCHEDULE OF QUANTITY

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

29

**Schedule of quantity**

| Name of Work:- A/R & M/O link road to Gulaban da Tobba Palkwah km. 0/00 to 1/700 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Estimated Cost: Rs | ₹ 98,099    |
|----------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-------------|
| (SH: C/O Retaining wall in Rd. 1/644 to 1/654 Lhs).                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Time:-             | One month   |
| S.NO                                                                             | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T.Rate  | Rate in words                            | Earnest Money:-    | 2000 Amount |
| 1                                                                                | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 10.40 | Cum. | 160.00  | Rupees One Hundred Sixty Only            |                    | 1664        |
| 2                                                                                | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 27.55 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only |                    | 90915       |
| 3                                                                                | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 18.00 | Each | 160.00  | Rupees One Hundred Sixty Only            |                    | 2880        |
| 4                                                                                | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 4.80  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           |                    | 2640        |
|                                                                                  | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)(3)17/2021 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PBW(B)(3)1/2020 dated 22.07.20                                                                                                                                                                                                                              |       |      |         | Total:                                   |                    | 98099       |
|                                                                                  | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |             |
|                                                                                  | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |                    |             |
|                                                                                  | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          |                    |             |

Executive Engineer,  
H.P.P.W.D. Division Haroli

30

Schedule of quantity

| Name of work:- C/O link road Laluwal to Polian km. 0/00 to 3/400 Under 5054-MMSY (Deposit work). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        | Estimated Cost: Rs | ₹ 99,085  |
|--------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|----------------------------------------|--------------------|-----------|
|                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        | Time:-             | One month |
| (SH: Providing & laying 20mm thick premix carpet at Rd. 1/360 to 1/698 )                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        | Earnest Money:-    | 2000      |
| S.NO                                                                                             | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty    | Unit | T.Rate  | Rate in words                          | Amount             |           |
| 1                                                                                                | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density. i/c c/o material with in all leads and lift, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                        | 13.94  | cum  | 1300.00 | Rupees One Thousand Three Hundred Only | 18125              |           |
| 2                                                                                                | Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                   | 241.67 | sqm  | 55.00   | Rupees FiftyFive Only                  | 13292              |           |
| 3                                                                                                | Providing, laying and rolling of open-graded premix carpet of 20 (Twenty) mm thickness composed of 13.2 mm to 5.6 mm aggregates either using penetration grade bitumen or emulsion to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN static roller capacity, finished to required level and grades to be followed by seal coat of either Type A or Type B or Type C as per Technical Specification Clause 508, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government. | 241.67 | sqm  | 200.00  | Rupees Two Hundred Only                | 48334              |           |
| 4                                                                                                | Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510. Including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                         | 241.67 | sqm  | 80.00   | Rupees Eighty Only                     | 19334              |           |
|                                                                                                  | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |        |      |         | Total                                  | 99085              |           |
|                                                                                                  | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PEW (B)A(3)1/2020 Dated 22.07 2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |        |      |         |                                        |                    |           |
|                                                                                                  | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |        |      |         |                                        |                    |           |
|                                                                                                  | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |         |                                        |                    |           |
|                                                                                                  | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |        |      |         |                                        |                    |           |

Executive Engineer,

H.P.P.W.D. Division Haroli

Distt. Una (H.P.)

**Schedule of quantity**

| Name of work : Retoration & rain damages on link road from Village Baliwal to Peersthan km. 0/00 to 3/050 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Estimated Cost: Rs | ₹ 99,222  |
|-----------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-----------|
| (SH: C/O R/wall Rd. 0/425.50 to 0/429.30 Lhs & CC on approach road)                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Time:-             | One month |
| DESCRIPTION                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Earnest Money:-    | 2000      |
| S.NO                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T.Rate  | Rate in words                            | Amount             |           |
| 1                                                                                                         | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 3.71  | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 593                |           |
| 2                                                                                                         | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. Including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                   | 16.83 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 55539              |           |
| 3                                                                                                         | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                   | 6.00  | nos  | 160.00  | Rupees One Hundred Sixty Only            | 960                |           |
| 4                                                                                                         | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 1.82  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           | 1003               |           |
| 5                                                                                                         | Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density, complete as per clause 401. Including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                | 4.40  | Cum. | 1100.00 | Rupees One Thousand One Hundred Only     | 4840               |           |

|   |                                                                                                                                                                                                                                                                                                                                                                               |      |      |         |                                        |               |
|---|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|---------|----------------------------------------|---------------|
| 6 | Providing and laying reinforced cement concrete in superstructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 R.C.C M 25 1:1.5:3 Design Mix. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 6.60 | Cum. | 5500.00 | Rupees Five Thousand Five Hundred Only | 36300         |
|   | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                             |      |      |         | Total                                  | 94232<br>9922 |
|   | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021                                                                                                                                 |      |      |         |                                        |               |
|   | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                             |      |      |         |                                        |               |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                               |      |      |         |                                        |               |
|   | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                  |      |      |         |                                        |               |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

32

# Draft Schedule of quantity

| Name of work :-Restoration of rain damages on Panjawa Bathri road km. 0/00 to 34/00 |                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                             |        | Estimated Cost: Rs | ₹ 99,268  |
|-------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------------------------------------|--------|--------------------|-----------|
| (S.H :Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-II                |                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                             |        | Time:-             | One month |
|                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                             |        | Earnest Money:-    | 2000      |
| S.NO                                                                                | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                | Qty   | Unit | T.Rate  | Rate in words                               | Amount |                    |           |
| 1                                                                                   | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and Technical Specification Clauses 802, 803, 1202 and 1203. Plain Cement concrete grade M10 Nominal mix 1:3:6. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 20.80 | Cum. | 4250.00 | Rupees Four Thousand Two Hundred Fifty Only | 88400  |                    |           |
| 2                                                                                   | Back filling behind abutment, wing wall and return wall complete as per drawings and Technical Specification Clause 1204.3.8 HPSR 2009 Item No. 12.14 (i). including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                               | 19.76 | Cum  | 550.00  | Rupees Five Hundred Fifty Only              | 10868  |                    |           |
|                                                                                     | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(8)@17/2/0212 dated 7.8.2018                                                                                                                                                                                                                                                   |       |      |         | Total:                                      | 99268  |                    |           |
|                                                                                     | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                     |       |      |         |                                             |        |                    |           |
|                                                                                     | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         |                                             |        |                    |           |
|                                                                                     | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                             |        |                    |           |
|                                                                                     | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                              |       |      |         |                                             |        |                    |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

484

33

Schedule of quantity

| Name of work:- Repair & Restoration of Pandoga Barrier to panjawar Km. 0/00 to 9/00<br>(SH: C/O U-Shape drain at RD. 2/708 to 2/735 & C/o Approach road Rhs). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Estimated Cost: Rs                        | ₹ 98,431  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------------------------------------------|-----------|
|                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Time:-                                    | One month |
|                                                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         | Earnest Money:-                           | 2000      |
| S.NO                                                                                                                                                          | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty   | Unit | T.Rate  | Rate in words                             | Amount    |
| 1                                                                                                                                                             | Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material. including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government | 29.16 | CUM. | 160.00  | (Rupees one hundred sixty only)           | 4666      |
| 2                                                                                                                                                             | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802,803,1202 & 1203. P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government                                                                                               | 19.60 | CUM. | 3900.00 | (Rupees Three Thousand Nine hundred only) | 76440     |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                  |      |      |         |                                            |       |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|---------|--------------------------------------------|-------|
| 3 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 1.50 | CUM. | 3300.00 | (Rupees Three Thousand Three hundred only) | 4950  |
| 4 | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i) nominal mix 1:1.5:3. The rates are inclusive octroi, royalty malkana toll tax sale tax, GST, labour cess or other taxes imposed by the Government                                                                                    | 2.25 | CUM. | 5500.00 | (Rupees Three Thousand Three hundred only) | 12375 |
|   | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@172/0212 dated 7.8.2018                                                                                                                                                                                                                                          |      |      |         | Total:                                     | 98431 |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                           |      |      |         |                                            |       |
|   | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                |      |      |         |                                            |       |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                  |      |      |         |                                            |       |
|   | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                    |      |      |         |                                            |       |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

500

# SCHEDULE OF QUANTITY

Name of work: -C/O Height & width gauge barricade at entry point to Swan river at Pandoga Near bridge on Panjwar Bathri road  
Tehsil Haroli distt. Una ( Deposit work )

Estimated Cost 57453/-  
Earnest Money 1200/-  
Time limit One month

| Sl. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit             | RATE In |                                               | AMOUNT |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|-----------------------------------------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  | Figures | Words                                         |        |
| 1       | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malikana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                     | 2.02     | Per cubic metre  | 170     | Rupees hundred seventy only                   | 343    |
| 2       | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803 1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. | 0.22     | Per cubic metre  | 3400    | Rupees three thousand four hundred only       | 748    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                    | 1.01     | Per cubic metre  | 4750    | Rupees four thousand seven hundred fifty only | 4797   |
| 4       | Centering and shuttering including strutting, propping etc. and removal of form work for Foundations, footings, bases for columns the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | 4.5      | Per square metre | 280     | Rupees two hundred eighty only                | 1260   |
| 5       | Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required wherever required, all complete in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malikhana ,toll tax,GST,labour cess or other taxes imposed by the Government..                                                                                                                                                                                                                                                                                                              | 439.27   | Per Kilogr amme  | 110     | Rupees One hundred ten only                   | 48319  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |                  |     |                            |          |
|---|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|-----|----------------------------|----------|
| 6 | Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete the direction of the Engineer-in-charge, including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.. | 15.52 | Per square metre | 128 | Rupees hundred twenty only | One 1986 |
|   | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                               |       |                  |     | Total:                     | 57453    |
|   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                     |       |                  |     |                            |          |
|   | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                         |       |                  |     |                            |          |
|   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                           |       |                  |     |                            |          |
|   | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                             |       |                  |     |                            |          |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

5/4

### Schedule of quantity

| Name of work :- C/O Sampark marg from Link road to the House of Sh. Ram Asra at Village Kangar G.P. Kangar, |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                              | Estimated Cost: Rs | ₹ 92,236     |
|-------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------------------|--------------------|--------------|
| [BIDDING/CLASIFICATION Blocks at Rd. 0/040.30 to 0/045 & CC Pavement at Rd. 0/045 to 0/050]                 |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                              | Time               | Days 10 days |
|                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                              | Earnest Money:-    | 2000         |
| S.NO                                                                                                        | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                           | Qty   | Unit | T.Rate  | Rate in words                                | Amount             |              |
| 1                                                                                                           | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.,                          | 7.88  | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only     | 26004.00           |              |
| 2                                                                                                           | Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504, including carriage of materials within all leads and lifts and other incidental . The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.,                                                              | 18.80 | sqm  | 800.00  | Rupees Eight Hundred Only                    | 15040.00           |              |
| 3                                                                                                           | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,804,1202 & 1203 P.C.C. grade M 20 Nominal Mix 1 : 2 : 4 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax , sale tax or other taxes imposed by the Government., | 0.38  | Cum. | 4500.00 | Rupees Four Thousand Five Hundred Only       | 1692.00            |              |
| 4                                                                                                           | Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 25(i)nominal mix 1:1.5:3, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkhana, toll tax, sale tax or other taxes imposed by the Government.,                   | 9.00  | Cum. | 5500.00 | Rupees Fifty five Thousand Five hundred Only | 49500.00           |              |
|                                                                                                             | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                       |       |      |         | Total                                        | 92236              |              |
|                                                                                                             | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                     |       |      |         |                                              |                    |              |
|                                                                                                             | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                              |                    |              |
|                                                                                                             | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                              |                    |              |
|                                                                                                             | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                          |       |      |         |                                              |                    |              |

Executive Engineer,  
M.P.W.D. Division Haroli  
Distt. Una (H.P.)

# **Draft Schedule of quantity**

| Name of work :- Restoration of rain damages on Panjavar Bathri road km. 0/00 to 34/00 |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | Estimated Cost: Rs                   |              |
|---------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|---------|--------------------------------------|--------------|
| (S.H. : Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-VI                |                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         | Time:-                               | One month    |
| S.NO                                                                                  | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                         | Qty    | Unit | T.Rate  | Earnest Money:-<br>Rate in words     | Amount       |
| 1                                                                                     | Providing and laying reinforced cement concrete in superstructure complete as per drawings and Technical Specification Clauses 800, 1205.4 and 1205.5 Reinforced Cement Concrete Grade M25 (1:1.5:3) Nominal mix. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 5.08   | Cum  | 6100.00 | Rupees Six Thousand One Hundred Only | 30978        |
| 2                                                                                     | Supplying, fitting and placing HYSD bar reinforcement in superstructure complete as per drawings and technical specification Clauses 1002, 1010 and 1202. HPSR 2009 Item No. 13.3. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                | 720.00 | Kg   | 95.00   | Rupees NinetyFive Only               | 68400        |
|                                                                                       | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                           |        |      |         | <b>Total:</b>                        | <b>99378</b> |
|                                                                                       | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                              |        |      |         |                                      |              |
|                                                                                       | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                   |        |      |         |                                      |              |
|                                                                                       | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                     |        |      |         |                                      |              |
|                                                                                       | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                       |        |      |         |                                      |              |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

505

37

## Draft Schedule of quantity

Name of work :- Restoration of rain damages on Panjwar Bathri road km. 0/00 to 34/00

(S.H. : Construction of 4.00 mtrs span culvert at Rd. 32/350) Phase-III

| Estimated Cost: Rs |                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         | Time:-                                      |  | One month |
|--------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|---------------------------------------------|--|-----------|
| Earnest Money:-    |                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         | Rate in words                               |  | 2000      |
| S.NO               | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty   | Unit | T.Rate  | Rate in words                               |  | Amount    |
| 1                  | Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and Technical Specification Clauses 802, 803, 1202 and 1203. Plain Cement concrete grade M10 Nominal mix 1:3:6. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government           | 5.76  | Cum  | 4250    | Rupees Four Thousand Two Hundred Fifty Only |  | 24480     |
| 2                  | Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Plain Cement concrete grade M15 nominal mix 1:2.5:5. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 15.60 | Cum  | 4800.00 | Rupees Four Thousand Eight Hundred Only     |  | 74880     |
|                    | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)@172/0212 dated 7.8.2018                                                                                                                                                                                                                                                             |       |      |         | Total:                                      |  | 99360     |
|                    | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                               |       |      |         |                                             |  |           |
|                    | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                             |  |           |
|                    | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                             |  |           |
|                    | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                       |       |      |         |                                             |  |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

485

**Schedule of quantity**

Name of work:- Repair & Restoration of Pandoga Barrier to panjwar Km. 0/00 to 9/00  
( SH: C/O U-Shape drain at RD. 2/735 to 2/850 Rhs ).

| S.NO | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty   | Unit | T.Rate  | Estimated Cost: Rs                        |           |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|-------------------------------------------|-----------|
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         | Time:-                                    | One month |
|      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         | Earnest Money:-                           | 2000      |
| 1    | Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty maikana toll tax sale tax, GST, labour cess or other taxes imposed by the Government | 21.50 | CUM. | 160.00  | (Rupees one hundred sixty only)           | 3440      |
| 2    | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802.803.1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty maikana toll tax sale tax, GST, labour cess or other taxes imposed by the Government                                                                                               | 24.55 | CUM. | 3900.00 | (Rupees Three Thousand Nine hundred only) | 95745     |
|      | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)6(17)2/02212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                               |       |      |         | Total:                                    | 99185     |
|      | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                           |           |
|      | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                           |           |
|      | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         |                                           |           |
|      | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |      |         |                                           |           |

**Executive Engineer,**  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

502



**Schedule of quantity**

| Name of work:- Restoration of rain damages on link road from Panjawan Bathri -Goundpur Tarf Jaichand road to Kutharbeet 0/0 to 3/400 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Estimated Cost: Rs | ₹ 99,498  |
|--------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-----------|
| (SH:- C/o R/wall at RD 0/020 to 0/032 LHS )                                                                                          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Time:-             | One month |
|                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                 | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T.Rate  | Rate in words                            | Amount             |           |
| 1                                                                                                                                    | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 12.48 | Cum. | 160.00  | Rupees one hundred sixty Only            | 1997               |           |
| 2                                                                                                                                    | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                   | 27.81 | Cum  | 3300.00 | Rupees three thousand three hundred only | 91773              |           |
| 3                                                                                                                                    | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 2 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204, 3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                              | 16.00 | Each | 160.00  | Rupees one hundred sixty Only            | 2560               |           |
| 4                                                                                                                                    | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204, 3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                   | 5.76  | Cum. | 550.00  | Rupees five hundred fifty only           | 3168               |           |
|                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | <b>Total:</b>                            | <b>99498</b>       |           |
|                                                                                                                                      | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PHW/B/06/1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                          |                    |           |
|                                                                                                                                      | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PHW(B/A(31)/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         |                                          |                    |           |
|                                                                                                                                      | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |                    |           |
|                                                                                                                                      | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |                    |           |
|                                                                                                                                      | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          |                    |           |

  
**Executive Engineer,**  
**H.P.W.D. Division Haridwar**  
**Distt. Haridwar**

530

**Schedule of quantity**

| Name of work : Restoration of rain damages on Una Rampur Haroli Jailon road Km. 0/00 to 23/00                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          |        | Estimated Cost: Rs | ₹ 99,338  |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------|--------------------|-----------|
| (SH: C/O Retaining wall at Rd. 13/712 TO 13/724 Rhs)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |         |                                          |        | Time:-             | One month |
| DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                          |        | Earnest Money:-    | 2000      |
| S.NO                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Qty   | Unit | T.Rate  | Rate in words                            | Amount |                    |           |
| 1                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 12.48 | Cum. | 160.00  | Rupees one hundred sixty Only            | 1997   |                    |           |
| Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. |       |      |         |                                          |        |                    |           |
| 2                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 27.81 | Cum. | 3300.00 | Rupees three thousand three hundred only | 91773  |                    |           |
| Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                   |       |      |         |                                          |        |                    |           |
| 3                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 15.00 | Each | 160.00  | Rupees one hundred sixty Only            | 2400   |                    |           |
| Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax.                                                                                                  |       |      |         |                                          |        |                    |           |
| 4                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 5.76  | Cum. | 550.00  | Rupees five hundred fifty only           | 3168   |                    |           |
| Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    |       |      |         |                                          |        |                    |           |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW/H/06/17/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                         |       |      |         |                                          |        | Total:             | 99338     |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(01A/311/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |         |                                          |        |                    |           |
| Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |        |                    |           |
| Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |                    |           |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          |        |                    |           |

  
 Executive Engineer,  
 H.P.W.D. Division Haroli,  
 Distt Una

**Schedule of quantity**

|                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------|-----------|
| Name of work:- Restoration of rain damages on link road from Panjawan Bathri - Goundpur Tarf Jaichand road to Kutharbeet D/O to 3/400                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Estimated Cost: Rs                       |        | ₹ 99,485  |
| (SH:- C/o R/wall at RD 0/032 to 0/044 LHS )                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Time:-                                   |        | One month |
|                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Earnest Money:-                          |        | 2000      |
| S.NO                                                                                                                                                                        | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T. Rate | Rate in words                            | Amount |           |
| 1                                                                                                                                                                           | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 12.40 | Cum. | 160.00  | Rupees one hundred sixty Only            | 1984   |           |
| 2                                                                                                                                                                           | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803,1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                   | 27.81 | Cum. | 3300.00 | Rupees three thousand three hundred only | 91773  |           |
| 3                                                                                                                                                                           | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 16.00 | Each | 160.00  | Rupees one hundred sixty Only            | 2560   |           |
| 4                                                                                                                                                                           | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 5.76  | Cum. | 550.00  | Rupees five hundred fifty only           | 3168   |           |
|                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Total:                                   | 99485  |           |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)(6)/1712/0212 dated 7.8.2018 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)(A)(3)1/2020 dated 22.07.20    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |
| Percentage quoted rate in Figures                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |
| Percentage quoted rate in words                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |

**Executive Engineer,**  
H.P.P.W.D. Division Haridwar  
Distt. Uttarakhand (H.P.)

529

| SCHEDULE OF QUANTITY                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                |         |                                | Estimated Cost | 99663     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------|---------|--------------------------------|----------------|-----------|
| Name of work : A/ R & M/O Una Rampur Haroli Palkwah Jaizon road Km 0/00 to 23/00 (SH: P/ F railing to Police Guard Post near swan bridge at RD 1/800) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                |         |                                | Earnest Money  | 2000/-    |
|                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                |         |                                | Time limit     | One month |
| Sl. No.                                                                                                                                               | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Quantity | Unit           | Figures | RATE In Words                  | AMOUNT         |           |
| 1                                                                                                                                                     | Providing and fixing Structural steel work riveted, bolted or welded in builtup section, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government                                                                                                                          | 568.35   | Per Kilogramme | 102.00  | Rupees one hundred two only    | 57972          |           |
| 2                                                                                                                                                     | Steelwork (Tata/Sail) make welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works <b>ANARKALI GRILL</b> complete upto all floor level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government | 320.70   | Per Kilogramme | 130.00  | Rupees one hundred thirty only | 41591          |           |
|                                                                                                                                                       | NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)(17)/20212 dated 7.8.2018                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                |         | Total:                         | 99663          |           |
|                                                                                                                                                       | 3) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B) A(3)/1/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B) A(3) 1/2020-1 dated 7.10.2021                                                                                                                                                                                                                                                                                                                                                                                       |          |                |         |                                |                |           |
|                                                                                                                                                       | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                |         |                                |                |           |
|                                                                                                                                                       | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |          |                |         |                                |                |           |
|                                                                                                                                                       | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          |                |         |                                |                |           |

4

Executive Engineer,  
H.P.W.D. Division Haroli  
Distt. Una (H.P.)

Schedule of quantity

| Name of work :- A/R & M/O PWD Non-Residential Building at Haroli Div & C/o CHC Bldg at Beetan ( SH: PAF Flex printing glow Sign<br>bard at haroli div & CHC bldg at Beetan |                                                                                                                                                                                                                                                                                               |      |      |                    |                                              |              |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|------|--------------------|----------------------------------------------|--------------|
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                               |      |      | Estimated Cost- Rs |                                              | ₹ 65,000     |
|                                                                                                                                                                            |                                                                                                                                                                                                                                                                                               |      |      | Time:-             |                                              | One month    |
| S.NO                                                                                                                                                                       | DESCRIPTION                                                                                                                                                                                                                                                                                   | Qty  | Unit | T. Rate            | Earnest Money:-<br>Rate in words             | Amount       |
| 1                                                                                                                                                                          | Providing and fixing flex printing glow sign board rectangle shape size 10.00FT x 4.00FT including carriage of materials within all leads and lifts and other incidentals.<br>The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 2.00 | Nos  | 32500.00           | Rupees thirty two thousand five hundred Only | 65000        |
|                                                                                                                                                                            | <b>Total</b>                                                                                                                                                                                                                                                                                  |      |      |                    |                                              | <b>65000</b> |
|                                                                                                                                                                            | Note: All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B)                                                                                                                                               |      |      |                    |                                              |              |
|                                                                                                                                                                            | Percentage quoted rate in Figures                                                                                                                                                                                                                                                             |      |      |                    |                                              |              |
|                                                                                                                                                                            | Percentage quoted rate in words                                                                                                                                                                                                                                                               |      |      |                    |                                              |              |
|                                                                                                                                                                            | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                 |      |      |                    |                                              |              |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

55

### Schedule of quantity

| Name of work:- Restoration of rain damages on Polian Janani road km. 0/000 to 6/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        | Estimated Cost: Rs | ₹ 97,131  |
|------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------------|--------------------|-----------|
| (SH:- C/O Wire crate work at Rd. 4/807.80 to 4/015.50 Lhs)                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        | Time:-             | One month |
| S.NO                                                                               | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty   | Unit | T.Rate  | Rate in words                          | Earnest Money:-    | 2000      |
| 1                                                                                  | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 15.71 | Cum. | 160.00  | Rupees One Hundred Sixty Only          |                    | 2513      |
| 2                                                                                  | Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                 | 29.57 | Cum. | 3200.00 | Rupees Three Thousand Two Hundred Only |                    | 94618     |
|                                                                                    | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Total                                  |                    | 97131     |
|                                                                                    | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(3)1/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(3)1/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                        |                    |           |
|                                                                                    | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                        |                    |           |
|                                                                                    | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |           |
|                                                                                    | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                        |                    |           |

Executive Engineer,  
H.P.P.W.D, District Haridwar  
Distt. Una (H.P.)

537

46

| Name of work:- Restoration of rain damages on Pollan Janani road km. 0/000 to 6/00 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                |
|------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------------|----------------|
| (SI:- C/O Wire crate work at Rd. 4/800 to 4/807.40 Lhs)                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                |
| S.NO                                                                               | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Qty   | Unit | T.Rate  | Estimated Cost: Rs                     |                |
|                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         | Time:-                                 | One month 2000 |
|                                                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         | Rate in words                          | Amount         |
| 1                                                                                  | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 25.91 | Cum. | 160.00  | Rupees One Hundred Sixty Only          | 2546           |
| 2                                                                                  | Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 130) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                  | 29.95 | Cum. | 3200.00 | Rupees Three Thousand Two Hundred Only | 95846          |
|                                                                                    | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         | Total                                  | 98392          |
|                                                                                    | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B/A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                |
|                                                                                    | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         |                                        |                |
|                                                                                    | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                |
|                                                                                    | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                        |                |

Executive Engineer,  
H.P.P.W.D. Division Barab  
Diath Una (H.P.)

W

536

54

# **SCHEDULE OF QUANTITIES**

Name of work :- Restoration of rain damage on Panjavar Bathri road Km 0/00 to 34/000 SH:- C/O approach road at RD 1/480, P/L paver block RD 0/237 to 0/274)

Estimates cost:- 99623  
 Earnest Money:- Rs. 2000/-  
 Time Limit:- One Month.

| S. No. | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Quantity | Unit              | RATE In |                                          | AMOUNT |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------------------|---------|------------------------------------------|--------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |          |                   | Figures | Words                                    |        |
| 1      | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                       | 1.80     | Per cubic metre   | 160.00  | Rupees one hundred sixty only            | 288    |
| 2      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203                                                                                                                                                                                                                                                                                      | 5.25     | Per Cubic metric  | 3300.00 | Rupees three thousand three hundred only | 17325  |
| 3      | Providing and laying of interlocking concrete block pavements having thickness 60mm thick as per drawing and technical specification clause 1504 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax (octroi), royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 92.50    | Per square metric | 800.00  | Rupees eight hundred only                | 74000  |
| 4      | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (Twenty) nominal mix 1:2:4 (One cement : two sand : four graded crushed / broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax (octroi), royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 1.78     | Per Cubic metre   | 4500.00 | Rupees four thousand five hundred only   | 8010   |
| Note:- | NOTE:- 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW(B)/1712/0212 dated 7.8.2018<br>2) The bidder are requested to submit their bid as per notification issued by the Principal Secy, PW to the Govt. of HP vide letter No. PBW(B)/A(3)/2020 dated 22.07.20<br>Percentage quoted rate in Figures<br>Percentage quoted rate in words<br>Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                          |          |                   |         |                                          | 99623  |

Executive Engineer,  
 H.P.P.W.D. Division Harbli  
 Distt. Una (H.P.)

54

418

| Schedule of quantity                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |        |           |        |
|-------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------------|--------------------|--------|-----------|--------|
| Name of work:- Restoration of rain damages on Polian Janani road km. 0/000 to 6/000 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |        |           |        |
| ( SH:- C/O Wire crate work at Rd. 4/900 to 4/905 Lhs)                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |        |           |        |
| S.NO                                                                                | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty   | Unit | T Rate  | Rate in words                          | Estimated Cost: Rs | Time:- | One month | 2000   |
|                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |        |           | Amount |
| 1                                                                                   | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and running of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 11.40 | Cum. | 160.00  | Rupees One Hundred Sixty Only          |                    |        |           | 1824   |
| 2                                                                                   | Providing and laying of boulder upon laid in wire crates with 4 mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 130) including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                    | 30.60 | Cum. | 3200.00 | Rupees Three Thousand Two Hundred Only |                    |        |           | 97920  |
|                                                                                     | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                    |        |           |        |
|                                                                                     | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                        |                    |        |           |        |
|                                                                                     | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                        |                    |        |           |        |
|                                                                                     | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                        |                    |        |           |        |
|                                                                                     | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                        |                    |        |           |        |
|                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         | Total                                  |                    |        |           | 98744  |

Executive Engineer,  
H.P.P.W.D. Division  
Distt. Una (H.P.)

524

Name of work:- Restoration of rain damages on Polian Janani road km. 0/000 to 6/00

(SH- C/O Retaining wall at Rd. 4/00 to 4/009.60 Rhs)

| Schedule of quantity |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Estimated Cost: Rs                       |        | One month |  |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------|-----------|--|
|                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         | Time:-                                   |        | 2000      |  |
| SNO                  | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Qty   | Unit | T. Rate | Rate in words                            | Amount |           |  |
| 1                    | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 8.06  | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 1290   |           |  |
| 2                    | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 in foundation and plinth. including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                  | 27.98 | Cum. | 3300.00 | Rupees Three Thousand Three Hundred Only | 92347  |           |  |
| 3                    | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                               | 12.00 | nos  | 160.00  | Rupees One Hundred Sixty Only            | 1920   |           |  |
| 4                    | Back filling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8 Granular material including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                                                                                    | 6.14  | Cum. | 550.00  | Rupees Five Hundred Fifty Only           | 3379   |           |  |
|                      | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         | Total                                    | 98936  |           |  |
|                      | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |        |           |  |
|                      | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |         |                                          |        |           |  |
|                      | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |      |         |                                          |        |           |  |
|                      | Note -Rate quoted in Figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |        |           |  |

Executive Engineer,  
H.P.P.W.D. Division  
Distt. Una (H.P.)

# SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damage on Panjawan Bathri road Km 0/00 to 34/00 (SH- C/O approach road at RD 1/480, P/W paver block RD 0/200 to 0/237)

Estimates cost:- 99938  
Earnest Money:- Rs. 2000/-  
Time Limit:- One Month.

| S. No.                                                                                                                                                                    | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Unit             | RATE In  |                                          | AMOUNT |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|----------|------------------------------------------|--------|
|                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  | Figures  | Words                                    |        |
| 1                                                                                                                                                                         | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkhana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                     | 1.80     | Per Cubic metre  | 180.00   | Rupees one hundred sixty only            | 288    |
| 2                                                                                                                                                                         | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement four sand: eight graded crushed / broken stone aggregate 20mm (twenty millimeter) nominal size in or under water/ ground complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203                                                                                                                                                                                                                                                                                         | 5.25     | Per Cubic metre  | 13125.00 | Rupees three thousand three hundred only | 17125  |
| 3                                                                                                                                                                         | Providing and laying of interlocking concrete block pavements having thickness 60mm thick as per drawing and technical specification clause 1504, including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | 92.50    | Per square metre | 800.00   | Rupees eight hundred only                | 74000  |
| 4                                                                                                                                                                         | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 (One cement two sand: four graded crushed / broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 1.85     | Per Cubic metre  | 4500.00  | Rupees four thousand five hundred only   | 8325   |
| Note:-                                                                                                                                                                    | Total                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                  |          |                                          | 99938  |
| NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PRW(B)S(17)2/0212 dated 7.8.2018 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  |          |                                          |        |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No. PRW (B)A(3)/2020 dated 22.07.20   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  |          |                                          |        |
| Percentage quoted rate in Figures                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  |          |                                          |        |
| Percentage quoted rate in words                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  |          |                                          |        |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |                  |          |                                          |        |

Executive Engineer,  
H.P.W.D. Division Harid  
Distt. Una (H.P.)

51

**Schedule of quantity**

| Name of work:- Restoration of rain damages on Polian Janani road km. 0/000 to 6/000 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                        | Estimated Cost: Rs | ₹ 99,744  |
|-------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|----------------------------------------|--------------------|-----------|
| ( SH:- C/O Wire crate work at Rd. 4/900 to 4/905 Lhs)                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                        | Time:-             | One month |
|                                                                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                        | Earnest Money:-    | 2000      |
| S.NO                                                                                | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty   | Unit | T Rate  | Rate in words                          | Amount             |           |
| 1                                                                                   | Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and raftering of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government. | 11.40 | Cum  | 160.00  | Rupees One Hundred Sixty Only          | 1824               |           |
| 2                                                                                   | Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS: 280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301, including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                 | 30.60 | Cum  | 3200.00 | Rupees Three Thousand Two Hundred Only | 97920              |           |
|                                                                                     | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         | Total                                  | 98744              |           |
|                                                                                     | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)(A)(3)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)(A)(3)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                        |                    |           |
|                                                                                     | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |      |         |                                        |                    |           |
|                                                                                     | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                        |                    |           |
|                                                                                     | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |      |         |                                        |                    |           |

Executive Engineer,  
H.P.P.W.D. Division Haridwar  
Distt. Una (H.P.)

538



53

| Schedule of quantity                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |       |          |                                                | Estimated Cost: Rs | ₹ 96,598  |
|---------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|----------|------------------------------------------------|--------------------|-----------|
| Name of work: Restoration of rain damages on link road from Una Jaljion road to Gudam da Toba Paliwadi km. 0/00 to 1/700. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |       |          |                                                | Time:-             | One month |
| (C/O Braast wall at Rd. 1/010.30 to 1/017 Rhs)                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |       |          |                                                | Earned Money:-     | 1000      |
| S.NO                                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Qty   | Unit  | T Rate   | Rate in words                                  | Amount             |           |
| 1                                                                                                                         | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 20.52 | cum   | 160.00   | Rupees One Hundred Sixty Only                  | 3283               |           |
| 2                                                                                                                         | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 ( CC 1:4:8), including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                    | 21.38 | cum   | 1300.00  | Rupees Three Thousand Three Hundred Only       | 70686              |           |
| 3                                                                                                                         | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia A.C. pipe extending through the full width of the structures with slope of 1 ( V ) : 20 ( H ) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                 | 8.00  | Each  | 160.00   | Rupees One Hundred Sixty Only                  | 1280               |           |
| 4                                                                                                                         | Providing concrete for plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 3 : 6, in foundation and plinth, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                      | 3.10  | Cum   | 3850.00  | Rupees Three Thousand Eight Hundred Fifty Only | 11948              |           |
| 5                                                                                                                         | Providing and laying reinforced cement concrete pipe NP2 for culvert on first class bedding of granular material in SINGLE row including living collar with cement mortar but excluding excavation, protection work in head walls and parapets clause 1108. Hume pipe 600 mm diameter, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                              | 5.00  | Metre | 21000.00 | Rupees Two Thousand Three Hundred Only         | 105000             |           |
|                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |       |          | Total                                          | 96598              |           |
|                                                                                                                           | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Hmt. of HP vide letter No. PBW (R) © (17) 2/02012 dated 07.08.2018.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |       |       |          |                                                |                    |           |
|                                                                                                                           | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (R)A/311/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (R)A/311/2020-1 Dated 07.10.2021.                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |       |          |                                                |                    |           |
|                                                                                                                           | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |       |       |          |                                                |                    |           |
|                                                                                                                           | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |       |       |          |                                                |                    |           |
|                                                                                                                           | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |       |          |                                                |                    |           |

Executive Engineer,  
H.P.P.W.D. Division Barab  
Distt. Una (H.P.)



54

| Name of work :-Restoration of rain damages on Palkwah Lalri Nangal Khurd Jatpur Road km. 0/00 to 10/400<br>(SH: C/O V-shpe drain at Rd. 7/696 to 7/742.10 Lhs). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |           |                                          |          |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|-----------|------------------------------------------|----------|
| Estimated Cost: Rs                                                                                                                                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Time:- |      | One month |                                          |          |
| Earnest Money:-                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |           |                                          |          |
| S.NO                                                                                                                                                            | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty    | Unit | T.Rate    | Rate in words                            | Amount   |
| 1                                                                                                                                                               | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material... including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty,malkhana,toll tax,GST,labour cess or other taxes | 19.36  | Cum. | 160.00    | Rupees One Hundred Sixty Only            | 3098.00  |
| 2                                                                                                                                                               | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803.1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government.                                                                                                                                    | 29.04  | cum  | 3300.00   | Rupees Three Thousand Three Hundred Only | 95842.00 |
|                                                                                                                                                                 | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                        |        |      |           | Total                                    | 98940    |
|                                                                                                                                                                 | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)JA(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)JA(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                          |        |      |           |                                          |          |
|                                                                                                                                                                 | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |        |      |           |                                          |          |
|                                                                                                                                                                 | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |        |      |           |                                          |          |
|                                                                                                                                                                 | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                             |        |      |           |                                          |          |

Executive Engineer,  
H.P.P.W.D. Division Haridwar  
Distt. Una (H.P.)

545

55

### Schedule of quantity

| Name of work: Restoration of rain damages on link road from Una Jaipon road to Gulaban da Toba Palkwah km. 0/00 to 1/700.                                                                                                                     |      |         |                                                |  |  |  | Estimated Cost Rs | ₹ 99,327  |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------|------------------------------------------------|--|--|--|-------------------|-----------|
| (C/O Breast wall at Rd. 1/00 to 1/010.30 Rhs)                                                                                                                                                                                                 |      |         |                                                |  |  |  | Time:-            | One month |
| S.NO                                                                                                                                                                                                                                          |      |         |                                                |  |  |  | Earnest Money:-   |           |
| DESCRIPTION                                                                                                                                                                                                                                   |      |         |                                                |  |  |  | Rate in words     | Amount    |
| Qty                                                                                                                                                                                                                                           | Unit | T Rate  |                                                |  |  |  |                   | 2000      |
| 25.49                                                                                                                                                                                                                                         | cum  | 160.00  | Rupees One Hundred Sixty Only                  |  |  |  |                   | 4079      |
| 25.73                                                                                                                                                                                                                                         | cum  | 3300.00 | Rupees Three Thousand Three Hundred Only       |  |  |  |                   | 88204     |
| 18.00                                                                                                                                                                                                                                         | Each | 160.00  | Rupees One Hundred Sixty Only                  |  |  |  |                   | 2880      |
| 1.08                                                                                                                                                                                                                                          | Cum  | 3850.00 | Rupees Three Thousand Eight Hundred Fifty Only |  |  |  |                   | 4164      |
| Total                                                                                                                                                                                                                                         |      |         |                                                |  |  |  |                   | 99327     |
| Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No. PBW (B) © (17) 2/2020 dated 07.08.2018                                                              |      |         |                                                |  |  |  |                   |           |
| 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021 |      |         |                                                |  |  |  |                   |           |
| Percentage quoted rate in figures                                                                                                                                                                                                             |      |         |                                                |  |  |  |                   |           |
| Percentage quoted rate in words                                                                                                                                                                                                               |      |         |                                                |  |  |  |                   |           |
| Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                  |      |         |                                                |  |  |  |                   |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

56

**Schedule of quantity**

| Name of work :- Restoration of rain damages on Palkwah Lalri Nangal Khurd Jatpur Road km. 0/00 to 10/400<br>(SH: C/O V-shape drain at Rd. 7/650 to 7/696 Lhs). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         | Estimated Cost: Rs                       | One month |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|-----------|
|                                                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         | Time:-                                   | 2000      |
| S.NO                                                                                                                                                           | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Qty   | Unit | T.Rate  | Earnest Money:-<br>Rate in words         | Amount    |
| 1                                                                                                                                                              | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana toll tax, GST, labour cess or other taxes imposed by the Government. | 19.32 | Cum. | 160.00  | Rupees One Hundred Sixty Only            | 3091.00   |
| 2                                                                                                                                                              | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203, P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                               | 28.98 | Cum  | 3300.00 | Rupees Three Thousand Three Hundred Only | 95634.00  |
|                                                                                                                                                                | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                    |       |      |         | Total                                    | 98725     |
|                                                                                                                                                                | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                        |       |      |         |                                          |           |
|                                                                                                                                                                | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                          |           |
|                                                                                                                                                                | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |      |         |                                          |           |
|                                                                                                                                                                | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |      |         |                                          |           |

Executive Engineer,  
H.P.P.W.D. Division Haridwar  
Distt. Una (H.P.)

546

57

| SCHEDULE OF QUANTITY                                                                                                                                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|------------------|---------|----------------------------------------------|----------------|---------------|------------|-----------|
| Name of work: Balance work for the repair of pot hole on link road Ispur to Pandoga via Kyarian Km 0/00 to 2/180 (SH: Patch work at RD 0/00 to 1/500) - <b>Inda MMSRRY</b>                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| S No                                                                                                                                                                                                                                        | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Unit             | Figures | Words                                        | Estimated Cost | Earnest Money | Time limit | One month |
| 1                                                                                                                                                                                                                                           | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (pug mill) carriage of mixed material compacting with smooth wheel roller of 80 to 100KN (Eighty to hundred kilo newton) capacity to achieve the desired density including lighting barricading and maintenance of diversion etc as per tables 400.11 & 400.12 and technical specification clause 406 including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 16.20    | Per cubic metre  | 1350.00 | Rupees One thousand three hundred fifty only | 99073          | 2000          |            |           |
| 2                                                                                                                                                                                                                                           | Providing and applying evenly a primer coat with bitumen emulsion (SS Type prepared surface of granular base to one point zero kilogram) per square metre using mechanical means as per technical specification clause 502 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts, and other incidentals. The rate includes octroi, royalty, malkhana, toll taxes, GST, labour cess or taxes imposed by the Government.                                                                                                                                                                                                                       | 217.13   | Per square metre | 55.00   | Rupees Fifty five only                       |                |               |            | 11942     |
| 3                                                                                                                                                                                                                                           | Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat with bitumen emulsion 20mm thick premix carpet VG-30 and seal coat type B specification clause includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                            | 217.13   | Per square metre | 300.00  | Rupees Three hundred only                    |                |               |            | 65139     |
| NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No PBW(B)/A(3)/17/20212 dated 7.8.2018                                                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy PW to the Govt. of HP vide letter No PBW(B)/A(3)/11/2020 dated 22.7.2020 & Govt. of HP vide letter No PBW(B)/A(3)/1/2020-1 dated 7.10.2021 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| Percentage quoted rate in Figures                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| Percentage quoted rate in words                                                                                                                                                                                                             |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              |                |               |            |           |
| Total:                                                                                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                  |         |                                              | 99073          |               |            |           |

Executive Engineer  
Haroli Division  
HP.PWD., Noida

58

### Schedule of quantity

| Name of work :- Restoration of rain damages on Palkwah Lalri Nangal Khurd Jatpur Road km. 0/00 to 10/400 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          | Estimated Cost: Rs | ₹ 98,725  |
|----------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------|--------------------|-----------|
| [SH: C/O V-shape drain at Rd. 7/650 to 7/696 Rhs].                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          | Time:-             | One month |
| S.NO                                                                                                     | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Qty   | Unit | T.Rate  | Rate in words                            | Earnest Money:-    | 2000      |
| 1                                                                                                        | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes imposed by the Government. | 19.32 | Cum. | 160.00  | Rupees One Hundred Sixty Only            |                    | 3091.00   |
| 2                                                                                                        | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                                 | 28.98 | Cum  | 3300.00 | Rupees Three Thousand Three Hundred Only |                    | 95634.00  |
|                                                                                                          | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) © (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                     |       |      |         | Total                                    |                    | 98725     |
|                                                                                                          | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of Hp vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                         |       |      |         |                                          |                    |           |
|                                                                                                          | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |      |         |                                          |                    |           |
|                                                                                                          | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |      |         |                                          |                    |           |
|                                                                                                          | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                          |       |      |         |                                          |                    |           |

Executive Engineer,  
H.P.W.D. Divisional  
Distt. Una (H.P.)

547

### Schedule of quantity

| Name of work: Restoration of rain damages on link road from Una Jaijon road to Gulaban da Toba Palkwah km. 0700 to 1/700. |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         | Estimated Cost: Rs                             | ₹ 98,390  |
|---------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|---------|------------------------------------------------|-----------|
| (C/O Breast wall at Rd. 1/022 to 1/032.20 Rhs)                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         | Time:-                                         | One month |
|                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         | Earnest Money:-                                | 2000      |
| S.NO                                                                                                                      | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty   | Unit | T.Rate  | Rate in words                                  | Amount    |
| 1                                                                                                                         | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. The rate including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 25.25 | Cum  | 160.00  | Rupees One Hundred Sixty Only                  | 4039      |
| 2                                                                                                                         | Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (CC 1:4:8) including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                                                     | 26.47 | Cum  | 3300.00 | Rupees Three Thousand Three Hundred Only       | 87348     |
| 3                                                                                                                         | Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia AC pipe extending through the full width of the structures with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                      | 18.00 | Each | 160.00  | Rupees One Hundred Sixty Only                  | 2880      |
| 4                                                                                                                         | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 P.C.C. grade M 10 Nominal Mix 1 : 3 : 6 in foundation and plinth. including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                      | 1.07  | Cum  | 3850.00 | Rupees Three Thousand Eight Hundred Fifty Only | 4123      |
|                                                                                                                           | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy: to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                                                               |       |      |         | Total                                          | 98390     |
|                                                                                                                           | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)/2020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                                                                   |       |      |         |                                                |           |
|                                                                                                                           | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |       |      |         |                                                |           |
|                                                                                                                           | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |      |         |                                                |           |
|                                                                                                                           | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |      |         |                                                |           |

Executive Engineer,  
H.P.P.W.D. Division

60

**Schedule of quantity**

| Name of work :- Restoration of rain damages on Palkwah Lahri Nangal Khurd Jatpur Road km. 0/00 to 10/400<br>(SH: C/O V-shape drain at Rd. 7/696 to 7/742.10 Rhs). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |                    |                                          |           |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------|--------------------|------------------------------------------|-----------|
|                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      | Estimated Cost: Rs |                                          | ₹ 98,940  |
|                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      | Time:-             |                                          | One month |
|                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      | Earnest Money:-    |                                          | 2000      |
| S NO                                                                                                                                                              | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Qty   | Unit | T.Rate             | Rate in words                            | Amount    |
| 1                                                                                                                                                                 | Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including carriage of materials within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malikana, toll tax, GST, labour cess or other taxes. | 19.36 | Cum. | 160.00             | Rupees One Hundred Sixty Only            | 3098.00   |
| 2                                                                                                                                                                 | Providing concrete for Plain concrete in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203.P.C.C. grade M 10 Nominal Mix 1 : 4 : 8 including carriage of materials within all leads and lifts and other incidentals. The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                       | 29.04 | cum  | 3300.00            | Rupees Three Thousand Three Hundred Only | 95842.00  |
|                                                                                                                                                                   | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter no. PBW (B) (17) 2/02012 dated 07.08.2018                                                                                                                                                                                                                                                                                                                                             |       |      |                    | Total                                    | 98940     |
|                                                                                                                                                                   | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PBW (B)A(31)72020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B)A(31)72020-1 Dated 07.10.2021                                                                                                                                                                                                                                                                               |       |      |                    |                                          |           |
|                                                                                                                                                                   | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |      |                    |                                          |           |
|                                                                                                                                                                   | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |      |                    |                                          |           |
|                                                                                                                                                                   | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                                                                                                                                                                                |       |      |                    |                                          |           |

Executive Engineer,  
H.P.P.W.D. Division  
Distt. Una (H.P.)

548

**Schedule of quantity**

|                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |        |                    |           |
|----------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|--------------------------------|--------|--------------------|-----------|
| Name of work: - Restoratin of rain damages on Laluwal Gondpur to Singha Jhungian upto Punjab Border road km. 0/0 to 13/575 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |        | Estimated Cost: Rs | ₹ 99,216  |
| (SH: Repair of Rain cuts at Various RDs from km. 12/275 to 13/575)                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |        | Time:-             | One month |
|                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |        | Earnest Money:-    | 2000      |
| S.NO                                                                                                                       | • DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Qty    | Unit | T.Rate | Rate in words                  | Amount |                    |           |
| 1                                                                                                                          | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 413.40 | Cum  | 240.00 | Rupees Two Hundred Fourty Only | 99216  |                    |           |
|                                                                                                                            | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(1712/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                           |        |      |        | Total:                         | 99216  |                    |           |
|                                                                                                                            | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                              |        |      |        |                                |        |                    |           |
|                                                                                                                            | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |      |        |                                |        |                    |           |
|                                                                                                                            | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |        |                    |           |
|                                                                                                                            | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                       |        |      |        |                                |        |                    |           |

*Executive Engineer,*  
H.P.P.W.D. Division

555

| Schedule of quantity                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        |                                    |           |
|--------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|------------------------------------|-----------|
| Name of work:- Balance work for the C/O Science Lab at Govt. Sr. Sec. School Lalri Tehsil Haroli Distt Una (H.P.)              |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        |                                    |           |
| [SH :-Providing and fixing sliding door bolt, tower bolts, adjustable friction windows stays,double acting spring hinges etc.) |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        |                                    |           |
| S.NO                                                                                                                           | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                              | Qty    | Unit | T.Rate | Estimated Cost: Rs                 |           |
|                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        | Time:-                             | One month |
| Earnest Money:-                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        |                                    |           |
|                                                                                                                                |                                                                                                                                                                                                                                                                                                                                                                          |        |      |        | Rate in words                      | Amount    |
| 1                                                                                                                              | Providing and fixing anodized aluminium sliding door bolts anodized transparent or dyed to required shade with bolt and nut and screws etc. 250 mmx16mm . The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                       | 28.00  | Each | 150.00 | Rupees One Hundred Fifty Only      | 4200.00   |
| 2                                                                                                                              | Providing and fixing anodized aluminium tower bolts (Barrel type) anodized transparent or dyed to required shades and color with screw etc. complete 1) 200x10 mm. The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                              | 140.00 | Each | 135.00 | Rupees One Hundred ThirtyFive Only | 18900.00  |
| 3                                                                                                                              | Providing and fixing anodized aluminium tower bolts (Barrel type) anodized transparent or dyed to required shades and color with screw etc. complete 125 mm (One hundred twenty five millimeter). The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                               | 20.00  | Each | 45.00  | Rupees FortyFive Only              | 1260.00   |
| 4                                                                                                                              | Providing and fixing anodized aluminium tower bolts (Barrel type) anodized transparent or dyed to required shades and color with screw etc. complete 75mm (Seventy five millimeter). The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                            | 230.00 | Each | 40.00  | Rupees Forty Only                  | 9200.00   |
| 5                                                                                                                              | Providing and fixing aluminium coating adjustable friction windows stays of approved quality with necessary stainless steel screws etc. to the side hung windows as per direction of Engineer-in-charge complete. 205x19 Door & windows 205x19. The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government. | 150.00 | Each | 220.00 | Rupees Two Hundred Twenty Only     | 33000.00  |
| 6                                                                                                                              | Providing and fixing oxidised aluminium double acting spring hinges with necessary screws etc. complete. The rate includes sale tax octroi/royalty/malkhana, toll tax, GST, labour cess or other taxes imposed by the Government.                                                                                                                                        | 330.00 | Each | 100.00 | Rupees One Hundred Only            | 33000.00  |
|                                                                                                                                | Note 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No. PBW (B) @ (17) 2/02012 dated 07.08.2018                                                                                                                                                                                         |        |      |        | Total                              | 99560     |
|                                                                                                                                | 2) The bidder are requested to submit there bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter no. PSW (B/A)31/2020 Dated 22.07.2020 & Govt. of HP vide letter no. PBW (B/A)31/2020-1 Dated 07.10.2021                                                                                                                              |        |      |        |                                    |           |
|                                                                                                                                | Percentage quoted rate in figures                                                                                                                                                                                                                                                                                                                                        |        |      |        |                                    |           |
|                                                                                                                                | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                          |        |      |        |                                    |           |
|                                                                                                                                | Note -Rate quoted in figures & words are mandatory by the contractor, other wise the tender will be rejected                                                                                                                                                                                                                                                             |        |      |        |                                    |           |

Executive Engineer,  
H.F.P.W.D. Division Haroli  
Distt. Una (H.P.)

63

## Schedule of quantity

| Name of work: - Restoratin of rain damages on Link road Bathu to Bathri via Goushala KM. 0/00 to 1/100 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Estimated Cost: Rs             | ₹ 98,280  |
|--------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|--------|--------------------------------|-----------|
| (SH: Repair of Rain cuts at Various RDs from km. 0/00 to 1/100)                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Time:-                         | One month |
|                                                                                                        |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        | Earnest Money:-                | 2000      |
| S.NO                                                                                                   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Qty    | Unit | T.Rate | Rate in words                  | Amount    |
| 1                                                                                                      | Restoration of rain cuts with soil, moorum gravel or a mixture of these, clearing the loose soil, benching for 300mm width laying fresh material in layers not exceeding 250 mm and compaction with plate compactor or power rammer to restore the original alignment, level and slopes as per drawings and technical specifications Clause 1902 Mechanical Means. The rate is including of octroi, royalty, Malkana, toll tax , sale tax or other taxes imposed by the Government. | 409.50 | Cum  | 240.00 | Rupees Two Hundred Fourty Only | 98280     |
|                                                                                                        | NOTE: 1) All type of material shall be arranged by the contractor vide Notification by Additional Secy to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018                                                                                                                                                                                                                                                                                                           |        |      |        | Total:                         | 98280     |
|                                                                                                        | 2) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No PBW(B)A(3)1/2020 dated 22.07.20                                                                                                                                                                                                                                                                                                              |        |      |        |                                |           |
|                                                                                                        | Percentage quoted rate in Figures                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |      |        |                                |           |
|                                                                                                        | Percentage quoted rate in words                                                                                                                                                                                                                                                                                                                                                                                                                                                     |        |      |        |                                |           |
|                                                                                                        | Note:- Rate quoted in figures & words are mandatory by the contractor, otherwise the tender will be rejected.                                                                                                                                                                                                                                                                                                                                                                       |        |      |        |                                |           |

Executive Engineer,  
H.P.P.W.D. Division Haroli  
Distt. Una (H.P.)

556